3.

TRANSLATIONS

OF

FOREIGN BIOLOGICAL MEMOIRS

II

THE

ANATOMY OF THE FROG

BY

Dr. ALEXANDER ECKER

PROFESSOR OF HUMAN AND COMPARATIVE ANATOMY
IN THE UNIVERSITY OF FREIBURG

Translated, with numerous Annotations and Additions

BY

GEORGE HASLAM, M.D.

SCIENTIFIC ASSISTANT IN THE MEDICAL DEPARTMENT IN THE UNIVERSITY
OF ZÜRICH ; FORMERLY ASSISTANT LECTURER IN PHYSIOLOGY IN THE
OWENS COLLEGE, VICTORIA UNIVERSITY, MANCHESTER

ILLUSTRATED WITH MANY WOOD ENGRAVINGS

*AND TWO COLOURED PLATES EXECUTED BY HOFMANN, WÜRTZBURG, BAVARIA*

Oxford

AT THE CLARENDON PRESS

1889

TRANSLATOR'S PREFACE.

I UNDERTOOK the publication of a translation of Ecker's 'Anatomie des Frosches' at the suggestion of Professor A. Gamgee while I was working under his superintendence in the physiological laboratory of the Owens College. The work was subsequently accepted by the Delegates of the Clarendon Press, as one of the series of 'Foreign Biological Memoirs,' published by them. Early in the progress of the work it became evident that a mere translation would be unsatisfactory, and that it would be desirable to recast and modify several portions of the book. It was deemed advisable to give greater completeness to the work by descriptions of the minute structure of the several organs. For these purposes the appearance of the work has been unavoidably delayed.

I have done my best to bring the book up to date by including the results of recent researches, to which I have added many facts derived from my own personal investigations. All such additions are enclosed within square brackets [ ]. More than a hundred new figures, of which one-third are original, have been added ; and copious, though it is feared still incomplete, lists of references to frog-literature have been drawn up. By these additions the size of the book has been considerably increased.

In the several sections into which the book is divided the following points may be more particularly noticed :—

Sect. I. The Bones and Joints. The nomenclature of Parker and Bettany has been adopted throughout.

Sect. II. The Muscles. This section remains in its original form.

Sect. III. The Nervous System. The chapters on the central

nervous system and the sympathetic system have been re-written. The description of the arteries of the brain is entirely new, while the chapters on cranial and spinal nerves have received many smaller additions, and have been re-arranged to facilitate reference.

Sect. IV. The Vascular System. The chapter on the heart is practically new, and many additions and alterations have been made in the descriptions of the blood-vessels and lymphatics.

Sect. V. The Alimentary Canal, with its appendages, the Spleen and the Peritoneum. In this section much new material has been added : the descriptions of the blood-vessels of the liver, the ducts of the liver and pancreas, etc., being the results of original investigation.

Sect. VI. The Respiratory Organs, the Thymus and Thyroid Glands. These organs have been carefully studied and numerous new details are noted. The lymphatic glands of the hyoid region have, after some hesitation, been designated tonsils.

Sect. VII. The Urino-Genital Organs. A very large number of preparations have been made to investigate the vessels and uriniferous tubes of the kidneys ; and the descriptions of the remaining organs of this section have received large additions from recent publications.

Sect. VIII. The Skin and the Sense-Organs. This section has, with the exception of very small portions, been re-written and very much enlarged.

Before concluding this preface, I must thank my friend Professor A. Milnes Marshall, of the Owens College, for all the help and kindness he has extended to me before and during the time this work has been in hand ; to him I am indebted not alone for the loan of books, pamphlets, etc., and for much useful information, but also for the care and patience with which he has read and corrected the whole of the proof-sheets.

To Professor G. Lunge, of Zürich, I am indebted for the use of the library of the Gesellschaft der Naturforscher of Zürich ; and

to my friend Mr. C. Herbert Hurst, of the Owens College, for the drawings for figures 132, 133, 134, and 136; also to Dr. Max Köppen, of Strasburg, for the proof-sheets of his valuable paper, 'Zur Anatomie des Froschgehirns': to these gentlemen I beg to express herewith my heartiest thanks. Lastly, I must express my sense of indebtedness to the Delegates of the Clarendon Press, who have kindly allowed me to alter the original plan of the book, and to make extensive additions far beyond the limits originally intended.

A second edition of the original German work is in course of publication. The first part, on the bones and muscles, has already appeared.

GEO. HASLAM.

ZÜRICH, 1888.

PREFACE TO THE FIRST PART.

THE idea of this manual on the anatomy of the frog, of which I now offer the first part to physiologists and to those who would become such, occurred to me during the preparation of the plates for my 'Icones Physiologicae.' I was then convinced of the necessity of such a book. I regret that many direct and indirect causes have hindered its earlier completion; fo.tunately, however, its appearance is still opportune, as the need for the book has not diminished. I am conscious that the book requires a recommendation to the indulgent judgment of my fellow-workers, since almost every one has studied the frog for one purpose or another, and each will closely criticize in that department with which he is most familiar. Although I shall not be able to satisfy all, still I hope that my work may serve as a useful basis for further investigations, and I would apply to it the words with which Sömmering prefaced his anatomy: 'Ich wünschte ein Handbuch zu liefern und seine Einrichtung so zu treffen, dass man künftig an ihm als einer Basis nach Erforderniss leicht ändern, wegnehmen und zusetzen könnte[1].'

Lest more be anticipated from the book than it is intended to supply, I would observe that I have throughout had in mind only a descriptive anatomy of the indigenous (German) frog; a comparative anatomy of Batrachians was as foreign to my intention as were developmental or histological questions: hence morphological details must not be expected. Any hope of formulating a systematic nomenclature of the muscles has been abandoned; as neither one based upon their mode of action, of which we know so little, nor one based upon their origins and insertions, as demonstrated by the unpronounceable names of Chaussier and Dugès, is really practicable. I have therefore preferred to avail myself, as far as possible, of the received names, which have been chosen partly

---

[1] 'I wished to furnish a manual so arranged that it might serve as a basis easily altered, pruned, or enlarged as the future might need.'

according to mode of action, partly according to origin and insertion, and partly according to position and form ; while in the choice of new names I have given preference to the simplest.

The figures are, with few exceptions, original, and drawn by myself. Their careful execution in woodcut has added a very necessary neatness to that correctness, which alone I claim as mine.

<div align="right">ALEXANDER ECKER.</div>

FREIBURG,
February, 1864.

PREFACE TO THE SECOND PART.

SIXTEEN years have elapsed since the first portion of this anatomy of the frog appeared ; this second portion, therefore, requires a somewhat apologetic introduction.

The nervous and vascular systems have, in substance, been known for some years ; still, certain points required a thorough revision : this seemed especially necessary with regard to the cranial nerves. In consequence of my anthropological investigations, and particularly through undertaking the editorship of the 'Archiv für Anthropologie,' my attention was drawn into another channel, and I found it impossible to work out this chapter : consequently the whole was deferred, and would have been still longer delayed had I not received assistance.

At my request Professor Wiedersheim undertook to investigate afresh the cranial nerves, the brain, the spinal cord, and the sympathetic system ; and the descriptions of these parts are the result of his work alone. I regard it as most advantageous to this second part that so experienced an investigator in the anatomy of Amphibia should have given me his help.

The remaining portions appear almost unaltered as written several years ago ; and the majority of the illustrations date from

the same period. I had neither the time nor the zeal necessary to re-examine the whole; besides, it is doubtful whether eyes some twenty years older would improve matters.

This somewhat neglected book is therefore commended to the indulgence of my fellow-workers, with the hope that it may at least form a basis upon which further work may easily be done; to proffer more than this, as I stated, with a quotation from Sömmering, in the preface to the first part, I have never even hoped.

The final part of the work, on the viscera and sense-organs, has been undertaken by Professor Wiedersheim, and will appear in the Spring of 1882.

ALEXANDER ECKER.

Freiburg,
    August, 1881.

CONTENTS.

—— ♦♦ ——

ILLUSTRATIONS.

INTRODUCTION.

THERE is no occasion, now-a-days, to offer a lengthened apology for devoting a treatise solely to the anatomy of the frog, which enjoys the doubtful honour of being, κατ᾽ ἐξοχήν, the physiological domestic animal. It is kept in every physiological laboratory, and is daily sacrificed in numbers upon the altar of science. The physiologist has recourse to it, not only to obtain answers to new questions, but for the sake of demonstrating easily and quickly the most important known facts of the science. These unlucky batrachians are to be had in any number, and are specially adapted for experimental investigation: they have consequently fallen under a harsher tyrant than the stork in the fable, and their prophetic outcry in the frog-chorus of Aristophanes, δεινὰ πεισόμεσθα, has been literally fulfilled.

As the history of the most important physiological discoveries is closely related with the employment of the frog in physiological research, it will not · be without interest to review briefly the history of its use in scientific, especially in physiological, investigations, and to record the services which it has already rendered to science. Swammerdam (1637–1685), as du Bois-Reymond justly remarks, was the first to make known the frog as an important means of research; he says concerning it :—' An den Thieren, die das heisseste Blut haben, ist die Bewegung der Muskeln nicht so merklich oder hält vielmehr nicht so lange an, als an Thieren die mit kälterem Blute begabt sind. Dergleichen sind die Fische und viele andere Wasserthiere, wie auch solche, die so wohl im Wasser als auf dem trocknen Lande leben können. Deswegen habe ich insonderheit mit dem Frosch meine Versuche angestellt. Denn an diesem Thiere sind die Sehnen sehr sichtbar und lassen sich leicht entdecken

B

und entblössen[1].' Swammerdam made the earliest experiments on the contraction of muscle by means of chemical and mechanical stimulation of its nerves; thus laying the basis of our present nerve and muscle physiology, which has been built up within rather less than two hundred years; though during the first half of this period but little advance was made.

From the famous September evening of the year 1786, on which Galvani first observed the twitchings of a frog's leg suspended by a metallic hook to an iron balcony, the frog has, down to the present time, afforded almost the only material for the investigation of the excitability of nerve and its associated electromotive changes, and also no inconsiderable part of the remaining nerve and muscle physiology. It was not until Müller devised the method of operating on the frog that Bell's law became capable of easy proof; and much of our knowledge of the functions of the spinal cord is derived from experiment upon it. Again, the muscles of frogs served, from the time of Swammerdam to that of Eduard Weber and his followers, for the investigation of the phenomena and the conditions of contraction; and in almost all other branches of physiology there are important doctrines which were first definitely established by experiment upon the frog. But for the web of the foot of this animal (and the gills and tail of its tadpole, in which Leeuwenhoek[2] describes the phenomena most clearly) we should not, perhaps for a long time, have arrived at a satisfactory knowledge of the existence and the conditions of the capillary circulation. As is well known, an accurate acquaintance with the constituents of the blood directly concerned in nutrition has been obtained by observation on the frog, as well as important facts in the physiology of the blood and lymph, such as the intimate knowledge of the corpuscles of both fluids, and the coagulability of the plasma; while in no less degree have experiments on these animals served to establish the laws of the heart's action. Moreover, physiology is not the only science indebted to the frog: in histology many important results have been obtained from observations on it, and for histological instruction it is now indispensable. To it we owe much of our

---

[1] 'In animals with warm blood the action of the muscles is neither so apparent nor so long continued as in those animals which have cold blood, such as fishes and many other aquatic animals, and those also which live both in water and on dry land. On this account I have made my investigations chiefly on frogs, for in them the nerves are very distinct, and are easily found and exposed.' Buch der Natur, Leipzig, 1752, p. 330.

[2] Leeuwenhoek, Arcana Naturæ III, epist. 65 ad Reg. Soc. Lond., p. 158.

knowledge of the structure of nerve fibres, their origin and termina-tion, especially in muscle, their relations within the ganglia, and even the structure of muscular fibre itself. For the study of reproduction and development the frog has, next to the chick, afforded the most important material: one need but refer to the investigations on impregnation from the time of Spallanzani to that of Newport[1], the phenomena of cleavage, and many others.

Thus with progress of time the field in which the frog has been submitted to observation and experiment, whether for the demon-stration of established facts to students or for the solving of new problems, has vastly increased, and this batrachian has indeed be-come, as we have stated, the physiologist's domestic animal.

That, for these manifold uses, a more exact anatomical know-ledge of the frog is very necessary is self-evident. The majority of students commencing the study of physiology have little more than a superficial knowledge of the sciatic nerve and the leg-muscles; at most, of the spinal cord and its nerve-roots; and only acquire any further knowledge in a disconnected manner. For this they can scarcely be reproached, the literature of the anatomy of the frog being so widely scattered in monographs and journals that reference to it involves the expenditure of much time. This attempt, there-fore, to produce a complete anatomy of the frog, based throughout upon my own observations, cannot be considered superfluous; it is rather to be feared it may be thought insufficient.

The European frogs[2] alone are treated of in the following description, *i.e.* the two species, *Rana esculenta*, L., and *R. tempo-raria*, L., the former being more particularly described, though such differences in structure as occur are noted. This is not the place to discuss the exact systematic characters of the two species, yet they cannot be ignored entirely. The species were, from their habitats, long ago distinguished by C. Gessner[3], and named *Rana rubeta*, *s. gibbosa*, the garden or grass-frog, and *Rana aquatica*, *s. innoxia*, the water-frog; at least, from his figure, the former can be no other than *R. temporaria*, though Gessner,

---

[1] It may be well to remind the reader that this introduction was written in 1864.

[2] For purposes of comparison other than European frogs were examined, especially American species of *Rana*, for which I am indebted to the kindness of my much esteemed friend Agassiz. These were *Rana Catesbyana*, Shaw (*R. mugiens*, Catesby— *R. pipiens*, Harlan); *R. sylvatica*, Leconte; *R. clamitans*, Daudin; *R. palustris*, Leconte; *R. halecina*, Leconte. To these, however, no further reference will be made in the text.

[3] C. Gessner, Thierbuch. Zürich. Fol., p. 157.

probably expecting to find in it the *rubeta* of older writers, adds that it 'ist für giftig zu halten.'

Leeuwenhoek[1] also correctly distinguished between them, but it is to Rösel[2] that we are chiefly indebted for a careful discrimination and an accurate knowledge of the life-histories of the two species.

Fig. 1.

The green water-frog, *Rana esculenta* L.

Rana esculenta, L. The green water-frog, Fig. 1, usually attains a larger size[3] and is more active than the other species, and for this

---

[1] Leeuwenhoek, Arcana Naturæ, Vol. III of Ecker's edition. Leyden, 1722. Epist. 65 ad Reg. Soc. Lond., p. 154.

[2] Rösel, Naturgeschichte der Frösche Deutschlands, ed. Schreber. Nürnberg, 1815, p. 36.

[3] The extreme sizes are much more pronounced in this species. I have never found *R. temporaria* of the size attained by large specimens of the water-frog.

reason is better adapted to the purposes of the physiologist; hence I have chosen it for description.

The head is flat, as broad as it is long, and triangular with an obtuse snout in front. The upper surface of the head, *i.e.* the space between the eyes, is slightly concave, grooved, and narrower than in *R. temporaria*. The tympanic membrane is circular, and relatively to the eye is larger. The upper eyelids have several transverse folds in their hinder part. The pupil is oval, with the long axis horizontal. The vomerine teeth are arranged in two clusters, which are relatively larger than in *R. temporaria* and lie exactly between the posterior nares, without however touching them. The openings of the Eustachian tubes do not exceed in size the posterior nares to so great an extent as they do in *R. temporaria*. The male possesses a vocal sac on either side, which reaches the surface beneath the tympanic membrane through a cleft placed behind the angle of the mouth, and is, in well-developed specimens, about the size of a cherry. The hind limbs are relatively longer. The toes are long, and taper towards their tips: the webs between the toes are cut out semicircularly, and that of the longest or fourth toe is continued to the tip of the last phalanx. The supplemental toe is an oval prominence of cartilaginous hardness. The skin of the back has wart-like tubercles arranged longitudinally in raised lines; one of these lines runs on each side from the posterior canthus as far as the thigh, and is very constant: in the male a second line surrounds the posterior margin of the vocal sac ; a corresponding line exists in the female.

The skin of the belly is quite smooth, the colour presenting many variations which appear to depend upon very diverse circumstances. It varies with changes in the physiological condition of the animal. Von Wittich[1] has shown that a bright green specimen changes to a dark leafy green colour on exclusion of light; also, that dark specimens become almost a lemon-yellow colour on exposure to bright sunlight; and he has pointed out that this brightening of the skin is an active condition dependent upon contraction of the stellate pigment-cells. It is therefore not surprising, as the same inquirer observes, that one should sometimes find specimens of *R. esculenta* in which the ground colour is almost a greenish yellow (as in Rösel's figure, Pl. XIII), whilst in others it can only be distinguished from the dorsal black patches by a faint greenish

---

[1] Von Wittich, Müller's Archiv, 1854, p. 41.

shade. There is no doubt that difference of habitat influences the colour; but this may again be modified by light[1], as has been established in the case of fish by direct observation[2]. Apparent varieties may thus occur.

In frog-tanks such diversities of colour may not unfrequently be observed in the same individual, as for example when the lower part of the body immersed in muddy water is dark, while the part above the water is bright. That the process of casting the skin exercises an influence on the brightness of the colouring is certain, yet there are, as von Wittich has correctly remarked, other alterations of colour which are in no way connected with this process, and are evidently more of a pathological nature; such as when the frog assumes a dirty green spotted appearance, the green fading more and more, until all the patches which are usually green appear of a dirty greyish-brown with a faint bronze shimmer. According to this author these changes are most readily brought about by starvation. The dark colour which frogs exhibit after hibernation is perhaps to be ascribed to the co-operation of several of the causes mentioned above.

The usual colouring of healthy animals is as follows: the back is bright green with three golden yellow longitudinal stripes, one median and two lateral, and a number of irregular brown or black stripes of approximately uniform width: on the head are a pair of black stripes which pass from the angles of the eyes across the nares to the tip of the nose; now and then the tympanic membrane and surrounding parts have also a black patch, as in *R. temporaria*: another black stripe is found on the anterior surface of the arm, in the region of the shoulder: and on the thighs are black, yellow, and white mottlings. The whole of the under-surface is white or yellowish. At times the yellow stripes of the back are wanting or are indistinct. It has already been mentioned that many varieties may occur; and these have in all probability given rise to the descriptions of reputed new species, such as *R. maritima*, Risso, found in South Europe; *R. alpina*, Risso, found in the high-lying Alpine lakes; *R. hispanica* of Fitzinger and Bonaparte, and *R. calcarata* of Michahelles, the last three of which certainly cannot be retained. It

---

[1] Lister, On the Cutaneous Pigmentary System of the Frog. Phil. Trans., 1857, p. 627.

[2] Agassiz et Vogt, Histoire naturelle des poissons d'eau douce (Neuchatel, 1839), Pl. IV, mention that the colour of trout is very variable and that in shaded and deep-lying brooks and rivers a variety is found which is black.

is not improbable that the water-frog, which Spallanzani[1] used in his experiments on impregnation, was the *R. maritima* of Risso. He says, one must not confound his frog with that which Rösel calls the green water-frog; the former being much smaller, without the three dorsal golden-yellow stripes, and the spawning season (in Lombardy) occurring during April and May. Rusconi[2] also describes two varieties in Northern Italy.

Rana temporaria, L., the brown or grass-frog, is so named from the large black patch in the temporal region, *i.e.* between the eye and the shoulder. While the separation of the preceding species into several varieties does not seem to be well founded, it appears that two distinct species have been included under the name of *R. temporaria*. Millet of Angers[3] first described, in his Fauna du département de Maine-et-Loire, as 'grenouille rousse,' a species differing from *R. temporaria*, and gave the species previously known as *R. temporaria* the name of *R. flaviventris*, 'grenouille à ventre jaune.' No further notice, however, was taken of this observation, not even by Duméril and Bibron in their 'Erpétologie.' Quite independently Steenstrup[4], in the year 1846, pointed out that two frogs, differing in structure and habits, had been confounded under the name *R. temporaria*; these he distinguished as *R. platyrhinus* and *R. oxyrhinus*. Von Siebold[5], and also Schiff[6] in part, have confirmed these statements. My own observations lead me to a like conclusion; I shall therefore distinguish two species, viz.:—(1) *Rana temporaria*, L., *Rana platyrhinus*, Steenstrup; (2) *Rana oxyrhinus*, Steenstrup.

Rana temporaria, L.; *Rana platyrhinus*, Steenstrup. The brown grass-frog, Fig. 2, does not attain the dimensions of *R. esculenta*, L., but is, however, always larger than *R. oxyrhinus*. The head is somewhat broader than long, and the upper surface of the skull is not grooved, as in *R. esculenta*, but is flat. The space between the eyes is wider (according to Duméril, equal to the width of the upper eyelid, whereas in *R. esculenta* it is just two-thirds this

---

[1] Spallanzani, Versuche über Erzeugung der Thiere und Pflanzen. Leipzig, 1786, p. 5.

[2] Rusconi, Développ. de la Grenouille. Milan, 1826, p. 6.

[3] Annales des Sciences naturelles. Zoologie, IV Série, Vol. IV, 1855, p. 368.

[4] Amtl. Bericht über die 24. Versammlung deutscher Naturforscher in Kiel, 1846, p. 141 ; Wiegmann's Archiv, 1847, Vol. II, p. 341 ; Steenstrup, Oversigt K. Danske Selsk. Forhandlgr., 1846, p. 92.

[5] Wiegmann's Archiv, 1852, Vol. I, p. 14.

[6] Annales des Sciences naturelles. Zoologie, IV Série, Vol. IV, 1885, p. 368.

width): the fronto-parietal bones are wide and flat. The tympanic membrane, in comparison with the eye, is smaller than in *R. esculenta*, and is usually less distinguishable from the surrounding parts as regards colour and transparency. The apertures of the Eustachian tubes are, relatively to the posterior nares, larger than in the water-frog. The vomerine teeth are comparatively small and lie in two groups placed obliquely to each other, their anterior ends diverging from each other and being prolonged as ridges to the anterior margins of the posterior nares. The two groups do not lie between

Fig. 2.

The brown grass-frog, *Rana temporaria*, L.

the nasal apertures, but behind a line drawn transversely through their posterior margins. Vocal sacs are absent in both sexes. The hind legs are relatively shorter: the toes are not so evenly tapered off, indeed they are slightly swollen: the fourth toe, as compared with the third and fifth, is somewhat longer than in *R. esculenta*; the web of this toe does not extend to the tip of the toe, but terminates in both sexes at the last phalanx but one; the web on the third toe is less developed on the thumb side than on the other: on the remaining toes also the margins of the web

are less developed than in *R. esculenta*, so that the free borders appear more crescentic. The supplemental toe forms only a soft and inconspicuous prominence. The back is mostly smooth; the raised glandular ridge, which extends along each side from the eye to the thigh, is present, but is much narrower and less prominent than in *R. esculenta*; another ridge passes from the angle of the mouth to the shoulder. The colouring in general, and especially the ground colour of the dorsal surface, varies from the brightest tints to the darkest brown-black; the conditions causing these variations being, no doubt, the same as those described above in *R. esculenta*. A dark-brown specimen taken from a dark frog-tank is usually yellowish red on the following day. The black patch between the angle of the mouth and the shoulder has given this species the name of *R. temporaria*, and is constant. A black stripe passes from the eye across the nostril to the tip of the snout, and a similar one is found upon the anterior surface of the upper arm. On the hind legs the bands are chiefly transverse. The ventral surface is yellowish, and sometimes spotted. The thighs have a granular appearance, and these as well as the belly and the neighbourhood of the anus have frequently a reddish coloration presenting the appearance of an irritated surface.

Rana oxyrhinus, Steenstrup. This species is always smaller and more elegant in shape than the preceding one. The head is conical, with the pointed snout projecting beyond the lower jaw; a feature which is especially evident on looking from below. The space between the eyes is narrower than in *R. temporaria*, and is not grooved, but convex; the fronto-parietal bones are narrow and arched. With respect to the arrangement of the vomerine teeth and the sizes of the apertures of the Eustachian tubes, this species holds an intermediate position between the other two. Next to the pointed snout, the greatest difference between this species and *R. temporaria* is the presence of a much larger supplemental toe, which is of cartilaginous hardness, compressed from side to side, and contains a larger bone[1]. The vocal sacs are absent. In the males the web of the longest toe reaches to the last phalanx but one; in the females, on the contrary, the last three phalanges project freely beyond the web. The extremities of the toes are more pointed than in *R. temporaria*, in which respect, as also in several

[1] According to Steenstrup, *l. c.*, the size of the supplemental toe is in *R. temporaria* one-half and in *R. oxyrhinus* two-thirds of that of the next toe.

others, it approaches *R. esculenta.* In colouring, *R. oxyrhinus* resembles *R. temporaria*; the throat, however, is usually pure white, at least in the males, the breast dusky white and spotted, while in *R. temporaria* the throat and breast are more uniformly coloured and yellowish. V. Siebold has remarked that, during the pairing-season, the males are covered with a bluish bloom[1]; and, the whole ground colour being bright at this period, very beautiful tints result. V. Siebold[2] moreover states that the note which the males produce during the pairing-season is different in the two species. On the whole, *R. oxyrhinus* appears to stand midway between *R. esculenta* and *R. temporaria.*

Thomas[3], in addition, distinguishes another species, *R. agilis,* which however may be the 'grenouille rousse' of Millet. Schlotthauber[4] has described a frog which, in marking and colouring, might hold a middle place between *R. esculenta* and *R. temporaria*; in my opinion this is probably a cross between the two. That attempts at copulation are made, despite the difference of the pairing-season, is well known; Pontallié[5] mentions this, and I have myself often found males of *R. temporaria* in conjunction with females of *R. esculenta.*

I use the following terminology. I suppose the animal to be in its natural position, the belly towards the ground, the back upwards; a horizontal plane passing from the snout to the anus divides the body into a superior or dorsal half and an inferior or ventral half. The terms superior and inferior, dorsal and ventral, indicate positions with relation to this plane. I call that part anterior which looks towards the head, and that posterior which looks towards the anus. A vertical plane at right angles to the middle of the longitudinal axis of the body, divides it into an anterior or cephalic and a posterior or caudal half. All sections and planes which lie parallel to this, as well as this itself, are frontal. Lastly, by a perpendicular section along the middle line of the body the animal is divided into right and left halves; this plane is the median plane; and the position relative to this plane is expressed by the terms median or lateral. Planes parallel to the median plane are termed sagittal.

[1] I do not find, however, that this disappears when the animals are on land; in fact I have animals before me in a glass in which it is plainly seen.

[2] *l. c.*, p. 15.

[3] Annales des Sciences naturelles. Zoologie, IV Série, Vol. IV, 1855.

[4] Wiegmann's Archiv, Vol. I, 1844, p. 255.

[5] Annales des Sciences naturelles. Zoologie, III Série, Vol. XVIII, 1852, p. 243.

SECTION I.

THE BONES AND JOINTS.

THE BONES AND JOINTS.

LITERATURE.

van Altena, Commentatio ad quæst. zoologicam in academia Lugduno-Batav. a. MDCCCXXVIII propositam, qua desideratur ut systematice enumerentur species indigenæ reptilium ex ordine batrachiorum addita unius saltem speciei anatomia et præsertim osteographia accurata. Lugd. Bat. 1829. 4°. With 4 Plates.

Ange, Martin St., Recherches sur les organes transitoires des batraciens. Annales des Sciences naturelles. 1re Série. Vol. XXIV. 1831.

Bell, Article Amphibia, in Todd's Cyclopaedia of Anatomy and Physiology. Vol. I, p. 90. 1835–1836.

Born, Dr. Gustav, Ue. d. Nasenholen u. d. Thränennasengang der Amphibien. Leipzig, 1877.

Bruch, G., Beiträge zur Naturgeschichte und Klassification der nackten Amphibien. Würzburger Naturzeitschrift, 1862.

Bruch, G., Neue Beobachtungen zur Naturgeschichte der einheimischen Batrachier. Würzburger Naturzeitschrift, 1863.

Cuvier, Recherches sur les ossements fossiles. Vol. V. Pt. II. Paris, 1825.

Cuvier, Leçons d'anatomie comparée. Paris, 1835. Vol. I.

Cuvier, Ueber die Rückenwirbel der Reptilien und Amphibien, Froriep's Notizen. Vol. XIII, p. 74. 1826.

Daudin, Histoire naturelle des Rainettes, Grenouilles et des Crapauds. Paris, 1802.

Ducrotay de Blainville, Ostéographie ou description iconographique comparée du squelette et du système dentaire des cinq classes d'animaux vertébrés. Paris, 1841.

Dugès, Recherches sur l'ostéologie et la myologie des batraciens à leurs différents âges. Paris, 1834. 4°. With 20 Plates.

Duméril et Bibron, Erpétologie générale ou Histoire complète des Reptiles. 1836.

Gegenbaur: 1. Ueber Bau und Entwicklung der Wirbelsäule bei Amphibien überhaupt und beim Frosche insbesondere. Abhandlungen der naturforschenden Gesellschaft zu Halle, Vol. VI. Halle, 1861.

2. Untersuchungen zur vergl. Anatomie der Wirbelsäule bei Reptilien und Amphibien. Pt. I. Leipzig, 1862. (Carpus and Tarsus.) With 4 Plates. 4°.

Gegenbaur, Untersuchungen zur vergl. Anatomie der Wirbelthiere. Pt. II. Schultergürtel. 1865.

Günther, Ueber geschlechtliche Differenzen in Knochen von lebenden und fossilen Fröschen und Fischen. Annals of Natural History. 1859. Vol. III.

Hallmann, Die vergleichende Osteologie des Schläfenbeins, etc. Hannover, 1837. 4°. With 3 Plates.

Hoffmann, C. K., Beiträge zur Erkenntniss des Beckens der Amphibien und Reptilien. Leyden, 1876.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs, Vol. VI. Amphibien. Leipzig, 1873-8.

Huxley, On the Theory of the Vertebrate Skull; Croonian Lecture, Proc. Royal Society, p. 381. 1858.

Huxley, Article Amphibia, Encyclopaedia Britannica, IXth Edition. 1875.

Huxley, Lectures on the Elements of Comparative Anatomy.

Huxley, Handbuch der Anatomie der Wirbelthiere. Deutsche Ausg. von T. Ratzel. 1873.

Kehrer, G., Beiträge zur Kenntniss d. Carpus und Tarsus d. Amphibien, Reptilien, und Säuger. Berichte d. naturf. Gesell. z. Freiburg. 1886.

v. Klein, Beiträge zur Anatomie der ungeschwänzten Batrachier. Jahres-Heft. Würtemberg, 1850.

Köstlin, Der Bau des knöchernen Kopfs. Stuttgart, 1844. 8°.

Leukart, Zwischenkiefer. Valentins Repertoire. 1841, p. 155.

Marshall, A. M., The Frog. Manchester and London. 2nd Edit., 1885, pp. 45–59.

Mayer, A. F., Beiträge zu einer anatomischen Monographie der Rana pipa. Acad. Caes. Leop. Nov. Acta. 1825. Vol. XII, p. 527 ; and Isis v. L. Oken. 1825. col. 317.

Meckel, System der vergleichenden Anatomie. II. Thl. I. Abthlg. Halle, 1824. 8°.

Meckel, Ueber das Zungenbein der Amphibien. Meckel's Arch. f. Physik. 1818. Vol. IV, p. 60.

Mertens, Anatomiæ batrachiorum prodromus sistens observationes nonnullas in osteologiam batrachiorum nostratium. Halæ, 1820. 8°.

Mivart, On the Classification of the Anurous Batrachians. Proc. Zool. Soc. 1869.

Morren, Observations ostéologiques sur l'appareil costal des batraciens. Bulletins de l'Acad. de Bruxelles, 1835, II.—Mémoires de l'Académie, 1837. Tome X.

Müller, Beitrag zur Anat. d. Amph. Zeitschrift f. wissenschaftliche Zoologie. Vol. IX. 1858, p. 178.

Parker, W. K., Structure and Development of the skull of the common frog. Phil. Trans. 1871, p. 137.

Parker, W. K., Skull of Batrachia. Phil. Trans. 1876, p. 601.

Parker, W. K., and Bettany, G. T., Morphology of the Skull. London, 1877.

Pouchet, Note sur les différences que le sexe imprime au squelette des grenouilles. Comptes rendus. Vol. XXV, p. 761. 1847.

Reichert, K. B., Vergleichende Entwicklungsgeschichte des Kopfs der nackten Amphibien nebst den Bildungsgesetzen des Wirbelthierkopfs im Allgemeinen und seinen hauptsächlichen Variationen durch die einzelne Wirbelthier-Classe. Königsberg, 1838.

Remak, Untersuchungen über die Entwicklung der Wirbelthiere. Berlin, 1855.

Rösel, von Rosenhof, Historia naturalis ranarum nostratium. Nörnberg, 1758.

Rudolphi and Breyer, Observationes anatomicae circa fabricam Ranae pipae. Berolini, 1811.

Rusconi, Développement de la grenouille commune. Milan, 1826.

Rusconi, Sulle metamorfosi delle osse della testa della rana. Annali di Bologna. 1re Série, Vol. II, p. 357.

Schneider, Historia amphibiorum. Jenae, 1799.

Shaw, General Zoology. London. Vol. II, Pt. I, p. 167.

Stannius, Zootomie der Amphibien (Handb. der Zootomie der Wirbelthiere, 2. Buch). 2nd Edit. Berlin, 1856. 8°.

Stricker, Untersuchungen über die Entwicklung des Kopfes der Batrachier. Arch. f. Anat. u. Physiol. 1864, pp. 52–76.

Stricker, Beiträge zur Biologie der Batrachier. Verhandl. der Wiener Akademie. 1866. Vol. XVI, pp. 451–456.

Townson, R., Facts and Observations in Natural History. London, 1799.

Troya, Mémoire sur la structure singulière du tibia et du cubitus des grenouilles et des crapauds. Mémoires de mathématique et de physique présentées à l'acad. de Paris. Vol. IX. 1780.

Wagner, Icones Zootomicae. Leipzig, 1841.

Wagner, Lehrbuch der vergleichenden Anatomie. Leipzig, 1834–1835.

Wiedersheim, R., Lehrbuch d. vergleichenden Anatomie der Wirbelthiere auf Grundlage d. Entwickelungsgeschichte. Jena, 1886. 2nd Edit.

Wiedersheim, R., Elements of Comparative Anatomy of Vertebrates, translated by W. Newton Parker. London, 1886.

THE BONES AND JOINTS.

THE consideration of the differences in form, number, and histological structure, which the parts of the skeleton present during the various stages of development does not fall within the scope of this book : we have here but to deal with the adult frog.

The skeleton is made up of histologically different materials; these are :—(1) bone, (2) hyaline cartilage, and (3) so-called calcified cartilage. Concerning the last it is necessary to make some observations. I have chosen for it the name calcified cartilage in place of the more usual names 'cartilaginous bone' or 'primordial ossification,' as by this term its nature appears to be expressed without any ambiguity [1]: it is hyaline cartilage in which calcareous particles have been deposited to a greater or less extent : in the fresh state it has the appearance of moderately firm cartilage; when dry it becomes opaque and white, like the calcareous crusts on the cartilages of the Plagiostomata. The calcareous material is deposited in the cartilage in finer or coarser granules; after removal of the lime by means of acids, the cartilaginous structure becomes apparent although not so perfectly as in unchanged cartilage.

This calcified cartilage is widely distributed in the frog's skeleton : very many parts, which in higher animals consist only temporarily of this substance during the transition from cartilage to bone, are in the frog formed of it throughout life. It is especially well-marked in the epiphyses of the long bones in the hand and foot, in the bones of the shoulder-girdle, etc. To avoid repetition later on I will briefly describe it as found in the first-mentioned situation. Dugès [2] has described its external appearance, while Bruch [3] has made us

---

[1] Compare Müller, Zeit. f. wissen. Zoolog., Vol. IX.

[2] Dugès, Recherches sur l'ostéologie et la myologie des batraciens à leurs différents âges, p. 116.

[3] Bruch, Beiträge zur Entwicklungsgeschichte des Knochensystems. Schweiz. Denkschriften, p. 118.

acquainted with its histological peculiarities.   If a long bone of the frog be dried, the femur for example, the middle part is found to

Fig. 3.

differ considerably from the epiphyses in colour and in other particulars.   The shaft alone has the appearance of bone, the epiphysis consisting of a white, opaque, firm substance, resembling plaster of Paris or lime, but which in the fresh moist state is exactly like cartilage.   The epiphyses, which are fitted to the ends of the diaphysis like the cap of a stick-handle, have sharply defined margins (Fig. 3), as is well seen in Figs. 36, 39, 45, and 46.   If a section be made through the epiphysis and part of the diaphysis, the long tube of true bone is seen to cease abruptly above *o*, Fig. 3, and over the end of it the epiphysis *E* is fixed.   This epiphysis consists almost entirely of calcified cartilage *c'*, and has merely a superficial layer of hyaline cartilage *A*.   The bony cylinder of the diaphysis *o*, which contains the marrow *M* in its interior, is shut off from the epiphysis by hyaline cartilage, the cells of which are arranged in transverse layers, *o*.

Longitudinal section through the upper extremity of the femur of *Rana esculenta*, magnified.

A Hyaline cartilage (articular cartilage).
c Hyaline cartilage closing end of bony cylinder.
c' Calcified cartilage of epiphysis.
D Bony cylinder of diaphysis.
E Epiphysis.
M Marrow cavity.
o End of diaphysis.

I.   THE VERTEBRAL COLUMN.

The *vertebral column* of the frog consists of ten bones, *viz.* nine true vertebrae, and the rod-shaped urostyle, which alone is almost as long as all the remaining vertebrae.

I.   GENERAL DESCRIPTION OF THE NINE VERTEBRAE.

a. The *bodies* of the vertebrae are compressed from above downwards; the posterior surface of each body, with the exception of

the eighth, presents an articular head covered with cartilage ; the anterior surfaces, with the exception of the ninth, present corresponding articular depressions, covered with cartilage.

b. The *arches*, which have somewhat sharp margins both before and behind, bear the following processes :—

1. The **articular processes** (Figs. 4 and 5 *o o*) are similarly placed to those of the dorsal vertebrae of man : they project horizontally, the cartilaginous articular surfaces on the posterior processes being directed downwards, those on the anterior upwards.

2. The **transverse processes** (Figs. 4 and 5 *t t'*) are strong, flat, and of very varying size and direction. The transverse processes of the fourth vertebra are the longest, those of the third only a little shorter; the shortest are those of the seventh and eighth. The atlas has no transverse processes. Those of the second and third vertebrae project directly outwards and slightly downwards; those of the fourth, fifth, and sixth upwards and backwards. The seventh and eighth project more directly outwards and at the same time backwards; the ninth upwards and markedly backwards. All the transverse processes have cartilaginous epiphyses; the largest are those of the second, third, fourth, and ninth vertebrae.

3. The **spinous processes** are generally small, but individually of varying size, appearance, and direction. The longest are those of the third, fourth, and fifth vertebrae;

Fig. 4.

Vertebrae of *Rana esculenta*, seen from below, twice the natural size.

1 to 9 First to ninth vertebrae.
c Urostyle.
o o Articular processes.
sc The two facets for articulation with the urostyle.

these are, in transverse section, of a three-sided prismatic form, as

C

in the dorsal vertebrae of man; they are directed backwards and provided with cartilaginous epiphyses. The spinous processes of the sixth and seventh are shorter, compressed from side to side, project directly upwards, and are usually without cartilaginous epiphyses; that of the eighth is still shorter. As regards the spinous processes, those of the third, fourth, and fifth vertebrae resemble those of the dorsal vertebrae in man; those of the sixth, seventh, and eighth, lumbar vertebrae. The ninth has either no spinous process or only a rudimentary one. The first and second vertebrae may be looked upon as cervical vertebrae: the second has a short spinous process with a cartilaginous epiphysis. In the first, the cartilage which unites the two halves of the arch represents the rudiment of a spinous process.

Fig. 5.

Vertebral column of *Rana esculenta*, from above, twice nat. size.

1 to 9 First to ninth vertebræ.
c Urostyle.
o o Articular processes.
sc Facets for articulation with the urostyle.
t t' Transverse processes.

II. Description of Particular Vertebræ.

1. The **atlas** or **first vertebra** has a thin body, compressed from above downwards, and an arch. The body has posteriorly a slightly raised, cartilaginous, articular head, which is broader transversely: in front it has two oval articular facets, which are separated from each other by a median projection. Each facet is concave, and directed forwards, outwards, and slightly upwards. The arch is completed above by cartilage, which projects slightly to form the rudiment of a spinous process. The hinder margin of the arch bears two articular processes. Transverse processes are wanting.

2. The **second vertebra** presents all the general characters of an

ordinary vertebra, except that the transverse processes are directed somewhat downwards.

3. The transverse processes of the **third vertebra** are longer than those of the second : each is directed downwards, is broader at its extremity than at its base, and bears a hammer-shaped cartilaginous epiphysis larger than those of the remaining transverse processes.

4. The transverse processes of the **fourth vertebra** are the longest : each is broader at its free end than at its base, is directed upwards and backwards, and provided with a cartilaginous epiphysis.

5, 6, 7. The transverse processes of the **fifth, sixth, and seventh vertebrae** are smaller, contracted towards their free extremities, and directed upwards.

8. The **eighth vertebra** is distinguished from the rest by its body possessing no articular head. It presents, at each end, a concave articular depression. The transverse processes resemble those of the seventh.

9. The **ninth vertebra** unites the vertebral column with the hip-bones, and is hence to be regarded as a **sacrum**. The body bears on its anterior surface an articular head for articulation with the eighth vertebra: on its posterior surface are two small rounded and closely approximated processes (Figs. 4 and 5 *sc*) for articulation with the urostyle. The transverse processes are strong, broader at the free ends than at their origin, directed upwards and backwards, and provided with cartilaginous epiphyses.

III. Articulations of the Vertebrae.

The articular heads and depressions of the vertebral bodies, together with the joint surfaces of the articular processes, are covered with hyaline cartilage. The periosteum of the bodies, as also that of the articular processes, forms true capsular joint ligaments. The articulations of the vertebrae are still further strengthened by longitudinal fibres, which extend along the anterior and posterior surfaces of the vertebrae, and correspond to the *ligamentum vertebrale commune anticum et posticum* of man. Between the vertebral arches are membranes which represent the *ligamenta intercruralia*. Between the spinous processes are bands of connective tissue which form *ligamenta interspinalia*. (For the articulation of the atlas with the occiput, see page 24.)

IV. Structure of the Vertebrae [1] (Figs. 6 and 7).

Each vertebral body consists of a cylinder of compact bone, which is directly continued into the bony substance of the arch. In the interior of the cylinder is found an isolated persistent vestige of the *chorda dorsalis* (*Ch*): this is surrounded by cancellous bone (*c*), which extends backwards towards the articular head and forwards directly into the articular cartilage, compact bone being absent in these parts. In a transverse section of a vertebral body the following parts are seen (Fig. 6):—a. An outer layer of compact bone (*o*) (the transverse section of the above-mentioned cylinder), which is formed of parallel lamellae of varying thickness. These, according to Gegenbaur, and as I can confirm, are arranged in well-defined groups, each of five to eight lamellae. The number of the secondary lamellae increases with the age of the animal. b. In the interior, in the form of a cylinder, is the remnant of the *chorda dorsalis*. It consists of a double sheath (*Ch'*) and contents (*Ch*) composed of chorda-cells. c. Immediately around the persistent portion of the chorda lies the central part of the vertebral body, formed by transformation of the vertebral cartilage and of the bases of the original cartilaginous arches. At each side of the *chorda* are large marrow-spaces (*c*), filled with cells, from which proceed narrower canals, winding in various directions, and anastomosing freely with one another both before and behind. Their walls are constituted partly of true bone, partly of cartilage.

Fig. 6.

Transverse section through a vertebra of *Rana esculenta*, magnified.

c   Cancellous bone.
Ch Chorda dorsalis.
Ch' Sheath of chorda dorsalis.
o　Compact bone on the upper and lower surfaces of the body.

Fig. 7.

Longitudinal section through the posterior half of the body of a vertebra of *Rana esculenta*.

a   Cartilage of the head.
c   Cancellous bone.
o   Shell of compact bone.

[1] Cf. Gegenbaur, (1) Über Bau u. Entwicklung der Wirbelsäule bei Amphibien überhaupt u. beim Frosch insbesondere. Abhand. d. Naturforsch. Gesell. zu Halle, vol. vi, 1861 ; (2) Untersuch. zur vergleich. Anat. d. Wirbelsäule bei Amphibien u. Rept., Leipzig, 1862. As regards the adult animal I can bear out Gegenbaur's observations. The scope and limits of this book forbid me to go further into the developmental history.

V. THE UROSTYLE (Figs. 8 and 9).

The **urostyle** is a long, median, rod-like bone, which projects backwards, midway between the two hip-bones, and terminates over the anus. The anterior end (Fig. 8 *a*) is the thicker and broader part of the bone, and has two articular depressions (Fig. 9) for articulation with the two facets of the ninth vertebra. The hinder end is pointed and cylindrical, and terminates in a cartilage, which is fixed in the tubular end of the bone. The middle portion is almost cylindrical, and has a groove along the ventral surface which gradually becomes less marked behind. The dorsal surface bears a ridge (Figs. 8 and 9 *s*), which is high and thick in front, becomes sharper and less prominent as it proceeds backwards, and gradually disappears towards the hinder third of the bone, so that in transverse section the anterior two-thirds of the bone appear triangular, with a ventral and two lateral surfaces: while the hinder third is cylindrical. The anterior portion of the bone contains a canal, *canalis vertebralis* (Fig. 9 *c.v.*), which is a continuation of the vertebral canal, along which the hindermost spinal nerves pass. On each side of the anterior portion of the urostyle are small apertures (Fig. 8 *c.c.*), which lead into canals (*canales coccygei*), which open into the vertebral canal, and through which the coccygeal nerves pass. In front of these openings and partly overhanging them are small triangular projections (Fig. 8) (*processus transversarii*): these, however, are not constant, and are more often found in *R. esculenta* than in *R. temporaria*, in which latter species the openings are smaller.

Fig. 9.

Urostyle of *Rana esculenta*, seen from the side, twice nat. size.

c Ventral border.
c.v. Canal. verte-bralis.
s Dorsal ridge (pr. spinos.).

Fig. 8.

Urostyle of *Rana esculenta*, seen from the side, twice nat. size. A bristle is passed through the *canal. vert.* and out through the *canal. coccyg.* of the right side.

a Anterior extremity.
c.c. Canal. coccyg.
s Dorsal ridge (pr. spinos.).

II. THE SKULL.

The flat form of the frog's head, as in batrachians generally, depends upon the wide separation of the jaw-bones of the two sides, and on the large size of the orbital cavities and the horizontal

direction of their floors. The outer circumference of the head forms a parabolic frame (Figs. 10 and 11), composed of the maxillary (*m*), premaxillary (*i*), and quadratojugal bones (*j*). In the middle of this curved framework lies the elongated prismatic cranium. Anteriorly, this is attached to the fore-part of the frame by means of the cartilaginous skeleton of the organs of smell (Fig. 11 *e'*); posteriorly, it widens out into two transverse arms (*p*), which contain the organs of hearing. From this base, on either side, a bony strut, composed of the posterior arms of the squamosal (*t'*) and of the pterygoid bones, passes backwards to the hinder end

Fig. 10.   Fig. 11.

Skull of *Rana esculenta*, seen from above,
twice natural size.

- *e* Sphenethmoid.
- *fn* Nasal.
- *f.p.* Fronto-parietal.
- *i* Premaxillary.
- *j* Quadrato-jugal.
- *m* Maxillary.
- *o* Exoccipital.
- *op* Opisthotic.
- *p* Prootic.
- *pt* Pterygoid.
- *pt'* Posterior limb of pterygoid.
- *t* Squamosal.
- *t'* Posterior arm of the same.

Skull of *Rana esculenta*, seen from below,
twice natural size.

- *c* Cartilaginous wall of skull.
- *e* Sphenethmoid.
- *e'* Cartilaginous skeleton of nose.
- *h'* Stylo-hyoid.
- *i* Premaxillary.
- *m* Maxillary.
- *m'* Quadrate tract.
- *o* Exoccipital.
- *p* Prootic.
- *p'* Anterior arm of prootic (*ala magna* autt.).
- *p''* Trigeminal foramen.
- *pl* Palatine.
- *pt* Pterygoid.
- *pt'* Posterior arm of pterygoid.
- *s* Parasphenoid.
- *v* Vomer.

of the frame. The anterior arm of the squamosal bone (*t*) does not quite reach the framework, but is attached to it by ligament alone. Between the last-named arm posteriorly, the cranium on the inner side, and the maxillary frame-work laterally, is a large space representing the orbital and temporal fossae of human anatomy.

A. THE CRANIUM.

The cranium of the frog is a prismatic tube, wide behind, narrow in front, and formed in great part of cartilage (Figs. 15 and 17). Our indigenous species are characteristically distinguished from one another by peculiarities in the form of the cranium. In *R. esculenta* it is long and narrow, in *R. temporaria* short and wide. The superior surface in the former is markedly concave, while in the latter it is flat, and in *R. oxyrhinus* arched. These differences are readily recognised in the living animal.

The Bones of the Cranium.

1. The **exoccipital bones**, *ossa occipitalia lateralia*, Cuvier (Figs. 10, 11, 12, 14, 16 *o*).

Cuvier, *l.c.*, p. 387, Pl. XXIV, bb.—Dugès, *l.c.*, n. 14.—Parker and Bettany, *l.c.*, p. 166, exoccipitals.

These paired bones form the hinder part of the cranium; they bound the *foramen magnum*, and articulate with the vertebral column. They are imbedded in the cartilaginous matrix of the skull, and are separated above by an unossified part of this matrix (*occipitale superius*, Dugès), which represents the tabular portion of human anatomy: below they are separated by a similar part (*occipitale basilare*, Dugès) which represents the body of the occipital bone. They therefore properly represent only the condylar portions (*partes condyloideae*) of the human occipital

Fig. 12.

Skull of *Rana esculenta*, seen from behind, twice natural size.

a   Stapes.
a'   Columella auris.
a'' Extrastapedial.
c   Condyles of exoccipitals.
h   Stylo-hyoid.
o   Exoccipitals.
p   Prootic.
p'   Process to which the jaw is attached.
t   Squamosal.

bone. Each possesses a cartilaginous articular head, for articulation with the first vertebra: these converge below, and surround the lower half of the circumference of the *foramen magnum*. This latter has, in *R. esculenta*, a transversely oval outline; in *R. temporaria*, a somewhat heart-shaped outline, with the apex directed upwards: in accordance with this the whole bone is wider than high in the first species; and in the latter it is higher than it is wide. From the upper and outer border of the *foramen magnum* on each side

a ridge runs obliquely outwards and downwards, in which lies
the suture between this bone and the prootic bones. This bony
ridge (*processus mastoideus*, autt.) is usually cartilaginous in *R. escu-
lenta*, even in old animals; in *R. temporaria*, even in young speci-
mens, it is bony. In the latter species the bones unite very early,
while in the former they remain separated by the primitive carti-
lage. Between this crest and the *processus condyloideus* there is a
depression (*fossa condyloidea*), with a hole (*foramen condyloideum*)
through which the vagus nerve leaves the cranium. The exoccipital
take part in the formation of the labyrinth of the ear, as will be
noticed later on.

Articulation of the Exoccipital Bones with the Atlas. From the
middle of the anterior surface of the body of the atlas a ligament
arises, representing to a certain extent the *lig. suspensorium dentis*,
and attached to the basal portions of the exoccipital bones.

2. The prootic bones, *ossa petrosa*, Cuvier (Figs. 10, 11, and
12 *p*).

> Cuvier, rocher, *l. c.*, p. 388, Pl. XXIV, ee.—Dugès, n. 12, rupéo-ptéréal.
> —Stannius, ala temporalis.— Meckel, Schädelstück des Schlä-
> fenbeins.—Parker and Bettany, *l. c.*, prootic.

These paired bones lie at the sides and in front of the exoccipital
bones. As already explained, they remain in *R. esculenta* separated
from these by cartilage, while in *R. temporaria* they early enter into
bony union with them; this is due to the complete ossification of
the *processus mastoideus* in the latter species, as stated above. The
prootics form the lateral expansions of the posterior part of the
skull in which the organs of hearing are placed. The large cavity
which contains the ear labyrinth is completed by the exoccipital:
internally it opens freely into the skull, and externally on the
posterior wall of the skull through the *foramen ovale*, which is
formed by both these bones. The postero-lateral part of the prootic
usually remains cartilaginous: at the side and in front of the
foramen ovale this cartilage is pierced by a small opening, through
which passes the *nervus facialis* or *ramus tympanicus n. vagi* (Volk-
mann). At the side there is a process to which the suspensorium
of the lower jaw is attached (Fig. 12 *p*): behind this is a hollow in
which the auditory ossicles lie, and which may be designated *fossa
tympanica* (Fig. 12 *t*). The anterior border of the bone forms the

hinder and inner walls of the orbit. Here also is the trigeminal foramen (Fig. 11 *p″*) through which the *N. trigeminus* and the several nerves for the muscles of the eye pass; it represents the *foramen ovale, for. rotundum,* and the *fissura orbitalis superior* (sphenoidal fissure) of the human sphenoid bone. The foramen is sometimes, especially in young animals, only a notch, which is completed by cartilage. On account of the relation of this part (Fig. 11 *p′*) of the bone to the nerves which pierce it, the whole bone has been named by Stannius the *ala magna* or *temporalis* of the sphenoid; it has been also looked upon as a bone which contains these elements, as by Dugès, who on this account calls it rupéo-ptéréal.

Fig. 13.

Skull of *Rana esculenta*, seen from below, twice natural size.

c	Cartilaginous wall of skull.
e	Sphenethmoid.
e′	Cartilaginous nasal skeleton.
h′	Stylo-hyoid.
i	Premaxillary.
m	Maxillary.
m′	Quadrate tract.
o	Exoccipital.
p	Prootic.
p′	Anterior arm of prootic.
p″	Trigeminal foramen.
pl	Palatine.
pt	Anterior arm of pterygoid.
pt	Posterior arm of pterygoid.
s	Parasphenoid.
v	Vomer.

Appendages of the Prootic Bones.

1. The **styloid cartilage.** From the cartilaginous portion of the prootic the styloid cartilage runs downwards, backwards, and inwards, and is continued directly into the anterior cornu of the hyoid bone (Figs. 11 *h′* and 12 *h*).

2. The **auditory ossicles.**

a. A thick cartilaginous disc, the *operculum* (Fig. 12 *a*), closes the *foramen ovale.*

b. To the *operculum* is attached a bony, club-shaped piece, the *columella auris* (Fig. 12 *a′*), which has at its inner, thicker end a cartilaginous epiphysis, the **interstapedial**; it lies transversely with the apex directed outwards, and this longer portion is the **mediostapedial.**

c. To the apex of the mediostapedial is attached, at an

obtuse angle, the third cartilaginous piece, the **extra-stapedial** (Fig. 12 *a''*). It is attached to the tympanic membrane, and by its upper portion is fastened to the cartilaginous tympanic ring by a smaller piece, the **supra-stapedial**.

3. The **tympanic ring** (*annulus tympanicus*) is an annular cartilaginous frame; or more exactly, has the shape of a short, truncated cone, as it narrows towards the middle line : it is attached to the squamosal bone. (See Organ of hearing.)

3. The **parasphenoid**, *os sphenoideum*, Cuvier (Figs. 11 and 16 *s*).

Cuvier, *l.c.*, p. 388, Pl. XXIV, d.—Dugès, n. 8.—Meckel, Theil des Grundbeins.—Parker and Bettany, *l.c.*, parasphenoid.

A large portion of the base of the cranium is taken up by this cruciform bone. Of the two longitudinal median processes, the posterior is by far the shorter, and lies in front of and partly below the cartilaginous *os occipitale basilare*. The anterior longer longitudinal arm closes in the greater part of the cranium from below, and articulates by its outer edges with that part of the prootic bones often described as the *alae magnae*, and also with the cartilage lying in front, which forms the greater part of the lateral walls of the cranium. The anterior extremity of the bone articulates with the palatine bones. The transverse arms lie on the under surface of the exoccipitals and of the prootics.

The greater width of the cranium in *R. temporaria* is associated with the greater relative width of the anterior arm of this bone.

4. The **fronto-parietal bones**, *ossa fronto-parietalia*, Cuvier (Figs. 10 and 14 *fp*).

Cuvier, *l.c.*, p. 387, Pl. XXIV, c.c.—Dugès, n. 1.—Parker and Bettany, *l.c.*, fronto-parietal.

These are a pair of somewhat long, flat bones, which form the principal part of the upper wall or roof of the cranium, and cover in superiorly the cartilaginous cranium, which is here, in great part, persistent. They are united in the middle line by the sagittal suture; posteriorly they articulate with the exoccipital and prootic bones ; anteriorly with the sphenethmoid, which they overlap like tiles. The outer margin of each bone is bent somewhat downwards (Fig. 16 *fp*), and between it and the parasphenoid there is a space in the wall of the cranium which is closed in by cartilage and connective tissue only.

These bones are narrower in *R. esculenta,* and along the sagittal suture are depressed into a groove: where the superior surface bends down to become lateral the edges are much more prominent. In *R. temporaria* the bones are broader and flat or even somewhat arched. The latter condition is still more marked in *R. oxyrhinus.*

5. The **sphenethmoid,** *os ethmoideum* (Figs. 10, 11, 14, and 16 *e*).

> Cuvier, os en ceinture, *l. c.,* p. 387, Pl. XXIV, a.—Dugès, n. 15.—**Rathke,** anterior or sphenoidal wing (Vortr. z. vergl. Anat. d. Wirbelthiere, Leipzig, 1862, p. 42).—Meckel, Riechbein, *l. c.,* p. 502.—**Parker** and **Bettany,** *l.c.,* ethmoid.

The long tubular cranium is completed anteriorly by a single bone, which forms at once the roof, floor, and lateral walls. It is consequently more or less ring-shaped, on which account it has been named 'os en ceinture' by Cuvier. Only the posterior portion is annular, however : the anterior portion forms a double canal, with a median partition, for the passage of the nerves of smell, and as these canals are widened out anteriorly, this part of the bone helps to complete the nasal cavities, which, however, are bounded for the most part by cartilage, as described below. In some species of frogs (as for example *R. occellata,* Rathke) this cartilage is partly ossified.

The sphenethmoid has on each side a small bony canal, running forwards and inwards, through which the *ramus nasalis* of the first division of the trigeminal nerve passes.

The **cartilaginous skeleton of the nose** (Figs. 14 and 16 *n, n″, n‴, n″″*). The anterior borders of the funnel-shaped cavities of the sphenethmoid pass into cartilage, which forms two capsules, separated from each other by a median cartilaginous septum, and opening laterally. We can distinguish, (*a*) a cartilaginous septum, forming a continuation of the bony one; (*b*) the floor of the nasal cavity, narrower behind, wider in front ; (*c*) a roof somewhat narrower than the floor. The floor and roof are united in front by an arched surface. From this cartilaginous capsule various processes project, which unite it to other portions of the facial skeleton : firstly, from the most posterior portion of the capsule there passes transversely outwards a bar of cartilage (*sn*), which, widening, becomes continuous with the cartilage (*sp″*) forming the basis of the anterior arm of the pterygoid bone. From the anterior angle a cartilaginous process passes outwards (Figs. 14, 16 *n″*), which is attached to a projection on the

anterior end of the maxillary bone; from the same spot a horn-shaped cartilaginous process (n'', n''') curves round backwards and towards the middle line. This projection bounds the nasal cavity externally, sending off a free process (n''') on the way, and ends with a double point on the roof of the cartilaginous nasal cavity (n''''). On the floor of the nasal capsule, on either side, is a knob-shaped cartilaginous eminence, running from behind, forwards and outwards; this may be regarded as an indication of a turbinated bone. From the anterior wall there passes into each nasal cavity an almost horizontal, partly ossified plate (*c.n.*), ending posteriorly in a free pointed border. These are the *cornets* of Dugès (*l. c.*, p. 12, Pl. I, Figs. 1, 5), who correctly regarded them as turbinated bones. Cuvier described them as rudimentary nasal bones[1].

Fig. 14.

Cartilaginous basis of the skull of *Rana esculenta*, from above, twice natural size. Cartilage shown by stippling.

a.n.	Wings of nasal cartilage.	*p.*	Prootic.
c.n.	Concha narium.	*pt*	Anterior arm of pterygoid.
e	Sphenethmoid.	*pt'*	Posterior arm of pterygoid.
ff'	Foramina of cranium.		goid.
fn	Nasal.	*s'*	Cartilaginous cranium.
fp	Fronto-parietal.	*sp*	Cartilage of suspensorium.
i	Premaxillary.	*sp'*	Cartilage under the squamosal.
j	Quadrato-jugal.		mosal.
m	Maxillary.	*sp''*	Cartilage under the pterygoid.
n,sn	Cartilaginous nasal skeleton.	*s¹*	Anterior
		s²	Middle arm of the
n', *n''*, *n'''*	Processes of the cartilage.	*s³*	Posterior squamosal.
o	Exoccipital bones.		

The alar cartilages of the nose have still to be described. They are (*a.n.*) shell-shaped cartilages, hollowed out on the inner sides and

---

[1] Cuvier (Ossem. fossil., V, 2. 388) says that these little bones are fixed outside the nasal cavity, so that we may suppose that he confounded them with the nasal cartilages found in this situation. Dugès correctly indicates their position to be inside of the nasal capsule. Meckel (Vergl. Anat. II, 504) also regards them as nasal bones. Bruch (Würzb. naturwiss. Zeitschrift, vol. II, 1861, p. 213) could not find them in any frog-skull, doubtless because he did not look inside the nasal capsules.

decreasing in width from before backwards. They are movably attached by their anterior broader ends to the tips of the projecting portions of the premaxillary bones, and are so arranged as to bound the lateral margins of the nasal apertures, which they overlap.

6. The cartilaginous basis of the skull, *Primordial cranium* (Figs. 14, 16).

a. If the fronto-parietals be removed, (Figs. 14, 16), a cartilage (s') is found which partially closes the cranial cavity, and which is usually perforated on either side by a foramen (f'). More anteriorly in the median line is found a space (f) which extends to the sphenethmoid bone, and is only closed by connective tissue : posteriorly the cartilage extends between the exoccipitals as far as the *foramen magnum,* representing the *os occipitale superius.*

b. The base of the cranium is (Fig. 16) also partly cartilaginous. If the parasphenoid (s) be removed we find above it a cartilage (s') which passes backwards between the exoccipitals, and extends as far back as the *foramen magnum*: it corresponds to the *os occipitale basilare.*

c. The sides of the cranium are formed almost entirely of car-

Fig. 15.

Nasal cartilages of frog, front view.

an Concha narium.
i Premaxillary bones.
i' Ascending process of same.
m Upper jaw.
m' Lower jaw.
n Olfactory capsule.

Fig. 16

Cartilaginous skull of *Rana esculenta*, from below, twice natural size. Cartilage shown by stippling.

c Cartilage of prootic.
e Sphenethmoid.
fp Fronto-parietal.
i Premaxillary.
j Quadrato-jugal.
m Maxillary.
n, sn Cartilaginous nasal skele-ton.
n', n'', n''', n'''' Processes of nasal cartilage.
o Exoccipital.
p Prootic.
pl Palatine.

pt Pterygoid.
pt' Articular surface for pterygoid.
r Optic foramen.
r' Foramen for N. abducens.
s Parasphenoid.
s' Cartilaginous cranium.
sp Cartilage of suspensorium.
sp' Cartilage under squa-mosal.
sp'' Cartilage under ptery-goid.
v Vomer.

tilage. This cartilage fills the space bounded by the nasals above, the parasphenoid below, the so-called *ala magna* of the prootic bone behind, and the sphenethmoid in front; and has in its posterior part an aperture (*r*) through which passes the *nervus opticus*, and below this a smaller one (*r'*) for the *nervus abducens*. The extent of the cartilage in the antero-posterior direction is greater in *R. esculenta* than in *R. temporaria*, or in other words the sphenethmoid stretches further back in the latter than in the former.

B. THE BONES OF THE FACE.

Fig. 17.

Cartilaginous basis of the skull of *Rana esculenta*, from above, twice natural size. Cartilage shown by stippling.

a.n. Wings of nasal cartilage.
c.n. Concha narium.
e Sphenethmoid.
ff' Foramina of cranium.
fn Nasal.
fp Fronto-parietal.
i Premaxillary.
j Quadrato-jugal.
m Maxillary.
n,sn Cartilaginous nasal skeleton.
n', n'', n''' Processes of the cartilage.

o Exoccipital bones.
p. Prootic.
pt Anterior arm of pterygoid.
pt' Posterior arm of pterygoid.
s' Cartilaginous cranium.
sp Cartilage of suspensorium.
sp' Cartilage under the squamosal.
sp'' Cartilage under the pterygoid.
t1 Anterior ⎫ arm of the
t2 Middle ⎬ squamosal.
t3 Posterior ⎭

The Suspensorium.

7. The **squamosal** bones, *ossa tympanica*, Cuvier (Figs. 10, 14 *t*).

Cuvier, *oss. foss.*, V, 2. 390, Pl. XXIV, Figs. 1, 2 n.—Dugès, *temporo-mastoidien*, n. 10. — Meckel, Articular part of temporal. — Hall-mann and others, quadrate-bone. — Parker and Bettany, *l.c.*, squamosal.

The suspensorium, which forms the articulation between the cranium and the lower jaw, is ⊤ shaped, and consists of cartilage covered by bone. Of the three arms of the ⊤ the anterior has a free pointed extremity (Fig. 14 *t1*) at the postero-lateral margin of the temporo-orbital fossa; it forms a true *processus zygomaticus*, and is bound to the upper jaw by ligaments. In *R. temporaria* it is comparatively much shorter than in *R. esculenta*. The posterior upper arm (*t2*) articulates with the prootic

bone : the third or lower arm (t^3), supported by a cartilage [1], runs backwards and downwards to unite with the side of the broad hinder extremity of the quadrato-jugal bone.

The cartilaginous basis [1] of the suspensorium (Fig. 17 *sp, sp'*) is a direct continuation of the cartilaginous basis of the cranium, and proceeds from it to the outer extremity of the prootic; from this point the cartilage runs backwards and divides into two branches; of these, one (*sp'*) retains the original course backwards and outwards towards the articulation of the lower jaw, and in conjunction with the quadrato-jugal (*j*) forms this joint. The other (*sp''*) is directed forwards along the anterior arm of the pterygoid bone; it widens in front (*sn*), and becomes directly continuous with the cartilaginous strut described above as projecting from the hinder part of the cartilaginous olfactory capsule.

8. The **quadrato-jugal bones**, *ossa jugalia*, Cuvier (Figs. 10, 17, 19 *j*).

> Dugès, *tympano-malléal*, n. 11.—Cuvier, *l. c.*, p. 399, Pl. XXIV, Figs. 1, 2 o.—Hallmann, quadrato-jugal bone, *l. c.*, p. 39.—Parker and Bettany, *l. c.*, quadrato-jugal.

This is a small process of bone, likened by Dugès to a comma, which rests by its posterior broader extremity on the cartilage of the mandibular arch [1], and forms with it a portion of the articular head for the lower jaw. The anterior extremity is pointed, directed forwards, and attached by ligament to the maxillary bone.

9. The **pterygoid bones**, *ossa pterygoidea* (Figs. 10, 11, 17, 19 *pt*).

> Cuvier, *l. c.*, p. 389, Pl. XXIV, Figs. 1, 2 m m.—Dugès, n. 9.—Parker and Bettany, *l. c.*, pterygoid bones.

These bones, shaped like the Greek letter λ, possess each three arms : of these the middle one is attached to the under surface of the prootic bone by a cartilaginous process (Fig. 18 *sp*); the hinder grooved arm lies upon the under surface of the cartilaginous suspensorial arch (Fig. 18 *sp'*); and the anterior arm (*pt*) runs forwards along the inner border of the anterior ramus of the suspensorium (*sp''*), in contact with the maxillary, palatine, and nasal bones.

The cartilage just mentioned, by means of which the middle arm of the pterygoid is connected with the cranium (compare Fig. 18), proceeds from the cranial origin of the cartilaginous arch (*sp*), turns downwards and then forms a sort of articular head (*cpt*), which is articulated to an oval flat elevation of the prootic cartilage

---

[1] This cartilage is the quadrate cartilage of Parker ; others regard it as the upper end of the cartilaginous mandibular arch, of which Meckel's cartilage is the lower distal part.

Fig. 18.

Origin of the suspensory cartilage (*sp*) from the skull, with attachment of the pterygoid ; front view. Cartilage shown by stippling.

cpt Cartilaginous epiphyses of the pterygoid bone, from the cartilaginous suspensorium.
j Quadrato-jugal bone.
pt Pterygoid bone.
sp Origin of suspensorial cartilage from the skull.
sp′ Hinder arm of same.
sp″ Anterior arm of same.

Fig. 19.

Cartilaginous skull of *Rana esculenta*, from below, twice natural size. Cartilage shown by stippling.

c Cartilage of prootic.
e Sphenethmoid.
fp Fronto-parietal.
i Premaxillary.
j Quadrato-jugal.
m Maxillary.
n,sn Cartilaginous nasal skeleton.
n′, n″, n‴, n⁗ Processes of nasal cartilage.
o Exoccipital.
p Prootic.
pl Palatine.
pt Pterygoid.
pt′ Articular surface for pterygoid.
r Optic foramen.
r′ Foramen for N. abducens.
s Parasphenoid.
s′ Cartilaginous cranium.
sp Cartilage of suspensorium.
sp′ Cartilage under squamosal.
sp″ Cartilage under pterygoid.
v Vomer.

by a movable joint. Externally the articular head curves somewhat abruptly into the bony substance (Fig. 18 *pt*) of the pterygoid bone.

10. The **maxillary bones**, *ossa maxillaria superiora*, Cuvier (Figs. 10, 11, 17, 19 *m*).

Cuvier, *l.c.*, p. 389, Pl. XXIV, Figs. 1, 2 k k. —Dugès, n. 4, *maxillo-jugal.* — Parker and Bettany, *l.c.*, maxillary bones.

These are elongated, curved bones, narrower behind, broader in front, and forming with the quadrato-jugals the bony support of the face. The superior surface is convex and directed outwards, the inferior surface is grooved and bears teeth along the outer edge of this groove. From the upper and inner border of the anterior half of this bone a process (*processus frontalis*) passes upwards, which articulates with the nasal bone. The anterior extremity of the bone articulates with the premaxillary bone, the posterior with the quadrato-jugal.

The maxillary bone articulates at its anterior end (Fig. 19 *n″*) with a process of the cartilaginous capsule of the nose. The broad plate of cartilage (Fig. 19 *n*), under

cover of the *processus frontalis*, connects the hindermost transverse portion of the nasal cartilage with the cartilage which runs forwards from the suspensorium upon the anterior arm of the pterygoid.

11. The **nasal bones**, *ossa fronto-nasalia*, Dugès (Figs. 10, 17 *fn*).

Cuvier, *frontale anterius*, *l. c.*, h.—Dugès, n. 2.—Meckel, nasal bone.— —Parker and Bettany, *l. c.*, nasal bones.

These flat, triangular bones, which rest upon the nasal cartilages (*n*), assist to bound the orbital cavities in front, and are connected by their external angles with the maxillary bone on either side [1].

12. The **premaxillary bones**, *ossa intermaxillaria* (Figs. 10, 11, 17, 19 *i*).

Cuvier, *l. c.*, p. 388, Pl. XXIV, Figs. 1, 2 f f.—Dugès, n. 3.—Parker and Bettany, *l. c.*, premaxillary bones.

These two bones are united in the middle line : each consists of a tooth-supporting portion, which completes the maxillary arch, and an ascending process, to the apex of which the nasal cartilage is articulated by a movable joint (*an*). As muscles are attached to this process, it becomes a lever, by which movements are effected.

13. The **palatine bones**, *ossa palatina* (Figs. 19, 20 *pl*).

Cuvier, *l.c.*, p. 389, Pl. XXIV, Figs. 1, 2 i i.—Dugès, n. 7.—Parker and Bettany, *l. c.*, palatine bones.

Are two transverse bony bars, situated under the anterior portion of the sphenethmoid bone on either side : each extends outwards from the apex of the parasphenoid to the maxillary bone, where this gives off its ascending process to the nasal bone.

Fig. 20.

Skull of *Rana esculenta*, seen from below, twice natural size.

c	Cartilaginous wall of skull.
e	Sphenethmoid.
e'	Cartilaginous nasal skeleton.
h'	Stylo-hyoid.
i	Premaxillary.
m	Maxillary.
m'	Quadrate tract.
o	Exoccipital.
p	Prootic.
p'	Anterior arm of prootic.
p"	Trigeminal foramen.
pl	Palatine.
pt	Anterior arm of pterygoid.
pt'	Posterior arm of pterygoid.
s	Parasphenoid.
v	Vomer.

[1] For *os nasale*, Cuvier (*l.c.*, g), *cornet* (*concha*), Dugès, see cartilaginous nasal capsule, p. 27.

14. The vomers, *vomer* (Figs. 19, 20 *v*).

Cuvier, *l.c.*, p. 389, Pl. XXIV, Figs. 1, 2 1 1.—Dugès, n. 6.—Parker and Bettany, *l.c.*, vomer.

A pair of flat bones, placed horizontally on the under surface of the cartilaginous nasal capsule in the triangular space between the palatine bone and the anterior portion of the arch of the jaw. They limit the outer border of the floor of this capsule, which lies in a groove on the dorsal surface of the bone. The outer border of each bone has three processes, and between them two notches; the hinder of these notches bounding the posterior nares. The inner borders of the two bones touch, and the under surface of each bears a transverse row of small, pointed teeth.

15. The mandible, *maxilla inferior* (Fig. 21).

Cuvier, *l.c.*, p. 398, Pl. XXIV, Figs. 1, 2 *rst.*—Dugès, n. 16, 17, 18, 19.—Parker and Bettany, *l.c.*, mandibular arch.

The mandible consists of two bony arches united by ligament in the middle line, and each formed of four pieces. These are, (1) the angulosplenial, a strong, bony piece (Fig. 21 *C*, *B* 1, *A* 1), which forms the inferior and internal part of the lower jaw; below, it extends posteriorly, as far as the articulation; in front, it is attached to the dentary. In the greater part of its length it has a groove directed upwards and outwards (*C*, *b*), and above has a process which represents the *processus coronoideus*: (2) the dentary (*A* 2, *B* 2), a bony lamella which rests on the

Fig. 21.

A Mandible of *Rana esculenta*, from above, nat. size.
B External view of left side, } twice nat. size.
C Angulosplenial,
   1.   Angulosplenial.
   2.   Dentary.
   3.   Mentomeckelian.
   4, 4' Meckel's cartilage.
   a.   Rudimentary *processus coronoideus.*
   b.   Groove for Meckel's cartilage.

outer surface of the anterior half of the angulosplenial, and articulates in front with Meckel's cartilage; it is a thin, flat lamella of bone; (3) in the groove of the angulosplenial is found a cartilage occupying its entire length (*A* 4, *B* 4), **Meckel's cartilage**; it is broader behind, and here forms the articular fossa of the lower jaw; anteriorly it is covered by the dentary, and articulates with the (4) **mentomeckelian** (*A* 3, *B* 3) at its anterior end, which is bound to its fellow of the opposite side by ligaments, and unites the two halves of the lower jaw.

The upper part of Meckel's cartilage, which forms the joint with the suspensorium, must be regarded as the *articulare*; to this also belongs the anterior, ossified portion of the mentomeckelian[1]; the dentary, which covers Meckel's cartilage, must represent the *os dentale*[2]; the first and largest bone, the angulosplenial, which lies on the inner side of the cartilage, must be considered as the *os operculo-angulare*, Dugès, for it contains the elements of these bones.

16. The **hyoid bone,** *os hyoideum* (Fig. 22).

Parker and Bettany, *l.c.*, hyoid.

This consists of a broad, thin, cartilaginous plate, with processes passing from it as represented in the figure. We distinguish in it:—

(a) the body (*H*), somewhat oblong, and wider in front than behind. From the anterior angles there projects on either side a blunt rounded process (*h*); from either posterior angle a more pointed process (*h'*).
(b) The anterior cornua (*H'*) (*cornua styloidea*) project from the anterior border of the body, first in a forward direction, then in a curve backwards and upwards (compare Fig. 12), to unite with the cartilage of the prootic bone. Where the direction of these *cornua* is changed each sends off a short blunt process. (c) The posterior cornua (*cornua thyroidea*) (*H''*) are bony rods which run from the hinder margin of the body, diverge posteriorly, and enclose the larynx.

Fig. 22.

Hyoid of *Rana esculenta,*
twice nat. size.
H Body; *h h'* processes.
H' Anterior horn.
H'' Posterior horn.

---

[1] Dugès, *os dentale*.

[2] Dugès, *surangulaire*.

III. THE STERNUM (Fig. 24 *es, hs*).

Cuvier, *l.c.*, p. 401, Pl. XXIV, Fig. 31 *e f.*—Dugès, n. 27, 28.—Parker and Bettany, *l.c.*, sternum.

The bones of the sternum are in very close relationship with the shoulder-girdle, and some difference of opinion exists as to the relations of the several parts.

Fig. 23.

Omosternum of *Rana esculenta*, twice nat. size.
a Anterior,
p Posterior extremity.

The following parts must be regarded as undoubtedly belonging to the sternum :—

1. An anterior part, consisting of a bony and a cartilaginous portion.

    a. The **omosternum** (Figs. 23, 24 *e.s.*) is a bony rod, wider behind, narrower in front, and supports

    b. The **episternum** (Fig. 24 *es′*), a semicircular plate of calcified cartilage, with a thin free border of unchanged hyaline cartilage.

2. A posterior part, which also consists of a bony and a cartilaginous portion.

Fig. 24.

Shoulder-girdle and sternum of *Rana esculenta*, twice nat. size.
The scapula and suprascapula are turned outwards.

c.	Connecting cartilage.	*h s.*	Sternum proper.
cl.	Clavicles and precoracoids.	*hs′*	Xiphisternum.
co	Coracoid.	*o*	Bone.
e.s.	Omosternum.	*o′*	Calcified cartilage.
es′	Episternum.	*sc.*	Scapula.
h	Hyaline cartilage.	*sc′*	Suprascapula.

a. The **sternum proper** (Fig. 24 *h.s.*), a rod of cartilage ensheathed in bone, broader in front and narrower behind. To its posterior extremity is attached

b. The cartilaginous **xiphisternum** (Fig. 24 *hs'*), a plate, the shape of which is best understood by referring to Fig. 24, and the structure of which is similar to that of the episternum.

3. The **epicoracoids**[1] lie between the episternum and the sternum proper: they are a pair of narrow cartilages, closely applied to each other and placed between the ventral ends of the precoracoids and coracoids, see p. 40.

IV. THE BONES OF THE ANTERIOR EXTREMITY.

A. BONES OF THE SHOULDER-GIRDLE.

The shoulder-girdle of the frog (Fig. 25) consists of four bones, two in the upper or **scapular portion**, and two in the lower or **coracoid portion**.

1. The **scapular portion**.
a. The **suprascapula**, *pars suprascapularis scapulae, scapula superior s. omolita* (Figs. 25 *s'*, 26, 27). This forms the upper, thinner portion. It is trapezoid in shape, its narrowest, thickest, and lowest border articulating with the scapula. The remaining three borders are free; the posterior and superior borders are very considerably thinned out, the inferior surface is curved towards the ventral surface. Only the thin upper and hinder borders (*hh*) are of hyaline cartilage; the middle portion (*co*) consists of calcified cartilage; the lateral part (*o*) and the anterior border (*o'*) of true bone.

Fig. 25.

Shoulder-girdle of the frog in transverse section, diagrammatic.

c   Connecting cartilage.
c' Epicoracoids.
cl Clavicle.
h   Humerus.
s   Scapula.
s' Suprascapula.
ss Articulation of these two.
v   Vertebra.

The bony part forms a thin plate striated both radially and

[1] Dugès, *l.c.*, p. 61, regards the cartilaginous laminae as *os episternale* and *proc. xiphoideus*, and the two bones *e.s.* and *h.s.* (Fig. 24) as sternum.

concentrically with the margin. The anterior border (*o'*) is bent on itself so as to form a groove (Fig. 27). The dorsal surface of this bony plate is quite smooth, and covered only by periosteum; the ventral surface, on the contrary, is for the most part covered

Fig. 26.

Fig. 27.

Suprascapula of *Rana esculenta*, from above, twice nat. size.

co   Calcified cartilage.
h   Hyaline cartilage.
o   Bony portion.
o'   Anterior curved border.

Suprascapula of *Rana esculenta*, from below, twice nat. size.

co   Calcified cartilage.
co'   Layer of calcified cartilage on the under surface of the bone.
h   Hyaline cartilage.
o   Bony portion.
o'   Anterior curved border.

by an even layer of calcified cartilage (Fig. 27 *co'*). This passes directly into the second portion of calcified cartilage (*co*); so that if the whole be dried, the thin hard lamina of bone can easily be split away from the underlying parchment-like cartilage. The layer of calcified cartilage is, however, not so complete that the *suprascapula* can be said to consist of calcified cartilage.

b. The **scapula** (Figs. 25 *s*, 28, 29) is a long, flat, four-cornered plate of compact bone, contracted in the middle, and wider at either end. From above (Fig. 28 *l*) it descends to the shoulder-joint with a slight curvature, with the convexity directed outwards. The inferior or ventral border (Fig. 28 *m*), which assists in the formation of the shoulder-joint, is cleft into two processes, a ventral and a dorsal. This may be best seen by looking at the border of the bone from behind or before (as in Fig. 29). The lower ventral process (Fig. 29 *v*) may be regarded as the *acromion*, or at

Fig. 28.

Fig. 29.

Left scapula of *Rana esculenta*, from below, twice nat. size.

a   Anterior border.
c.a. Cavitas articularis.
l   Outer border.
m   Inner border.
p   Posterior border.

Scapula seen from behind, twice nat. size.

c.a. Cav. articularis.
d   Dorsal process.
v   Ventral process.

least as a rudiment of the acromion, *i. e.*, *spina scapulae*. The upper dorsal process evidently represents a rudimentary *processus coracoideus*. The anterior border (Fig. 28 *a*) is free, somewhat sharp, and slightly concave; the posterior (Fig. 28 *p*), also concave, is free externally; while internally, where the division of the ventral border commences, it takes part in the formation of the articular cavity of the shoulder (Figs. 28 and 29 *c.a.*).

Articulation with the suprascapula. The scapula consists of a shell of compact bony tissue and an inner portion of cancellous tissue; this latter passes, at the boundary between this bone and the suprascapula, through an intermediate layer of calcified cartilage, which is directly continuous with the cartilage of the suprascapula. The compact superficial layer ceases where the calcified cartilage begins, and the periosteum of the scapula passes directly into the perichondrium of the suprascapula.

2. The **ventral portion** of the shoulder-girdle consists of three parts, which lie one behind the other.

a. The larger and posterior bone, the **coracoid** (Figs. 24 *co*, 30), is contracted in the middle, and expanded at either end, especially at the sternal end. The inner half is flattened from above downwards; externally it becomes more cylindrical. The anterior and posterior borders are markedly concave; the outer border (Fig. 30 *l*) articulates by means of a cartilage with the *proc. coracoideus* of the scapula; the inner border (*m*) is separated from its fellow of the opposite side by the epicoracoids. This inner border is so broad, that it almost touches the inner end of the clavicle (Fig. 24 *cl.*). A **coracoid foramen** is thus formed between the two bones, similar to the *foramen ovale* of the pelvis.

Fig. 30.

Left coracoid, twice nat. size.

a From below.
b From behind.
l Outer extremity.
m Inner extremity

b. The small anterior bones of the ventral portion of the shoulder-girdle (Figs. 24 *cl.*, 31), I, like Cuvier and others, regard as **clavicles**. Dugès (n. 33) names them '*acromial.*' Each bone is narrower than the coracoid, smaller internally (*m*), broader externally (*l*), and articulates by this broader end with the cartilage uniting the

Fig. 31.

Clavicle of the left side, twice nat. size.
l Outer extremity.
m Inner extremity.

Fig. 32.

Right shoulder-girdle of *Rana esculenta*, from above.

ca Cav. articularis.   *co* Coracoid.
c c Cartilage.   *sc* Scapula.
cl Clavicle.   *sc'* Suprascapula.

dorsal and ventral portions; the inner extremity rests upon the epicoracoid. The clavicle is grooved on its superior and posterior surfaces in almost its whole length; the groove widens externally (*l*), and contains

c. The **precoracoid** (Fig. 34 *cl'*), a slender bar of cartilage, connecting the anterior edge of the scapula with the sternum.

Cartilages of the shoulder-girdle (Figs. 24, 32, 34). A cartilage (*c*), described by Dugès as the 'paraglénal,' connects the scapula with the coracoid, and converts the notch between the two processes (*s* and *v*) on the inner border of the scapula into an aperture opening posteriorly into the glenoid cavity, and which is filled up by the lining cartilage. This cartilage connects the two processes with the coracoid; being thicker between this and the *proc. coracoideus*, it takes an important share in the formation of

Fig. 33

Fig. 34.

Hinder border of the scapula and coracoid, with the connecting cartilage and shoulder-joint, twice nat. size.

c Connecting cartilage.
d Dorsal process.
co Coracoid.
sc Scapula.
v Ventral process.

Clavicular cartilage of a young specimen of *Rana esculenta*, enlarged to the adult size.

c   Connecting cartilage.
e   Epicoracoids.
c' Ligament between the two cartilages.
cl Clavicle.
cl' Clavicle and precoracoid.
co Coracoid.
co' Cartilage of same.
es Omosternum.
hs Sternum proper.

the floor of the glenoid cavity. At the outer extremity of the clavicle the cartilage projects and is then continued in the groove

on this bone towards the middle line (Figs. 32, 34), where it widens out, and is united by its external margin with the sternum, thus forming the precoracoid as already described, see p. 40. These connections are best seen in young animals, as is shown in Fig. 34.

The clavicle (*cl*) is of ossifying cartilage; the cartilage (*c*), the epicoracoid, is very large, and hyaline, and at *cl* runs directly into the epicoracoids, which are here united mesially by ligament. In the fully developed animal the whole of the epicoracoid changes to calcified cartilage, as also does the precoracoid lying in the groove of the clavicle.

B. BONES OF THE FORE LIMB.

1. The **arm** has but one bone.

The **humerus**, *os humeri* (Figs. 35, 36, 37). The shaft of the humerus is, on the whole, cylindrical, the middle part being the

Fig. 35.	Fig. 36.	Fig. 37.

Humerus of *Rana esculenta*, female, seen from below.

Humerus of *Rana esculenta*, male, seen from below.

Humerus of *Rana esculenta*, female, outer side.

Figures twice natural size.

c Anterior extremity.　　*c'* Posterior extremity.　　*cd* Crista deltoidea.
cm Crista medialis.　　*t* trochlea.

narrowest; its dorsal surface is slightly concave, the ventral surface convex. In the upper half the cylindrical form is indistinct, from the presence of a well-marked crest (*crista deltoidea*) upon the under or ventral surface. The hinder half of the bone has very different

shapes in the two sexes : in the female it remains cylindrical as far as the elbow-joint in the male, on the posterior surface, where the *crista deltoidea* ceases, a marked ridge (*crista medialis*) arises, which gradually winds inwards and terminates at the inner condyle. This sexual difference is found in all the three species described in the Introduction, and it would seem that this ridge increases in height during the pairing season. The muscle which arises from this process is the *flexor carpi radialis* (Fig. 74 *Fc*), and it attains, in the males, a very large size at the same period ; indeed, it is at its origin twice as broad as in the female. Dugès[1] has incorrectly stated that this *crista* is a peculiarity of *Rana temporaria*, and is wanting in *Rana esculenta*. Pouchet[2] first observed that it was a sexual distinction.

The anterior articular extremity presents a rounded head, which is somewhat flattened externally. The inferior ventral border is sharp, and developed into the above-mentioned bony crest (*crista deltoidea*) ; the free border is arched and curved outwards. Above, on the outer surface of the head, is found an eminence which may be a rudimentary *tuberc. maius*. The inner half of the head is articular.

The posterior articular extremity consists of a rounded head (*c'*), attached to the posterior extremity of the shaft ; internal to this is a small *trochlea* (*t*), placed upon the inner condyle. The external condyle is but small. The head is embraced by these condyles. Upon the under surface, above the head, is the *fossa cubitalis anterior*. The structure of the two articular extremities of the humerus differs ; the upper, as in long bones generally (see page 16), consists of hyaline cartilage surrounded by calcified cartilage, which again is covered by hyaline articular cartilage ; the lower extremity is composed of spongy bone, with roundish marrow spaces, and for the most part covered by a layer of calcified cartilage.

The **shoulder-joint**. The socket is formed by the posterior border of the scapula, by both the processes of that bone, the outer portion of the coracoid, and besides these by cartilage, which forms the articular surface already described (Fig. 33). In the macerated bone the floor of the socket opens dorsally into a fossa between the processes of the scapula (Fig. 32). This opening, in the natural condition, is closed by synovial membrane only ; the cartilage covering the rest of the space being absent (the sac may

---

[1] *l.c.*, p. 68.   [2] Compt. rend. vol. XXV, 1847, p. 761.

easily be inflated, either from the joint itself or through the opening). The margin of the socket consists of a *labrum*, partly fibrous and partly cartilaginous, which is easily removed entire. The capsule, which is attached beneath the *caput humeri*, arises from this. From the articular cartilage of the ventral margin of the socket, and from the adjacent part of the scapula, proceeds a strong band, which is inserted into the flattened outer surface of the head.

2. The **forearm**.

The **radio-ulnar,** *os antibrachii* (Fig. 38). The two bony elements of the forearm are fused into one, which, however, shows traces of its compound character. Of these two bones, that which forms the inferior (in man anterior) border is the radius, the other the ulna. The relative positions of the bony elements are such that they appear to be in a state of semi-pronation; by this the thumb-border of the arm is directed downwards (in man forwards). The two bones so united form a flattened, tube-like bone, the grooved surfaces of which are directed inwards and outwards respectively; the borders being dorsal and ventral. The shaft of the bone is narrower above, becoming gradually wider below. In the upper half, the groove showing the line of junction of the two bony elements is scarcely visible, and it appears as though this part consisted of ulna alone, the radius not reaching so far; below the groove is more marked. The upper articular extremity appears to consist of an *olecranon* (Fig. 38 u′) and a *processus coronoideus* (r′), between which is the greater sigmoid cavity (*cavitas sigmoidea major*) for the *processus cubitalis humeri*. A more careful examination shows this to be incorrect : the portion of the concave articular surface, which lies in the immediate neighbourhood of the ventral border, undoubtedly represents the articular surface of the *capitulum radii*, and the upper portion of the articular surface (at u′) belongs to the *ulna* and articulates with the *trochlea* (Figs. 35, 36 t) of the humerus. The inner border of the upper extremity of the bone articulates with the groove t of the humerus. The inferior extremity forms one of the usual cartilaginous epiphyses, enclosing the two bones. That part of the extremity corresponding with the radius is triangular and convex, it is prolonged upon the inner or under surface of the bone by means of a process; the

Fig. 38.

Radio-ulnar of the right side of *Rana esculenta*, twice nat. size.

r Radius.
r′ Capitulum radii.
u Ulna.
u′ Olecranon.

ulnar portion of the bone forms a *capitulum*. The structure of the inferior extremity is that of epiphyses in general, except that there are two medullary cavities in a common sheath of calcified cartilage ; the anterior head consists of cancellous tissue, with a covering of calcified cartilage.

Fig. 39.

Bones of the forearm and hand of *Rana esculenta*, right side, dorsum, twice nat. size.

a Os antibrachii.
hc Os capitato-hamatum.
l Os lunatum.
m Ossa metacarpi.
n Os naviculare.
p Os pyramidale.
r Radial portion of the radio-ulnar.
t Os multangulum majus or trapezium.
t' Os multangulum minus or trapezoides.
u Ulnar portion of the radio-ulnar.
I—V First to fifth fingers, the fifth only of os metacarpi, the second and third of two, fourth and fifth of three phalanges.

3. **Bones of the hand** (Fig. 39).

Dugès, Pl. VIII, Figs. 37, 38, 39, 40, 41, 42, 43, 52.

a. Bones of the **wrist**, *ossa carpi*. These are arranged in two rows, proximal and distal. The proximal or anterior row has three bones, viz. :—

1. *Os lunatum*, the middle bone (Fig. 39 *l*), Dugès, n. 38, articulates with the radial part of the articular surface of the radio-ulnar by a concave surface ; with the large bone of the second row (*hc*) it articulates by means of a rounded head ; and with the two other bones of this row, *os naviculare* (*n*) and *pyramidale* (*p*), with the former by a saddle-shaped surface, with the latter chiefly by ligament. The bone is irregularly cuboid ; the dorsal and palmar surfaces are non-articular. With Dugès I regard this bone as *os lunatum* ; Mertens [1] regards it as *os naviculare*.

2. *Os pyramidale* (Fig. 39 *p*), Dugès, n. 37, articulates with the ulnar part of the posterior articular extremity of the radio-ulnar. Anteriorly the bone has a facet which receives the *capitulum ulnae*, and alongside this a small flat surface which articulates with the radius. Posteriorly, opposite to the second row, it presents a long raised articular surface, extending from the dorsum to the palmar surface ; and on

[1] Mertens, *l. c.*

the palmar aspect of the bone is a ridge running from before back-wards. Mertens names this bone *os lunatum*.

3. *Os naviculare* (Fig. 39 *n*), Dugès, n. 39. The third bone of the first row does not articulate with the bones of the forearm. It is connected with the *os lunatum* by a saddle-shaped surface, pos-teriorly with the *os capitatum* by means of a concave surface. On the inner surface is a small concave articular facet for the *os mult-angulum minus* or *trapezoides* (Fig. 39 *t'*). The convex palmar surface of the bone articulates with the *os multangulum majus (t)*; the radial side is non-articular, and with the *os lunatum* forms a ridge directed forwards. Mertens names this bone *os triquetrum*. It is evident, however, that if the arrangement in man obtains as a standard, the nomenclature of Dugès, which I have here used, is correct; but the *os naviculare* is no longer in contact with the articular surface of the *os antibrachii*.

The second or distal row also consists of three bones:—

4. *Os capitato-hamatum* (Fig. 39 *hc*), Dugès, n. 40, 41, 42, corresponds with the *os capitatum* and *hamatum*[1], which are here fused together. It is the largest bone, and articulates with all three bones of the first row; it is crescentic, with the concavity directed posteriorly, and on the convex surface has three facets for the three outer *ossa metacarpi*.

5. *Os multangulum minus, s. trapezoides* (Fig. 39 *t'*), Dugès, n. 43, is a small bone lying next to the foregoing; it articulates with the *os metacarpi II*, and anteriorly with the *os naviculare*. Dugès considers it to be the *os trapezium*.

6. *Os multangulum majus, s. trapezium* (Fig. 39 *t*), is a small bone, which is placed on the convex palmar auricular side of the *os naviculare*. Dugès regards this bone as *os metacarpi pollicis* (Dugès, n. 44), Mertens as *multangulum minus*. It appears to me that the interpretation here given is justified, because it articulates with the rudiment of the thumb, and as it possesses no resemblance to a long bone it cannot be regarded as an *os metacarpi*.

Structure of the carpal bones. All the carpal bones consist of calcified cartilage, though variations due to age occur in the amount of the deposit.

Wrist joint. As stated above, the *os lunatum* and *os pyramidale* are articulated with the forearm. In addition to the capsules uniting the parts, there are strengthening ligaments, two of which require special mention. One of these arises from the palmar surface of

---

[1] Dugès thinks that *os trapezoides* is also included.

the posterior extremity of the ulna, and passes to the sharp palmar ridge of the *os pyramidale*, where it is attached, and is inserted into the *os capitato-hamatum*; the second ligament passes in a similar manner on the palmar surface from the radius to the *os naviculare*. Between the two ligaments there is on the volar surface a deep excavation.

Fig. 40.

Bones of the forearm and hand of *Rana esculenta*, right side, dorsum, twice nat. size.

a Radio-ulnar.
hc Os capitato-hamatum.
l Os lunatum.
m Ossa metacarpi.
n Os naviculare.
p Os pyramidale.
r Radial portion of the radio-ulnar.
t Os multangulum maius or trapezium.
t' Os multangulum minus or trapezoides.
u Ulnar portion of the radio-ulnar.
I – V First to fifth fingers, the first only of a metacarpal, the second and third of two, fourth and fifth of three phalanges.

Movements of the hand. The two bones of the forearm being firmly united, pronation and supination, as in man, are impossible. The normal position, as already remarked (see radio-ulnar), is that of semi-pronation (compare Figs. 2 and 74). If the animal be in its natural posture, with the arm bent at the elbow (Fig. 1), it can touch the ground with the ulnar border only; but when the whole surface of the hand rests upon the ground, the action is brought about as follows: the plane of the carpus is in extension parallel with that of the forearm; in flexion, almost at right-angles with that plane (Fig. 74). The *os lunatum* glides on the prolongation of the articular surface on the inner palmar surface of the radius, while the *os pyramidale* is held firmly by the ligament just described. The hand follows the movement of the *os lunatum*, and at the same time the three outer *ossa metacarpi* gliding with it inwards, the fingers of the hand turn inwards.

b. The Bones of the **metacarpus**, *ossa metacarpi* (Fig. 40 *m*). Of these there are five: the second to the fifth are of about equal length; the first, forming the rudiment of the thumb, hidden beneath the skin, is much shorter. This metacarpal bone of the **thumb** is regarded by Dugès and others as the first phalanx. My reason for describing it as a metacarpal has

already been given. This bone also presents differences in the two sexes. Meckel's[1] observation that it exists only in the male is incorrect; it is a large, broad and sickle-shaped mass of calcified cartilage or even true bone, while in the female it is simply a small cartilaginous rod; as this almost entirely disappears in dried specimens, Meckel's statement is explained. The second finger has in the frog assumed the functions of the thumb, and, in the males, in the breeding season swells and undergoes an essential alteration of structure. The metacarpal of this finger also displays differences in the sexes, being in the male stronger, broader, and on the inner side provided with a spine-like prolongation, for the tendon of the *abductor digiti II (pollicis) longus,* which attains an unusual development during the breeding season. The remaining metacarpal bones, the **third, fourth,** and **fifth,** are of similar form, the last being provided with a tubercle. The anterior articular extremities are rather broad and concave, and the posterior have rounded heads.

c. The **phalanges,** *phalanges digitorum.* The hand has four fingers and the rudiment of a fifth, which latter is completely hidden under the skin, and as already explained, consists of a metacarpal only. Of the four fingers, the fourth is the longest, the third the shortest, the second and fifth of intermediate and about equal length; the fourth and fifth fingers have each three phalanges, the second and third have each two. Their shape is not unlike that of the human phalanges.

V. THE BONES OF THE HINDER EXTREMITY.

A. Bones of the Pelvic Girdle (Fig. 41).

The **pelvis** has a characteristic V-shape, the pubic and ischiatic bones of the two sides together forming a vertical plate (*a p*), which divides anteriorly into the two iliac bones (*il*). The pubic and ischiatic bones being united by their median surfaces, one can only speak of the pelvic cavity as the space between the two ilia.

1. The **ilia,** *ossa ilii* (Fig. 42 *il*). In these a broader part or

---

[1] *l. c.,* II, 464.

body can be distinguished, which takes part in the formation of the *acetabulum* (*a*). The hinder and broadest part of the bone is joined to the corresponding portion of its fellow by ligament; anteriorly the two diverge, bounding a cone-shaped cavity, the pelvis. The suture, by which the body of the iliac bone is united with the ischiatic and pubic bones, runs from above downwards through the middle of

Fig. 42.

Fig. 41.

Pelvis of *Rana esculenta*, from below, nat. size.

a Acetabulum.
il Iliac bone.
p Pubic bone.

Pelvis of *Rana esculenta*, left side, twice nat. size.

a Acetabulum.
d Upper sharp border.
il Iliac bone.
il' Superior process.
is Ischium.
is' Tuber ischii.
p Os pubis.
s Inferior process of the ilium.
v Lower border of same.

the *acetabulum* (Fig. 42, from *p* through the *acetabulum* to *is*). Inferiorly and in front the united *ilia* form a prominence (*s*), which represents the *symphysis oss. pub.* of man. The expanded portions of the ilium rest directly over the articular cavity by means of a somewhat constricted part or root. The *ala* is a sabre-like bone, with the sharper, more convex border directed upwards; the more concave, thicker border downwards. The two surfaces, of which the inner is grooved, are directed respectively inwards and outwards. The broader part of the blade springs directly from the neck or root (at *il'*), and at this end of the sharp convex border is a process, *process. sup.*, from which the tendon of the *m. vastus externus* arises. The anterior end of the blade is a hollow cylinder, containing cartilage, movably articulated to the transverse process of the last vertebra or sacrum.

2. The **ischia**, *ossa ischii* (*is*), are irregular, four-cornered plates of bone, united together by the whole extent of their inner surfaces. The vertical plate formed by the union of the two bones takes only a very small share in the formation of the articular cavity. Above, it has a somewhat sharp border, continued with the ilium into a process

(*is′*) corresponding with the united *tubera ischii*; the hinder border, which is united below with the pubic cartilage, is curved.

3. The **pubes**, *os pubis* (Figs. 41, 42, 43 *p*). Ossified pubic bones do not exist; even in old animals they are composed of calcified cartilage. Each is a triangular cartilage, wedged between the ilium and ischium, but also taking part in the formation of the *acetabulum*. The pubes of opposite sides are, as shown in section in Fig. 43, united by ligaments in the median plane.

Fig. 43.

Horizontal section through the iliac, pubic, and ischiatic bones.

a Acetabulum.
il Ilium.
is Ischium.
p Pubic cartilage.
s Ligaments which unite the bones of opposite sides.

B. BONES OF THE HIND-LIMB.

1. The **thigh**.

The **femur**, *os femoris* (Fig. 44). The shaft is cylindrical, with a slight double or S-shaped curve. In the anterior portion the convexity is directed upwards, in the two hinder thirds downwards. Towards the hinder extremity it is flattened from above downwards. The anterior extremity is a. rounded articular head placed directly on the shaft like that of the *humerus*. This head is somewhat flattened from side to side; and in structure resembles that of the humerus. The inferior extremity is rounded below, but flattened above (towards the hollow of the knee) and behind.

Hip-joint. The articular cavity is deepened by a fibrous ring, *labrum cartilagineum*, which fits closely upon the *caput femoris*; from this *labrum* the joint-capsule arises, to be inserted behind the head; close to the lower border of the cavity a *ligamentum teres* arises, which is inserted into the *caput femoris*.

2. The **leg**.

Tibio-fibula, *os cruris* (Fig. 45). This consists of a single bone, the *os cruris*; it is often called the *tibia*, but presents, however, distinct indications of being formed of two bones, the *tibia* and *fibula*. The shaft is not quite straight; it is thinner in the middle and flattened

Fig. 44.

Femur of *Rana esculenta*, right side, twice nat. size.

a Anterior extremity.
p Posterior extremity.

E

Fig. 45.

from above downwards. On the upper as also on the lower surface of the bone is a groove, passing from the middle towards each extremity; this deepens as it proceeds, and is an indication of the compound nature of the bone. In the middle of each surface of the bone is the opening of a canal, through which a bristle may be passed: the canal has bony walls. The medullary cavity is, for the most part, double, being single only in the middle. The anterior extremity is articular, and presents a median groove, which is prolonged on to the under surface. The posterior extremity forms a transverse condyle, which has at its inner part a notch for the tendon of the *m. tibialis posticus*.

The **knee-joint** consists of a capsule strengthened by the insertions of numerous tendons.

Fig. 46.

Within this the articular surfaces of the *femur* and tibio-fibula are connected by means of fibro-elastic bands, which spring from the latter bone and cross each other, thus representing the *lig. cruciata*. The articular surfaces are moreover deepened by loose semilunar cartilages, corresponding with the inter-articular cartilages of the knee-joint of man. In addition, on either side of the joint, are found auxiliary ligaments.

Tibio-fibula of *Rana esculenta*, twice nat. size, seen from below.
a a Grooves.
f Foramen nutritium.
t Anterior articular extremity.
t' Posterior articular extremity.
t'' Groove on malleolus internus for tendon of *m. tibialis posticus*.

Section of the tibio-fibula through the under extremity.
a Cartilaginous epiphysis.
m Marrow cavities.
t'' Connecting mass.
t t' The two cylinders of bone.

3. The foot (Fig. 47).

a. The **ankle**, *ossa tarsi*. The **tarsus** consists of two rows of bones.

a. The **proximal row** consists of two long tubular bones (Fig. 47 *ac*), which are parallel to each other, and undoubtedly correspond with the **astragalus** (*talus*) and **calcaneum.** The bones are separated in the middle, but approach each other at either end. The outer of these bones (*c*) I have named calcaneum, following Cuvier and Dugès; the inner, astragalus (*a*). The two bones are

Fig. 47.

surrounded and enclosed at their anterior and posterior extremities in a common epiphysis of calcified cartilage, which has the usual structure found elsewhere. The *ligamentum calcanei*, which will be described below (see Muscles of Foot, Fig. 88 *lc*), may be regarded as an unattached process of the heel[1].

β. The **distal** row of the tarsals are all composed of calcified cartilage. They are :—

1. *Os cuboideum* (Fig. 47 *cb*), a flat plate of cartilage, concave in front, convex behind, placed between the common epiphysis of the astragalus and calcaneum (*ac*) and the *ossa metatarsi II* and *III*. This corresponds, as Dugès suggests, with the separated *os cuboideum* and *cuneiforme III* of other batrachians, *e.g.* Bufo.

2. On the inner side of the above, between the *astragalus* and *metatarsus I* lies a small body, concave in front, convex behind, which we may regard, with Dugès, as the analogue of the *os naviculare* (Fig. 47 *n*).

3. This' latter supports a cartilage which forms a projection on the inner border, covered with skin. This consists of closely-united pieces, a small round, basal

Right foot of *Rana esculenta*, palmar surface, twice nat. size.

a Astragalus.
ac Common epiphysis.
c Calcaneum.
cb Os cuboideum.
h First, *h'* second cartilage of supplemental toe.
m Ossa metacarpi.
n Os naviculare.
I to *V* First to fifth toe.

[1] Meckel, *l.c.*, II, p. 488, regards the cartilage in the *tendo Achillis* as such.

piece (*h*), and a flattened beak-like piece (*h′*).   Dugès considers these pieces as the first and second *ossa cuneiformia*; I rather incline to Meckel's opinion that they represent a rudimentary hallux, the first being the *os metatarsi*, the second a *phalanx*.   Both are composed of calcified cartilage; in *R. temporaria* the lime-deposit seems to be less than in *R. oxyrhinus* and *R. esculenta*, and the projection consequently softer [1].

b. The **metatarsal bones**, *ossa metatarsi* (Fig. 47, *m I–V*).   The five *ossa metatarsi* are long, thin tubular bones, the anterior articular extremities of which are broader above and narrow below, hence are wedge-shaped, and anteriorly present flat surfaces for articulation with the *tarsus*.   The shafts are long and thin; the posterior extremities have rounded heads.   The comparative length of these is as follows: the fourth is the longest, then come the third, fifth, second, and first in order.   In structure they resemble other tubular bones.

c. The **phalanges**, *phalanges digitorum* (Fig. 47).   The total lengths of the separate toes correspond with that of the *ossa metatarsi*, but the distinctive differences are increased, partly by the difference in number and partly by the varying lengths of the phalanges.   The first and second toes have each only two phalanges, the third and fifth have each three, the fourth, which is the longest, has four. The terminal phalanges are somewhat hooked towards the plantar surface.

[1] In the text these two cartilages are termed the 'supplemental toe.'

SECTION II.

THE MUSCLES.

THE MUSCLES.

LITERATURE.

v. Altena, see p. 13.

Anonymous, Ueber das Schultergerüst der Schildkröten mit den daran sitzenden Muskeln. Isis, 1827. (Contains remarks on the shoulder-muscles of the frog.)

Carus, C. G. (1) Lehrbuch der vergleichenden Zootomie. 2nd Edit. Leipzig, 1834. (2) Erläuterungstafeln zur vergleichenden Anatomie. 1 Part. 1826. (Muscles of the Leg.)

Chappuis, Morphologische Stellung der kleinen hintern Kopfmuskeln. Zeit. f. Anat. u. Entwickl. 1876. Vol. II, pages 287-297.

Cuvier, Leçons d'anatomie comparée. Paris, 1835. Vols. I, II.

Dugès, Recherches anatomiques et physiologiques sur la déglutition dans les Reptiles. Ext. des Annales des Sciences naturelles. Paris, 1827.

Dugès, Leçons d'anatomie comparée. Paris, 1835.

Duméril and Bibron, Erpétologie générale ou Histoire complète des Reptiles. 1836.

Führbringer, Zur vergleichenden Anatomie d. Schultermuskeln. Jenaische Zeitschr. 1873. Vol. VII.

Klein, Beiträge zur Anatomie der ungeschwänzten Batrachier (Rana temporaria, L.): in Jahrshefte des Vereins für vaterländische Naturkunde in Würtemburg. 6 Jahrgang. 1850. Page 1.

Kuhl, Beiträge zur Zoologie der Rana esculenta: in Beitr. z. Zool. Frankfurt, a. M. 1820. Page 115.

de Mann, Vergelykende myologische en neurologische studien over Amphibien en Vogels. Acad. Proefschrift. 1873.

de Mann, Myologie comparée de l'extrémité post. chez les amphibiens. Niederl. arch. f. Zool. 1874. Vol. II.

Marshall, The Frog. London and Manchester. 2nd Edit. 1885. Pages 60-71.

Martin St. Ange, Annales des sciences naturelles. Vol. XXIV. 1831. Page 393.

Meckel, System der vergleichenden Anatomie. Halle, 1828. Vols. III and IV.

Pfeiffer, Zur Anatomie des Schultergürtels und der Schultermuskeln bei Säugethieren, Vögeln und Amphibien. Giessen, 1854.

Rymer Jones, Article 'Reptiles' in Todd's Cyclop. of Anatomy and Physiology. 1847-1852. Vol. IV. Page 263.

Stannius, Handbuch der Anatomie der Wirbelthiere. Vol. II. Zootomie der Amphibien. Berlin, 1856.

Wagner, Icones Zootomicae. Leipzig, 1841.

Wagner, Lehrbuch der vergleichenden Anatomie. Leipzig, 1834-35.

Zenker, Batrachomyologia. Diss. Jena, 1825.

THE MUSCLES.

———◆———

I. MUSCLES OF THE HEAD.

I. MUSCLES OF THE EYE.

1. *M. rectus inferior* (Fig. 48 *ri'*).

Dugès, post-orbito-sous-oculaire, n. 12.—**Zenker,** *depressor oculi.*

This muscle arises by a very thin, almost thread-like tendon from the parasphenoid, near the *foramen opticum*, and becomes rapidly broader; it lies beneath the tendon of the *membrana nictitans* and a part of the *m. retractor bulbi*: then runs forwards and outwards to be attached into the lower part of the circumference of the eyeball.

2. *M. rectus externus* (Fig. 48 *re*).

Dugès, post-orbito-ex-oculaire, n. 14.

Arises by a thin, thread-like tendon from the parasphenoid near the *foramen opticum*, internal to and a little behind the *m. rectus inferior*: it then passes obliquely outwards over the *m. retractor bulbi* and the tendon of the *membrana nictitans*, to be inserted into the outer and hinder part of the circumference of the eyeball.

3. *M. rectus internus* (Fig. 48 *ri*).

Dugès, post-orbito-in-oculaire, n. 13.

A long, thin muscle, which arises by a thread-like tendon from the parasphenoid at the inner and

Fig. 48.

Eye muscles of *Rana esculenta*, from below.

On the right side (*i. e.* in the left eye) the lev. bulbi (*l*) is taken away; on the left side it is still present.

l   M. levator bulbi.
l.a M. lev. anguli scapulae.
oi M. obliquus inferior.
os M. obliquus superior.
p   M. pterygoideus.
r   M. retractor bulbi.
re M. rectus externus.
1   First cervical vertebra.

hinder angle of the orbit, passes along its inner wall, and is inserted into the ~~to the~~ ~~inter-internal~~ part of the circumference of the eyeball.

4. *M. rectus superior* (Fig. 49 *rs.*).

Dugès, post-orbito-sous-oculaire.

Arises by a slender tendon from the fronto-parietal bone, widens rapidly, and runs forwards and outwards to be inserted into the upper part of the circumference of the *bulbus*.

Fig. 49.

Eye-muscles of *Rana esculenta*, from above.

n Membrana nictitans.
n' Tendon of membrana nictitans.
p M. pterygoideus.
rs. M. rectus superior.
t M. temporalis.

5. *M. obliquus inferior* (Fig. 48 *oi*).

Dugès, pré-sous-orbito-oculaire.

This muscle arises near the floor of the orbital cavity, at the inner and anterior angle, from the palatine bone by a thin and long tendon, runs under Harder's gland outwards and backwards, and is inserted, almost at a right angle with the axis of the eye, into the anterior part of the circumference of the eyeball.

6. *M. obliquus superior* (Fig. 48 *os*).

Dugès, pré-sus-orbito-oculaire, n. 7.

The tendon of this small muscle arises from the inner end of the palatine bone, near the origin of the *m. obliquus inferior*, runs upwards, backwards, and outwards, and passes into a flat muscle, which rapidly becomes broader, and is inserted into the upper surface of the eyeball.

Fig. 50.

Eye-muscles of *Rana esculenta*, from below, the m. recti and obliqui have been removed.

n' Tendon of membrana nictitans.
r M. retractor bulbi, lower part.
r' Second part of same.

7. *M. retractor bulbi* (Figs. 48 *r*, 50 *r, r'*).

Dugès, orbito-post-oculaire or choanide, n. 10.—Zenker, *m. opticus.*

This muscle surrounds the optic nerve, and is situated within the cone formed by the four recti muscles; it consists of three portions, which take their broad and fleshy (the *recti* and *obliqui* arise by thin tendons) origins from the under surface of the parasphenoid. The first portion (Fig. 50 *r*) arises from the under surface of the parasphenoid, nearly as far as the

middle line, is broad and fleshy, and covers, from below, the tendon of the *rectus externus,* then runs forwards and outwards. The second portion (*r′*), which lies over this and the tendon of the *m. rectus externus,* has also a broad and fleshy origin, but runs more directly forwards, slightly crossing the preceding. The third portion arises above the two others by a strong thin tendon from the parasphenoid : it runs almost in the direction of the *m. rectus internus,* but more directly forwards. The first two portions pass more to the upper surface of the eyeball, the third more to the under surface; consequently the whole muscle forms a sheath surrounding the eyeball. The fibres to the upper surface of the eyeball are inserted somewhat in front of the equator of the eyeball, those to the under surface somewhat behind it.

8. *M. levator bulbi,* Dugès (Figs. 48 *l,* 51 *l,* 52 *l*).

Dugès, fronto-pterygoidien, n. 9.—Klein, *sustentator bulbi.*

There is no bony floor to the orbital cavity, and the oral and orbital cavities are only separated by soft tissues; these are :—the mucous membrane of the mouth, a thin fascia, and above this the muscle under consideration. The fibres of this muscle run from before and from the inner side obliquely backwards and outwards, below all the remaining muscles of the eye, with the exception of the origin of the *m. retractor bulbi,* and the tendons of the *m. obliquus inferior,* and the *m. pterygoideus;* they arise on the inner side from the upper and outer border of the fronto-parietal bone (Fig. 51),

Fig. 51.

Transverse section through the skull and orbital cavities of *Rana esculenta.*

b Bulb of eye.
c Skull cavity.
g Mucous membrane.
l M. levator bulbi.
m Upper jaw.
n Membrana nictitans.
n′ Continuation of same to the lower eyelid.
p Upper eyelid.

Fig. 52.

M. levator bulbi of *Rana esculenta,* seen from above; the eyeball which rests on it has been removed.

d.p M. depressor palpebrae inferioris.
l M. levator bulbi.
n Membrana nictitans.
p. M. pterygoideus.
t M. temporalis.

also from the transverse portion of the parasphenoid and ptery-goid bones, anteriorly from the sphenethmoid and palatine bones; they run first downwards, then, in the direction indicated, under-

neath the eye; and are inserted externally by means of tendinous fibres into the superior border of the upper jaw.

9. From the foregoing muscle certain fibres pass to the lower eyelid, which may be regarded as a **depressor palpebrae inferioris** (Fig. 52 *d.p*).

Manz[1] has described a muscle as *depressor palpebrae inferioris* which arises in the neighbourhood of the external angle of the eye, somewhat behind and below the lower border of the orbit, thence passes obliquely upwards to be inserted into the lower eyelid. This description is right as regards the insertion, but needs correction as regards the origin. The muscle is attached to the orbital border in so far that the tendinous expansion, into which the *levator bulbi* passes at its external border, is attached into the upper jaw; this bundle splits off from the upper surface of the *levator bulbi* at its middle, and runs outwards on the under surface of the eyeball to the hinder part of the lower eyelid.

10. Tendon of the *membrana nictitans*[2] (Fig. 53 *n′*). The pigmented free border of the nictitating membrane passes, at the

Fig. 53.

Eye-muscles of *Rana esculenta*, from below, the m. recti and obliqui have been removed.

n′ Tendon of membrana nictitans.

r M. retractor bulbi, lower part.

r′ Second part of same.

inner and outer angles of the eye, into a tendon which passes for some distance through fibrous tissue, then descends to the under surface of the eyeball and joins that of the opposite side, so that the free border of the eyelid, together with this tendon, form a complete ring. The tendinous part of the ring, which is thin and thread-like, is found on the under surface of the eyeball, and lies under the *m. retractor bulbi*, and is bound to this muscle by connective tissue. Manz is right in saying that the two muscles described by Dugès as *levatores palpebrae inferiores* (orbito-palpebral anterieur and posterieur, n. 5 and 6) do not exist; as is also the suggestion that he has confounded the tendon of the nictitating membrane with these; this is clearly shown in the figure in Plate VI of Dugès. With regard to the actions of these eye-muscles, it is plain that the four straight

---

[1] Manz, Berichte der naturf. Gesellschaft zu Freiburg, 2 Band, 4 Heft, 1862, p. 391.

[2] Compare Manz, *l. c.*

and two oblique muscles rotate the eyeball about three axes, one the axis of the eye, one vertical, and the third passing from behind forwards and inwards. The *m. retractor* pulls the eyeball into the orbital cavity backwards and downwards, while the *levator* raises it.

There is less agreement about the movements of the eyelids, or rather of the lower eyelid, for the upper has no independent movements. Dugès (*l.c.*) says that the two muscles, which he considers to be *levatores palpebrae inferiores*, and which, according to him, are connected with the *m. retractor bulbi*, draw up the lid as it is being drawn backwards and downwards by the latter muscle. The depression of the lid on the relaxation of the retractor and projection of the eyeball is due simply to elasticity. Manz[1], on the contrary, has shown that the sinking of the eyeball by the contraction of the *retractor* must necessarily cause a rising of the nictitating membrane, as its tendons are attached to that muscle and so must follow its movements.

The depression of the lower lid occurs simultaneously with the raising of the eyeball by means of the *m. levator bulbi*, through the contraction of the *m. depressor palpebrae inferioris*, which proceeds from that muscle; this is easily understood, as they are but parts of the same muscle.

II. MUSCLES OF THE FACE.

11. *M. intermaxillaris* s. *dilatator narium* (Fig. 54 *im*).

Dugès, intermaxillaire, n. 1.—Zenker, intermaxillaris medius.

This small muscle lies in the space between the vertical processes of the two premaxillary bones, and consists of obliquely-crossing fibres arising from the one bone and inserted into the opposite one. It brings together the processes of the intermaxillary bones, so that their upper extremities approach each other. At the same time, the cartilaginous nasal coverings or wings (*an*) diverge and the nares expand; hence we may regard this muscle as corresponding to a *dilatator narium*.

Fig. 54.

Facial muscles of *Rana esculenta*.
an Cartilaginous nasal alae.
i¹ Vertical process of premaxillary bone.
im M. intermaxillaris.
ln M. lateralis narium.
n Cartilaginous nose capsule.

[1] *l.c.*, p. 4.

12. *M. lateralis narium* (Ecker), (Fig. 54 *ln*).

Zenker, *m. intermaxillaris lateralis.*—Klein, *m. nasalis inferior.*—Dugès, sus-maxillo-pré-nasal, n. 2.

This small muscle occupies the space between the anterior portion of the maxillary bone and the ascending process of the premaxillary bone. It arises from the maxillary, and ascends obliquely forwards to be inserted into the outer border of the ascending process of the premaxillary bone. It is antagonistic to the foregoing.

A third muscle is described by Dugès as *sus-maxillo-post-nasal*, n. 3 (*nasalis externus*, Klein); according to him it passes from the *proc. nasalis* of the maxillary bone to the outer border of the nasal opening, which it widens. According to Klein (*l. c.*, p. 9), this muscle in *R. temporaria* runs to the upper border of the maxillary bone beneath the lower eyelid, and is long and narrow. I have, however, never been able to find muscular fibre in this situation.

III. Muscles of the Lower Jaw.

Fig. 55.

Muscles of the back and shoulder.

c	M. cucullaris.
dm,dm	M. depressor maxillae, arising from the fascia dorsalis. On the right side it is cut through and reflected.
fd	Fascia dorsalis.
fd'	Same cut near the spinous processes.
i	M. infraspinatus.
l.a	M. levator anguli scapulae.
l.d	M. latissimus dorsi.
r	M. retrahens scapulae.
sc	M. sternocleidomastoideus.

13. *M. depressor maxillae inferioris*, Carus, Zenker (Figs. 55, 56, 63 *d.m.*).

Cuvier, *l. c.*, II, 141, *digastricus.*—Dugès, sus-occipito-dorso-angulaire, 32.

This is a strong, triangular muscle, wide above, pointed below. It is placed between the head and the shoulder-blade. It arises in two portions; the greater, from the *fascia dorsalis* (*fd*), covers the scapula, and passes inwards and backwards over the muscles of the back; anteriorly it passes over the *m. temporalis* and is attached to the fronto-parietal and squamosal, being continued to the fascia of the upper eyelid. The second part is smaller, and arises by fleshy fibres from the postero-superior

arm of the squamosal, and from the posterior and inferior border of the cartilaginous tympanic ring. The two parts unite and are inserted into the hinder angle of the lower jaw. Cuvier correctly considers that only the anterior portion corresponds to the *digastricus*, the posterior answering to the *m. cervico-maxillaris* of snakes. It draws the lower jaw down and opens the mouth.

14. *M. temporalis* (Figs. 49, 52, 56, 57 *t*).

Cuvier, *m. temporalis*, I, *l.c.*, p. 138.—Dugès, sous-rupéo-temporo-coronoidien.

This muscle, together with the *m. pterygoideus*, occupies the space between the prootic and the eyeball; it arises by the greater part of its fibres from the upper surface of the prootic; it passes, narrowing, beneath the anterior arm of the squamosal, then over the pterygoid bone, between this and the maxillary and quadrato-jugal, receiving on the way other fibres which arise from the anterior border of the inferior arm of the squamosal and from the anterior circumference of the tympanic ring. The collected fibres end in a broad, flat tendon, which is inserted into the inner surface of the so-called *proc. coronoideus*.

Fig. 56.

Muscles of the lower jaw of *Rana esculenta*.

d M. deltoideus.
dm M. depressor maxillae, its origin where covering the m. temporalis reflected at *.
ld M. latissimus dorsi.
m M. masseter.
t M. temporalis, origin.
t' Lower portion of same.

15. *M. pterygoideus* (Figs. 49 *p*, 52, 57 *pt*).

Cuvier, *m. temporalis*, II, *l.c.*—Zenker, *m. massetericus*, *l.c.*, p. 25.—Dugès, pré-rupéo-pterygo-maxillaire, 31.

This is partly covered by the foregoing, and lies between it and the eyeball. It arises at the inner wall of the orbit from the frontoparietal, and from that portion of the prootic which may be regarded as the *ala magna*, above the *m. retractor bulbi*. The muscle is broad, and compressed from before backwards: it runs downwards covered by the *m. temporalis*, and soon passes into a long, thin tendon (Fig. 57 *pt*), which is inserted, behind the *m. temporalis* and immediately in front of the joint, into the inner surface of the lower jaw.

16. *M. masseter* (Figs. 56, 57 *m*).

Dugès, zygomato-maxillaire, n. 29.

Arises as a somewhat broad muscle from the horizontal process of the quadrato-jugal and is inserted into the outer side of the lower jaw, opposite the insertion of the *m. temporalis.*

Fig. 57.

Muscles of the lower jaw of *Rana esculenta.*

dm M. depressor maxillae cut through and reflected.
l.a M. levator anguli scapulae.
l.d. M. latiss. dorsi, cut through and reflected.
m M. masseter.
pt M. pterygoideus.
s Scapula.
s' Suprascapula.
s.c. M. sternocleidomastoideus.
t t M. temporalis cut through and reflected.

17. *M. submaxillaris* (Figs. 58, 59, 61 *sm, sm'*).

Cuvier, *m. mylo-hyoideus, l. c.,* II, 536. — Zenker, *mylo-sternoideus,* p. 25. — Dugès, sous-maxillaire, n. 15.

This muscle forms the floor of the mouth as does the *mylo-hyoideus* in man; it is, however, not inserted into the hyoid bone.

It arises—1. From the whole of the inner surface of the upper border of the lower jaw[1], except near the angle (Fig. 58 *sm*);

2. By a small portion (Figs. 58, 59, 61 *sm'*) near the skull, from the cartilaginous anterior cornu of the hyoid-bone which projects from the cartilaginous part of the prootic bone. This portion descends along the cornu to unite with the other portion. The two together form a membranous layer, the fibres of which run transversely and meet in a band of connective tissue along the middle line, forming a kind of *linea alba.* The sheath runs forwards to the most projecting part of the lower jaw superficially to the *m. submentalis.* Slightly in front of its posterior border the muscle is attached in its whole breadth to the skin of the throat by a fine lamella of connective tissue, which is not always complete. The posterior border of the muscle is attached to a fascia, which passes between the deeper muscles and is attached to these. It is known that this muscle plays an important part in the movements of respiration and swallowing; but its precise action has not yet been worked out.

---

[1] A second origin from the lower border of the mandible, described by Klein, is not to be found. The appearance is due to the exit of vessels and nerves from the groove between the mandible and the muscle.

18. *M. submentalis* (Fig. 59 *smt*).

Cuvier, *transversus, l. c.*, p. 588. — Dugès, 4, sous-mentonnier. — Zenker, *m. lingualis* (incorrectly brought into connection with *m. hyoglossus*).

This small muscle lies in the anterior angle of the lower jaw between the dentary bones. It consists of transverse fibres which

Fig. 58.

Muscles of the throat, chest, and abdomen of *Rana esculenta*.

sm M. submaxillaris.
sm' Hinder portion of same arising from the anterior cornu of the hyoid bone.
(For other references see page 68.)

pass from one bone to the other. Below it is covered by the most anterior portion of the *m. submaxillaris.*

Its action is to approximate the sides of the lower jaw : according to Dugès (*l. c.*, p. 123), it assists in closing the nostrils, by drawing together the sides of the lower jaw and thus raising the premaxillae.

IV. MUSCLES OF THE HYOID BONE AND THE TONGUE.

19. *M. geniohyoideus* (Figs. 59 *gh*, 60 *gh*).

Cuvier, IV, 1, 536.—Dugès, n. 16.—Zenker, p. 30.—M. St. Ange, *l. c.*, Pl. XXVI, f. 1, 13, p. 423.

Arises from the lower jaw in two portions, the one from near the middle line above the *m. submentalis,* the other more externally

Fig. 59.

Muscles of the hyoid bone and the tongue of *Rana esculenta.*

The m. submaxillaria has been removed close to its insertion.

cm' Origin of the hinder portion of same from the hyoid bone.
gh M. geniohyoideus.
gh' External portion of same.
gh'' Internal portion of same.
H Body of hyoid bone.
H' Anterior horn.
hg M. hyoglossus.
oh M. omohyoideus.
ph Mm. petrohyoidei.
sh M. sternohyoideus.
sh' External origin of same.
sh'' Internal origin of same.
sm M. submaxillaria.
sm' Origin of hinder portion of same.
smt M. submentalis.

from the upper border of the lower jaw. The two parts unite to form a long, flat muscle, which lies on the ventral surface of the body of the hyoid bone, and divides posteriorly into two portions. One of these, the median (Figs. 59, 60 *gh''*), is inserted into the inner border of the posterior horn of the hyoid bone, and is here attached to a fascia which covers the *m. hyoglossus* from beneath. By the same fascia the muscles of opposite sides are connected in the space between the two posterior cornua. The lateral division (Figs. 59, 60 *gh'*) is attached to the posterior cartilaginous process of the hyoid bone.

20. *M. sternohyoideus* (Figs. 59, 60 *sh*).

Cuvier, IV, 1, 538 (*pubio-hyoideus*). — Dugès, n. 17, sterno-xipho-hyoidien.—Zenker, p. 30.

This muscle forms the cervical part of the *m. rectus abdominis* and is, in fact, a direct continuation of it. It arises by an inner portion (Fig. 59 *sh''*) from the upper surface of the inner extremity of the coracoid and from the xiphisternum, while the

outer portion (*sh'*) is an immediate continuation of the *m. rectus abdominis*, which passes into this muscle at about the fifth *inscriptio tendinea.* The muscle passes forwards on the upper surface of the coracoid and of the clavicle, under the pericardium towards the hyoid bone; here the muscle, hitherto horizontal, suddenly becomes (compare Fig. 60) vertical, and passes between the two insertions of the *m. geniohyoideus*, and is inserted for a considerable length into the lower surface of the hyoid bone and the anterior extremity of the posterior cornu.

Fig. 60.

Muscles of the tongue and of the hyoid bone of *Rana esculenta*, from below.

gh   M. geniohyoideus.
gh'   External origin }
gh''   Internal origin } of same.
H   Body of hyoid.
H'   Anterior cornu.
H''   Posterior cornu.
hg   M. hyoglossus.
hg'   Hinder origin of same.
oh   M. omohyoideus.
*ph.*1, 2, 3, 4, first, second, third, and fourth
     m. petrohyoideus.
sh   M. sternohyoideus.

21. *M. omohyoideus* (Figs. 59, 60 *oh*).

> Cuvier, *l. c.*, p. 539.—Dugès, n. 18, interscapulo-hyoidien ou omohyoidien. — Zenker, p. 31. — M. St. Ange, *l. c.*

Arises from the anterior border of the bony scapula, and is inserted into the outer part of the ventral surface of the body of the hyoid : it is partially covered by the *m. sternohyoideus.*

22. *M. petrohyoideus anterior* (Ecker), (Fig. 61 *ph*1).

> Dugès, 10, rupéo-cérato-hyoidien.—Zenker, *m. petro-ceraus?* p. 30.— Klein, *basio-hyoideus, l. c.*, p. 71.

A thin, flat muscle, narrow above, but broadening rapidly below, which arising from the outer extremity of the prootic bone, partially surrounds the pharynx below, into which some of its fibres are inserted ; it is attached to the ventral surface of the body of the hyoid bone, near the lateral notch. The chief action of this muscle appears to be that of a *m. constrictor pharyngis.*

23, 24, 25. *Mm. petrohyoidei posteriores* (Ecker), (Figs. 61 *ph* 2, 3, 4).

> Cuvier, *mm. stylohyoidei, l. c.*, p. 537.—Dugès, 20, 21, 22, masto-hyoideus (Fig. 4).— Zenker, *petro-hyoideus superior* and *inferior.*— Klein, *stylo-hyoideus, l. c.*, p. 18.

These are three long, thin muscles, which lie nearly parallel to one another, and run from the prootic bone to the posterior cornu of the hyoid bone. All three arise, covered by the *m. sternocleidomastoideus*, from the lateral extremity of the prootic, pass round the pharynx and are attached, the *m. petrohyoideus posterior primus* (Fig. 61 *ph* 2) to the anterior extremity, the *secundus* (Fig. 61 *ph* 3) to the middle; and the *tertius* (Fig. 61 *ph* 4) to the hinder extremity of the posterior horn of the hyoid bone.

Fig. 61.

Muscles of the hyoid bone of *Rana esculenta*, seen from the right side and below.

H' Anterior cornu.
H" Posterior cornu.
hg M. hyoglossus.
H H Body of hyoid bone.
ph 1 M. petrohyoideus anterior.
ph 2, 3, 4 Mm. petrohyoidei posteriores.
sm M. submaxillaris.
sm' Hinder portion of same.

26. *M. hyoglossus* (Figs. 59, 60, 61 *hg*).

> Cuvier, *l. c.*, p. 588.—Dugès, 24, hyo-glosse.

Arises from the bony posterior extremity of the hinder process of the hyoid bone (*hg'*). The muscles of the two sides pass forwards and converge to the middle line, where they unite. The azygos muscle thus formed runs forwards on the ventral surface of the hyoid bone, between the *mm. geniohyoidei*, over the anterior border of the hyoid, and passes into the tongue, where it turns backwards and runs to the tip. (For action, see tongue.)

27. *M. genioglossus.*

> Cuvier, *l. c.*, p. 587.—Meckel, *l. c.*, IV, 339.—Dugès, 23, genio-glosse.

Arises above the insertion of the *m. geniohyoideus* on either side near the middle line from the two anterior bones of the lower jaw. The two origins quickly unite to form a thick, very firm muscular belly, which in its course backwards rapidly thins, and is distributed by numerous bundles; decussating with the fibres of the *m. hyoglossus* at an acute angle, it runs on to the anterior extremity of the tongue.

II. MUSCLES OF THE TRUNK.

I. Muscles of the Abdomen.

In the formation of the abdominal wall the following muscles take part :—(1) *m. rectus abdominis,* (2) *m. obliquus externus,* (3) *m. obliquus internus,* (4) the *portia abdominalis* of the *m. pectoralis.* Above, the *m. obliquus internus* forms a kind of **diaphragm,** partially separating the abdominal from the thoracic cavity (p. 70).

28. *M. rectus abdominis* (Fig. 62 *r*).

Dugès, pubio-thoracique, n. 52.

These muscles, situated on either side of the middle line of the abdomen, are as a rule traversed by five notched *inscriptiones ten-dineae.* Each muscle arises, by a narrow, strong tendon, from the inferior border of the pubes, passes forwards, and quickly widening, divides at the second *inscriptio tendinea* (counting from behind) into two portions.

(*a*) The Outer portion (Fig. 62 *r*) runs into the *portio abdominalis* of the *m. pectoralis,* and forms the greater lateral division of that muscle.

(*b*) The Inner (*r'*) continues as the *m. rectus abdominis* and gradually narrows anteriorly. At the sternum some of the fibres (the median) are inserted into the dorsal surface of the cartilaginous plate of the xiphisternum, while the greater part of the muscle continues forwards over the coracoid to become the *m. sternohyoideus* at about the fifth *inscriptio tendinea* (p. 64).

29. *M. obliquus externus* (Fig. 63 *oe, oe'*).

Zenker, *l. c.,* p. 31, *m. obliquus.*—**Dugès,** dorso-sous-abdominal, n. 54.

The *m. obliquus externus* arises from—

(*a*) The aponeurosis covering the long muscles of the back, and by this from the spinous processes. The anterior edge of the *m. obliquus externus* covers the posterior edge of the *m. latissimus dorsi,* which arises from the inferior, ventral surface of the aponeurosis. The aponeurosis also divides laterally into two parts, one of which, the posterior, passes into the *obliquus externus,* while the anterior forms the tendon of origin of the *depressor maxillae inf.* (*dm*) (compare Fig. 66).

(*b*) A second, narrow portion, *portio omo-abdominalis* (Fig. 63 *oe'*)

(*m. xipho-adscapulaire*, Dugès, n. 62), arises from the posterior border of the scapula by a thin tendon, and becomes broader as it

Fig. 62.

Muscles of the chest, throat, and belly of *Rana esculenta*.

ch   M. coraco-humeralis.
d   M. deltoideus.
oi   M. obliquus abdom. internus.
oe   M. obliq. abdom. externus.
oe' Scapular portion of same.
oh   M. omohyoideus.
p'   Port. sternalis anterior of m. pectoralis.
p'' Port. sternalis posterior of same.
p''' Port. abdominalis of same.
r   M. rectus abdominis.
r'   Inner portion of same.
sh   M. sternohyoideus.
sm   M. submaxillaris.
sm' Hyoid origin of same.
sr   M. sternoradialis.

runs downwards and backwards, to join the anterior border of the other and larger portion.

The whole muscle is attached by its most anterior fibres to the cartilage of the xiphisternum, the rest passing into an aponeurosis

Fig. 63.

Muscles of trunk of *Rana esculenta*, from the right side.

cd	M. cutaneus femoris.
d	M. deltoideus.
d.m.	M. depressor maxillae.
i	M. infraspinatus.
ld	M. latiss. dorsi.
oe	M. obliquus abdom. externus.
oe'	Scapular origin of same.
ss	M. subscapularis.
t	M. triceps brachii.

which, inseparably connected with the *inscriptiones tendineae*, traverses the lower surface of the *m. rectus abdominalis* to the *linea alba*.

30. *M. obliquus internus* (and *transversus*), (Figs. 64, 65 *oi*).

Dugès, ileo-transverso-sous-sternal, p. 53.—Zenker, *transversus*, *l. c.*, p. 31.—Kuhl, *transversus*, *l.c.*, p. 116.

This muscle corresponds with the combined *obliquus internus* and *transversus*, and has therefore been described either as the one or the other, by various authors.

The fibres arise tendinously—

a. From the transverse processes of the vertebrae from the fourth backwards, and from the fascia covering the *mm. intertransversarii*.

b. From the iliac bone, by a strong tendon from its upper border, and by a few weaker fibres from its outer surface. The latter fibres are covered by the former, and these end posteriorly in a sharp concave border.

The muscular bundles diverge from these points, some running forwards, some backwards; the former are only partially covered by the *portio omo-abdominalis* of the *m. obliquus externus* (compare

Figs. 62, 63), in front of the anterior edge of that muscle. The posterior border of the muscle is uncovered.

Fig. 64.

Second layer of abdominal muscles of *Rana esculenta*, from the right side and below. The m. obliquus externus and the right anterior extremity has been removed.

dm M. depressor maxillae.
hg M. hyoglossus.
ld M. latissimus dorsi and infraspinatus.
oi M. obliquus internus.
oi' Insertion of third portion of same.
oi'' Second portion inserted into the pharynx.
pc Pericardium.
ph4. M. petrohyoideus quartus.
r M. rectus abdominis.
ss M. subscapularis.

The insertions of the muscle are very various, and as a consequence very various functions are accomplished by it.

a. The most anterior part of the muscle (Fig. 65 *oi'''*), the fibres of which run forwards, is attached—

1. Partly to the xiphisternum and the coracoid.

2. A second portion, *viz.* that arising from the transverse processes of the fourth vertebra (Fig. 64 *oi''*), surrounds the pharynx like a diaphragm (Fig. 65 *oe*), and is attached to its side as far as the dorsal aspect (Fig. 65 *oi'*). This portion is lightly separated from the following.

3. A third portion, placed behind the preceding, runs from the pharynx over the pericardium (Fig. 64 *pc*), and is attached to this nearly as far as the middle line (Figs. 64 *oi'* and 65 *oi''*), resting on the sternum, the *m. rectus* and *m. sterno-hyoideus.* The lines of insertion of the muscles of opposite sides form an angle, open in front. In the thin borders of this portion the muscular bundles lie almost entirely in simple layers, and they are therefore well adapted for microscopical purposes.

b. The middle and posterior portions of the muscle pass down-

wards and slightly backwards, towards the outer border of the *m. rectus*; there they pass into a tendon which, for the most part, runs on the upper surface of the *rectus* to the *linea alba*.

II. MUSCLES OF THE BACK.

The muscles of the back are covered by a fascia, the **fascia dorsalis** (Fig. 66 *fd*), attached to the spinous processes of the vertebrae. Anteriorly, where it covers the *m. temporalis*, it is attached to the frontoparietal and squamosal bones, posteriorly to the superior border of the iliac bones and the extremity of the urostyle. The posterior part, which covers the origins of the *m. longissimus dorsi*, of the *m. coccygeo-iliacus*, and of the *coccygeo-lumbaris*, is especially strong. From the anterior part several muscles arise laterally, viz. a portion of the *m. obliquus abdominalis externus*, of the *m. latissimus dorsi*, and of the *m. depressor maxillae inferioris*. In the uppermost layer, immediately covered by the *fascia dorsalis*, lie the *m. cucullaris*, the *m. retrahens scapulae*, the *m. latissimus dorsi* arising from the fascia itself, and the scapula with its muscles; then come the long muscles of the back; and in the third and deepest layer the short muscles of the back.

Fig. 65.

M. obliquus internus, showing its attachments superiorly.

h   Xiphisternum.
oe   Oesophagus.
oi   M. obliquus internus.
oi'   Fibres of m. obliq. int., which are inserted into the oesophagus.
oi'' oi'''   Fibres of same, which are attached to coracoid and xiphisternum.
p   Pericardium.
r   M. rectus abdominis.

The individual muscles are as follows:—

A. *LIMB MUSCLES OF THE BACK* (for moving the shoulder-girdle and arm).

31. *M. cucullaris* (Fig. 66 *c*).

    Cuvier, *angularis*.—**Dugès,** n. 38, sous-occipito adscapulaire.—**Zenker,** *levator scapulae sublimis*.

In order to see this muscle, it is necessary to separate the *fascia dorsalis* from the spines of the vertebrae and to turn it back with the *m. depressor maxillae inf.* arising from it. It is then seen to

rise from the posterior surface of the exoccipital as far as the middle line; the muscles of the two sides run backwards, diverging each from the other, so as to form an angle, and are then attached on each side to the anterior superior angle of the suprascapula at its under surface and median border.

Cuvier considers this muscle as the analogue of the *m. levator anguli scapulae*. Dugès and Meckel consider it to be the anterior part of the *m. cucullaris*, the former thinking the posterior part of the muscle to be the *m. rhomboideus*. I cannot agree with these opinions, and I regard the muscle as simply representing the *m. cucullaris* of man (Ecker).

32. *M. latissimus dorsi* (Figs. 56, 66 *ld*).

Dugès, n. 66, lombo-huméral.—**Zenker**, *depressor brachii*.

This thin, triangular muscle arises from the ventral surface of the *fascia dorsalis*, and is posteriorly covered in part by the anterior border of the *m. obliquus abdominis externus*. The muscle becomes narrower towards the sides, and passes into a flat tendon, which blends with that of the *m. infraspinatus*, and is attached to the outer surface of the *crista deltoidea* of the humerus by a triangular expansion.

Fig. 66.

Muscles of the back and shoulder-blade.

c M. cucullaris.
dm M. depressor maxillae arising from the fascia dorsalis, cut through and reflected on the right side.
fd Fascia dorsalis.
fd' Same cut through at the spines.
i M. infraspinatus.
l.a M. levator anguli scapulae.
ld M. Latissimus dorsi.
r M. retrahens scapulae.
sc M. sternocleidomastoideus.

33. *M. retrahens scapulae* (Ecker), (Fig. 66 *r*).

Dugès, n. 59, lombo-adscapulaire. —**Klein**, *m. rhomboideus, l. c.*, p. 26. — **Zenker**, *omoplateus rectus?* p. 37, *l. c.*—**Kuhl**, *l. c.*, 124, *retrahens rhomboideus*.

This flat, oblong muscle arises from the transverse process of the fourth vertebra, and is connected with the third tendinous inscription (counting from before) of the *m. longiss. dorsi*. Posteriorly its origin forms a convex border, whence it runs forwards and to the side; it is inserted into the ventral surface of the suprascapula, near its inner border.

This muscle lies near the *m. serratus* or *transv. scap. tertius* (Fig. 68 *ts"*), and has an analogous position. It would, therefore, possibly be more correct to regard it also as a *m. serratus*. It arises from parts which represent ribs, and is inserted into the scapula. It has, at any rate, no analogy to the *m. cucullaris*, with which Dugès connects it, nor with the *m. rhomboideus*, which Klein holds it to be, as it does not arise from spinous processes.

B. *Long Muscles of the Back.*

34. *M. extensor dorsi communis* (Fig. 67 *lg.d.*).

> Dugès, n. 33–40, masse des muscles surspinaux devisée en huit faisceaux principaux : 1. vertebro-sus-occipital, 2–5. transverso-spinaux, 6. transverso-coccyg., 7. sacro-coccygien, 8. ileo-coccygien. The muscles 1–7 form the lombo-costal, 8 the ischicoccyg., Cuv.—Zenker, *m. sacrolumbaris.*—Klein, *longiss. dorsi, coccygeo-lumb., coccyg.-iliac.*

This muscular mass is covered by the *fascia dorsalis*, the *m. cucullaris* and *retrahens scapula*, and the suprascapula : it corresponds with (1) the *m. ileo-costalis* and *longissimus dorsi, dorsi* and *cervicis* (Henle); (2) the *semispinalis* and *spinalis* (Henle).

The following separate portions may be made out :—

35. (1) *M. longiss. dorsi* (Fig. 67 *lg.d.*).

This muscle arises from the most anterior part of the urostyle, runs forwards near the middle line, separated from the muscle of the opposite side by the spinous processes of the vertebrae. The inner portion passes over the posterior spinous processes without being connected with them, as far as the fifth, it is then inserted into the succeeding spines as far as the exoccipital bone. The lateral portion runs outwards and forwards to be attached to the transverse processes and oblique processes of all the vertebrae, from the sixth forwards, while accessory muscular slips arise from the transverse processes and from the anterior spinous processes which, merging in the general muscle-mass, are inserted with this into the occiput.

The muscle is subdivided by a series of wavy, tendinous partitions (Fig. 67), which arise from the transverse processes, and traverse the muscle in planes, the upper surfaces of which are directed upwards and forwards. This arrangement of the muscle indicates its relation with the lateral trunk muscles of fish and fish-like amphibians.

36. (2) *M. coccygeo-sacralis* (Fig. 67 *c.l.*).

This muscle is partially covered by the preceding, it arises from the lateral surfaces of the anterior half of the urostyle; from this

origin the fibres pass forwards and outwards to be inserted in two portions, the anterior set into the arch and the posterior set into the transverse process of the last vertebra. The former may be regarded as *m. intercruralis*, the latter as *m. intertransversarius*.

Fig. 67.

Muscles of the back and pelvic girdle of *Rana esculenta*.

c.i.	M. coccygeo-iliacus.
c.l.	M. coccygeo-sacralis.
g.l.	M. glutaeus.
i	MM. intertransversarii.
i'	MM. intercrurales.
i.c.i.	M. intertransv. capitis inferior.
i.c.s.	M. intertr. cap. sup.
il.	M. ilio-lumbaris.
lg.d	M. longissimus dorsi.
o.i.	M. obliq. internus.
t	M. temporalis.

37. (3) *M. coccygeo-iliacus* (Fig. 67 *c.i.*).

This muscle arises from nearly the whole length of the lateral surface of the urostyle, the anterior portion being concealed by the preceding muscle. The fibres pass outwards and forwards to be inserted into the anterior two-thirds of the inner surface of the ilium.

38. *M. ilio-lumbaris* (Klein), (Fig. 67 *il.*).

Duges, n. 51, transverso-iliaque.—Cuvier, Zenker, etc., *quadr. lumborum*.

Evidently represents the *quadratus lumborum* of human anatomy; it takes its origin from the anterior extremity of the ilium, and runs forwards to be inserted into the transverse processes of the vertebrae from the seventh to the fourth.

C. *Short Muscles of the Back.*

39. *M. intertransversarius capitis superior* (Ecker), (Fig. 67 *i.c.s.*).

Dugès, n. 41, ex-occipito-transversaire sup.

A small muscle arising from the prootic : it lies above the *levator anguli scapulae,* and is inserted into the transverse process of the second vertebra.

40. *M. intertransversarius capitis inferior* (Fig. 67 *i.c.i.*).

Dugès, n. 42, ex-occipito-transv. inf.

This muscle lies on the ventral surface of the preceding one, but is easily separable from it; it arises from the angle of the prootic and is inserted, together with the preceding muscle, into the transverse process of the third vertebra. The *n. vagus* passes outwards between these two muscles.

41. *MM. intertransversarii dorsi* (Fig. 67 *i*).

Dugès, n. 43 to 50, intertransversaires.

Seven small muscles, placed between adjacent transverse processes of the vertebrae; from the second to the last, in continuity with the muscles last mentioned.

42. *MM. intercrurales* (Ecker), (Fig. 67 *i'*).

Klein, p. 29, interspinales, interobliqui.

Those muscular fibres found between the arches of adjacent vertebrae are so named. On account of the shortness of the spinous processes they can scarcely be named *m. interspinales.*

III. MUSCLES OF THE ANTERIOR EXTREMITY.

I. Muscles of the Shoulder-girdle.

A. *Dorsal Muscles of the Shoulder-blade.*

(I.) Muscles arising from the head or trunk, and inserted into the scapulae, which they act upon primarily, and upon the shoulder-girdles secondarily.

Some of these muscles, such as *m. cucullaris* and *retrahens,* are situated on the back, and have already been described with the muscles of that region. Others are attached partly to the under-surfaces of the scapulae and are only visible from below; they are best seen in such a preparation as is shown in Fig. 68, made by cutting through the sternum in the middle line, and reflecting each half outwards.

(a) *Muscles which arise from the skull.*

43. *M. levator anguli scapulae* (Fig. 68 *la*).

> Dugès, sous-occipito-adscapulaire, n. 60.—Zenker, *protractor scapulae*,
> Pl. I, Fig. 5.—Cuvier, Leçons I, p. 379, describes this muscle as part
> of the *m. serratus anticus magnus.*

A fairly strong muscle, which has a broad origin from the prootic
and exoccipital bones as far as the *foramen magnum*, a few fibres
are also attached to the lateral portions of the parasphenoid.   The
fibres run backwards and outwards, first in a frontal plane and
then in a sagittal plane, to be inserted into the under surface of
the suprascapula near the posterior border, where it encloses the
hinder border of the *m. interscapularis.*

Its action is to draw the shoulders forwards and inwards, or the
head downwards.

44. *M. sternocleidomastoideus* (Fig. 68 *sc*).

> Dugès, scapulo-mastoidien, n. 65.—Cuvier, sterno-mastoidien.—Zenker,
> *protractor scapulae*, Pl. I, Fig. 5, 1.

A narrow muscle placed in front of and externally to the pre-
ceding muscle; its general direction resembles that of the *m. levator
ang. scap.*

The fibres arise from the most external part of the prootic and
from the hindermost part of the squamosal, under cover of the
m. digastricus maxillae, and from the hinder portion of the cartila-
ginous tympanic ring.   Covered by these muscles, it passes
backwards and downwards to be inserted into the concavity of
the anterior border of the scapula; externally to the origin of
the deltoid.

The action of this muscle is to draw the shoulder forwards
and towards the middle line, or to bend the head downwards.

45. *M. protrahens scapulae* (Fig. 68 *ps*).

> Dugès, Zenker, *protractor acromii*, Pl. I, Fig. 5, 3.

· This muscle lies to the outer side of the *rectus capitis inferior*:
it arises from the prootic, and runs backwards and outwards upon the
levator anguli scapulae, to be inserted into the scapula.

It pulls the scapula forwards.

(b) *Muscles which arise from the vertebrae.*

46. *M. transverso-scapularis major* (Ecker), (Fig. 68 *ts*).

> Dugès, transverso-interscapulaire, n. 63.—Cuvier, *l. c.*, p. 380, probably regarded as a portion of the *serratus.*—Zenker, Pl. I, Fig. 5, 3 ; *depressor acromii*, Pl. II, Fig. 3, 15.—Klein, *depressor scapulae.*

This muscle arises by tendon from the cartilage of the transverse process of the fourth vertebra and by a slip from the cartilage of the transverse process of the third vertebra. Diminishing in size, the muscle passes outwards, forwards, and upwards to be inserted into the posterior border of the scapula, opposite the insertion of the *m. sternocleidomastoideus.* It draws the shoulder inwards, backwards, and downwards.

47. *M. transverso-scapularis minor* (Ecker), (Fig. 68 *ts'*).

> Dugès, transverso-adscapulaire, n. 61.—Cuvier, regarded as part of the *serratus.*—Zenker, Pl. I, Fig. 5, 7, *detractor scapulae.*

This is much shorter than the muscle just described; it arises under cover of the *m. levator scapulae*, from the transverse process of the third vertebra in front of the *transverso-scapularis major*; and runs outwards and forwards to be inserted into the ventral surface of the cartilage of the scapula. The action of the muscle is to draw the shoulder inwards, backwards, and outwards. Dugès regards this muscle as a portion of the *serratus anticus magnus,* the remainder of which he considers is to be found in the *portio scapularis* of the *m. obliquus externus* (xipho-adscapulaire, Dugès, n. 62).

Fig. 68.

Muscles of the shoulder, from below ; the sternum has been cut through and the sides drawn apart.

d	Deltoideus.
is	Interscapularis.
it	Intertransversarii.
la	Lev. anguli scapulae.
ps	Protrahens scapulae.
sc	Sternocleidomastoideus.
ss	Subscapularis.
ts	Transverso-scap. major.
ts'	Transverso-scap. minor.
ts''	Transverso-scap. tertius.

48. *M. transverso-scapularis tertius s. serratus* (Ecker), (Fig. 68 *ts''*).

This is larger than the muscle just described; arising by a broad and flat origin from the transverse processes of third and fourth vertebrae, it runs upwards and inwards to be inserted into the ventral surface of the cartilaginous scapula near its inner border. In position, course, and action the muscle most nearly represents the *m. serratus anticus* of human anatomy.

(II.) Muscles on the scapula, that is, arising from the scapula and inserted into the scapula or humerus.

(a) *Muscles on the deeper surface.*

Fig. 69.

Muscles of right shoulder and upper arm. The coracoids (*co*) and the clavicles (*cl*) have been drawn apart after cutting through the sternum.

c.h.   M. coraco-humeralis.
cl   Clavicle.
c.o.   Coracoid.
d   M. deltoideus.
d'   Clavicular portion of m. deltoideus.
i   M. infraspinatus.
i.s.   M. interscapularis.
l.a.   M. levator anguli scapulae.
l.d.   M. latissimus dorsi.
p'   Sternal portion of m. deltoideus.
p''   Anterior sternal portion of the m. pectoralis.
p'''   Posterior sternal portion of the m. pectoralis.
s   Scapula.
s.r.   M. sternoradialis.
t.r.   M. triceps brachii.

49. *M. interscapularis* (Fig. 69 *i.s.*).

Dugès, interscapulaire, n. 64.

One end of this muscle is tendinous, and is attached to the outer extremity of the suprascapula; from this the muscle, becoming fleshy and narrower, runs towards the middle line to become attached to the ridge on the ventral surface of the scapula, from which the *m. deltoideus* and the *m. subscapularis* arise, and between which it passes. It approximates the scapula and suprascapula and lessens the angle between them.

50. *M. subscapularis* (Fig. 70 *ss*).

Dugès, sous-scapulo huméral, n. 72.

This muscle is situated on

the upper or visceral surface of the scapula. It arises from a bony ridge found on the upper surface of the coracoid and of the *proc. coracoideus* of the scapula. The muscle runs outwards and is inserted, after widening, into the inner surface of the *crista deltoidea* of the humerus; it is antagonistic to the deltoid, and draws the raised arm backwards and towards the trunk.

Fig. 70.

Right shoulder, from below, arm strongly abducted.

cl Clavicle.
co Coracoid.
d Deltoideus.
d' Clavicular portion of deltoid.
h Humerus.
ss Subscapular muscle.

(b) *Muscles on the superficial surface.*

51. *M. infraspinatus* (Fig. 57, between *ld* and *dm*, Fig. 71 *i*).

Dugès, adscapulo-huméral, n. 67.

The *m. infraspinatus* represents the *m. infraspinatus, teres major* and *minor* of human anatomy. It is of triangular form, with the broad base directed inwards; it arises from the whole of the upper surface of the suprascapula except along the inner border which is formed of hyaline cartilage alone: from this origin the fibres converge outwards to a flat tendon which unites with that of the *m. latissimus dorsi* to be inserted into the *crista deltoidea humeri,* by means of a thin, triangular, tendinous expansion.

Fig. 71.

Muscles of the back and shoulder.

c M. cucullaris.
dm M. depressor maxillae.
ftl Fascia dorsalis.
fd' Fascia dorsalis reflected.
i M. infraspinatus.
l.a M. levator anguli scapulae.
ld M. latissimus dorsi.
r M. retrahens scapulae.
sc M. sternocleidomastoideus.

General arrangement of the muscles of the shoulder-blade.
The muscles attached to the scapula and suprascapula are :

1. Muscles of the back (*m. cucullaris* and *m. retrahens scap.*).
2. Muscles of the neck (*m. omohyoideus*).
3. Muscles of the abdomen (*portio scapularis* of the *m. obliquus externus*).
4. True shoulder muscles (*m. levator anguli scapulae*; *m. sternocleidomastoideus*; *m. protrahens scapulae*; *mm. transverso-scapularis major, minor*, and *tertius s. serratus*; *m. interscapularis*; *m. subscapularis*; and the long head of the *m. triceps*).

From above the following are visible : *m. cucullaris*, a portion of the *m. subscapularis*, and the *transverso-scapularis maior*.

From below (after cutting through and drawing aside the two halves of the sternum) may be seen : the *omohyoideus, sternocleidomastoideus, levator anguli scapulae, protrahens scapulae, transverso-scapularis minor* and *tertius, interscapularis* and *subscapularis*.

B. Ventral Muscles of the Shoulder (Pectoral Muscles.)

These arise from the sternum or shoulder-girdle and are inserted either into the humerus or into the radio-ulnar.

52. *M. pectoralis* (Fig. 72).

This is placed on the ventral surface of the shoulder-girdle and consists of the following parts :

(a) *Portio sternalis anterior* (Ecker), (Figs. 72, 73 *p'*).

> Dugès, clavi-huméral, n. 70 (port. clavic. du grand pectoral).

This is the anterior portion of the *m. pectoralis*, it arises from the sternum proper and the epicoracoids. Broad at the origin, it becomes narrower as it runs outwards into a tendon attached to the *crista deltoidea humeri*.

(β) *Portio sternalis posterior* (Ecker), (Figs. 72, 73 *p"*).

> Dugès, sterno-huméral, n. 71 (port. sternal du grand pectoral).—Klein, *humero-sternalis*.

This muscle is placed immediately behind the *portio sternalis anterior*, it has a somewhat broad origin from the sternum and xiphisternum ; the muscle runs outwards and slightly forwards to be inserted into the groove beside the *crista deltoidea humeri*. The tendon of the *m. sterno-radialis* passes between these two portions of the *m. pectoralis*.

(γ) *Portio abdominalis* (Figs. 72, 73 *p'''*).

Dugès, abdomino-huméral, n. 69 (port. costal du grand pectoral).—
Zenker, *brachio-abdominalis.*—**Klein,** *humero-abdominalis.*

This portion represents that part of *m. pectoralis major* of human

Fig. 72.

Muscles of the chest, throat, and belly of *Rana esculenta.*

ch	M. coraco-humeralis.
d	M. deltoideus.
oi	M. obliquus abdom. internus.
oe	M. obliq. abdom. externus.
oe'	Scapular portion of same.
oh	M. omohyoideus.
p'	Port. sternalis anterior to m. pectoralis.
p''	Port. sternalis posterior to same.
p'''	Port. abdominalis of same.
r	M. rectus abdominis.
r'	Inner portion of same.
sh	M. sternohyoideus.
sm	M. submaxillaris.
sm'	Hyoid origin of same.
sr	M. sternoradialis.

G

anatomy which arises from the costal cartilages, and more par-
ticularly that part which is connected with the aponeurosis of the
m. obliquus abdominis externus.   The muscle arises (1) from the
m. rectus abdominis (Fig. 72 *r*), that is, it forms a direct continua-
tion of the outer portion of this muscle; (2) the inner, smaller part
arises from the superficial surface of the aponeurosis of the *m. obli-
quus abdominis.*   The muscle becomes narrower as it courses out-
wards and forwards, the outer fibres being longer and more oblique
than the inner.   The action of this muscle will necessarily vary
according to the part or parts which are brought into action;
speaking generally, the anterior extremities will be drawn down-
wards and towards each other.

53. *M. coraco-humeralis* (Dugès), (Figs. 72, 73 *c.h.*).
        Dugès, n. 72.—**Klein,** *adductor humeri.*

A long, narrow muscle, lying upon the posterior border of the
coracoid and the lowest part of the *m. subscapularis.*   By its posi-
tion it corresponds most nearly with the *m. pectoralis minor,* although
its insertion does not.   It has a narrow origin from the coracoid
near the sternum, whence it courses outwards, under cover of the
port. sternalis anterior and *posterior* of the *m. pectoralis,* to be inserted
into the middle of the humerus between the deltoid and internal
head of the triceps.   It draws the limb towards the trunk.

54. *M. sternoradialis* (Cuvier), (Figs. 72, 73 *s.r.*).
        Dugès, pré-sterno-clavi-radial, n. 74.

This muscle evidently represents the biceps of man, it lies in
front of the *portio sternalis anterior* of the *m. pectoralis,* its hinder
border being under cover of the latter muscle.   It takes origin from
the episternum, omosternum, and the epicoracoid; from this broad
origin the fibres converge while coursing backwards and outwards to
be attached to a strong tendon.   This tendon plays in a groove along
the *crista deltoidea,* and is held in position by tendinous bands
arising from the insertion of the *m. pectoralis;* it then pierces the
lower portion of the muscular belly of the deltoid, and is inserted
into the anterior extremity of the radial side of the radio-ulnar.
The muscle is a powerful flexor of the forearm.

55. *M. deltoideus* (Figs. 70, 72, 73 *d*).
        Dugès, pré-sterno-scapulo-huméral, n. 68.

It is placed in front of and external to the *m. sternoradialis,* and
represents both the *m. deltoideus* and *supraspinatus* of man.   The
muscle has two points of origin :—

Fig. 73.

Muscle of right shoulder and upper arm. The coracoids (*co*) and the clavicles (*cl*) have been drawn asunder after cutting through the sternum.

c.h. M. coraco-humeralis.
cl Clavicle.
c.o. Coracoid.
d M. deltoideus.
d' Clavicular portion of m. deltoides.
i M. infraspinatus.
i.s. M. interscapularia.
l.a. M. evator anguli scapulae.
l.d. M. latissimus dorsi.
p' Sternal portion of m. deltoides.
p'' Anterior sternal portion of the m. pectoralis.
p''' Posterior sternal portion of the m. pectoralis.
s Scapula.
s.r. M. sternoradialis.
t.r. M. triceps brachii.

(a) *Portio scapularis*, the larger, external portion is attached to the outer end of the clavicle, and to the anterior process of the precoracoid, but it arises chiefly from the dorsal surface of the scapula (from the same ridge as the *m. subscapularis*), and lastly from the anterior border and ventral surface of the scapula. The fibres pass outwards over the shoulder-joint.

(b) *Pars clavicularis* (*musc. cleido-humeralis*, Klein) arises from the inner extremity of the clavicle and from the omosternum and joins the *portio scapularis*.

The muscle is inserted into the humerus, the under part of the *portio scapularis* being attached to the upper portion of the *crista deltoidea*; the outer fibres of this part, together with those of the *pars clavicularis*, are attached to the extremity of the *crista deltoidea* and to the inner surface of the humerus as far as the distal extremity; just before its insertion the muscle is pierced by the tendon of the *m. sternoradialis*. The deltoid draws the limb forwards.

II. MUSCLES OF THE FORE-LIMB.

A. *MUSCLES OF THE ARM.*

M. sternoradialis (*biceps*). See page 82.

56. *M. triceps brachii* (Fig. 73 *t.r.*).

Dugès, scapulo-huméro-olecranien, n. 75.—Capes, Zenker, *m. anconaeus*.

This muscle lies on the upper or dorsal surface of the arm, and has relations similar to those of the corresponding muscle in man. The long head arises from the posterior border of the scapula at the upper border of the glenoid cavity, and is here attached to the capsule of the joint; the inner head arises from the upper and inner surfaces

G 2

of the anterior half of the humerus as far as the extremity; the outer head arises from the outer surface of the humerus. Additional fibres, which may be regarded as a fourth origin (*m. subanconaeus*), arise from the upper surface of the hinder half of the humerus. The fibres from these several origins unite to form a strong muscle, which covers the upper, inner, and outer surfaces of the bone, and then passes into a tendon. This tendon is attached to the capsule of the elbow-joint and inserted into the proximal extremity of the radio-ulnar. A cartilage, representing the olecranon, is found in the capsule at the point of attachment of the tendon.

B. MUSCLES OF THE FOREARM.

(I.) Muscles of the flexor surface.

The muscles of this surface are arranged in two groups, so as to form, at the elbow-joint, a triangular depression (*plica cubiti*), into which the tendon of the *m. sternoradialis* sinks.

A. Muscles of the Inner Group.

Fig. 74.

Muscles of the right arm of
Rana esculenta.

ed M. extens. digitorum communis.
rl M. abductor digiti II longus.
Fa′ M. flexor antibrachii lateralis superficialis.
Fc M. flexor carpi radial.
Fc′ M. flexor carpi ulnar.
Fd M. flexor digitorum communis.
sr Tendon of the M. sternoradialis.

57. *M. flexor carpi I s. radialis* (Fig. 74 *Fc*).

Dugès, sous-huméro-carpien, n. 83.

This represents either the *flexor carpi radialis longior* or *radialis brevior* of man; it has a broad origin from the inner border of the humerus above the epicondylus medialis. It becomes narrower as it passes downwards to be inserted by a tendon into the *os semilunare* and *naviculare*. The muscle is much stronger in males than in females, and the crest from which it takes origin is correspondingly larger in the former sex (p. 42). Tendinous fibres connect it with the following muscles:—

58. *M. flexor carpi II s. ulnaris* (Fig. 74 *Fc′*).

Dugès, epitrochlo-carpien, n. 84.

This muscle represents the *flexor carpi ulnaris* or *ulnaris anterior*, and is close to the inner side of the foregoing. It arises from the *epicondylus medialis*, being connected by fibres with the *flexor digitorum communis*, and is inserted into the *os naviculare*.

59. *M. flexor digitorum communis* (Figs. 75, 76, 77 *Fd*).

Dugès, epitrochlo-sous-phalangettien, n. 118.

This muscle lies most internally, and corresponds to the *m. flexor digitorum sublimis* of man. It arises in common with the foregoing muscle from the *epicondylus medialis*, and runs downwards to the palm of the hand. At its entrance into this it diminishes and passes into the flat *aponeurosis palmaris*. (See hand, B.)

60. *M. flexor antibrachii medialis* (Ecker), (Fig. 75 *Fa*).

Dugès, epitrochlo-sous-radial, n. 79. (Frequently described as the *pronator rotundus*, a description which cannot be retained, as the implied movement does not occur in the frog.—Ecker.)

This muscle lies deeply on the inner side of the forearm, covered by the *flexores carpi*; it arises tendinously from the *epicondylus medialis* and is inserted into the inner surface of the radial side of the radio-ulnar as far as the inferior articular extremity.

61. *M. flexor antibrachii lateralis superficialis* (Ecker), (Figs. 74, 75 *Fa'*).

Dugès, premier ex-huméro-radial, n. 76. (Usually described as *supinator longus*, this, for reasons similar to those in the case of *m. flexor antibrachii medialis*, cannot be retained.)

Fig. 75.

The situation of this muscle corresponds with that of the *supinator longus* of man; it lies to the outer side of the tendon of the *m. sternoradialis*, and arises by two heads, the one, above from the outer edge of the humerus, the other deeper from the *epicondylus lateralis*. They unite and pass into a tendon which, running over the lower articular extremity of the radio-ulnar, is partly attached to the carpus and partly connected with the tendon of the *m. extensor digiti II proprius longus*. From its position and insertion, this muscle evidently flexes the forearm and extends the hand.

Muscles of the right arm of *Rana esculenta*, deep layer.

ed Extensor digit. communis.
Fa Flexor antibrachii medialis.
Fa' Flexor antibrachii lat. super ficialis.
Fa" Flexor antibr. lat. profundus.
Fc Flexor carpi radialis.
Fc' Flexor carpi ulnaris.
Fd Flexor digitorum communis.

62. *M. flexor antibrachii lateralis profundus* (Ecker), (Fig. 75 *Fa"*).

Dugès, epicondylo-sus-radial, n. 78.—Klein, *flexor antibrachii*. (Supinat. brevis autt.)

This muscle arises under cover of the foregoing, from the *epicondylus lateralis* of the outer surface of the humerus, it becomes

broader and is inserted into the whole length of the lower (volar)
ridge of the radio-ulnar. It is a powerful flexor of the forearm.

(II.) Muscles of the extensor surface.

63. *M. extensor digitorum communis longus* (Fig. 75 *ed*).

       Dugès, huméro-sus-digital, n. 95.

This muscle lies on the outer border of the forearm ; it arises in
common with the short head of the *flexor antibr. lateralis superfici-
alis* from the *epicondylus lateralis*, and from the surface above it ;
it runs downwards along the outer side of the forearm, in order to
pass into an aponeurosis on the back of the hand, which expands
upon the third, fourth, and fifth fingers, and ends between them in
a free concave border. This aponeurotic expansion is connected
with the tendons of the *extensor brevis digitorum*.

63*. *M. abductor digiti II (i. e. pollicis) longus* (Fig. 74 *ei*).

       *Dugès, cubito-métacarpien, n. 87.

This muscle lies between the foregoing and the *flexor antibrachii
lateralis superficialis*, and appears superficially in the interval between

Fig. 76.

them. It arises from the lateral surface of the
radio-ulnar, and runs obliquely over the *m. flexor
antibrachii lateralis profundus* and the hinder
extremity of the radio-ulnar towards the second
finger into the metacarpal bones of which it is
inserted.

    64. *M. extensor carpi ulnaris s. ulnaris post.*
(Fig. 76 *ec*).

       Dugès, epicondylo-sous-carpien, n. 85.—**Klein**,
          abductor carpi internus.

This muscle has a somewhat narrow origin
from the *epicondylus lateralis* ; during its course
through the forearm, where it lies between the
mm. anconaei on the one side and the *extensor
digitorum communi* on the other, it becomes

Muscles of forearm of
Rana esculenta, dorsal
view.

aa M. anconaei.
ec M. extens. digit.
    communis.
Fd M. flex. digit.

broader and is inserted into the outer surface of
the carpus in the following manner. By one
tendinous slip it is attached to the palmar
border of the *os pyramidale*, by a second slip
to the outer border of the *os capitato-hamatum*.
This latter slip is usually connected in its dorsal portion with the
extensor digitorum communis brevis.

65, 66. *M. anconaei s. extensores antibrachii* (Fig. 76 *aa*).

Both these muscles lie on the extensor side of the forearm; they spring, the one from the *epicondylus lateralis*, the other from the *epicondylus medialis*; converging, they run downwards, enclose the olecranon, and are inserted into the upper (dorsal) border of the ulna, each forming a penniform muscle. They are extensors of the forearm and assist the *m. triceps*.

C. MUSCLES OF THE HAND.

(I.) Muscles on the palmar surface.

(1) Muscles common to all the digits.

67. *M. flexor digitorum communis* and *m. palmaris brevis* (Fig. 77 *fd, pb*).

The origin and course of this muscle has been described above. At its entrance into the palm it suddenly diminishes in size and passes into a triangular aponeurosis, *aponeurosis palmaris*. Into the outer border of this aponeurosis is inserted the *m. palmaris brevis* (Fig. 77 *pb*); this latter muscle arises from the posterior or ulnar border of the lower extremity of the radio-ulnar below the insertion of the *mm. anconaei*, and runs obliquely downwards to this insertion.

From the lower free border of the aponeurosis a number of muscles arise which will be described with the rest of the digital muscles.

(2) Muscles of the rudimentary thumb.

68. *M. abductor pollicis* (Figs. 77, 78 *ap*).

This short muscle arises from the upper border of the lower extremity of the radio-ulnar, passes transversely outwards, and is then inserted into the anterior border of the rudimentary thumb.

69. *M. adductor pollicis* (Figs. 77, 78 *ad.p*).

This lies more superficially than the last, it arises from the palmar surface of the *os capitato-hamatum*, and is inserted together with the *abductor pollicis* into the thumb. Several fibres of the *extens. dig. II brevis* are also inserted into the thumb. As this member is completely covered with skin, the motions of which it is capable are very limited.

(3) Muscles of the second finger, which serves the purposes of a thumb. www.libtool.com.cn

70. *M. flexor digiti II longus s. sublimis* (Fig. 77 *f*2).

Dugès, sous-carpo-phalangettien de l'index, n. 133.

This is a flat muscle, which arises for the most part by fleshy fibres from the hinder free border of the *aponeurosis palmaris*, also

Fig. 77.

Muscles of hand of *Rana esculenta*, volar surface, larger than nature.

A   Aponeurosis palmaris.
*ab*5   M. abductor dig. V primus.
*ab*5′   M. abductor dig. secundus.
ac   MM. anconaei.
adp   M. adductor pollicis.
ap   M. abductor pollicis.
cc   M. extensor digitorum communis.
*c*5   M. extens. dig. commun. brevis.
*f*2   M. flexor dig. II longus.
*f*3   M. flexor dig. III longus.
*f*4   M. flexor dig. IV longus.
*f*5   M. flexor dig. V longus.
*fb*2   M. flexor dig. II brevis.
*fb*3 and *fb*3′ MM. flexores dig. III breves.
*fb*4 and *fb*4′ MM. flexores dig. IV breves.
*fb*5   M. flexor dig. V primus.
fd   M. flexor digitorum communis.
o   M. opponens.
pb   M. palmaris brevis.
I   First finger, rudimentary thumb.
II   Second finger, functions as thumb.
III–V Third to fifth fingers.

Fig. 78.

Second layer of muscles on volar surface of hand of *Rana esculenta*, larger than nature.

*ab*5   M. abductor dig. V primus.
*ab*5′   M. abductor dig. V secundus.
*ad*2   M. adductor dig. II.
ad.p   M. adductor pollicis.
ap   M. abductor pollicis.
cc   M. extensor carpi.
*fb*2   M. flexor dig. II brevis.
*fb*2′   M. flexor dig. II tertius.
fp   MM. flexores proprii phalangum.
*i*3
*i*4
*i*4′   } MM. interossei volares.
*i*5
o   M. opponens dig. II.
o′   M. opponens dig. V.
t t′   MM. transversi metacarpi.
I–V as in Fig. 77.

by a smaller part from the palmar surface of the *os capitato-hamatum*. It quickly passes into a thin long tendon which is inserted into the terminal phalanx of the thumb (second finger).

71. *M. flexor digiti II brevis s. profundus* (Fig. 77 *fb*2).

Dugès, sous-carpo-phalangien de l'index, n. 102.

This flat muscle, covered by the preceding, has a tendinous origin from the palmar surface of the *os capitato-hamatum*, together with one head of the *flexor sublimis*, and is inserted into the basal phalanx.

72. *M. flexor digiti II tertius* (Fig. 78 *fb*2′).

Dugès, tendini-phalangien de l'index, n. 103.

A small, thin muscle which arises close to the foregoing from the *os capitato-hamatum*, and is inserted into the basal phalanx (see below, *m. interosseus volaris I*).

73. *M. adductor digiti II* (Fig. 78 *ad*2).

Dugès, métacarpo-métacarpien de l'index, n. 90.

This muscle represents the *adductor pollicis* of man; it arises from the base of the third os metacarpal and is inserted into the metacarpal of the second finger, which latter it draws towards the third finger.

74. *M. opponens digiti II* (Figs. 77 and 78 *o*).

Dugès, sous-carpo-métacarpien de l'index, n. 90.

This muscle represents the muscle of like name in man. It arises from the palmar process of the *os capitato-hamatum* by a narrow tendon and passes into a broad, flat muscle, which is inserted into the under surface and outer border of the metacarpal of the second finger throughout its length. It has, undoubtedly, the same action as the corresponding muscle in man.

(4) Muscles of the third finger.

75. *M. flexor digiti III longus s. sublimis* (Fig. 77 *f*3).

The smaller portion of this muscle arises from the free border of the *aponeurosis palmaris*, the chief portion, together with the *flexor brevis*, from the palmar surface of the *os capitato-hamatum*. The two portions pass into one long tendon, which is inserted into the last phalanx.

76, 77. *MM. flexores digiti III breves s. profundi I, II* (Fig. 77 *fb*3 and *fb*3′).

Dugès. tendini-phalangiens du medius, n. 104, 105.

These two muscles arise in part from the free border of the *aponeurosis palmaris*, in part from the volar surface of the *os capitato-hamatum*, and pass backwards on either side of the muscle last described, to be inserted into the basal phalanx. Dugès regards these as analogues of the *mm. lumbricales*.

78. *M. flexor metacarpi dig. III.*

This is a somewhat strong muscle, which arises by fleshy fibres from the palmar surface of the *os capitato-hamatum*, and is inserted into the palmar surface of the metacarpal bone.

(5) Muscles of the fourth finger.

79. *M. flexor digiti IV longus s. sublimis* (Fig. 77 *f*4).

It arises at the free border of the *aponeurosis palmaris*, and is inserted into the terminal phalanx by a thin tendon.

80, 81. *MM. flexores digiti IV breves s. profundi I, II* (Fig. 77 *fb*4 and *fb*4′).

Dugès, tendini-phalangiens de l'annulaire, n. 108, 109.

Dugès regards these also as analogues of the *m. lumbricales*; they arise on either side of the foregoing muscle from the free border of the *aponeurosis palmaris*, and are inserted by tendons into the basal phalanx.

82. *M. flexor proprius phalangum dig. IV* (Fig. 78 *fp*).

Dugès, phalango-phalangien, n. 115.

A small muscle which arises by two slips from the palmar surface of the basal phalanx, and is inserted into the base of the middle phalanx.

83. *M. flexor metacarpi dig. IV* (Fig. 78 *i*4).

This somewhat strong muscle arises from the *os capitato-hamatum*, and is inserted into the palmar surface of the metacarpal bone.

(6) Muscles of the fifth finger.

84. *M. flexor dig. V longus s. sublimis* (Fig. 77 *f*5).

This corresponds exactly with the corresponding muscle of the fourth finger.

85. *M. flexor dig. V brevis* (Fig. 77 *fb*5).

This muscle arises from the free border of the aponeurosis and is inserted into the basal phalanx.

86. *M. flexor proprius phalangum dig. V* (Fig. 78 *fp*).

Dugès, phalango-phalangien, n. 17.

It corresponds exactly with the corresponding muscle of the fourth finger.

87. *M. opponens dig. V* (Fig. 78 *o*′).

Dugès, deuxième sous-carpo-métacarpien du digitule, n. 92.

This muscle has a narrow origin from the palmar surface of the

os capitato-hamatum, it widens and is inserted into the outer border of the metacarpal of the small finger. It draws this finger towards the thumb.

88. *M. abductor dig. V primus* (Figs. 77 and 78 *ab*5).

Dugès, sous-pyro-pré-métacarpien du digitule, n. 93.

This muscle arises from the palmar border and the outer surface of the *os pyramidale,* and is inserted into the basal phalanx by a thin tendon.

89. *M. abductor dig. V secundus* (Figs. 77 and 78 *ab*5′).

Dugès, sous-pyro-post-métacarpien du digitule, n. 94.

It arises from the posterior part of the *os pyramidale,* is short, and is inserted into the outer side of the metacarpal.

(II.) Muscles on the dorsal surface.

M. extensor digitorum communis longus (Figs. 75 *ed* and 77 *ec*).

90. *M. extensor digitorum communis brevis* (Fig. 79 *e3, e4, e5*).

Dugès, sous-pyro-phalangettien du III, IV, V, n. 124, 128, 131.

Covered by the foregoing, this muscle arises from the *os pyramidale* in conjunction with the *extensor pollicis* and from the *os capitato-hamatum.* The part destined for the third finger, together with that for the fourth, arises from the *os pyramidale,* passes obliquely backwards into a tendon which runs along the inner side of the corresponding finger to be inserted into the last phalanx. That for the fifth finger arises from the inner projection of *os capitato-hamatum* being here attached to the insertion of the *m. extensor carpi ulnaris,* and is inserted in a similar manner into the terminal phalanx of the fifth finger.

91. *M. abductor digiti II (i. e. pollicis) longus* (Figs. 74 *ei* and 79 *ab*.2).

For the origin and course of this muscle in the forearm see No. 63. The muscle passes obliquely over the wrist-joint from the little finger towards the inner side and from before backwards, it is inserted into the metacarpal of the second finger (thumb). The place of insertion of this muscle into the metacarpal (compare p. 47) is, in the males, developed into a ridge and process, the muscle itself is enlarged during the breeding season. This muscle abducts the thumb and by this means presses upon the chest of the female when clinging to her.

92. *M. extensor digiti II proprius longus* (Fig. 79 e2, e2').

Dugès, cubito-radio-sous-phalangien de l'index, n. 96.

This muscle lies obliquely on the back of the hand, parallel

Fig. 79.

Muscles of hand of *Rana esculenta.* Dorsal view, twice natural size.

ab.2. M. abductor dig. II longus.
ab.2' M. abductor dig. II brevis.
ad2 M. adductor dig. II.
e2
e2' } M. extensor dig. II longus.
e3
e4 } M. extensor digitorum communis
e5   brevis.
eb2 M. extensor dig. II proprius brevis.
ec   M. extensor carpi ulnaris.
fa   M. flexor antibr. lat. superficial.
i'3
i'4 } MM. interossei.
i'5
II–V as in Fig. 77.

with the *m. abductor digiti II*. It arises by two heads, one from the tendon of the *flexor antibr. lat. superf.* (n. 60) upon the hinder extremity of the radio-ulnar. This tendon conceals the hinder end of this bone by means of a patella-like thickening, and sends forth three tendinous prolongations; of these, the one is attached to the ulnar border of the radio-ulnar, the second to the *os naviculare*, while the third constitutes that portion of the *m. extens. dig. II proprius long.* which is under consideration. The second head arises from the *os pyramidale* in connection with the *extensor digitorum communis brevis* (n. 90). The heads unite to form a long muscle, which runs obliquely towards the second finger, passes into a tendon, which, after forming connections by some muscular fibres with the metacarpal, is inserted into the terminal phalanx.

93. *M. extensor dig. II proprius brevis* (Fig. 79 eb2).

Dugès, sus-luno-phalangettien de l'index, n. 120.

This muscle lies between the preceding muscle and the *abductor dig. II longus*. It arises from the *os naviculare,* and also includes some fibres which arise from the second metacarpal. The tendon runs along the radial side and is inserted along with the last muscle into the terminal phalanx.

94. *M. abductor dig. II brevis* (Fig. 79 ab.2').

Dugès, sus-luno-métacarpien de l'index, n. 88.

This represents the *abduct. pollic. brevis* of man, lies on the outer side of the hand, arises from the *os naviculare,* and is inserted into the second metacarpal.

95. *M. extensor dig. III proprius.*

Dugès, sus-luno-phalangettien du médius, n. 122.

This muscle has two heads of origin, from the *os naviculare* and *lunatum*. These form one muscular belly, which rapidly diminishes and passes into a tendon; this, after receiving a few muscular fibres from the second metacarpal, runs to the outer part of the dorsal surface of this finger as far as the terminal phalanx, where it is inserted.

96. *M. extensor dig. IV proprius.*

Dugès, sus-pyro-phalangettien de l'annulaire, n. 128.

By a somewhat broad base, this muscle arises from the *os naviculare* and *lunatum*. The tendon receives fibres from the fourth metacarpal and runs on the outer half of the dorsal surface of this finger as far as the middle phalanx, where it is inserted.

(III.) *MM. interossei.*

97, 98. [a.] *MM. transversi metacarpi* (Ecker), (Fig. 78 *t, t', ad2*).

These lie transversely between the metacarpals. There are three; the first has been already described as *m. adductor digiti II* (n. 73); the second is stretched between the third and fourth metacarpals, and the third between those of the fourth and fifth fingers.

99, 100, 101. [b.] *MM. interossei volares.*

One may regard as such, four long, thin muscles, which take origin near one another on the palmar surface of the carpal bones, and diverge from this towards the second and fifth fingers.

1. The first of these muscles (Fig. 78 *fb2'*) has already been described above as the *m. flexor digiti II tertius* (n. 72).

2. The second (Fig. 78 *i3*) passes from the origin already described to the palmar surface of the basal phalanx of the third finger.

3. The third (Fig. 78 *i4*) runs, in like manner, to the fourth finger.

4. The fifth (Fig. 78 *i5*) to the fifth finger[1].

102 to 108. *MM. interossei dorsales.*

These arise in common from the metacarpals, and are inserted into the basal phalanx of the corresponding surface on the finger.

---

[1] Whether these muscles may be regarded as *mm. interossei* is open to discussion, as they appear to act more as *mm. opponentes.*

1. The *third* finger has two, one to the radial side (Fig. 79 *i'*3), one to the ulnar side.

2. The *fourth* finger has three, the third (Fig. 79 *i'*4) arises from the carpus, and perhaps ought rather to be regarded as an extensor.

3. The *fifth* finger has two.

IV. MUSCLES OF THE HINDER LIMB.

I. MUSCLES OF THE THIGH.

General arrangement (Figs. 80, 81).

a. The *m. triceps femoris* forms the *outer border* of the thigh, and extends on to both the dorsal and ventral surfaces. The outer border therefore corresponds with the anterior surface of the thigh of man, in consequence of the thigh in the frog being normally rotated outwards.

b. The *m. vastus internus* (*v. i.*) and a portion of the *adductor longus* (*ad'*), the *sartorius* (*s*), a portion of the *adductor magnus* (*ad'''*), and the *rectus internus major* (*r. i'*) are found on the *inner surface* of the thigh.

c. The *rectus internus minor* (*r. i''*) forms the *inner border*.

d. On the *dorsal surface* are to be seen, nearest the trunk, the *glutaeus* (*gl*), on the outer border the *vastus externus* (*v. e.*), the *pyriformis* and *biceps* (*p* and *b*), then the *semimembranosus* (*sm*), and lastly the *rectus internus minor* (*ri''*).

e. By reflecting the *rectus internus major* (compare Fig. 82) there are exposed to view : the *semitendinosus* (*st*), the whole length of the *adductor longus*, *magnus* (*ad'* and *ad'''*), and *brevis* (*ad''*). By reflecting the triceps, one sees (Figs. 84, 85) the *ilio psoas* (*ip*), and beneath the *semimembranosus*, the *quadratus* (*qf*), and *capsularis femoris* (*og*).

Description of the separate Muscles.

(A.) Muscles of the dorsal surface

109. *M. glutaeus* (Fig. 80 *gl*).

Dugès, ex-ilio-trochantérien.—Zenker, *glutaeus maior.*

The tendinous origin of this muscle is found on the outer surface and upper border of the two hinder thirds of the iliac bone. Thence it runs outwards and backwards between the head of the *m. vastus externus* (*ve*) on the one side, and the *ilio-psoas* and *rectus anticus* (*ra*)

on the other, to be inserted into a tubercle (trochanter) of the femur.

110. *M. Pyriformis* (Fig. 80 *p*).

> Cuvier, pyramidal.—Dugès, coccy-fémoral, n. 136.

A narrow, slender muscle, arising from the apex of the coccyx; it passes obliquely outwards and backwards to the thigh, to be inserted deeply between the *m. vastus externus* and the *biceps*, into the inner surface of the femur, but towards the ventral surface.

M. triceps femoris s. extensor cruris communis (Fig. 80).

> Dugès, pelvi-fémoro-rotulien, n. 145, 146, 147.

This is a large, strong muscle, having three heads of origin, and inserted by a tendon into the tibio fibula. The three heads are the *caput longum* or the *rectus femoris anticus* (r.a.), the *caput externum* or the *vastus externus* (v.e.), and the *caput internum* or the *vastus internus* (Fig. 82 *vi*); of these, the first is situated on the outer border of the thigh, the second on the dorsal surface, and the third on the ventral surface.

111. [a.] *M. rectus femoris anticus* (Figs. 80, 82 *ra*).

This arises from the under (ventral) surface of the iliac bone about its middle and beneath the *m. glutaeus*. The muscular belly quickly passes into

Fig. 80.

Muscles of left thigh of *Rana esculenta*. Dorsal view.

b	M. biceps.
ci	M. coccygeo-iliacus.
g	M. gastrocnemius.
gl	M. glutaeus.
p	M. pyriformis.
pe	M. peroneus.
r.a.	M. rectus anterior.
ri''	M. rectus internus minor.
sm	M. semimembranosus.
t.a.	M. tibialis anticus.
tr.	M. triceps fem.
v.e.	M. vastus externus.

an aponeurosis, which covers the other two muscular masses and combines with their tendons.

112. [**b.**] *M. vastus externus* (Fig. 80 *v.e.*).

It arises from the upper and hinder extremity of the iliac bone (Fig. 42 *il'*) behind the *glutaeus*, which here sinks in between this muscle and the *rectus anterior*.

113. [**c.**] *M. vastus internus* (Figs. 81, 82 *vi*).

It arises from the whole of the under and outer surfaces of the hip-joint capsule, and from tendinous slips which pass from this capsule downwards on the under surface of the muscle, (from the pubis and the femur I have not seen any fibres of origin, as stated by others). Anteriorly the *vastus* may easily be separated into two heads. The two *vasti* unite and form one muscular belly, in the formation of which, as above stated, the *rectus anticus* takes no part. This united muscle passes into a tendon which, without the mediation of a patella, passes over the knee-joint to be inserted into the anterior extremity of the tibio fibula, and is prolonged into the fascia of the leg.

114. *M. ilio-fibularis s. biceps* (Fig. 80 *b*).

Dugès, ilio-péronien, n. 149.—Zenker, flexor externus tibiae, p. 42.

This is a long, somewhat narrow muscle, which lies to the inner side of, and partly covered by, the *vastus externus*, between which and the semimembranous it is placed. It arises by a tendon between the *ilio-psoas* and *pyriformis* from the ilium above the acetabulum and behind the origin of the *vastus externus*. From here it passes backwards, separated from the *vastus externus* by a strong *ligam. intermusculare*. On the inner side of this muscle, between it and the *m. semimembranosus*, run the vessels of the thigh and the *N. ischiadicus*. The muscle then divides into two portions, of which one is inserted high up on the inner and under surface of the femur. This is probably the muscle which Klein (*l. c.*, p. 61) describes as the *extensor brevis*. The other long muscular belly passes into a thin tendon, opposite the hinder extremity of the thigh, it divides into two portions; the anterior is inserted into the dorsal surface of the hinder extremity of the femur, the other into the dorsal surface of the tibio-fibula. Between the two is stretched an arch with the concavity outwards. This insertion of the biceps is covered by the stronger tendon of origin of the *m. gastrocnemius* (compare Fig. 87).

115. *M. semimembranosus* (Figs. 80, 86 *sm*).

> **Dugès,** sous-ischio-poplité, n. 148.—**Klein,** p. 60, *extensor femoris sublimis.*

This muscle lies on the dorsal surface of the thigh, to the inner side of the *biceps* and *pyriformis*: it is a broad muscle, which takes a tendinous origin from the hinder and upper angle of the *symphysis ossis ilei,* and is inserted by a flat tendon into the dorsal surface of the ligaments of the knee-joint, and through these into the tibio-fibula. The tendon is formed rather abruptly from the muscle, and is surrounded, (Fig. 86) by the concave arch, which forms the tendon of origin of the *gastrocnemius* (*q. v.*). A little behind its middle (compare Fig. 81) the muscle is divided obliquely into an anterior and a posterior portion by an aponeurotic septum. As all the fibres are interrupted by this structure, the muscle may very easily be torn through.

(B.) Muscles on the ventral surface.

116. *M. sartorius* (Figs. 81, 82 *s*).

> **Dugès,** sous-iléo-tibial, n. 150.—**Klein,** *gracilis.*

This long, flat muscle lies along the middle of the ventral surface of the thigh ; it arises by a tendon from the anterior inferior angle formed by the symphysis of the innominate bones, and terminates in a tendon behind the knee-joint, forming a kind of *pes anserinus* in the fascia of the leg, similar to that of the *semitendinosus*[1].

117. *M. rectus internus major* (Ecker), (Figs. 81 *r.i'*, 82 *ri'*).

> **Dugès,** post-ischio-tibial profond, n. 152.—**Klein,** *semimembranosus.*

This is a broad and flat muscle, thinned out at either extremity ; it occupies the inner half of the ventral surface of the thigh, and is in relation with the *adductor magnus* externally and anteriorly, with the *sartorius* posteriorly, and the *rectus minor* muscle internally. The muscle arises by a tendon from the pubic symphysis; it covers in its course the *semitendinosus,* then passes into a strong tendon, which blends with the tendon of the *rectus minor,* to be inserted by a slip into a·process of the tibio-fibula representing the *tuberositas tibiae,* first passing between the tendons of the *sartorius* and *semimembranosus,* which here form an aponeurotic arch ; a second slip passes under the tendon of the

---

[1] The sartorius has lately been used by Kühne in his researches on the nerve-endings in muscle and on muscle contraction without nerve supply (du Bois-Reymond's and Reichert's Archiv, 1859. Page 314).

Fig. 81.

www.libtool.com.cn

Muscles of left thigh of *Rana esculenta.* Ventral surface.

ad'	M. adductor longus.
ad"	M. adductor brevis.
ad"'	M. adductor magnus.
e.c.	M. extensor cruris.
f.t.	M. flexor tarsi.
g.c.	M. gastrocnemius.
r.i'	M. rectus internus major.
r.i"	M. rectus internus minor.
s	M. sartorius.
t.a.	M. tibialis anticus.
t.p.	M. tibialis posticus.
v.i.	M. vastus internus.

m. semitendinosus to be inserted into the upper surface of the tibio-fibula, under it passes the *N. tibialis.* A third thread-like tendon passes to the *m. semimembranosus.* Somewhat behind its middle (Fig. 82) the muscle is traversed by an *inscriptio tendinea,* by which the whole of the fibres are interrupted.

118. *M. rectus internus minor* (Ecker), (Figs. 80, 81 *r.i"*). ·

Dugès, post-ischio-tibial superficiel, n. 151.—Zenker, *flexor tibiae magnus.*—Klein, *ischio-tibialis.*

Situated entirely on the inner surface of the thigh, this narrow muscle arises by a tendinous band which runs the whole length of the pubic symphysis, and is connected posteriorly with the *sphincter ani,* anteriorly with the *rectus abdominis;* posteriorly it passes into a thin tendon which is also connected with the muscle just described (117). In its course

this muscle is attached to the skin by strands of vessels and connective tissue.

The vastus internus major and minor together undoubtedly correspond with rectus internus or gracilis of human anatomy. The rectus internus major is, however, regarded as corresponding with the adductor magnus by Dugès, and with the semimembranosus by Klein; by considering the position and attachments of these muscles one must arrive at a different conclusion.

MM. adductores femoris.

119. [a] *M. adductor longus* (Fig. 82 *ad'*).

> Dugès, sous-ilio-fémoral, n. 141.

Without further dissection this muscle is only partially visible between the *m. sartorius* and *vastus internus* (Fig. 81 *ad'*). The muscle is flat and long, and arises by a tendon from the anterior inferior angle of the pubic symphysis (Fig. 42 *s*), partially covered by the origin of the *sartorius*. Thence the muscle passes between the *vastus internus* and the *adductor magnus*, and finally is inserted below the middle of the femur, together with the latter muscle.

120. [b] *M. adductor magnus* (Figs. 81, 82 *ad'''*).

> Dugès, sous-ischio-pubi-fémoral (adductor 1 and 2), n. 142, 143.—
> Klein, *adductor magnus* and *extensor femoris profundus*.

This muscle is visible between the *sartorius* and *rectus internus major* in the anterior half of the thigh, posteriorly it is covered by these muscles. It arises by a tendon from (a) the pubic symphysis and *ischii*, and is in this position divided into two portions, between

Fig. 82.

Muscles of the left thigh of *Rana esculenta.*
Ventral surface.

ad' M. adductor longus.
ad''' M. adductor magnus.
gl M. glutaeus.
ip M. ilio-psoas.
ra M. rectus fem. anticus.
ri' M rectus int. major.
s M. sartorius.
st M. semitendinosus.
vi M. vastus internus.

H 2

which passes the tendon of one head of the *m. semitendinosus* (Fig. 83 *st"*) ; (*b*) a second part arises from this same tendon (Fig. 83 *st'"*) and joins with the first part. Thus formed the muscle passes to be inserted into the distal half of the inner surface of the femur as far as the condyle. Near its hinder extremity, however, it passes on to the dorsal and outer surfaces, and thus forms a kind of muscular sheath surrounding the distal portion of the bone.

121. [c] *M. adductor brevis* (Figs. 81, 83 *ad"*), and

122. [d] *M. pectineus* (Fig. 83 *pe*).

> Dugès, sous-pubio-fémoral (analogue of the *pectineus*, possibly of the add. brevis also).

These two small muscles which lie under cover of the *sartorius, adductor longus* and *magnus*, appear externally as one muscle, but may easily be separated (Fig. 83). They arise close together from the pubic symphysis, and are inserted into the inner surface of the anterior half of the femur. They are not attached to the *adductor magnus*.

123. *M. semitendinosus* (Fig. 83 *st, st', st"*).

> Dugès, bis-ischio-tibial, n. 153. — Zenker, biceps.

This is a long thin muscle, only visible after removal of the *m. rectus internus*, by which it is entirely covered. It arises by two long thin tendons, one (*caput posticum, st'*) from the pubic symphysis, the other (*caput anticum, st"*) from the hollow between the symphysis and the acetabulum. The latter

Fig. 83.

Deep muscles of left thigh of *Rana esculenta*.

ad'　M. adductor longus.
ad"　M. adductor brevis.
ad'"　M. adductor magnus.
ip　M. ilio-psoas.
pe　M. pectineus.
ra　M. rectus anticus.
ri'　M. rectus internus maior } cut through.
ri"　M. rectus internus minor }
s　M. sartorius.
st　Belly of m. semitendinosus.
st'　M. semitendinosus (cap. posticum).
st"　M. semitendinosus (cap. anticum).
st'"　Fibres passing into the adductor magnus.
vi　M. vastus internus.

passes through a slit in the *adductor magnus*, and so affords this muscle another point of origin; then backwards between the *adductor magnus* and the *rectus internus major* and under the lower third of the thigh, and unites with the posterior head of origin. The muscle so formed passes into a thin tendon, and, together with that of the *sartorius*, forms an aponeurotic arch, connected with the fascia of the leg, under which the tendons of the *rectus internus major* and *minor* pass.

(C.) Deep muscles of the thigh.

To these, in addition to the *adductor brevis, pectineus*, and the portion of the *biceps* already described, belong also the following :

124. *M. ilio-psoas* (Figs. 82, 83, 84 *ip*).

> **Dugès,** intra-ilio-fémoral (=*iliacus* and *psoas*).—**Cuvier, Zenker, Klein,** *iliacus internus.*

The fibres of this muscle take a broad origin from the pelvic surface of the ilium, pass outwards over the lower margin of the

Fig. 84.

Fig. 85.

Deep muscles of the left thigh of *Rana esculenta.* Dorsal view.

ad' M. adductor brevis.
ci M. coccygeo-iliacus.
cx Coccyx.
gl M. glutaeus.
il Ileum.
ip M. ilio-psoas.
o.g. M. obturatorius.
qf M. quadratus femoris.

Left half of pelvis of *Rana esculenta.* Thigh turned forwards under the abdomen.

gl M. glutaeus.
og M. obturatorius.

bone and form a flat muscle with its apex pointed posteriorly. It crosses the hip-joint between the *m. rectus* and *vastus internus,*

covering the hinder part of the *m. glutaeus*, and is inserted into the outer surface of the middle third of the femur.

125. *M. quadratus femoris* (Fig. 84 *qf*).

Dugès, post-ilio-fémoral (Homologue of the *glutaeus maximus*), n. 197.— Zenker, *glutaeus minor*, p. 42.

This muscle is of a somewhat elongated, triangular shape, and arises, under cover of the *pyriformis*, from the ilium behind the acetabulum; it passes backwards over the joint to be inserted into the inner and under surfaces of the femur, between the *pyriformis* and *ilio-psoas*; below, it is in direct relation with the *adductor brevis*.

126. *M. obturatorius* (Figs. 84, 85 *og*).

Dugès, ischio-pubi-fémoral, n. 139 (?).—Zenker, *m. capsularis femoris*.

This small muscle is deeply situated upon the hip-joint, and covered by all the other muscles that arise from the symphysis. Its origin from the innominate bone extends from the superior posterior angle of the *symph. ossis ilii* to about the middle of the pubic symphysis; the muscle fills the space between the crest of the symphysis and the acetabulum. The fibres converge to pass into a strong tendon, which is inserted into the posterior and anterior surfaces of the head of the femur. The muscle appears to represent collectively the small rotators of human anatomy, *m. obturator externus* and *internus* and the *gemelli*.

II. MUSCLES OF THE LEG.

General description.

On the outer surface (the anterior of man), covered by the *fascia cruris*, into which the tendon of the *extensor communis cruris* or *triceps* is prolonged, are found the following muscles : nearest to the bone, the *m. extensor cruris brevis* (*ec*); externally, the *m. tibialis anticus* (*ta*) and the *m. peroneus* (*pe*). On the inner surface (the hinder of man) lie the *gastrocnemius* (*gc*) and *tibialis posticus* (*tp*), and deeply the *flexor tarsi sup.* (*ft*).

127. *M. gastrocnemius* (Figs. 80, 81, 86).

Dugès, bi-fémoro-plantaire, n. 159.

This important muscle arises by two tendinous heads. The one (Fig. 86 *g'*) rather nearer the middle line of the popliteal space, is by far the stronger: it arises by a broad, tendinous expansion, which covers the knee-joint, and is attached to the femur and the tibio-fibula by anterior and posterior bands respectively; it ends

internally in a concave aponeurotic arch : the second head is a thin, tendinous slip, arising from the common tendon of the *triceps* as this lies on the knee-joint. The muscle is thickest near its origin, and then gradually diminishes in size as it passes backwards ; the superficial surface is convex, the deep surface is flat. By tracing the tendons of origin, they are seen soon to unite and form a common flat tendinous surface, broad in front, contracted behind ; this aponeurosis lies in a plane running obliquely from the deep surface towards the superficial surface, without, however, reaching this. The muscular fibres arise from both surfaces of the aponeurosis, the fibres of the two sides diverging slightly as they pass backwards so as to be inclined at a small angle to each other. The fibres are inserted into a fibrous expansion (*Ap*) which lies on the superficial surface of the muscle ; thin and slight in front, this aponeurosis rapidly thickens posteriorly until it passes into the *tendo Achillis*.

128. *M. tibialis posticus* (Fig. .86 *t.p.*).

Dugès, cruro-astragalien, n. 160.

Covered by the *gastrocnemius* this

Fig. 86.

Muscles of the right leg and foot of *Rana esculenta*. Dorsal view.

a.h.	M. abductor hallucis.
a.l:	M. abductor longus digiti I.
A.p.	Aponeurosis plantaris.
b	M. biceps.
e.t.	M. extensor tarsi.
F.l.	M. flexor digitorum III, IV, V longus.
F.F.	M. flexor digitorum I and II longus.
g	M. gastrocnemius, drawn towards the right.
g'	Tendon of origin of gastrocnemius.
l.c.	Ligamentum calcanei.
p	M. plantaris.
r.i.	MM. internus major and minor.
s.m.	M. semimembranosus.
s.t.	M. semitendinosus.
t.A.	Tendo Achillis.
t.A'.	Thickening of tendo Achillis.
t.p.	M. tibialis posticus.
v.e.	M. vastus externus.
v.i.	M. vastus internus.

muscle occupies the whole of the inner and upper surfaces of the
tibio-fibula, from which it arises by numerous fibres.   Opposite the
hinder extremity of the bone the muscle becomes free and passes
somewhat abruptly into a tendon, which courses behind and over the
malleolus internus, on to the dorsum of the foot, and is here inserted
into the anterior extremity of the *astragalus.*   I cannot agree with
Dugès that this muscle corresponds with the *soleus* (Ecker).

129. *M. extensor cruris brevis* (Fig. 87 *ec*).
   Dugès, pré-fémoro-tibial, n. 154.

Covered by the strong *fascia cruris,* and lying between the *m. ti-
bialis anticus* and the tibio-fibula, this muscle arises by a long tendon
from the inner condyle of the femur; it passes backwards in the
groove on the anterior extremity of the tibio-fibula, covered by the
tendon of the triceps femoris, and is then inserted by muscular
fibres into the outer surface of the tibio-fibula almost as far as the
posterior third of the bone.   (Dugès regards this muscle as the
upper, i. e. anterior, portion of the *tibialis anticus.*)

130. *M. tibialis anticus* (Figs. 80, 81, 87 *ta*).
   Dugès, pré-fémoro-astragalien and pré-fémoro-calcanien, n. 156 and 157;
      the former he regards as one part of the *tib. anticus,* the latter
      as the *peroneus longus I.*—**Zenker,** *tib. ant. biceps.*

The tendon of origin of this muscle is attached to the femur near
the tendon of the *m. extensor cruris brevis,* and to the joint-ligaments.
The muscle is placed under the *fascia cruris,* its long tendon of
origin passing beneath the tendon of the *triceps* in a special sheath
through the joint; the tendon then gains a muscular belly which
bifurcates at about the middle of the leg, forming two muscular
masses, coursing along the outer and the inner side of the leg re-
spectively.   The latter is inserted into the dorsal surface of the *astra-
galus* by a tendon, and the former into the dorsal surface of the
calcaneus in a similar manner.   The muscle extends the foot and
flexes the tarsus; the latter movement is very distinct on account of
the insertion of the muscle being so near the *hypomochlion.*

131. *M. flexor tarsi anterior* (Ecker), (Fig. 87 *Ft*).
   Dugès, ex-tibio-astragalien, n. 155.—**Zenker,** *tibialis anticus simplex.*

This muscle arises where the insertion of the *extensor cruris brev*
ceases, from the middle of the under surface of the tibio-fibula, and
passes backwards between the two tendons of the *m. tibialis anticus*
along the outer side of this muscle, to be inserted by a tendon

into the inner side of the anterior articular extremity of the *astragalus* and the *fascia dorsalis pedis*.

132. *M. peroneus* (Figs. 80 *pe*, 87 *p*).

> Dugès, génio-péronéo-calcanieu, n. 158.

This is a strong muscle which is attached by a long tendon of origin to the hinder extremity of the femur and the ligaments of the knee-joint. The tendon runs in a sheath through the joint and posteriorly becomes muscular; the muscle passes downwards on the outer side of the tibio-fibula to be inserted into the *malleolus externus* of this bone and into the anterior extremity of the *calcaneus*. It has an action similar to that of the *m. tibialis anticus*.

III. Muscles of the Foot.

A. Muscles on the Plantar Surface.

133. *Aponeurosis plantaris* (Fig. 88 *A.p.*).

As already mentioned, the tendon of the *m. gastrocnemius* is, at the heel, continued into a strong aponeurosis, and possesses at this place a thickening [1]. The aponeurosis is of triangular form, the base directed towards the toes and attached to these. The lateral borders of this triangle are continued into weaker *fasciae*, which are attached to the two long tarsal bones. The inner border in particular gives a strong bundle of

Fig. 87.

Muscles of leg and foot of *Rana esculenta*, seen from below.

a.b.5 M. abductor dig. V longus.
cc M. extensor cruris brevis.
e.d.1 M. extensor digit I longus.
e.d.4 M. extensor digit IV longus.
e.d.5 M. extensor digit V longus.
Ft M. flexor tarsi anterior.
Ft' M. flexor tarsi posterior.
g M. gastrocnemius.
p M. peroneus.
ta M. tibialis anticus.
tF M. triceps femoris.

[1] Lehmann, Ueber den Knorpel in der Achillessehene des Frosches, Zeitschr. f. U. Zool. XIV, p. 109. (See also literature on cartilage, Sect. VII.)

fibres to the astragalus, and is thus connected with the fascia of the dorsum of the foot; externally this aponeurosis is attached to a cartilage (Dugès, os sesamoïde, *l. c.*, n. 66), situated on the plantar surface of the joint between the *calcaneus* and the *os metatarsi IV*.

134. *Ligamentum calcanei* (Ecker), (Figs. 88, 89 *l.c.*).

If the *tendo Achillis* be divided and the *aponeurosis plantaris* reflected towards the toes, there is seen, arising from the posterior head of the tibio-fibula, in its whole breadth, a ligament (between the *tib. posticus* and *peroneus*). This ligament forms a firm surface on which the thickened portion of the *tendo Achillis* may move, and which evidently represents the tuberosity of the heel bone. I have therefore named the entire structure the *ligamentum calcanei.*

Several muscles arise from this ligament, viz. :—

135. *M. extensor tarsi* (Klein), Figs. 88, 89 *e.t.*).

Dugès, tibio-sous-astragalien (regarded by him as the homologue of the *tibialis posticus*).

Covered by the two succeeding muscles, this muscle arises from the

Fig. 88.

Muscles of the right leg and foot of *Rana esculenta.*
Dorsal view.

a.h.   M. abductor hallucis.
a.l₁   M. abductor longus digiti I.
A.p.   Aponeurosis plantaris.
b   M. biceps.
e.t.   M. extensor tarsi.
F.l.   M. flexor digitorum III, IV, V longus.
F.l'.   M. flexor digitorum I and II longus.
g   M. gastrocnemius, drawn towards the right.
g'   Tendon of origin of gastrocnemius.
l.c.   Ligamentum calcanei.
p   M. plantaris.
r.i.   MM. internus maior and minor.
s.m.   M. semimembranosus.
s.t.   M. semitendinosus.
t.A.   Tendo Achillis.
t.A'.   Thickening of tendo Achillis.
t.p.   M. tibialis posticus.
v.e.   M. vastus externus.
v.i.   M. vastus internus.

ligamentum calcanei, runs backwards, and is inserted into the whole length of the plantar surface of the *astragalus*. It extends the foot.

136. *M. plantaris* (Figs. 88, 89 *p*).

This takes its origin from the *ligamentum calcanei* to the inner side and below the last muscle. It passes backwards and is inserted into the dorsal surface of the *aponeurosis plantaris*.

137. *M. flexor digitorum III, IV, V longus* (Ecker), Figs. 88, 89 *F.l.*).

Dugès, péronéo-sous-phalangettien (*flexor dig. longus*).

This muscle also arises from the *ligamentum calcanei* to the outer side of the *m. plantaris*. It runs backwards over the *aponeurosis plantaris*, and at the free margin of this passes somewhat suddenly into a strong tendon, which traverses an aponeurotic canal, formed by fibres of the aponeurosis passing above and below the tendon, from

Fig. 89.

Muscles of the plantar surface of foot of *Rana esculenta*, twice natural size.

A.p. Aponeurosis plantaris, divided.
ab.5. M. abductor dig. V.
ad.5. M. adductor dig. V.
ad.l.1. M. adductor longus dig. I.
e.t. M. extensor tarsi.
F.5. M. flexor brevis dig. V.
F.l. M. flexor digitorum III, IV, V longus.
F.l'. M. flexor digitorum I, II longus.
l.1.
l.2.
l.3.
l.3'. ⎫ Musculi lumbricales.
l.4'.
l.4".
l.5.
l.t. Ligamentum calcanei.
p M. plantaris.
t.A. Tendo Achillis.
t.A'. Thickening in tendo Achillis.
t.p. M. transversus plantae posterior.
t.p'. M. transversus plantae anterior.

the cartilaginous enlargement in the tendon to the median border
of the aponeurosis. The tendon forms three slips for the fifth,
fourth, and third toes: these are slightly attached to the aponeurosis,
but reach beyond its free border to be inserted into the terminal
phalanges of the toes mentioned, and are held down by fibrous
bands. (The small *m. lumbricales* arising from these tendons are de-
scribed below.)

138. *M. flexor digitorum I, II longus* (Ecker), (Figs. 88, 89 *F.l'.*).
The tendons, by means of which the terminal phalanges of the
first and second toes are flexed, arise directly from the posterior
border of the aponeurosis.

139, 140. *MM. transversi plantae* (Ecker), (Fig. 89 *t.p., t.p'.*).
The movements of the aponeurosis and through it the move-
ments of the tendons attached to it are influenced not only by
the *m. gastrocnemius* and *plantaris*, but also by two other muscles,
which together have been described as the *flexor dig. longus internus*
(Klein), or as the tarso-sous-phalangettien (Dugès, 221).

a. *M. transversus plantae posterior (t.p.).*

This takes its origin from the plantar cartilage, widens as it
courses backwards and inwards to be inserted into the dorsal
surface of the *aponeurosis plantaris*; from this the tendons for
the first and second toes (*flexor dig. longus I* and *II*) arise, thus there
is no direct connection between the muscular fibres of the two
muscles.

b. *M. transversus plantae anterior (t.p'.).*

This muscle is covered by the last; broader anteriorly, it arises
from the calcaneum, and is inserted to the inner side of the last
muscle into the dorsal surface of the aponeurosis. This muscle,
like that just described, is not continued directly into the tendon
of the flexor of the toes, they cannot therefore be regarded as
flexors of the toes.

141 to 149. *Musculi lumbricales* (Fig. 89 *l.*1–5).
(A.) From the posterior border of the *aponeurosis plantaris* arise:—
(1) *M. lumbricalis digiti I (l.1).*
> **Dugès**, tendini-sous-phalangien de pouce, n. 185.

This is inserted into the anterior extremity of the proximal
phalanx.

(2) *M. lumbricalis digiti II (l.2).*

> Dugès, tendini-sous-phal. du I doigt, n. 186 (and 187), double according to Dugès.

Similarly inserted.

(3 and 4) *MM. lumbricales digiti III (l.3).*

> Dugès, tendini-sous-phal. du III doigt, n. 188, single according to Dugès.

One of these (*l*3) is inserted into the anterior extremity of the basal phalanx, the other (*l*3′) into a corresponding position on the middle phalanx.

(5) *M. lumbricalis digiti IV.*

> Dugès, tendini-sous-phal. du IV doigt.

Inserted into the anterior extremity of the basal phalanx.

(B.) Arising from the tendons of the *flexor longus III, IV, V*:

(6 and 7) *MM. lumbricales digiti IV (l.4′. and l.4″.).*

> Dugès, tendini-sous-phalanginien du IV doigt, n. 201, 202.

The first (*l.4′*) is inserted into the posterior end of the basal phalanx, the second (*l.4″*) in a similar position into the second phalanx.

(8) *M. lumbricalis digiti V (l.5.).*

> Dugès, tendini-sous-phalangien du V doigt, n. 203.

This arises from the tendon for the fifth toe, runs backwards as a thin tendon alongside that of the flexor, and is inserted into the middle phalanx.

Special Muscles of the Separate Toes.

(I.) Muscles of the rudimentary great toe.

150. *M. abductor hallucis* (Figs. 88 a.h., 90).

> Dugès, tibio-sous-tarsien, n. 163.

This muscle arises from the inner border of the *aponeurosis plantaris*, at the spot where the *m. plantaris* is inserted, it may therefore almost be regarded as a continuation of this muscle; it is inserted into the anterior border of the rudimentary toe.

(II.) Muscles of the great and first toes.

151. *M. adductor longus digiti I* (Figs. 89, 90 ad.*l*1).

> Dugès, calcanéo-scaphoidien, n. 164.

This powerful muscle arises from the plantar surface of the calcaneum and astragalus; its fibres converge towards a tendon lying in

its middle, which becomes free towards its posterior end; the tendon passing inwards under the *ligamentum tarsi transversum* through a groove on the hinder extremity of the astragalus in an arched direction, to be inserted into the *os naviculare*, which bears the rudimentary great toe and the *os metatarsi 1*.

(III.) Muscles of the first toe.

152. *M. abductor longus digiti I* (Figs. 88 *al.*1, 90 *a.b.*1).

It takes its origin from the inner border of the *aponeurosis plantaris*, and lies on the plantar surface of the *abductor hallucis*. Its tendon runs in the hollow which the great toe forms, and is inserted into the inner side of the *os metatarsi I*.

153. *M. flexor brevis digiti I* (Fig. 90 *F.b.*1).

A small, thin muscle, which arises from the anterior extremity of the *os metatarsi II*, and is inserted into the basal phalanx of the first toe. In this small muscle, and also in the *m. lumbrical. dig. V* (Fig. 89 *l.*5.), the nerve distribution may be very well seen.

154. *M. opponens dig. I* (Fig. 90 *op*).

Dugès, sous-metatarso-phalangien du pouce, n. 192.

This is situated to the inner side of the preceding muscle, arises from the *os metatarsi II* somewhat narrow, widens in a fan-like manner towards the *os metatarsi I*, into the anterior half of which it is inserted.

(IV.) Muscles of the second toe.

155. *M. flexor metatarsi dig. II* (Fig. 90 *F.m.*2).

Dugès, sous-tarso-metatarsien du II doigt.—Klein, extensor metatarsi.

By a narrow origin from the hinder end of the calcaneum, posteriorly this muscle becomes broader and is inserted, somewhat thinned out, into the plantar surface of the second *os metatarsi*.

156. *M. flexor dig. II proprius* (Fig. 90 *F.p.*2).

Dugès, sous-metatarso-phalangien, n. 194.

It arises from the plantar surface of the *os metatarsi II*, and is inserted by a thin tendon into the plantar surface of the first phalanx.

Dugès describes this and the analogous muscles of the third, fourth, and fifth toes (*F.p.*3, 4, 5) as the *interossei plantares*, a no-

menclature which, to me, does not appear correct, as these muscles lie entirely on the plantar surface, and do not adduct or abduct the toes, but flex them.

(V.) Muscles of the third toe.

157. *M. flex. metatarsi dig. III* (Ecker), (Fig. 90 *F.m.*3).

> Dugès, sous-calcaneo-métatarsien du III doigt, n. 174.—
> Klein, *extensor metatarsi.*

Like the corresponding muscle of the second toe (n. 155), this arises by a small tendon from the hinder extremity of the calcaneum, runs backwards and is inserted into the plantar surface of the *os metatarsi III*. The greatest portion of the muscle lies beneath the *m. transversus metatarsi* (*tm*), the most anterior portion, however, lies above this. Dugès has described this latter portion as a special muscle (n. 176, metatarso-métatarsien du III), the same description holds good for the second toe (n. 177, Dugès).

158. *M. flexor dig. III proprius* (Ecker), (Fig. 91 *Fp*3).

> Dugès, sous-métatarso-phalangien du III doigt, n. 195.

Like the corresponding muscle of the second toe, this arises from the plantar surface of the *os metatarsi III*, and is inserted by a thin tendon into the plantar surface of the anterior extremity of the first phalanx.

Fig. 90.

Muscles of plantar surface of foot of *Rana esculenta*.

*a.b.*1   M. abductor longus digiti I.
*ab*5   M. abductor digiti V.
*ad.l.*1   M. adductor longus digiti I.
a.h.   M. abductor hallucis.
*F.b.*1   M. flexor brevis digiti I.
*F.m.*2, 3, 4 M. flexores metatarsi II, III, IV.
*F.p.*2, 3, 4, 5 MM. flexor. proprii digit. 2, 3, 4. 5.
*F.ph.*3, 4, 4′, 5 MM. flexor. phalang. digit. 3, 4, 5.
op   M. opponens digiti I.
t.m′
t.m″ } MM. transversi metatarsi 1, 2. 3.
t.m‴

159. *M. flexor phalangum proprius digiti III* (Ecker), (Fig. 91 *F.ph.*3).

Dugès, phalango-phalangien, n. 204.

This arises by tendon from the plantar surface of the basal phalanx, and is inserted into the anterior extremity of the terminal phalanx.

Fig. 91.

Muscles of plantar surface of foot of *Rana esculenta.*

*a.b.*1　M. abductor longus digiti I.
*ab*5　M. abductor digiti V.
*ad.l.*1　M. adductor longus digiti I.
a.h.　M. abductor hallucis.
*F.b.*1　M. flexor brevis digiti I.
*F.m.*2, 3, 4 M. flexores metatarsi II, III, IV.
*F.p.*2, 3, 4, 5 MM. flexor. proprii digit. 2, 3, 4, 5.
*F.ph.*3, 4, 4', 5 MM. flexor. phalang. digit. 3, 4, 5.
op　M. opponens digiti I.
t.m'
t.m''　} MM. transversi metatarsi 1, 2, 3.
t.m'''

(VI.) Muscles of the fourth toe.

160. *M. flexor metatarsi dig. IV* (Fig. 91 *F.m.*4).

Dugès, métatarso-métatarsien, n. 175.

Similarly to the corresponding muscle of the third toe, this one arises from the hinder extremity of the calcaneum, and is inserted into the anterior portion of the plantar surface of the *os metatarsi IV*, but not into the greater portion of this surface, as in the second and third *os metatarsi.*

161. *M. flexor dig. IV proprius* (Fig. 91 *Fp4*).

Dugès, sous-métatarso-phalangien du IV doigt (*interosseus plantaris*), n. 196.

The origin and insertion are similar to those of the muscles of the second and third toes.

162. *M. flexor brevis dig. IV.*

A small muscle, which arises with the *m. flexor brevis* of the fifth toe, from enlargement of *aponeurosis plantaris*, and is inserted into the basal phalanx of the fourth toe.

163. *M. flexor phalangum proprius dig. IV anterior* (Fig. 91 *F.ph.*4).

Dugès, phalango-phalanginien, n. 205.

It resembles the corresponding muscle of the third toe.

164. *M. flexor phalangum proprius posterior* (Fig. 91 *F.ph.*4′).

Dugès, phalangino-phalangettien, n. 209.

This extends from the plantar surface of the second phalanx to the anterior extremity of the third.

(VII.) Muscles of the small toe.

165. *M. abductor dig. V* (Fig. 91 *a.b.*5).

Dugès, calcanéo-ex-métatarsien du digitule, n. 169.

This muscle arises from the hinder extremity of the calcaneum, and is inserted into the outer surface of the fifth metatarsal.

166. *M. adductor dig. V* (Fig. 89 *a.d.*5).

Dugès, sous-tarso-in-phalangien, n. 191.

This arises from the cartilage of the plantar aponeurosis, and is inserted into the hinder end of the fifth metatarsal.

167. *M. flexor brevis dig. V* (Fig. 89 *F.*5).

Dugès, sous-tarso-ex-phalangien, n. 190.

Arising from the same place as the preceding, it extends to the basal phalanx.

168. *M. flexor dig. V. proprius* (Fig. 91 *F.p.*5).

(Analogues of Muscles, n. 156, 158, 161; see note at n. 156).—Dugès, sous-métatarso-phalangien, n. 197 (= *inteross. plant.*).

This muscle arises from the plantar and inner surfaces of the fifth metatarsal, and is inserted into the basal phalanx.

169. *M. flexor phalangum proprius* (Fig. 91 *F.ph.*5).

Dugès, phalango-phalanginien, n. 206.

Its origin and insertion are as in the corresponding muscles of the second, third, and fourth toes, n. 159, 163, 164, 169.

170 to **172.** *MM. interossei* (Fig. 91 *t.m.*).

Dugès, 1, 2, and 3, intermétatarsien, n. 170, 171, 172.

These are three muscles with their fibres arranged transversely, which occupy the anterior portion of the spaces between the

I

metatarsals, and approximate these. The first arises (*tm'*) from the edge of the plantar surface of the first metatarsal, and is inserted into the corresponding part of the second : the second (*tm''*) passes from this point to the third, and the third (*tm'''*) to the fifth.

B. MUSCLES OF THE DORSAL SURFACE.

173. *M. flexor tarsi posterior* (Ecker), (Fig. 92 *F.t.*).

Dugès, péronéo-sus-astragal, n. 161.

This is a strong muscle, which has a narrow origin from the outer side of the tibio-fibula, directly over the distal extremity, and is inserted into the dorsal surface of the astragalus from the middle to the distal extremity.

Muscles of the first toe.

174. *M. extensor longus dig. I* (Fig. 92 *e.l.*1).

Dugès, calcanéo-sus-métatarsien du pouce, n. 166.

This lies to the outer side of and near the foregoing muscle; it arises by a long, strong head from the middle of the calcaneum, runs obliquely backwards and inwards to unite with a small head which arises from the common epiphysis of the astragalus and calcaneum, in common with the *m. extensor dig. II*. The muscle so formed passes into a flat tendon to be inserted into the basal phalanx of the first toe.

175. *M. extensor brevis dig. I* (Fig. 92 *e.b.*1).

A small, short muscle which arises from the *os naviculare* and is inserted into the dorsal surface of the first metatarsal.

176. *M. abductor brevis dig. I* (Fig. 92 *a.b.*1).

Dugès, ex-tarso-métatarsien du pouce, n. 168.

This small muscle is situated near the preceding; it arises from the first bone of the supplemental toe, and is inserted into the inner side of the first metatarsal.

Muscles of the second toe.

177. *M. extensor dig. II longus* (Fig. 92 *e.l.*2).

Dugès, calcanéo-sus-phalangien du II doigt, n. 182.

This arises from the calcaneum, in common with the *m. extensor longus* of the third toe, and is inserted into the basal phalanx of the second toe by a tendon.

178. *M. extensor dig. II brevis* (Fig. 92 *e.b.*2).

> Dugès, astragalo-sus-phalangien du II, n. 183.

This is partly covered by the preceding muscle: it arises from the astragalus, and unites with the tendon of the preceding muscle.

Muscles of the third toe.

179. *M. extensor dig. III longus* (Fig. 92 *e.l.*3).

> Dugès, sus-astragalo-phalangien du médius, n. 199.

This arises with the *extensor longus* of the second toe from the calcaneum : its tendon unites with that of the following muscle.

180. *M. extensor dig. III brevis* (Fig. 92 *e.b.*3).

> Dugès, astragalo-sus-phalangien du médius, n. 181.

This muscle arises from the astragalus, and is inserted with the tendon of the preceding muscle into the dorsal surface of the basal phalanx.

Fig. 92.

Dorsal view of muscles of foot of *Rana esculenta*.

*a.b.*1 M. abductor brevis dig. I.
*e.b.*1 M. extensor brevis dig. I.
*e.b.*2 M. extensor brevis dig. II.
*e.b.*3 M. extensor brevis dig. III.
*e.b.*4 M. extensor brevis 1 dig. IV.
*e.b.*4' M. extensor brevis 2 dig. IV.
*e.b.*5 M. extensor brevis dig. V.
*e.l.*1 M. extensor longus dig. I.
*e.l.*2 M. extensor longus dig. II.
*e.l.*3 M. extensor longus dig. III.
*e.l.*4 M. extensor longus dig. IV.
*e.l.*5 M. extensor longus dig. V.
F.t M. flexor tarsi posterior.
*i.*2 to *i.*10 MM. interossei.

Muscles of the fourth toe.

181. *M. extensor longus dig. IV* (Fig. 93 *e.l.*4).

Dugès, péroneo-sus-phalangien du IV, n. 178.

A narrow muscle arising in common with the *flexor tarsi inf.*, but external to it. It is inserted into the tendinous expansion on the dorsum of the toe.

182. *MM. extensores dig. IV breves* (Fig. 93 *e.b.*4 and *e.b.*4′).

Dugès, calcanéo-sus-phalangien and sus-calcanéo-phalanginien, n. 179 and 198.

These two small muscles arise from the calcaneum : one is inserted into the basal phalanx, the other, by means of a long thin tendon, passes along with the tendon of the corresponding *m. interosseus* to the second phalanx, to which it is attached.

Muscles of the fifth toe.

183. *M. extensor dig. V longus* (Fig. 93 *e.l.*5).

Dugès, calcanéo-sus-métatarsien, n. 165.

A strong muscle which covers almost the whole length of the calcaneum ; it arises from the anterior extremity of this bone, runs backwards to the outer side of the dorsum of the foot, and is attached to the outer surface of the fifth metatarsal.

184. *M. extensor dig. V brevis* (Fig. 93 *e.b.*5).

Dugès, calcanéo-sus-phalangien du V, n. 180.

This is a long thin muscle, which, together with the muscle last described, arises from the calcaneum and is inserted into the basal phalanx of the fifth toe.

185. *M. abductor dig. V brevis* (Fig. 93 *i.*10).

This, the last *m. interosseus*, arises from the outer side of the fifth metatarsal, and is inserted into the hinder extremity of the second phalanx of the same toe.

186 to 195. *MM. interossei dorsales* (Fig. 93 *i.*1 to *i.*10).

First toe.

(1) The analogue of the first *m. interosseus* is the *m. abductor brevis dig. I* (*a.b.*1).

(2) The second *m. interosseus* (*i.*2) arises from the outer side of the first metatarsal, and is inserted into the outer surface of the second phalanx of the same toe, dorsally to the *m. opponens* and *flexor brevis dig. I.*

Second toe.

(3) The third *m. interosseus* (*i.3*) takes origin from the anterior part of the outer surface of the first metatarsal by a thin tendon; it is inserted into the inner surface of the second phalanx by a similar tendon.

(4) The fourth *m. interosseus* (*i.4*) arises from the outer side of the second metatarsal, and is inserted into the outer surface of the second phalanx.

Third toe.

(5) The fifth *m. interosseus* arises from the outer surface of the second metatarsal, and is inserted by a thin tendon into the inner surface of the second phalanx of the same toe.

(6) The sixth arises from the outer surface of the third metatarsal, and is inserted laterally by a thin tendon into the hinder extremity of the second phalanx of the same toe.

Fourth toe.

(7) The seventh *m. interosseus* (*i.7*) arises by a thin tendon from the

Fig. 93.

Dorsal view of muscles of foot of *Rana esculenta*.

a.b.1 M. abductor brevis dig. I.
e.b.1 M. extensor brevis dig. I.
e.b.2 M. extensor brevis dig. II.
e.b.3 M. extensor brevis dig. III.
e.b.4 M. extensor brevis 1 dig. IV.
e.b.4' M. extensor brevis 2 dig. IV.
e.b.5 M. extensor brevis dig. V.
e.l.1 M. extensor longus dig. I.
e.l.2 M. extensor longus dig. II.
e.l.3 M. extensor longus dig. III.
e.l.4 M. extensor longus dig. IV.
e.l.5 M. extensor longus dig. V.
F.t M. flexor tarsi posterior.
i.2 to *i.10* MM. interossei.

Fig. 94.

Dorsal view of muscles of foot of *Rana esculenta.*

*a.b.*1 M. abductor brevis dig. I.
*e.b.*1 M. extensor brevis dig. I.
*e.b.*2 M. extensor brevis dig. II.
*e.b.*3 M. extensor brevis dig. III.
*e.b.*4 M. extensor brevis 1 dig. IV.
*e.b.*4' M. extensor brevis 2 dig. IV.
*e.b.*5 M. extensor brevis dig. V.
*e.l.*1 M. extensor longus dig. I.
*e.l.*2 M. extensor longus dig. II.
*e.l.*3 M. extensor longus dig. III.
*e.l.*4 M. extensor longus dig. IV.
*e.l.*5 M. extensor longus dig. V.
F.t M. flexor tarsi posterior.
*i.*2 to *i.*10 MM. interossei.

hinder extremity of the astragalus, and by fleshy fibres from the hinder extremity of the fourth metatarsal; it is inserted by a thin tendon into the inner surface of the second phalanx of the same toe.

(8) The eighth *m. interosseus* (*i.*8) takes its origin from the outer surface of the fourth metatarsal and from the inner surface of the fifth: it is inserted into the hinder extremity of the second phalanx.

Fifth toe.

(9) The ninth *m. interosseus* (*i.*9) arises from the inner surface of the fifth metatarsal, and is inserted into the hinder extremity of the second phalanx.

(10) The tenth *m. interosseus* has already been described as the *abductor digiti V brevis* (Fig. 94 *i.*10).

If we take the fourth toe as the axis of movement, the first, third, fifth, seventh, eighth, and tenth *mm. interossei* will abduct from an imaginary line which runs through this toe. The second, fourth,

sixth, and ninth will adduct towards this line. If we compare them with those of man (in whose case the second toe affords the central line), those of the first group must be regarded as *mm. interossei dorsales*, of the latter as *plantares*. Dugès holds all these *interossei* (with the exception of the first, *abductor brevis dig. I*) to be *mm. interossei dorsales* (métatarso-sus-phalangettiens, n. 210, 211, 212, 214, 215, 216, 218, 219). Those which I have described as *flexores proprii digitorum*, he regards as *interossei volares*.

V. MUSCLES OF THE SKIN.

196. *M. cutaneus pectoris* (Fig. 95 *cp*).

> Dugès, abdomino-guttural, n. 53.—Klein, abdomino-cutaneus.—Zenker, subcutaneus pectoris.

This is an elongated quadrangular muscle, attached by its hinder margin to the side of the xiphisternum, and to the superficial surface of the aponeurosis of the *m. obliquus externus*. The fibres course forwards and slightly outwards to be inserted, at a very acute angle, into the skin: lying between the two muscles and attached to them on either side is a thin fascia, which, together with the muscles and the *septum thoracicum*, assists in closing a triangular space between these structures and the deeper muscles.

The thinness and transparency of this muscle render it especially suitable for the investigation of nerve-terminations [1].

Fig. 95.

Pectoral region of *Rana esculenta*.

cp M. cutaneus pectoris.
p'' Port. abdominalis of the m. pectoralis.

197. *M. cutaneus dorsi* (Fig. 96 *cd*).

> Dugès, pubio-dorso-cutané, n. 56.—Zenker, *cutaneus iliacus*.

This muscle has a narrow origin in the space between the muscles

---

[1] Kölliker, Mikrosk. Anatomie, 1866, vol. II. 1, p. 247; Reichert, Müller's Archiv, 1851, p. 29, Pl. I; Kölliker, Untersuchungen über die letzten Endigungen der Nerven in den Muskeln des Frosches; Leipzig, Engelmann, 1862.

of the belly and of the thigh, and is here inserted into the fasciae, which are attached to the pubic symphysis; it passes inwards and upwards to the outer side of the anterior insertion of the *m. rectus femoris anticus*, then widens and is inserted by diverging fibres into the inner surface of the skin of the hinder portion of the back.

Fig. 96.

Hind portion of back and thigh of *Rana esculenta*.

cd   M. cutaneus dorsi.
cx. Coccyx.
gl. M. glutaeus.
H   Skin reflected to left side.
oe   M. obliquus externus.
rf   M. rectus femoris anterior.
sm   M. semimembranosus.
v.e M. vastus externus.

198. *M. coccygeo-cutaneus.*

Dugès, coccy-dorso-cutanés, n. 57.

The muscular fibres which Dugès has described under this name, lie covered by the *m. pyriformis*, behind the *m. coccygeo-iliacus*, etc., and above the muscles of the rectum. They arise from the hinder extremity of the urostyle: they appear to be connected with the rectal muscles, and pass outwards to be attached to the skin.

Among the cutaneous muscles may perhaps be included the *m. submaxillaris* (p. 62).

The fibrils passing from the flexor tendons to the warty bodies on the plantar surface of the toes are described [1] with the skin (p. 373).

---

[1] Compare Klein, Beiträge zur Anatomie der ungeschwänzten Batrachier (R. temporaria, L.): Jahreshefte des Vereins für vaterländische Naturkunde in Württemberg, 1850, p. 72.

SECTION III.

THE NERVOUS SYSTEM.

THE NERVOUS SYSTEM.

LITERATURE.

Ahlborn, F., Ueber die Bedeutung der Zirbeldrüse. Zeit. f. wiss. Zool. 1884. Vol. XL, pp. 331–337.

Allen, H., The Spinal Cord in Batrachia and Reptilia. Proc. Acad. Nat. Sci. Philadelphia. 1883, pp. 56–57.

Arndt, A. W., Untersuchungen über die Ganglienkörper des Nervus sympathicus. Arch. f. mikrosk. Anat. 1874. Vol. X, pp. 208–241.

Arndt, R., Untersuchungen über die Endigung der Nerven in den quergestreiften Muskelfasern. Arch. f. mikrosk. Anat. 1873. Vol. IX, p. 481.

Arndt, R., Untersuchungen über die Ganglienkörper der Spinalganglien. Arch. f. mikrosk. Anat. 1875. Vol. XI, p. 140.

Arnold, J., Zur Histologie der Lungen des Frosches. Virchow's Arch. 1863. Vol. XXVIII, p. 433.

Arnold, J., Histologische Verhältnisse des Frosch-Sympathicus. Centralbl. f. d. med. Wiss. 1864. p. 657.

Arnold, J., Ueber die feineren histologischen Verhältnisse der Ganglienzellen in dem Sympathicus des Frosches. Virchow's Arch. 1865. Vol. XXXII, p. 1.

Arnold, J., Die Spinalfasern im Sympathicus des Frosches. Arch. f. Anat. und Physiol. 1866, p. 398.

Arnold, J., Das Gewebe der organischen Muskeln. Leipzig, 1869; and Chap. IV in Stricker's Handbook.

Arnstein, C., and Gonjaew, K., Ueber die Nerven des Verdauungskanals. Bericht. f. Physiol. u. Histologie. Mittheilung. aus. d. 4 Vers. wissensch. Naturforsch. zu Kasan. Pflüger's Arch. d. ges. Physiol. 1874. Vol. VIII, pp. 614–615.

Aubert, H., Die Innervation der Kreislaufsorgane, Hermann's Handbuch der Physiologie. Leipzig, 1880. Vol. IV, Pt. I, p. 377.

Axmann, De Gangliorum systematicis structura perstitiori eiusque functionibus. Berolini, 1847.

Axmann, Beiträge zur mikroskopischen Anatomie und Physiologie des Ganglien-nervensystems. 1853, p. 20.

Baculo, B., Nuove ricerche intorno l'apparechio ganglionare intrinseco dei cuori linfatici. Naples, 1885.

Balfour, F. M., Treatise on Comparative Embryology. London, 1880.

Balfour, F. M., Handbuch der vergleichenden Embryologie. Aus dem Englischen von B. Vetter. Jena, 1880.

Beale, L. S., On the Structure and Formation of the so-called Apolar, Unipolar, and Bipolar Nerve-cells of the Frog. Phil. Trans. 1863, p. 543. (Hyla arborea.)

Beale, L. S., Further observations in favour of the view that nerve-fibres never end in voluntary muscle. Proc. Roy. Soc. 1863. Abstract in Quart. Journ. Micros. Sci. 1863. Vol. XII, p. 668.

Beale, L. S., New observations upon the structure, etc. of certain nervous centres. Proc. Roy. Soc. 1860. Vol. III.

Beale, L. S., On the Distribution of Nerves to the elementary fibres of Striped Muscle. Phil. Trans. 1864, p. 611.

Beale, L. S., Of very fine nerve-fibres ramifying in certain fibrous tissues and trunks, and plexuses consisting entirely of very fine nerve-fibres in the bladder of the frog. Beale's Archives of Medicine, 1864. Vol. IV, pp. 19-251.

Beard, J., The Ciliary or Motor-oculi ganglion and the Ganglion of the ophthalmicus profundus in Sharks. Anatom. Anzeiger. 1887. Vol. II, p. 565.

Beck, K., Zur Kenntniss der Herznerven. Arch. f. mik. Anat. 1885. Vol. XXIV, pp. 11-19.

Bellonci, G., Intorno alla struttura e alle connessioni dei lobi olfattorii negli arthropodi superiori e nei vertebrati. Atti Accad. Lincei Ann. 279 Mem. Accad. Bologna, Vol. XIII, pp. 555-564: and in Arch. Ital. Biol. 1883; Vol. III, pp. 191-196.

Bellonci, G., Sulla terminazione centrale del nervo ottico nei mammiferi. Mem. Accad. Bologna, Vol. VI, pp. 199-205: and in Arch. Ital. Biol. 1884, Vol. VI, pp. 405-411.

Bidder, F. H., Die Endigungsweise der Herzzweige des N. vagus beim Frosch. Arch. f. Anat. u. Physiol. 1839, p. 1.

Bidder, F. H., Zur Lehre von dem Verhältniss der Ganglienkörper zu den Nervenfasern. Nebst einem Anhange von Dr. A. W. Volkmann. Leipzig, 1847.

Bidder, F. H., Zur Lehre vom Verhalten der Ganglienkörper, u. s. w. Leipzig, 1847.

Bidder, F. H., Ueber functionelle verschiedene und räumlich getrennte Nervencentra im Froschherzen. Arch. f. Anat. u. Physiol. 1852, p. 163.

Bidder, F. H., Endigungsweise der Herzzweige des N. vagus beim Frosch. Arch. f. Anat. und Physiol. 1868, p. 1.

Bidder, F. H., Zur näheren Kenntniss des Froschherzens und seiner Nerven. Arch. f. Anat. u. Physiol. 1866, p. 1.

Bidder, F. H., and Kupffer, Untersuchungen über die Textur des Rückenmarks. Leipzig, 1857.

Bidder, F. H., and Volkmann, A. W., Die Selbständigkeit des sympathischen Nervensystems, durch anatomische Untersuchungen nachgewiesen. Leipzig, 1842.

Bidder and Gregory, Beiträge zur Physiologie der Herzbewegung beim Frosche. Dorpat, 1865.

Bikfalvi, K., Ueber die Hornscheide der markhaltigen Nervenfasern. Orvostermészettudomanyi Ertesito, 1884, p. 133. Abstract in Centralbl. f. d. med. Wiss. 1886, p. 34.

Biroege, E. A., Die Zahl der Nervenfasern u. der motor. Ganglienzellen im Rückenmark des Frosches. Arch. f. Anat. u. Physiol. 1882. Physiol. Abth., p. 435.

Bischoff, Nervi accessorii Willisii anatomia et physiologia. Heidelberg, 1832.

Blasius, G., Gerardi Blasii Anatomia Animalium. Amstelodami, 1681.

Blattmann, A., Mikrosk. anatom. Darstellung der Centralorgane des Nervensystems bei den Batrachiern. Dissert. Zürich, 1850.

Boll, F., Studj sulle immagini microscopiche della fibra nervosa midollare. Atti della R. accademia dei Lincei, 1876-1877. Vol. II.

Boll, F., Ueber Zersetzungsbilder der markhaltigen Nervenfasern. Arch. f. Anat. u. Physiol. 1877, p. 288.

Bojanus, Testudinis anatomia. 1819.

Bosse, De ganglior. spinal. vi in nutr. radic. poster. nervor. spinal. Dissert. 1859.

Boveri, T., Beiträge zur Kenntniss der Nervenfasern. Abhandl. d. bayr. Akad. d. Wiss. 1885. Vol. XV, p. 421.

Bremer, D. L., Die Nerven der Capillaren, der kleinen Arterien und Venen. Arch. f. mik. Anat. 1882, p. 663.

Bremer, L., Ueber die Muskelspindeln sowie über Structur, Neubildung u. Innervation der quergestreiften Muskelfaser. Waldeyer's Arch. 1883. Vol. XXII, p. 2.

Bremer, L., Ueber die Endigungen der markhaltigen und marklosen Nerven im quergestreiften Muskel. Arch. f. mikrosk. Anat. 1882. Vol. XXI, p. 165.

Brenner, A., Ueber das Verhältniss des nervus laryngeus inferior vagi zu einigen Aortenvarietäten des Menschen und zu dem Aortensystem der durch Lungen athmenden Wirbelthiere überhaupt. His u. Braune's Arch. 1883, pp. 373–397.

Budge, J., Ueber den Verlauf der Nervenfasern im Rückenmark des Frosches. Arch. f. Anat. u. Physiol. 1844, p. 160.

Budge, J., Ueber die Bewegung der Iris. (Concerning ganglia of motor-oculi, p. 36.)

Budge, J., Wagner's Handwörterb. d. Physiologie. 1846. Vol. III, p. 451.

Burdon-Sanderson, J., Circulation of the Blood. Handbook for the Physiological Laboratory. London, 1873.

Calberla, E., Ueber die Endigungsweise der Nerven in den quergestreiften Muskeln bei Amphibien. Zeit. f. wiss. Zool. 1874. Vol. XXIV, p. 164.

Calberla, E., Studien über die Entwicklung der quergestreiften Muskeln und Nerven der Amphibien und Reptilien. Arch. f. mik. Anat. 1875. Vol. XI, p. 442.

Carus, Versuch einer Darstellung des Nervensystems und Gehirns. Leipzig, 1814.

Champness, F., The septum atrium of the Frog and Rabbit. Journ. of Anat. and Physiol. 1874.

Christmas-Dirckinck-Holmfeld, J., Experimentaluntersuchungen über den Bau der Regio olfactoria. Nord. med. ark. 1883. Vol. XV, No. 3.

Ciaccio, G. V., On the nerves of the Cornea, and their distribution in the corneal tissue of man and animals. Proc. Roy. Soc. 1863. Abstract in Trans. Micros. Soc. London, 1863. Vol. XI, pp. 77–93.

Ciaccio, G. V., On the distribution of nerves to the skin of the frog, with physiological remarks on the ganglia connected with the cerebro-spinal nerves. Quart. Journ. Micros. Sci. 1864. Vol. IV, pp. 15–31.

Ciaccio, G. V., Intorno alla minuta fabbrica delle pelle Rana esculenta. Giornale di Scienze naturali ed economiche. Palermo, 1866. Vol. II, p. 103.

Clarke, J. Lockhart, Ueber den Bau des Bulbus olfactorius und der Geruchsschleimhaut. Zeit. f. wiss. Zool. 1862. Vol. XI, p. 31.

Cornil and Ranvier, A Manual of Pathological Histology. London, 1880, p. 359. Fig. 199 (Ganglia of heart).

Courvoisier, G., Beobacht. über den sympathischen Gränzstrang. Arch. f. mik. Anat. 1866. Vol. II, p. 13.

Courvoisier, L. G., Ueber die spinalen und sympathischen Zellen des Frosches. Centralbl. f. d. med. Wiss. 1867, p. 897.

Courvoisier, G., Ueber die Zellen der Spinalganglien, sowie des Sympathicus beim Frosch. Arch. f. mikrosk. Anat. 1868. Vol. IV, p. 125.

Cuvier, Leçons d'anatomie comparée. 2nd Edit. Vol. II.

Cyon, Ueber die Nerven des Peritoneum. Berichte über die Verhandlungen d. königl. sächs. Gesellsch. d. Wissensch. zu Leipzig. Math.-physik. Classe. 1868. Vol. XX, p. 119.

Czermak, J. N., Ueber die Hautnerven des Frosches. Arch. f. Anat. u. Physiol. 1849, p. 252. Leipzig, 1869.

Czermak, J. N., Ueber die Herznerven des Frosches, Rana temporaria. Arch. f. Anat. u. Physiol. 1851, p. 160.

v. Darkschewitsch, L., Zur Anatomie der Glandula pinealis. Neurol. Cent. Bl. 1886. Vol. V, p. 29.

v. Deen, De differentia et nexu inter nervos vitae animalis et vitae organicae. Diss. inaugur. Lugduni-Bat., 1834.

v. Deen, Over de zijdelingsche Takken dar swervende zenuw van den Proteus anguineus, aus Bijdragen tot de Naturkundige. Wettenschappen, 1834.

v. Deen, Ueber den Ramus lateralis n. vagi bei den Batrachiern. Arch. f. Anat. u. Physiol. 1834, p. 477 (abstract from Diss. inaugur. De differentia et nexu inter nervos vitae animalis et vitae organicae). Lugduni-Bat.

Deiters, O., Untersuchungen über Gehirn und Rückenmark. Braunschweig, 1865.

Denissenko, G., Zur Frage über den Bau der Kleinhirnrinde bei verschiedenen Klassen von Wirbelthieren. Arch. f. mikrosk. Anat. 1877. Vol. XIV, p. 203.

Dietl, M. J., Beobachtungen über Theilungsvorgänge an Nervenzellen. Wiener Sitzungsber. 1874. Vol. LXIX, Pt. III, p. 71.

Dietl, M. J., Casuistische Beiträge zur Morphologie der Nervenzellen. Wiener Sitzungsber. 1874. Vol. LXIX, Pt. III, p. 80.

Dogiel, J., Die Ganglienzellen und Nerven des Herzventrikels beim Frosche. Arch. f. mikrosk. Anat. 1877. Vol. XIV, p. 470.

Dogiel, J., Die Ganglienzellen des Herzens bei verschiedenen Thieren und beim Menschen. Arch. f. mikrosk. Anat. 1877. Vol. XVII, p. 471.

Dogiel, J., Die Nervenzellen und Nerven des Herzventrikels beim Frosche. Arch. f. mikrosk. Anat. 1882. Vol. XXI, p. 21.

Duméril, A. M. C., and **Bibron, G.,** Erpétologie générale ou histoire naturelle complète des reptiles. Paris, 1841.

Eberth, Untersuchungen zur normalen und pathologischen Anatomie der Froschhaut. Leipzig, 1869.

Ecker, A., Icones physiologicae. Leipzig, 1851 to 1859.

Eckhard, C., Beiträge zur Anatomie und Physiologie. Giessen, 1860. Vol. II.

Eckhard, C., Experimentale Physiologie des Nervensystems. Giessen, 1867, p. 208 (Ganglion cells of heart).

Edinger, L., Nachtrag zu dem Bericht über Leistungen auf dem Gebiete der Anatomie des Centralnervensystems. Schmidt's Jahresb. 1887.

Egorow, W., Ueber die Nervenzellen der Lungen. Centralbl. f. med. Wiss. 1879. Vol. XVII, p. 305.

Eichholtz, De piscium atque amphibiorum nudorum lobis opticis atque olfactoriis. Berolini, 1841.

Engelmann, T. W., Zur Physiologie des Ureter. Pflüger's Arch. f. d. ges. Physiol. 1869. Vol. II, p. 243. (Treats also of histological details of frog's bladder.)

Engelmann, T. W., Ueber die Discontinuität des Axencylinders und den fibrillären Bau der Nervenfasern. Pflüger's Arch. f. d. ges. Physiol. 1880. Vol. XXII, p. 1.

Engelmann, T. W., Der Bulbus aortae des Froschherzens. Pflüger's Arch. f. d. ges. Physiol. 1882. Vol. XXIX, p. 425.

Fischer, E., Ueber die Endigung der Nerven im quergestreiften Muskel der Wirbelthiere. Arch. f. mik. Anat. 1876. Vol. XIII, pp. 365-390.

Fischer, J. G., Amphibiorum nudorum neurologiae specimen primum. Berlin, 1843; and Arch. f. Anat. u. Physiol. 1844, p. 57.

Fowelin, C., De causa mortis post nervos vagos dissectos instantis. Inaug. Dissert. Dorpati, 1851.

Frenkel, S., Nerv und Epithel am Froschlarvenschwanze. Arch. f. Anat. u. Physiol. 1886. Physiol. Abth., p. 405.

Frey, Handb. d. Histologie u. Histochemie d. Menschen. 3rd Edit., p. 341. (Ganglia of heart.)

Friedländer, Ueber die nervösen Centralorgane des Froschherzens. Untersuch. aus d. physiol. Laborat. zu Würzburg. 1867.

Frommann, Ueber Structur der Nervenzellen. Virchow's Arch. 1864. Vol. XXXI, p. 129.

Fubini, S., Gewicht des centralen Nervensystems im Vergleich zu dem Körpergewicht der Thiere, bei R. esculenta u. R. temporaria, Moleschott's Untersuchungen zur Naturlehre d. Menschen. 1881. Vol. XII, pp. 455-461.

Gad, J., Ueber Centrum und Leitungsbahnen im Rückenmark des Frosches. Verhandl. der Physiol. Gesellsch. zu Berlin, No. 10, 1884. Arch. f. Anat. u. Physiol.

1884, p. 304. Verhandl. d. physick. med. Gesellsch. zu Würzburg. 1884. Vol. XVIII.

Gaskell, W. H., On the augmentor (accelerator) nerves of the heart of cold-blooded animals. Journ. of Physiol. 1884. Vol. V, p. 46.

Gaskell, W. H., and Gadow, On the anatomy of the cardiac nerves in certain cold-blooded animals. Journ. of Physiol. 1884. Vol. V, p. 362.

Gaskell, W. H., The Structure, Distribution, and Function of the Nerves which innervate the Visceral and Vascular System. Journ. of Physiol. 1886. Vol. VII, p. 1.

Gegenbaur, C., Grundzüge der vergleichenden Anatomie. 1870. 2nd Edition, p. 728.

Gerlach, J., Ueber das Verhalten der Nerven in den quergestreiften Muskelfäden der Wirbelthiere. Sitzungsber. d. phys.-med. Societät zu Erlangen. 1873. Vol. V, p. 97.

Gerlach, J., Das Verhältniss der Nerven zu den willkürlichen Muskeln der Wirbelthiere. Leipzig, 1874.

Gerlach, J., Ueber die Nervenendigungen in der Muskulatur des Froschherzens. Virchow's Arch. 1876. Vol. LXVI, pp. 187-223.

Gerlach, J., Das Verhältniss der nervösen und contractilen Substanz d. quergestreiften Muskels. Arch. f. mikrosk. Anat. 1877. Vol. XIII, p. 399.

Giuliani, Sulla struttura del midollo spinale della Lacerta viridis. Memorie della R. academia dei Lincei. Roma, 1878.

Goette, A., Kurze Mittheilungen aus der Entwicklungsgeschichte der Unke. Arch. f. mik. Anat. 1873. Vol. IX, p. 396.

Goette, A., Entwickelungsgeschichte der Unke. Leipzig, 1875.

Golgi, C., Sulla fina anatomia degli organi centrali del sistema nervoso. Milano, 1866.

Golgi, C., Sui Nervi dei Tendini dell' Uomo e di altri Vertebrati e di un nuovo organo nervoso terminale muscolo-tendineo. Estr. dalle Memorie della Reale Acc. di Torino. 1880. Vol. XXXII, p. 29.

Gonjaew, K., Die Nerven des Nahrungsschlauches. Arch. f. mikrosk. Anat. 1875. Vol. XI, pp. 479-496.

de Graaf, H. W., Zur Anatomie u. Entwicklung d. Epiphyse bei Amphibien u. Reptilien. Zool. Anz. 1886. Vol. IX, No. 219.

de Graaf, H. W., Over den bouw der epiphyse bij de amphibien. Tijdschr. der Nederl. dierkundige Vereeniging. 1886. Vol. II, p. 1.

de Graaf, H. W., Bijdrage tot de kennis van der bouw ende entwickkeling der epiphyse bij amphibiën en reptiliën. Inaug.-Diss. Leiden, 1886. Abstract in Centralbl. f. d. med. Wiss. 1886, p. 706.

Grant, R., Comparative Anatomy. London, 1839.

Grant, R., Umrisse der vergleichenden Anatomie von R. E. Grant. Aus dem Englischen von C. C. Schmidt, M.D. Leipzig, 1842.

Gruenhagen, A., Ueber ein Endothelialelement der Nervenprimitivscheide. Arch. f. mik. Anat. 1884. Vol. XXIII, p. 380.

Gscheidlen, R., Ueber Nervenendigung in den glatten Muskelfasern. Arch. f. mik. Anat. 1877. Vol. XIV, pp. 320-332.

Guillot, Exposition anatomique de l'organisation des centres nerveux dans les quatres classes d'animaux vertébrés. Paris, 1844.

Hannover, A., Die Chromsäure, ein vorzügliches Mittel bei mikroskopischen Untersuchungen. Arch. f. Anat. u. Physiol. 1840, pp. 549-556. (Describes the connection between fine fibres and small ganglia in the central nervous system of fish, frogs, and birds.)

Hannover, A., Recherches microscopiques sur le système nerveux. Recherches sur le cerveau de la grenouille, pp. 20-22. Kopenhagen, Paris, and Leipzig, 1844.

Harless, Ern., Ueber die Functionen verschiedener Parthien des Rückenmarks der Amphibien. Arch. f. Anat. u. Physiol. 1846, p. 74.

Hartmann, D. B., Ueber die Endigungsweise der Nerven in den Papillae fungiformes der Froschzunge. Arch. f. Anat. u. Physiol. 1863, p. 634.

Heidenhain, Disquisitiones de nervis organisque centralibus cordis. Dissert. inaug. Berol. 1854; and in Arch. f. Anat. u. Physiol. 1858, p. 479.

Hénoque, Du mode de distribution et de la terminaison des nerfs dans les muscles lisses. Arch. de l'Anat. et de la Physiol. 1870.

Hensen, V., Ueber die Entwicklung des Gewebes und der Nerven im Schwanze der Froschlarve. Virchow's Arch. 1864. Vol. XXXI, p. 51.

Hensen, V., Ueber die Nerven im Schwanz der Froschlarven. Arch. f. mik. Anat. 1868. Vol. IV, p. 111.

Hesse, F., Zur Kenntniss der peripherischen markhaltigen Nervenfaser. His u. Braune's Arch. f. Anat. u. Physiol. 1879. Vol. VI, p. 89. Abstract in Centralbl. f. d. med. Wiss. 1880, p. 324.

His, W., Ueber die Endigung der Gefässnerven. Virchow's Arch. 1863. Vol. XXVIII, p. 427.

Hjelt, De nervis cerebralibus parteque cephalica nervi sympathici Bufonis cinerei adnotata quaedam. Helsingforsiae, 1852.

Hoffmann, C. K., in Bronn's Klassen und Ordnungen des Thierreichs. Leipzig and Heidelberg, 1873–1878. Vol. VI. Amphibia.

Holl, M., Ueber den Bau der Spinalganglien. Wiener Sitzungsber. 1876. Vol. LXXII, Pt. III, p. 31.

Horn, H., Ueber die Endschlingen des Geruchsnerven (Nervus olfactorius) in Rana temporaria. Arch. f. Anat. und Physiol. 1850.

Huizinga, D., Untersuchungen über die Innervation der Gefässe in der Schwimmhaut des Frosches. Pflüger's Arch. f. d. ges. Physiol. 1875. Vol. XI, pp. 207–221.

Huxley, T. H., Article Amphibia. Encyclopaedia Britannica, 9th Edition.

Isquierdo, V., Ueber die Endigungsweise der sensiblen Nerven. Arch. f. mikrosk. Anat. 1880. Vol. XVII, p. 367.

Jacubowitsch, M. N., Terminaisons des nerfs à la périphérie et dans les différents organes ou terminaisons périphériques du système nerveux en général. Comptes rendus. 1860. Vol. L, p. 859.

Jantschitz, J., Materialien zur Anatomie der Nerven des Pericardiums. Rudneff's Journ. f. normale u. patholog. Histologie u. klinische Med. St. Petersburg, 1874, pp. 417–442. (In Russian, Abstract in Centralbl. f. d. med. Wiss. 1874.)

Johnson, A., and Sheldon, L., Note on the Development of the Newt (Triton cristatus). Quart. Journ. Micros. Sci. 1886. Vol. XXVI, p. 573.

Kandaraski, M., Ueber die Nerven der Respirationswege. His u. Braune's Arch. f. Anat. u. Entwickelungsgesch. 1881, pp. 1–11.

Kanhel, G., Studien über Innervation der Lymphherzen. Medic. Jahrb. 1886, pp. 392–420.

Karabanowitsch, D., Ueber den Bau des Rückenmarkes vom Frosche. Arbeiten der St. Petersburger Gesellsch. der Naturforscher. St. Petersburg, 1872, pp. 402–421.

Key, A., and Retzius, G., Studien in der Anatomie des Nervensystems. Arch. f. mikrosk. Anat. 1873. Vol. IX, p. 308.

Klebs, E., Die Nerven der organischen Muskeln. Centralbl. f. wiss. Med. 1863, p. 561.

Klebs, E., Die Nerven der organischen Muskelfasern. Virchow's Arch. 1865. Vol. XXXII, p. 168.

Klein, E., Beiträge zur Anatomie der ungeschwänzten Batrachier. Württemberger Jahreshefte. 1850, pp. 1–84.

Klein, E., Auerbach's Plexus in the Intestine of Frog and Toad. Quart. Journ. Microsc. Sci. 1873. Vol. XIII, pp. 377–380.

Klein, E., Some ~~www.books of the finer~~ nerves of the Cornea. Monthly Micros. Journ. 1872. Vol. VII, pp. 156–164.

Klein, E., On the peripheral distribution of non-medullated nerve-fibres. Quart. Journ. Microsc. Sci. 1871. Vol. XI. New Series, p. 405.

Klug, F., Ueber die Herznerven des Frosches. Arch. f. Anat. u. Entwicklungs-gesch. 1881, pp. 330–346.

Klug, F., Ueber die Beschleunigungsnerven des Froschherzens. Centralbl. f. med. Wissensch. Berlin, 1881, pp. 945–948.

v. Kölliker, A., Neurologische Bemerkungen. Zeit. f. wiss. Zool. 1849. Vol. I, p. 135.

v. Kölliker, A., Handbuch der Gewebelehre. 5th Edit. 1861, p. 163. (On nerve-fibres of frog's heart.)

v. Kölliker, A., Vorläufige Mittheil. über den Bau des Rückenmarks bei niederen Wirbelthieren. Zeit. f. wiss. Zool. 1858. Vol. IX, p. 1.

v. Kölliker, A., Ueber die letzten Endigungen der Nerven in Muskeln des Frosches. Würzburger naturwissensch. Zeitschrift. Vol. III. Sitzungen, 8th and 22nd March, 1862.

v. Kölliker, A., Untersuchungen über die letzten Endigungen der Nerven. Zeit. f. wiss. Zool. 1863. Vol. XII, p. 149.

v. Kölliker, A., Histologische Studien an Batrachierlarven. Zeit. f. wiss. Zool. 1886. Vol. XII, pp. 1–4.

v. Kölliker, A., Ueber die Vitalität der Nervenrohren der Frösche. Würzburg. Verhandl. 1857. Vol. VII, p. 145.

Kollmann, J., Ueber den Verlauf des Lungenmagennerven in der Bauchhöhle. Zeit. f. wiss. Zool. 1859–1860. Vol. X, p. 413.

Kollmann, J., and Arnstein, Die sympathischen Ganglienzellen des Frosches. Zeitschr. f. Biologie. 1866. Vol. II, p. 271.

Königstein, L., Beobachtungen über die Nerven der Cornea und ihre Gefässe. Wiener Sitzungsber. 1878. Vol. LXXVI, Pt. III, p. 37.

Köppen, M., Zur Anatomie des Froschgehirns. Neurologisches Centralblatt. 1888.

Köppen, M., Zur Anatomie des Froschgehirns. Arch. f. Anat. u. Physiologie, 1888.

Korybutt-Daszkiewicz, W., Ueber die Entwicklung der Nerven aus Plasmazellen beim Frosche. Arch. f. mikrosk. Anat. 1878. Vol. XV, p. 1.

Krause, W., Die Nervenendigungen in den Froschmuskeln. Internat. Monats. f. Anat. u. Histologie. 1884. Vol. I, p. 194.

Krause, W., Ueber die Drüsennerven. Zeitschr. f. rat. Medicin. Dritte Reihe. Vol. XXIII, p. 60.

Krohn, A., Ueber den Ramus lateralis n. vagi bei niedrigen Amphibien. Fror. Not. 1836. Vol. XLVIII, p. 1043.

Krohn, A., Ergänzungen der Nachricht über den n. lateralis der Froschlarven. Fror. Not. 1838. Vol. VII, n. 137.

Kühne, W., Die Endigungsweise der Nerven in den Muskeln und das doppelsinnige Leitungsvermögen der motorischen Nervenfaser. Monatsbericht der Königl. Akademie der Wissenschaften zu Berlin, 19 May, 1859.

Kühne, W., Die peripher. Endorgane der motorischen Nerven. Leipzig, 1862.

Kühne, W., Zur Lehre von den Endplatten der Nervenhügel. Virchow's Arch. 1865. Vol. XXXIV, p. 412.

Kühne, W., Zur Histologie der motorischen Nerven. W. Kühne's Heidelberger Untersuchungen, 1879. Vol. II, p. 187. Abstract in Centralbl. f. d. med. Wiss. 1879, p. 405.

Kühne, W., Ueber Nervenendigungen in den Muskeln nach Beobachtungen von M. B. von Syckel. Verhandl. des naturf. Vereins z. Heidelberg, 1884. Vol. III, p. 238.

Kühne, W., Widerlegen der Bemerkung E. du Bois-Reymonds über mehrfache Nervenendigungen in einer Muskelfaser. Zeitschr. f. Biol. 1884. Vol. XX, pp. 531–539.

Kühne, W., Ueber das doppelsinnige Leitungsvermögen der Nerven. Zeitschr. f. Biol. 1886. Vol. XXII, p. 305.

Kuhnt, J. H., Die peripherischen markhaltigen Nervenfasern. Arch. f. mik. Anat. 1877. Vol. XIII, p. 427.

Kupffer, De medullae spinalis textura in Ranis. 1854. Dissert. inaug.

Kutschin, Zur Structur des Nervengewebes. Centralbl. f. d. med. Wiss. 1865, p. 561.

Küttner, C., De origine n. sympathici ranarum, ex nervorum dissectorum mutationibus dijudicatur. Dorpat, 1854. Dissert. inaug.

Lahousse, P., Die Structur des Nervenplexus in der Vorhofscheidewand des Froschherzens. Arch. f. Anat. u. Physiol. 1886, p. 19.

Langerhans, P., Zur Histologie des Herzens. Virchow's Arch. 1873. Vol. LVIII, p. 65.

Lantermann, A. J., Bemerkungen über den feineren Bau der markhaltigen Nervenfasern. Centralbl. f. d. med. Wiss. 1874, p. 706.

Lantermann, A. J., Ueber den feineren Bau der markhaltigen Nervenfasern. Arch. f. mikrosk. Anat. 1877. Vol. XIII, p. 1.

Lavdowsky, N., Die feinere Structur und die Nervenendigungen der Froschharnblase. Arch. f. Anat. und Physiol. 1872, p. 55.

Lavdowsky, N., Das Saugadersystem und die Nerven der Cornea. Arch. f. mikrosk. Anat. 1872. Vol. VIII, p. 538.

Lavdowsky, N., Zum Nachweis der Axencylinderstructurbestandtheile von markhaltigen Nervenfasern. Centralbl. f. d. med. Wiss. 1879, pp. 865, 881.

Lavdowsky, N., Ueber die Fortsätze der Nervenzellen in den Herzganglien. Arch. f. mik. Anat. 1887. Vol. XXIX, p. 609.

Lehmann, J. C., Ueber die Nervenendigungen und das Vorkommen von mikroskopischen Ganglien in den Gefässwandungen. Zeit. f. wiss. Zool. 1864. Vol. XIV, pp. 346–352.

Lenhossek, M., Untersuchungen über die Spinalganglien des Frosches. Arch. f. mikrosk. Anat. 1886. Vol. XXVI, pp. 370–453.

Leuret, Anatomie comparée du système nerveux de l'homme et des animaux vertébrés. Paris. Vols. I, II.

Lipmann, Die Nerven der organischen Muskeln. Dissert. Berlin, 1869.

Lominsky, T., Zur Frage über die Teilung der Nervenzellen. Centralbl. f. d. med. Wiss. 1882, p. 434.

Longet, Anatomie et Physiologie du système nerveux de l'homme et des animaux vertébrés. Paris, 1842.

Löwit, M., Die Nerven der glatten Muskulatur. Wiener Sitzungsb. 1875. Vol. LXXI, Pt. III, p. 355.

Löwit, M., Beiträge zur Kenntniss der Innervation des Froschherzens. Pflüger's Arch. f. d. ges. Physiol. Vol. XXIII, p. 313; Vol. XXV, p. 399; Vol. XXVIII, p. 312; Vol. XXIX, p. 469.

Löwit, M., Ueber die Gegenwart von Ganglienzellen im Bulbus aortae des Froschherzens. Pflüger's Arch. f. d. ges. Physiol. 1883. Vol. XXXI, pp. 88–94.

Löwit, M., Beiträge zur Kenntniss der Innervation des Herzens. Pflüger's Arch. f. d. ges. Physiol. 1881. Vol. XXV, pp. 399–496.

Luchsinger, B., Zur Innervation d. Lymphherzen. Pflüger's Arch. f. d. ges. Physiol. 1880. Vol. XXIII, p. 304.

Ludwig, C., Ueber die Herznerven des Frosches. Arch. f. Anat. u. Physiol. 1848, p. 139.

Macallum, A. B., The Nerve Terminations in the Cutaneous Epithelium of the Tadpole. Quart. Journ. Micros. Sci. 1885. Vol. XXVI, p. 53.

Maddox, On the apparent relation of Nerve to Connective-tissue Corpuscles. Monthly Microsc. Journ. Vol. IX, p. 109.

Maier, R., Die Ganglien u. d. harnbführenden Wegen des Menschen und einiger Thiere. Arch. f. pathol. Anat. u. Physiol. 1881. Vol. LXXXV, p. 49.

Marchi, P., Beobachtungen über Wimper-Epithel. Arch. f. mik. Anat. 1866. Vol. II, p. 467.

Marshall, A. M., The segmental value of the Cranial Nerves. Journ. of Anat. and Physiol. Vol. XVI, pp. 305-354.

Marshall, A. M., The Frog: an introduction to Anatomy and Physiology. Manchester and London, 1885.

Masius and Vaulair, De la situation et de l'étendue des centres réflexes de la moelle épinière chez la grenouille. Bruxelles, 1870.

Mason, J. J., A new group of Nerve-cells in the Spinal Cord of the Frog. New York Med. Journ. 1879.

Mason, J. J., Microscopic Studies on the Central Nervous System of Reptiles and Batrachia. Journ. of Nerv. and Mental Diseases. New York. 1880, Vol. VII, p. 8; 1881, Vol. VIII, p. 7.

Mason, J. J., Minute Structure of the Central Nervous System of certain Reptiles and Amphibia of America. Newport, 1884.

Mayer, A. F. J. C., Ueber das Gehirn der Amphibien und ein zoologisches Gesetz. Fror. Notizen, 1833. Vol. XXXVII, pp. 49-53.

Mayer, S., Zur Lehre der Struktur der Spinalganglien und der peripherischen Nerven in Rana esculenta. Arch. f. Anat. u. Physiol. 1858, p. 274.

Mays, K., Histo-physiol. Untersuchungen über die Verbreitung der Nerven in den Muskeln. Zeitschr. f. Biol. Vol. XX, p. 449.

Mays, K., Ueber die Nervatur des Musculus rectus abdominis des Frosches. Heidelberg, 1886.

Mays, K., Nervenfasertheilungen in den Nervenstämmen der Froschmuskeln. Zeitschr. f. Biologie. 1886. Vol. XXII, p. 354.

Meckel, A., System der vergleichenden Anatomie. Halle, 1833.

Meckel, J. F., Beiträge zur vergleichenden Anatomie. Leipzig, 1811.

Michel, Ueber den Bau des chiasma nervorum opticum. v. Gräfe's Arch. 1864. Vol. XIX, p. 59.

Müller, J., Beiträge zur Anatomie und Naturgeschichte der Amphibien. Tiedemann's Zeitschr. 1831. Vol. IV, pp. 190-275.

Namias, M., Sui ganglii miocardici della Rana. Osservazioni ed esperienze in Lo Spallanzani. 1881. Vol. X, pp. 402-419.

Niccolucci, G., Sul sistema nervoso e circolatorio della Salamandra aquaivola. Napoli, 1842.

Niura, M., Untersuchungen über die motorischen Nervenendigungen der quergestreiften Muskelfasern. Virchow's Arch. 1886. Vol. CV, p. 129.

Obersteiner, Ueber einige Lymphräume im Gehirne. Wiener Sitzungsber. 1870. Vol. LXI, Pt. I, p. 57.

Odenias, M. W., Undersökungar öfver de sensibla muskelnervena. Nord. Medic. Arch. Vol. IV, No. 18.

Onodi, A. D., Ueber die Entwicklung des sympathischen Nervensystems. Arch. f. mik. Anat. 1886. Vol. XXVI, p. 61.

Onodi, A. D., Ueber die Gangliengruppen der hinteren u. vorderen Nervenwurzeln. Centralbl. f. wiss. Med. 1885. Nos. 16 and 17.

v. Openchowski, Th., Beitrag zur Kenntniss d. Nervenendigungen im Herzen. Arch. f. mik. Anat. 1883. Vol. XXII, pp. 408-419.

v. Openchowski, Th., Histologisches zur Innervation der Drüsen. Pflüger's Arch. f. d. Ges. Physiol. 1882. Vol. XXVII, p. 223.

Osborne, H. F., Observations upon the Urodele Amphibian Brain. Zool. Anz. 1884. Vol. VII, p. 679.

Osborne, H. F., Observations on the presence of the corpus callosum in the brains of Amphibians and Reptiles. Zool. Anz. 1886. Vol. IX, p. 200.

Osborne, H. F., Note upon the cerebral commissures in the lower vertebrata and a probable fornix rudiment in the brain of Tropidonotus. Zool. Anz. 1886. Vol. IX, p. 577.

Partsch, C., Beiträge zur Kenntniss des Vorderdarmes einiger Amphibien und Reptilien. Arch. f. mik. Anat. 1877. Vol. XIV, p. 179.

Pertik, O., Untersuchungen über Nervenfasern. Arch. f. mik. Anat. 1881. Vol. XIX, p. 183.

Pfitzner, Nervenendigungen im Epithel. Morph. Jahrb. 1882. Vol. VII, pp. 726–745.

Popoff, N., Die Nerven der Gallenblase. Rudneff's Journ. f. normale und pathol. Histologie u. klin. Med. St. Petersburg, 1872. (In Russian. Abstract in Virchow and Hirschfeld's Arch.)

Priestley, J., An account of the anatomy and physiology of the batrachian lymph-hearts. Journ. of Physiol. 1878. Vol. I, p. 1.

Ranvier, L., Recherches sur l'histologie et la physiologie des nerfs. Arch. de physiol. normale et pathologique. 1872. Vol. IV, pp. 427–446.

Ranvier, L., Appareil nerveux terminaux des muscles de la vie organique. Leçons d'anat. générale. Paris, 1880, p. 350.

Ranvier, L., Des tubes nerveux en T et de leurs relations avec les cellules ganglionaires. Compt. rend. 1875. Vol. LXXXI, p. 1274.

Ranvier, L., Leçons sur l'histologie du système nerveux. 1878. Vol. I, pp. 98–101.

Rawitz, B., Ueber die Structur der Zellen in den Spinalganglien, etc. Arch. f. mik. Anat. 1880. Vol. XVIII, p. 283.

Rawitz, B., Ueber den Bau der Spinalganglien. Arch. f. mik. Anat. 1880. Vol. XVIII, p. 283.

Rawitz, B., Ueber den Bau der Spinalganglien. Arch. f. mik. Anat. 1882. Vol. XXI, p. 244.

Reichert, K. E., Ueber das Verhalten der Nervfasern bei dem Verlauf der Vertheilung und Endigung in einem Hautmuskel des Frosches, Rana temporaria. Arch. f. Anat. u. Physiol. 1851, p. 29.

Reissner, E., Der Bau des centralen Nervensystems der ungeschwänzten Batrachier. Dorpat, 1864.

Remak, R., Anatomische Beobachtungen über das Gehirn, das Rückenmark und die Nervenwurzel. Arch. f. Anat. u. Physiol. 1841, pp. 506–522.

Remak, R., Multipolare Ganglienzellen. Berliner Monatsberichte. 1854, p. 26.

Retzius, G., Undersökning öson cerebrospinalganglionus nervseller and särskild häusyn till dessus ut löpare. Nord. Med. Arkiv. 1879.

Retzius, G., Untersuchungen über die Nervenzellen der cerebrospinalen Ganglien, etc. Arch. f. Anat. u. Physiol. 1880, p. 360.

Reynier, Les nerfs du cœur. Paris, 1880 (pp. 32–37, ganglia of heart).

Rosenberger, De centris motuum cordis disquisitiones anatomico-pathologicae. Inaug. Diss. Dorpat, 1850.

Rouget, Note sur la terminaison des nerfs moteurs dans les muscles chez les reptiles, les oiseaux et les mammifères. Compt. rend. 1862. Vol. LV, pp. 548–555.

Rumph, T., Zur Histologie der Nervenfaser und des Axencylinders. W. Kühne's Heidelberger Untersuchungen. 1879. Vol. II, p. 355.

Sachs, C., Die Nerven der Sehnen. Reichert u. du Bois-Reymond's Arch. 1875, p. 402.

Sander, J., Die Spinalfasern im Sympathicus des Frosches. Arch. f. Anat. u. Physiol. 1866, p. 398.

Sanders, A., Contributions to the Anatomy of the Central Nervous System in Vertebrate Animals. Phil. Trans. 1882. Pt. III, p. 927.

Scheel, Ueber die Kreuzung der Sehnerven im Chiasma bei den Wirbelthieren u. beim Menschen. Klin. Monatsbl. f. Augenheilk. Vol. XII.

Scherhej, M. L., Zur Lehre der Innervation der Lymphherzen. Arch. f. Anat. u. Physiol. 1879. Physiol. Abth., p. 227.

Scherkey, M. L., Ueber die Feststellung und Bedeutung der Centren der Lymphherzen im Rückenmark. Dissert. Berlin, 1878. Abstract in Centralbl. f. d. med. Wiss. 1879, p. 117.

Schiefferdecker, P., Beiträge zur Kenntniss des Baus der Nervenfasern. Arch. f. mik. Anat. 1887. Vol. XXX, p. 435.

Schiess, Versuch einer speciellen Neurologie der Rana esculenta. St. Gallen und Bern, 1857.

Schmidt, M., Beiträge zur Kenntniss des Rückenmarkes der Amphibien. Zeit. f. Naturwiss. Vol. IV, pp. 1–45.

Schmidt, M., Beiträge zur Kenntniss des Rückenmarkes der Amphibien. Zeit. f. Naturwiss. Vol. LVIII, pp. 1–44.

Schöbl, J., Ueber die Blutgefässe des cerebrospinalen Nervensystems der Urodelen. Arch. f. mikrosk. Anat. 1882. Vol. XX, p. 87.

Schöbl, J., Ueber Wundernetze und divertikelbildende Capillaren bei nackten Amphibien und in pathologischen Neoplasmen. Arch. f. mik. Anat. 1885. Vol. XXV, p. 89.

Schönn, Ueber das angebliche Epithel des Rückenmarks und Centralcanals. Stettin, 1865.

Schönn, Ueber die Entwicklung des Rückenmarks. Stettin, 1865.

Schramm, Neue Untersuchungen über den Bau der Spinalganglien. Diss. Würzburg, 1864.

Schulgin, M. A., Lobi optici der Vögel; vergl. anat. Studien. Zool. Anz. 1885. Nos. 84 and 85.

Schultze, H., Axencylinder und Ganglienzelle. Reichert u. du Bois-Reymond's Arch. 1878, p. 259.

Schwalbe, G., Bemerkungen über die Kerne der Ganglienzellen. Jenaische Zeitschr. f. Naturwissensch. 1876. Vol. X, pp. 25–40.

Schwalbe, G., Ueber den Bau der Spinalganglien nebst Bemerkungen über die sympathischen Ganglienzellen. Arch. f. mik. Anat. 1868. Vol. IV, p. 45.

Schwalbe, G., Lehrbuch der Anatomie der Sinnesorgane. Erlangen, 1885.

Schwalbe, G., Das Ganglion oculomotorii. Jenaische Zeitsch. f. Naturwissensch. 1879. Vol. XIII, p. 173.

Schwalbe, G., Handbuch der Neurologie. Erlangen, 1881.

Schweiger-Seidel, Das Herz. Stricker's Gewebelehre, p. 177. (Ganglion cells of heart.)

Serres, C., Anatomie comparée du cerveau des quatres classes des animaux vertébrés. Paris, 1824.

Sokoloff, A. A., Ueber die Nervenendigungen in den Muskeln ausgehungerter Frösche. Med. Bote. St. Petersburg, 1876. Nos. 11, 15, and 16.

Sokolow, Sur les transformations des terminaisons des nerfs dans les muscles de la grenouille après la section des nerfs. Arch. de physiologie. 1864, p. 308.

Solly, S., The Brain. London, 1837.

Sommé, C. L., Recherches sur l'anatomie comparée du cerveau. Anvers, chez Ancelle, 1824.

Spencer, W. B., On the presence and structure of the parietal eye in Lacertilia. Quart. Journ. Micros. Sci. 1886. Vol. XXVII, p. 165.

Spina, A., Untersuchungen des lebenden Bindegewebes. Oesterr. med. Jahrb. 1885.

Stannius, Lehrbuch der vergleichenden Anatomie der Wirbelthiere. Berlin, 1856.

Stannius, Handbuch der Zootomie, 2nd Edit., 1856. Berlin. And Müller's Arch. 1852, p. 85.

Stannius, Handb. der Anatomie der Wirbelthiere. 2nd Edit., 1854.

Stieda, L., Studien über das centrale Nervensystem der Wirbelthiere. Zeitschr. f. wiss. Zool. 1870. Vol. XX, p. 273.

Stieda, L., Zur vergleichenden Anatomie und Histologie des Cerebellum. Reichert u. du Bois-Reymond's Arch. 1865, pp. 407-433.

Stirling, W., On the Nerves of the Lungs of the Newt. Journ. of Anat. and Physiol. 1882, p. 96.

Stirling, W., and Macdonald, F., The minute structure of the palatine nerves of the frog and the termination of nerves in blood vessels and glands. Journ. of Anat. and Physiol. 1884. Vol. XVII, p. 293.

Swan, Illustrations of the Comparative Anatomy of the Nervous System. London.

v. Thanhoffer, L., Neuer Nervenapparat im Dünndarm. Centralb. f. d. med. Wissen. 1883, pp. 33-35.

v. Thanhoffer, L., A csigolyaközti dúczsejtek szerkezetéhez. Értekezések á termé-szettudományok köréből. Kiadjá a. m. t. Akadémia. 1877.

Tiedemann, Anatomie und Bildungsgeschichte des Hirns. 1816.

Toel, G. H., Die Ranvierschen Schnürringe markhaltiger Nervenfasern und ihr Verhältniss zu den Neurilemmkernen. Dissert. Zürich, 1875.

Toloschinoff, Ueber das Verhalten der Nerven zu den glatten Muskelfasern der Froschharnblase. Arch. f. mik. Anat. 1869. Vol. V, p. 509; and in Stricker's Gewebelehre, p. 142.

Török, A., Beiträge zur Kenntniss der ersten Anlagen der Sinnesorgane und der primären Schädelformation bei den Batrachiern. Wiener Sitzungsber. 1886. Vol. LII, Pt. I, p. 646.

⟂ Traugott, Ein Beitrag zur feineren Anatomie des Rückenmarks von Rana tempo-raria. Dissert. Dorpat, 1861.

Treviranus, G. R., Untersuchungen über den Bau und die Functionen des Gehirns. 1820.

Treviranus, G. R., Ueber die hinteren Hemisphaeren des Gehirns der Vögel, Am-phibien und Fische. Zeit. f. Physiol. von Tiedemann und Treviranus. Heidelberg and Leipzig, 1831. Vol. IV, p. 39.

Treviranus, G. R., Bemerkungen über das Nervensystem des Fisches und über einige bisher unbeachtete Theile dieses Thieres in G. R. and L. Chr. Treviranus. Verm. Schriften Anat. u. Physiol. Vol. I, 1816, p. 94.

Tschiriew, S., Sur les terminaisons nerveuses dans les muscles striés. Arch. de physiol. norm. et pathol. 1879. Vol. VI, 2 sér., p. 89.

Valentin, Die letzten Enden der Nerven. Nova acta academ. caesar. Leop. 1836. Vol. XVIII, p. 51.

Vignal, Recherches sur l'appareil ganglionaire du cœur des vertébrés. Labora-toire d'histologie du Collège de France. Travaux de l'année 1881, p. 186. Also in Arch. de physiol. norm. et pathol. 1881, pp. 694-738, and pp. 910-934.

╋Vogt, C., Beiträge zur Neurologie der Reptilien. Neuchâtel, 1840.

Vogt, C., Zoologische Briefe. Frankfurt a. M., 1851, p. 197, etc.

Volkmann, A. W., Von dem Baue und den Verrichtungen der Kopfnerven des Frosches. Arch. f. Anat. u. Physiol. 1838, p. 70.

Volkmann, A. W., Ueber die Faserung des Rückenmarks und des sympathischen Nervensystems. Arch. f. Anat. u. Physiol. 1838, p. 274.

Volkmann, A. W., Ueber das Verhältniss des Nervus sympathicus zu dem übrigen Nervensystem beim Frosch. Fror. Not. 1842. Vol. XXI, p. 305.

Volkmann, A. W., Nachweise der Nervencentra, von welchen die Bewegung der Lymph- und Blutgefässherzen ausgeht. Arch. f. Anat. u. Physiol. 1844, p. 419.

Wagner, R., Icones Zootomicae. Leipzig, 1841.

Wagner, R., Sympathische Ganglien des Herzens. Handwörterbuch d. Physiol. Vol. III, p. 461.

Wagner, R., Lehrbuch der vergleichenden Anatomie. Leipzig, 1834–35, pp. 400–403.

Wagner, R., Icones Physiologicae. Leipzig, 1840.

Waldeyer, W., Zur Anatomie und Physiologie der Lymphherzen von Rana und Emys europaea. Studien des physiologischen Instituts zu Breslau. 1865. Vol. III.

Waller, A., On the minute structure of the Papillae and Nerves of the Tongue of the Frog and Toad. Phil. Trans. 1849, p. 139.

Waters, W. H., On the local Vaso-motor functions of the spinal nerves. Journ. of Physiol. 1885. Vol. VI, p. 460.

de Watteville, A Description of the Cerebral and Spinal Nerves of Rana esculenta. Journ. of Anat. and Physiol. 1875. Vol. IX, p. 145.

Weber, Beiträge zur Anatomie u. Physiologie. Bonn, 1832.

Weismann, Ueber das Wachsen der quergestreiften Muskeln nach Beobachtungen am Frosch. Henle und Pfeufer's Zeitschr. 1860. Vol. X, p. 264.

Wiedersheim, R., Zur Anatomie des Froschgehirns. Zool. Anz. 1881. No. 66, p. 497.

Wiedersheim, R., Ueber das Parietal-Auge der Saurier. Anat. Anz. 1886, p. 148.

Wiedersheim, R., Elements of Comparative Anatomy of Vertebrates, translated by W. Newton Parker. London, 1886.

Wiedersheim, R., Lehrbuch der vergleichenden Anatomie der Wirbelthiere auf Grundlage d. Entwicklungsgeschichte. Jena, 1886. 2nd Edit.

Wolff, W., Ueber Nervenendigungen im quergestreiften Muskel. Arch. f. mik. Anat. 1881. Vol. XIX, p. 331.

Wolff, W., Die Innervation der glatten Muskulatur. Arch. f. mik. Anat. 1882. Vol. XX, p. 361.

Wolff, W., Ueber freie, sensible Nervenendigungen. Arch. f. mik. Anat. 1882. Vol. XX, p. 377.

Wyman, J., Anatomy of the nervous system of Rana pipiens. Smithsonian Contributions to Knowledge. 1853. Vol. V.

Wyman, J., Results of microscopical examination of the structure of the brain and spinal cord in Frogs. Boston, Nat. Hist. Soc. 1851–1854. Vol. V, p. 107.

THE NERVOUS SYSTEM.

I. THE CENTRAL NERVOUS SYSTEM.

(Re-written by the translator.)

A. THE SPINAL CORD (Fig. 97).

1. External form. The spinal cord is, in comparison with the brain, somewhat small; the two organs are directly continuous, and present no distinct line of demarcation: the point of origin of the first spinal nerve is, therefore, arbitrarily accepted as the anterior limit of the spinal cord; posteriorly it terminates in the *filum terminale*.

The spinal cord is flattened dorso-ventrally, and is constricted at a point (*pars media*, Reissner) somewhat anterior to its middle: in consequence of this constriction the cord has two enlargements; an anterior smaller, and a posterior larger (*intumescentiae anterior v. posterior*), from which arise the nerves of the brachial and lumbar plexuses respectively. At about the sixth or seventh vertebra, the hinder enlargement diminishes rather abruptly to form the so-called *conus medullaris*; this is continued into the *filum terminale*, which enters the cavity of the urostyle. The hinder portion of the lumbar nerves forms a *cauda equina*, the constituent nerves of which surround the *filum terminale*.

A **dorsal longitudinal fissure** (*sulcus longitudinalis superior*) is well marked in the middle line of the dorsal surface of the posterior enlargement; anteriorly and posteriorly it rapidly fades away, its position being merely indicated by a small amount of connective-tissue and a blood-vessel.

The **ventral longitudinal fissure** (*sulcus longitudinalis inferior*) is well marked throughout the length of the cord. Neither fissure can be traced in the hinder part of the *conus medullaris* or in the *filum terminale*.

Ten pairs of nerves arise from the spinal cord, each nerve arising by two roots, a ventral and a dorsal (anterior and posterior), from

points near the ventral and dorsal longitudinal sinuses respectively : the two roots unite at their point of exit from the vertebral canal through the intervertebral foramen ; each dorsal root possesses a ganglion.

Fig. 97.

The nervous system of *Rana esculenta*, from the ventral surface. (From Icones physiologicae by A. Ecker. Pl. XXIV, Fig. 1.)

F	Facial nerve.
G	Ganglion of pneumogastric nerve.
He	Cerebral hemisphere.
Lc	Optic tract.
Lop	Optic lobe.
M	Boundary between medulla oblongata and spinal cord.
*M*1—10	Spinal nerves.
MS	Connection between fourth spinal nerve and sympathetic chain.
N	Nasal sac.
Nt	Sciatic nerve.
No	Crural nerve.
o	Eyeball.
S	Trunk of sympathetic.
*S*1—10	Sympathetic ganglia.
Sm	Rami communicantes of sympathetic.
Sp	Continuation of sympathetic into head.
I	Olfactory nerve.
II	Optic nerve.
III	Motor oculi nerve.
IV	Trochlear nerve.
V	Trigeminal and facial nerves.
Va	Ramus ophthalmicus of trigeminal.
Vc	Ramus maxillo-mandibularis of trigeminal.
Vd	Mandibular branch of trigeminal.
Ve	Hyomandibular branch of facial.
Vg	Gasserian ganglion.
Vs	Upper end of sympathetic trunk in connection with Gasserian ganglion.
VI	Abducens nerve.
VII	Facial nerve.
VIII	Auditory nerve.
X	Glossopharyngeal and pneumogastric nerves.
*X*1	Ramus anterior of glossopharyngeal.
*X*2	Ramus posterior of glossopharyngeal.
*X*3—4	Branches of pneumogastric.

2. Internal structure. As in other vertebrates, the spinal cord consists of white and grey matter, the latter being surrounded by the former; the relative amount of the one to the other varies in different parts of the cord.

A **transverse** section of the cord presents the same general characteristics as a similar section from a bird or mammal. The grey matter lies in the middle, surrounding the central canal, and is prolonged into each half of the section by ventral and dorsal horns or *cornua*. The grey matter is surrounded by the white, but is not so sharply marked off from this in amphibia as in birds and mammals.

A section through the **anterior enlargement** is almost quadrangular in outline, and somewhat broader below than above; the ventral longitudinal fissure is well marked and deep, while the dorsal is indistinct. The dorsal horns are narrow and short, the ventral longer and much broader. The space between the dorsal horns is narrow and deep, that between the ventral shallow; the outer boundary of the grey matter is almost straight, and the central canal is placed above the centre of the section.

In the **constricted portion** of the cord (*pars media*) the relative proportion of the white matter is increased at the expense of the grey; the horns are less distinct, the dorsal being directed outwards and the ventral somewhat flattened. The central canal is in the centre of the section.

The **posterior enlargement** shows the ventral horns projecting outwards, very much enlarged, and approaching the periphery; the space between them is semilunar. The dorsal horns are well developed, especially at their upper parts; the space between them is narrow and deep. The outer margin of the grey matter is again nearly a straight line. The central canal is below the centre of the section.

The arrangement of the parts in the *conus medullaris* approaches that in the *pars media*: the horns are much diminished in size, and posteriorly they entirely disappear, the ventral horns persisting longer than the dorsal. The central canal approaches the lower surface.

No cornua can be recognised in the *filum terminale* behind the origin of the last pair of spinal nerves. The grey matter has here a circular outline, with the exception of a very slight indentation below; the white matter is almost absent: the central canal is on the lower border of the section in the anterior part, while posteriorly it occupies almost the entire space below the *pia mater*.

The **Central Canal** lies in the median line, and always presents a

distinct lumen ; in the two enlargements this lumen forms a vertical ellipse [1], while in the *pars media* it is circular. The canal is lined by a single layer of ciliated columnar epithelium, the cells of which are usually conical, with their bases directed towards the lumen ; but other forms may be noticed. These cells average about 0·040 mm. in length and about 0·002 mm. in width at their broadest part. The peripheral extremities of the cells have processes, which, in the case of the cells above and below the cord, may often be traced as far as the *pia mater* ; the processes of the lateral cells are less distinct and seem to be shorter. Anteriorly the central canal opens into the floor of the fourth ventricle. The termination of the central canal, posteriorly, has been described by Masius and Vanlair. According to these observers, the canal towards the hinder end of the *filum terminale* increases very gradually in width, until its epithelial cells are immediately underneath the *pia mater*, its walls then converge somewhat more sharply to close the cavity. From the point where the canal commences to increase in width, a change takes place in its epithelial wall, which, instead of having a single layer of cells, now possesses two to three layers ; towards the posterior end it is again thinned out to a single layer.

The **grey matter** varies in different parts of the cord and in different parts of the same section. In a section through the anterior enlargement a portion of the grey matter, placed immediately above the central canal, is easily distinguished by its vertically-placed, elliptical outline, and by its transparency : it is known as the *substantia reticularis*. It consists of a mesh-work of branched cells, through which course distinctly contoured fine commisural fibres which are derived chiefly from the dorsal cornua, the vertical from the epithelial cells of the roof of the central canal. In a series of sections the *substantia reticulosa* may be seen to originate indistinctly in the most anterior part of the cord ; in the anterior enlargement it already possesses the elliptical form mentioned, and in the *pars media* it commences to send off lateral processes to either side. In the posterior enlargement it reaches its greatest absolute development, as it here surrounds the central canal ; while further backwards it encroaches until, together with the remaining grey matter, it constitutes almost the whole of the *filum terminale*.

Immediately underneath the central canal is a narrow band, which immediately connects the grey matter of the two sides ; above it is bounded by the epithelium of the central canal, below

---

[1] v. Kölliker states that the lumen is everywhere circular.

by medullated fibres. This *septum medium* (Reissner) may be traced backwards from the anterior extremity of the cord to the posterior enlargement. It consists chiefly of transverse fibres, together with vertical fibres derived from the epithelial cells on the floor of the canal, and like the *substantia reticulosa*, is distinguished by its greater transparency from the rest of the grey matter.

The grey matter consists of connective-tissue and nervous elements, which are very intimately united; each of these elements including its special cells and fibres. The **nerve-cells** vary much in size and appearance. A prominent group of large cells in the ventral cornua, the **lateral group** (Stieda), is very conspicuous. The individual cells are seldom rounded, but are usually spindle-shaped or angular, and each possesses one to five processes, which may often be traced through considerable distances. These cells have an average length of 0·040 mm., and are about 0·016 mm. broad; they are somewhat larger in the anterior enlargement than in the posterior, and are also more numerous in a section from the anterior enlargement than in a section from the posterior. In the terminal filament they gradually disappear. Some of their processes are continued into the lateral columns (Köppen).

Smaller, spindle-shaped or triangular cells are scattered irregularly throughout the grey matter, without forming distinct groups, though for descriptive purposes those of the centre have been named the **central group**. In a stained, transverse section of the cord are seen numerous **nuclei**; these undoubtedly belong both to small nerve-cells and to connective-tissue cells, but except under the most favourable conditions the two are indistinguishable. The larger nerve-cells present the usual characters of nerve-cells : more or less granular contents, nucleus, well-marked nucleolus, more or less marked fibrillation ; their processes are usually more homogeneous. The cells are frequently pigmented.

The **processes** of the cells belonging to the lateral group radiate in all possible directions, but certain well-marked processes directed towards the middle line can always be made out. From the lowest part of this group a few processes may be traced into the ventral roots. The small cells seem to be chiefly arranged vertically, although their processes radiate in all directions (Stieda).

The **Fibres of the grey substance** are nearly all non-medullated. They may be traced in all directions, but the best-marked groups are either vertical or transverse. The vertical fibres appear to arise from the central grey matter, and to ascend in larger or smaller

bundles towards the periphery. The transverse fibres are arranged chiefly in the two commissures: the dorsal commissure (*commissura superior*) is the smaller; the fibres are parallel, and show no trace of decussation; externally they radiate in various directions to the dorsal horns. The ventral commissure is composed of two layers, the upper grey (*commissura inferior grisea*), the lower white (*commissura inferior alba*): both are interrupted by the *septum medium*. A well-marked decussation of the fibres is seen in the middle line; the exact mode of termination of these fibres has not been made out, but many appear to communicate with the large cells of the ventral horns.

The **white matter** consists chiefly of longitudinal, medullated fibres, in which various columns may be distinguished. The dorsal columns are separated from the lateral by a process of neuroglia, continued from the general investment of neuroglia lying under the *pia mater*. The line of separation between the lateral and ventral columns is not well marked; it is about the line which would be formed by prolonging the ventral horns to the surface.

The fibres vary in size, and fibres of all sizes may be found in any particular part of a transverse section; still the fibres of the ventral columns have an average greater diameter than those of the lateral columns, and the fibres of the dorsal columns are finer than those of the lateral. The largest fibres of the ventral column are placed near the ventral fissure and on its lower border; they attain their greatest development in the posterior enlargement; these fibres frequently contain two or three axis-cylinders each. Köppen suggests that they may represent the *formatio reticularis* of higher animals.

In the lateral columns the larger fibres are placed close to the grey matter, these columns also receive fibres from the cells of the lateral group.

In the dorsal columns the radiating root-fibres never reach the median plane, but leave an area of purely longitudinal fibres on each side of the dorsal fissure; these represent Goll's columns, and have a club-shaped outline in transverse section.

The white matter is pierced in all directions by fine connective-tissue fibres and bundles of fibres which radiate from the grey matter; some branch and join with others to form a network, others pass almost uninterruptedly to the periphery. From the connective-tissue cells of the *pia mater*, processes pass into the white matter and assist in completing the connective-tissue matrix for the nervous elements.

Dorsal roots of the spinal nerves. Each root consists of a

single bundle of nerve fibres, which suddenly bends at the periphery of the cord in order to descend vertically through the white matter towards the dorsal horn; the fibres divide into three sets, one to the dorsal commissure, a second to the upper horn itself, and the third helps to form the dorsal columns.

Ventral roots of the spinal nerves. Each ventral root consists of three or four delicate threads, which may be traced to the ventral cornua, which they reach after a vertical or very slightly oblique course through the white matter. Other fibres arise from the ventral columns, but these oblique fibres never extend to the median plane.

Pigment is found distributed irregularly through a section from any part of the spinal cord; it is increased in amount in those parts in which there is an increased amount of grey matter. The pigmentation is always found more marked in the lower parts of the ventral horns than in other parts.

B. The Brain (Figs. 98, 102, 103, and 105).

1. General description. From behind forwards, the **dorsal** surface of the brain presents the following parts for examination : the *medulla oblongata*, the *cerebellum*, the optic lobes, the thalamencephalon, the cerebral hemispheres, and the olfactory lobes.

The *medulla oblongata* is a direct continuation of the spinal cord; it is wider anteriorly than posteriorly, and is separated in front from the optic lobes by a vertical plate of nervous matter, the *cerebellum*. The optic lobes are two symmetrical ovoid bodies touching each other in the median plane, and together forming the widest part of the brain. In front of the optic lobes is the thalamencephalon, with a thick vascular membrane, the choroid plexus, lying on its upper surface, and connected with the pineal gland; the thalamencephalon extends forwards between the posterior ends of the cerebral hemispheres. The cerebral hemispheres are two symmetrical ovoid bodies, narrow in front, wider and slightly diverging behind : each hemisphere is prolonged forwards to form an olfactory lobe.

The **ventral** surface has in front the olfactory lobes, then the cerebral hemispheres, behind these the *lamina terminalis*, the *tuber cinereum*, the optic chiasma, the pituitary body, the *crura cerebri*, and lastly the *medulla oblongata*, in the order here given.

The various **cranial nerves** (Figs. 102 and 103) may be seen to arise as follows :—The olfactory nerve (*I, I', L.ol'*) arises directly

from the anterior end and outer side of the corresponding olfactory lobe, and from the cerebral hemisphere. The optic nerve (*To* and *II*) arises, as the optic tract, from the side of the brain below the optic lobe, whence it passes to the chiasma on the under surface of the brain. The oculo-motor (*III*) takes its origin from the ventral surface close to the median line and between the *crura cerebri*. The pathetic or trochlear nerve (*IV*) is attached to the dorsal surface between the optic lobes and the *cerebellum*. The trigeminal nerve (*V*) arises from the side and anterior part of the *medulla oblongata*. The *abducens* (*VI*) arises behind the pituitary body close to the median line from the ventral surface of the medulla halfway between the *sulcus* and the origin of the *vagus*. The facial and auditory (*VII* and *VIII*) nerves arise from the *medulla oblongata* behind the trigeminal nerve, the facial being in front of the auditory nerve. The glossopharyngeal (*IX*) nerve arises, in common with the pneumogastric nerve (*X*), behind the auditory nerve.

2. The several parts of the brain.

a. The *medulla oblongata* (Figs. 98, 102, and 103 *Mo*)—a. **External form.** The *medulla* is limited behind by the origin of the first pair of spinal nerves, at which point a very faint constriction is sometimes found : it extends forwards as far as the *cerebellum*. It gradually widens as it passes forwards until just before it reaches its anterior limit, where it presents a shallow but sharp constriction. The **dorsal surface** is characterised by the presence of a deep, triangular fossa, the **fourth ventricle** (Fig. 98 *S.r*), (*ventriculus quartus*, Stieda; *sinus rhomboideus s. sinus triangularis*, Reissner; *fossa rhomboidalis*); the sides of the triangle are, however, not quite straight, but are slightly bent outwards just before they converge towards the posteriorly-directed apex; the base of the triangle is formed by the *cerebellum*. By careful examination, the ventricle is seen to be continued for a short distance under the *cerebellum*, where it opens into the Sylvian aqueduct. In the floor of the fourth ventricle is a well-marked median longitudinal fissure (*sulcus centralis*), (Fig. 98 *S*). Into the posterior part of the ventricle opens the central canal of the spinal cord. As the fourth ventricle is formed by the white matter passing to either side, and the simultaneous flattening of the grey matter, the floor of the fourth ventricle is composed of grey matter.

The fourth ventricle is closed in by a highly vascular membrane, the **choroid plexus** of the fourth ventricle (*plexus cho-*

roideus ventriculi quarti, Reissner; *velum medullare posterius*). The blood-vessels of the plexus will be described together with the other vessels of the brain (p. 162). They are supported by a connective-tissue matrix, and the whole covered with flattened epithelium, which in the fourth ventricle is ciliated and often pigmented.

Fig. 98.

The **ventral surface** of the *medulla oblongata* (Fig. 102 *Mo*) has a median ventral longitudinal fissure, a direct continuation of that of the cord; in the anterior part of the *medulla oblongata* there is also to either side of this a lateral fissure, continued on to the *crura cerebri*; these fissures correspond to the positions of the two *rami posteriores* of the internal carotid arteries; they are always well seen in microscopical sections. The *medulla oblongata* is so intimately connected with the *pars commissuralis* (pp. 149, 150) that the minute anatomy of the two is best described at the same time.

β. **Internal structure.** Examined by means of serial sections, the *medulla oblongata* is seen to have, in comparison with the cord, an increased amount of grey matter; this is especially the case in its anterior part. The floor and inner parts of the walls of the ventricle are formed of grey matter, in which the largest-sized cells have disappeared, to be replaced by medium-sized cells. Traced from behind, the ventral horns of the cord are seen to increase in size and to be more widely separated until they form two isolated masses, while the dorsal horns gradually diminish; at the

Dorsal view of brain of *Rana esculenta*.

Ad   Choroid plexus.
C   Cerebellum.
f   Groove between cerebral hemispheres and olfactory lobes.
G   Opening in the roof of the third ventricle.
Gp   Pineal body.
Hc   Cerebral hemispheres.
I   Olfactory nerve.
Li   Wall of fourth ventricle.
L.ol   Olfactory lobe.
L.op   Optic lobe.
Mo   Medulla oblongata.
S   Longitudinal fissure of the fourth ventricle.
S.r   Fourth ventricle.
Tho   Thalamencephalon.

same time they are forced outwards and upwards, until they lie under the floor of the ventricle, and so extend to the *pars peduncularis*.

Grey matter. The *substantia reticularis* is not present, but the *septum medium* extends forwards as far as the *pars peduncularis*. The central canal extends upwards at the expense of the tissue above it, and is here pear-shaped; at the same time the dorsal

longitudinal fissure deepens until the two meet in the fourth ventricle; beyond this point one cannot speak of dorsal and ventral horns.

Fig. 99.

Transverse section through hinder end of *Medulla oblongata* (magnified 30–80)[1], from Stieda.

b Inferior commissure.
f Dorsal horns.
g Ventral horns.
h Fourth ventricle.
i Nucleus centralis.
k Isolated mass of grey matter in which longitudinal fibres of the pneumogastric nerve course.

Small nerve cells are irregularly distributed throughout the whole of the grey matter and cannot be grouped; the larger cells, on the other hand, are arranged in distinct groups which have special relations with the nerves arising from the part. Occasionally these groups are not so isolated as usual; in this case processes of one group can be traced into another group (Reissner). Of these groups the chief are:

1. The *nucleus centralis* (upper inner group, Reissner), *nucleus medullae oblongatae*, Stieda (Fig. 99 *i*), is a group of cells found towards the hinder end of the *medulla oblongata*, on either side of and below the central canal; the group can be traced under the floor of the fourth ventricle to about its middle. The cells are rounded or spindle-shaped, the processes directed upwards, downwards, or outwards; their average size is 0·040–0·048 mm. long by 0·020 mm. broad.

2. The **auditory nucleus** (*nucleus acusticus*, Reissner, Stieda), (Fig. 100 *n*) is a large group of cells found in the wall of the fourth ventricle opposite the point of origin of the auditory nerve. The cells are rounded, pear-shaped, or of spindle form, and interspersed between the nerve fibres; these cells have an average length of 0·040 mm., and are about half as broad. The fibres of the auditory nerve radiate from their superficial origin in all

[1] In these diagrams, from Ludwig Stieda's *Studien über das centrale Nervensystem der Wirbelthiere*, the outline of the diagram is magnified thirty times, while the details are magnified eighty times.

directions through the grey matter towards these cells, and evidently communicate with them (Fig. 101 p). One small group (Fig. 101 r) passes to a lower level than the rest, and is regarded by Stieda as

Fig. 100.

Transverse section through the *Medulla oblongata* at the point of origin of the abducens nerve, from Stieda. Magnified 30×80.)

h   Fourth ventricle.
m   Abducens nerve.
n   Auditory nucleus.
o   Abducens nucleus.

the true auditory centre. Köppen considers that the auditory nerve has a threefold origin : (1) from small cells on the median surface of the auditory area ; (2) from the large cells between the above ; (3) from a group of free nuclei on the dorsal surface of the auditory area.

3. The **trigeminal nucleus** (*nucleus trigeminus*), (Fig. 101 q) lies in part beneath the auditory nucleus but extends further forwards. It forms a rounded group of cells placed under the outer angle of the grey matter. The cells are somewhat crowded together, and are chiefly of an elongated spindle-form, with their processes directed obliquely downwards and outwards. The fibres of the trigeminal nerve separate into two groups ; the upper group is best traced in a horizontal section, the fibres curving round to join the longitudinal fibres continued from the dorsal columns of the cord. The fibres of the lower, smaller group pass transversely inwards to the

L

trigeminal nucleus. According to Reissner the latter fibres are motor, the former sensory. Probably other nerves are connected with the hinder part of this group.

4. The **abducens nucleus** (Fig. 100 *o*). From its superficial origin, the fibres of the abducens nerve may be traced vertically upwards to a small, rounded, grey mass; at this point the mass is somewhat isolated, but further forwards it may be traced as belonging to the central grey matter; it contains small spindle cells.

Fig. 101.

Transverse section of the *Medulla oblongata*, at the point of origin of the auditory nerve, from Stieda. (Magnified 30 × 80.)

h Fourth ventricle.
n Auditory nucleus.
o Abducens nucleus.
p Auditory nerve.
p' Ganglion of auditory nerve.
q Hinder portion of trigeminal nerve.
r Bundle of fibres arising from trigeminal nucleus and joining the auditory nerve.

5. The **pneumogastric nucleus**. The pneumogastric, with its numerous irregular roots, arises from the side of the *medulla oblongata*. The hindermost fibres can be traced as a small bundle, passing almost transversely through the white matter to the outer margin of the grey matter. The larger portion of the fibres is placed in front of these; part of this seems to be directly continuous with the longitudinal fibres of the white matter; a second part, however, can be traced from the surface transversely

through the white matter to the grey matter. These latter fibres, together with those of the group first described, do not arise from the grey matter in this part of the *medulla oblongata*, but curve round and run backwards longitudinally through the grey matter, thus forming a rounded bundle of fibres (Fig. 99 *k*). Between these fibres are interspersed small nerve-cells and nuclei which disappear as the fibres approach the white matter. The vagus undoubtedly receives fibres from the grey matter throughout a long course, and again receives a large bundle just before leaving the grey matter. The more exact origin of the various fibres has not been traced.

6. The *nucleus magnus* (Reissner and Stieda) is a very peculiar group of cells placed on either side, in the most anterior portion of the *pars commissuralis*, that is, immediately underneath the *valvula cerebelli*. The large cells are arranged in a transverse section in a single row so as to enclose a pear-shaped space on either side, which has its long axis directed from above, downwards and outwards, the narrower end being above. In longitudinal section the line of cells is seen to be open in front. The space enclosed by these cells is occupied by a granular ground-substance which contains only few nuclei. Bellonci is of opinion that these nuclei represent the *corpora quadrigemina posteriora* of higher animals.

White matter. In the hinder part of the *medulla oblongata* the arrangement of the white matter resembles that of the white matter of the spinal cord; further forwards the white matter of the dorsal surface commences to pass to either side, and ultimately it forms the outer part of the walls of the fourth ventricle. The fibres of the white matter of the ventral surface are unchanged in direction as they proceed forwards. The fibres of the anterior part of the medulla are thinner than those of the posterior portion (Stieda), according to Reissner they gradually thin as they pass forwards. The fibres are nearly all longitudinal, such transverse and oblique fibres as are present being chiefly in connection with the various nerve-roots and the commissures.

The *commissura superior* is naturally lost in consequence of the opening of the central canal into the fourth ventricle; the *commissura inferior* is increased in the anterior half and decreased in the posterior half of the *medulla oblongata*; in the latter the fibres become more and more oblique, and decussate very freely; ultimately they seem to be either continued as longitudinal fibres or to join the ganglia.

Near the *pars commissuralis* is a transverse arched band of fibres, passing from the under surface of one half of the cord over the ventral longitudinal fissure through the *septum medium* to the under surface of the opposite half; part of the fibres are continued upwards along the periphery to the *cerebellum*, part to the *nucleus magnus*. Vertical, straight, or slightly arched fibres are found in the walls of the fourth ventricle.

A section from the *medulla oblongata* has a larger amount of pigment than a section from the spinal cord, and the anterior portion of the *medulla oblongata* contains more than the posterior portion. The pigment is chiefly found in a curved line, placed in the lower and outer parts of the grey matter; the amount present varies in different specimens.

b. The *Cerebellum* and *Valvula cerebelli*.

a. **External form.** The *cerebellum* is a thin, semilunar plate, which projects between the optic lobes and the fourth ventricle, its base covering the most anterior part of the ventricle; the posterior surface possesses a very faint median fissure (Reissner). The *valvula cerebelli* (*Velum medullare anterius*, Reissner) is the thin lamella which connects the anterior surface of the *cerebellum* with the optic lobes.

β. **Minute structure.** By means of longitudinal, vertical sections, the posterior surface of the *cerebellum* is seen to be covered with epithelium; in the lower part of the surface this is columnar or conical, above it is flattened: immediately beneath, that is in front of this is a finely granular layer, with very closely packed and granular nuclei. In front of these is a stratum of nerve-fibres forming the second layer of the cerebellum.

Still more anteriorly is the third layer of the cerebellum, an irregular double layer of large cells (Purkinje's cells, Denissenko); the cells have an average length and breadth of 0·040 mm. and 0·015 mm. respectively; they are pear-shaped or of spindle-form, and possess usually two well-marked processes, one passing into the layer behind, the other forwards into the anterior layer to be immediately described, while other less distinct processes radiate irregularly in all directions. The fourth and most anterior layer of the cerebellum is a thick stratum of nerve fibres with numerous nuclei (0·006 to 0·008 mm. diameter). The fibres are for the most part arranged transversely, but some course in various directions. These fibres underlie the flattened epithelium which covers the anterior surface of the cerebellum.

The fibres of the second layer course, for the most part, in an almost vertical plane; they connect the *cerebellum* with the optic lobes (*processus cerebelli ad corpora bigemina*) and with other parts of the brain.

The fibres of the fourth layer receive numerous long processes from the large cells of Purkinje; they form a large commissural system, which can be followed ventrally on each side into the *pars commissuralis*. A part of the fibres ends here in the grey matter, a second portion enters the auditory area and forms a descending auditory root, a third part joins the lateral columns (in the *medulla oblongata*), and more anteriorly some join the ventral columns. The descending fibres from the *cerebellum*, together with the *fibrae arcuatae* found in the ventral columns, indicate the presence of a *pons Varolii*. The fibres of this ventral commissure decussate only on its dorsal surface (Köppen).

The *Valvula cerebelli* contains a few medullated fibres and the roots of the trochlear nerves; these pass from the *medulla oblongata* into the *valvula cerebelli*, cross in the median line, and then proceed forwards as the trochlear nerves.

Fig. 102.

Ventral view of brain of *Rana esculenta*.

Cho Optic chiasma.
Hc Cerebral hemispheres.
Hy Pituitary body.
L.ol Olfactory lobe.
L.ol¹ Origin of olfactory nerve from the cerebral hemisphere.
Lt Lamina terminalis.
Mo Medulla oblongata.
To Optic tract.
Tu.c Tuber cinereum.
I 1st } root of the olfactory nerve.
I¹ 2nd }
II Optic nerve.
III Oculo-motor nerve.
IV Trochlear nerve.
VI Abducens nerve.
V, VII, VIII Trigeminal, facial, and auditory nerves.
IX, X, XI Glossopharyngeal, pneumogastric, and accessory nerves.

The **pigment** in the *pars commissuralis* is arranged in a curved line similar to that found in the *medulla oblongata*, but the line is shortened at either extremity, and consequently does not extend into the *cerebellum*.

c. The **optic lobes** and *Crura cerebri*. (*Corpora geminata* and *Pars peduncularis*, Reissner; *Lobus opticus*, Stieda; Vierhügel, Tiedemann; Vierhügel (Zweihügel) and *Pedunculi cerebri*, Schiess; Mesencephalon, Huxley.)

a. **External form** (Figs. 98, 102, 103 *L.op*).

Fig. 103.

Lateral view of brain of *Rana esculenta*.

Ad	Choroid plexus.	*Tu.c*	Tuber cinereum.
C	Cereballum.	*I* 1st	} root of olfactory nerve.
Gp	Pineal body.	*I'* 2nd	
Hc	Cerebral hemisphere.	*II*	Optic nerve.
Hy	Pituitary body.	*IV*	Trochlear nerve.
L.ol	Olfactory lobe.	*V*	Trigeminal nerve.
L.ol¹	Disc at origin of second root.	*VII*	Facial nerve.
L.op	Optic lobe.	*VIII*	Auditory nerve.
Mo	Medulla oblongata.	*IX, X, XI*	Glossopharyngeal, pneumo-
Tho	Thalamencephalon.		gastric, and accessory nerves.
To	Optic tract.		

The optic lobes are two prominent ovoid bodies placed immediately in front of the *cerebellum*, and connected with it by the *valvula cerebelli*; posteriorly they touch each other in the median plane, while anteriorly they diverge and thus constitute the widest part of the brain; in the angle thus formed is the thalamencephalon. The optic lobes are always more darkly pigmented than any other part of the central nervous system.

The *Crura cerebri* are two columns of white matter, placed beneath the optic lobes, and partly hidden by the pituitary gland. At their junction with the *medulla oblongata*, or rather with the *pars commissuralis*, is a very slight transverse fissure; at the same point the ventral longitudinal fissure is interrupted by an extremely small grey tubercle (Stieda).

β. **Internal structure.** From the anterior extremity of the fourth ventricle a canal, the Sylvian aqueduct (*Aqueductus Sylvii, iter a tertio ad quartum ventriculum*), may be traced forwards under the cerebellum, in the median line of this section of the brain. At about opposite the middle of the length of the optic lobes the canal is dilated and communicates with the cavities or ventricles (*Ventriculi lobi optici*, Stieda) enclosed by these; a general cavity is formed, which in transverse section has something of the form of the letter T. The roof of the cavity is thinner than the floor; this is especially the case in the median plane opposite the superior longitudinal fissure between the optic lobes; the floor is thinned in the middle line by the descending portion of the cavity. The cavity of each optic lobe extends both forwards and backwards beyond its point of communication with the dilated Sylvian aque-

duct, hence in a transverse section taken in front of this point (Fig. 104 *h*) the cavity of either side appears to be isolated; in a horizontal and longitudinal section (Fig. 105 *Aq*) the general arrangement of the parts may be well seen.

The grey matter is chiefly arranged in a layer so as to surround the cavity (Fig. 104), this layer being deeper on either side of the descending portion of the cavity than elsewhere. For the rest the grey matter is much interspersed among the white matter, except at the circumference of the section, which is entirely formed of white matter. It contains a large number of small cells, of which the nuclei are alone visible; in the parts mentioned where the layer is most marked these cells are arranged in oblique rows, between which pass fine bundles of medullated fibres

Fig. 104.

Transverse section through the anterior portion of the optic lobes opposite the origin of the motor-oculi nerve; from Stieda (magnified 30–80).

h	Lower portion of cavity.
h'	Lateral portion of cavity.
u	Ganglia of oculi-motor nerve.
v	Oculo-motor nerve.
w	Large cells of the optic lobe.
x	Roof of optic lobe.
y	Posterior commissure.
z	Anterior diverticulum of the cavity.

(Fig. 104, between *u* and *h'*). A group of large cells (Fig. 104 *u*) is found on either side of the middle line and under the floor of the cavity; the cells are about 0·032 mm. long, and 0·016 mm. broad; the oculo-motor nerve may be traced to this group, which is the **oculo-motor nucleus**. A small commissure of decussating fibres connects the nuclei of opposite sides (Köppen).

The substance of the roof of the optic lobes (Fig. 104 *x*) is arranged in very distinct layers: above is a layer free from cells;

the fibres of this layer are extremely fine and delicate, and have not been accurately traced; under this is a nuclear layer; a second layer of fine fibres follows, which is succeeded by a second layer of nuclei in a granular matrix, and lastly epithelium (Stieda). (Reissner describes three nuclear layers in *Bufo variabilis,* and this is also the case in *R. temporaria,* G. H.; according to Köppen, the number is variable.) In the anterior portion of the roof a distinct bundle of fibres may be made out; externally they bend downwards, and can be traced as far as the *crura cerebri.*

Fibres corresponding with the commissural and arched fibres of the *medulla oblongata* are continued into the hinder portion of the *crura cerebri,* the change from *pars commissuralis* to *crura cerebri* being very gradual. The longitudinal white fibres are much increased in number in the *crura cerebri,* and a portion of them can be traced to the *nucleus magnus.*

A peculiar irregular group of large cells (Fig. 104 *w*) is found where the roof meets the *crura cerebri;* these vary in diameter from 0·024 to 0·040 mm., and their processes are very indistinct.

The fibres of the optic tracts arise, according to Köppen, from two different origins: the one lies on the hindermost part of the optic lobe; from this point the fibres curve downwards and forwards to form longitudinal fibres; this root Köppen names the ventral ascending root, it can be traced through the entire length of the organ. The second root arises in the *tectum opticum* near the longitudinal fissure; it is smaller than the foregoing, and has been named the dorsal ascending optic root. The fibres of these two roots unite anteriorly near the posterior commissure, at which point they receive additional fibres (Köppen). Bellonci traces a large proportion of the fibres of the optic tract to the *nucleus magnus,* which pair of nuclei, as already stated, he regards as the posterior pair of *corpora quadrigemina* of higher animals.

The *pars peduncularis* is the continuation of the *pars commissuralis* underneath the optic lobes; a gelatinous mass lying in the median plane and containing numerous isolated nuclei (*Ganglion interpedunculare*) divides it into two lateral halves. The longitudinal fibres are ungrouped posteriorly, but arranged in rounded strands in the middle, especially dorsally; anteriorly the grouped arrangement is lost and the number of fibres diminished.

The **pigment** of this region has, in a transverse section, an outline which has something the form of a lyre; commencing on either side of the median line, and underneath the deepest portion of the cavity,

the pigment line passes, first, directly outwards; then suddenly turns upwards and slightly outwards parallel with the wall of the deeper part of the cavity; it then curves outwards to pass below the cavity of the optic lobe, where it divides, one portion passing outwards, the other between the Sylvian aqueduct and the ventricle of the optic lobe.

d. The **Thalamencephalon** (Huxley), (*Lobus ventriculi tertii*, Stieda; *Thalami optici*, Reissner; *Thalamus opticus s. Lobus ventriculi tertii*, Stannius; Ganglien der Haemisphaeren, Carus).

a. **External form.** From above (Fig. 98 *Tho*) the thalamencephalon is seen as a lozenge-shaped mass lying in front of the optic lobes, and behind and between the diverging posterior ends of the cerebral hemispheres; it is covered by a thick vascular membrane, the **choroid plexus**, through which passes the pedicle of the **pineal body** (*Glandula pinealis*). On removing the choroid plexus a small aperture is seen in the roof of the thalamencephalon, connecting the hollow pedicle of the pineal gland with the **third ventricle.** The ventricle appears as a narrow slit in the median line, its walls being formed by the optic thalami. By pressing aside the cerebral hemispheres the **posterior commissure** (*Commissura posterior*) may be seen lying quite in front and deep in the cleft of the ventricle. Immediately behind the pedicle of the pineal body is a slight but well-marked depression (Fig 98 *G*), the origin of which has not been investigated (Wiedersheim).

The choroid plexus is continued forwards between the cerebral hemispheres (Figs. 98, 103 *Ad*) for some distance, and terminates in a fine thread of connective-tissue.

The under surface of the thalamencephalon (Fig. 102) is divided into two parts by the **optic chiasma** (*Cho*): the anterior portion (*Lt*) is the *lamina terminalis* (*Substantia cinerea anterior*); the posterior (*Tu.c*) the *tuber cinereum*. The *lamina terminalis* is bounded on either side by the cerebral hemispheres. The *tuber cinereum* (Figs. 102, 103 *Tu.c*) is a small median swelling immediately behind the optic chiasma, and caused by the depression of the floor of the third ventricle to form the *infundibulum* (*Diverticulum infundibuli*, Reissner).

Fig. 105.

Horizontal section through the brain to show the ventricles.

Aq   Ventricles of optic lobes and the aqueduct of Sylvius.
Dv   Third ventricle.
MF   Foramen of Monroe.
Sv   Lateral ventricle.
Vv   Fourth ventricle.

The **pituitary body** (*Hypophysis cerebri*) is a flattened sac, placed behind the *tuber cinereum* and continuous with it by means of the *infundibulum*.

β. **Internal structure.** The aqueduct of Sylvius, after communicating with the ventricles of the optic lobes, again contracts (Fig. 105), but still remains somewhat larger than before. In the thalamencephalon the Sylvian aqueduct opens into the third ventricle, which gradually assumes the form of a vertical slit with the walls bulging slightly outwards in their upper parts. The thin roof of this ventricle, where complete, contains a band of transverse fibres. The floor is depressed both before and behind the part immediately above the optic chiasma, the posterior depression lying above the *tuber cinereum*, which here descends towards the *infundibulum* : a transverse section through this portion of the third ventricle has the form of a square standing on one angle, the superior angle being produced into the vertical slit of the general cavity. The anterior depression is formed by the general cavity being prolonged downwards and forwards to the *lamina terminalis* in the form of a narrow and shallow slit.

The white and grey matter of the thalamencephalon are only so far distinct in that the portion immediately surrounding the cavity is darker than the rest of the section. In the immediate neighbourhood of the cavity are many small cells and nuclei, which become scarcer further from the ventricle ; they are arranged in rows, separated by a fibrillated matrix. On either side is a distinct bundle of longitudinal fibres, the 'round bundle' of Köppen, which come from the optic lobes but appear to arise from either the *pars commissuralis* or the *medulla oblongata*, and to receive additional fibres from the optic thalami ; they pass forwards to the base of the cerebral hemispheres (Stieda). A second set of longitudinal fibres arises in the substance of the *tuber cinereum* and passes forwards to the hemispheres (strand of the *Tuber-cinereum* and *Thalamus*, Köppen); this band, together with the 'round bundle,' form a *crus cerebri* (Köppen).

The commissural fibres of the thalamencephalon are : (1) a *commissura transversa Halleri* in the posterior portion of the organ; (2) an optic commissure, consisting of fibres arising from the thalamencephalon (thalamencephalic root) and crossing the median line to join the optic tract of the opposite side ; (3) a probable commissure between the optic nerves just in front of the *chiasma opticorum* ; the existence of the latter is not yet proved beyond

doubt; (4) the large commissure of transverse fibres found in the roof of the third ventricle; whether the fibres decussate or not is uncertain (Köppen).

The fibres of the large commissure of the roof are, in part, continued into the strand of the *Tuber-cinereum* above mentioned, and thus conducted to the posterior parts of the hemispheres (Köppen). A group of fibres (Meynert's band, Köppen) is found in each lateral wall of the third ventricle; they pass from the region of the *nucleus parvus* downwards in a curved course almost parallel with the external border of the thalamencephalon.

A distinct group of cells may be noted in this section of the brain, an arciform or circular group (*Nucleus parvus*, Reissner; ganglion of the *habenula*, Köppen) of large spindle cells (average diameter 0·016 mm.), placed under the upper border close to the third ventricle; the group extends alongside the whole length of the ventricle. A second group lying in the middle and posterior parts beneath the ventricle, Köppen names the 'ventral nucleus' of the thalamencephalon.

The **pigment** in the posterior part of the thalamencephalon is arranged in a manner similar to that in the optic lobes and *crura cerebri*; anteriorly where the third ventricle is prolonged forwards and downwards the arrangement is different; the pigment lies in a curved line above the process of the ventricle, with its concavity directed downwards, each end bifurcating, in order that one branch may pass upwards, the other downwards.

The **pineal body** [1] is a small vesicle placed underneath the skin above the fronto-parietal bones; in the embryo it is connected with the third ventricle by means of the pedicle [2] already mentioned; the skin covering the body is always paler than the surrounding skin, and the usual cutaneous glands are absent in this part; the paler spot on the head may always be found, but is more distinct in *Rana temporaria* than in *Rana esculenta*. The structure on the roof of the third ventricle, which is usually known as the pineal body, is nothing more than a thickened portion of the choroid plexus, and consists of a group of convoluted vessels surrounded by *pia mater*, which is described by Wyman as being covered with ciliated epithelium (*R. pipiens*). The true pineal body is a small body with an outer con-

---

[1] Compare Ehlers, Ueber die Zirbel der Haifische, Zeit. f. wiss. Zool. 1878, Vo. XXX ; and Balfour, Development of the Elasmobranch Fishes, chap. ix.

[2] Wiedersheim states that the pedicle is hollow, and regards the part formerly known as the pineal body as a thickened portion of this pedicle.

nective-tissue capsule, derived from the *pia mater*; this encloses an irregular mass of epithelial cells; according to de Graaf a twig of the *ramus supramaxillaris* reaches it subcutaneously, and a blood-vessel accompanies the pedicle through the *foramen parietale*. According to Darkschewitsch, the pedicle contains medullated nerve-fibres derived directly from the brain.

The **pituitary body** (Figs. 102, 103 *Hy*) when examined with a lens is seen to consist of two portions: an anterior, superior, and smaller white portion, and a larger, inferior, posterior, and reddish portion. The anterior portion has the form of a very small, flat disk, and is enclosed in a connective-tissue capsule which sends in larger and smaller processes. In either transverse or longitudinal section it is seen to be formed of two horizontal layers separated by a line of blood-vessels and connective-tissue. The upper layer consists of a granular and reticular matrix, containing many nuclei (averaging 0·006 to 0·010 mm. diameter), and divided into irregular rounded or polyhedral spaces by bands of tissue derived from the capsule. This layer is more vascular than the lower. The lower layer consists of a mass of clear, nucleated rounded or polyhedral cells (0·016 to 0·024 mm. in diameter; nuclei from 0·008 to 0·012 mm. in diameter, Reissner), pierced by very fine connective-tissue septa derived from the capsule. The septa are, for the most part, vertical and longitudinal (Reissner), the blood-vessels are very few.

The posterior larger portion of the pituitary body (Fig. 106) is also compressed from above downwards, and in transverse section as an oval outline. It possesses an external thin connective-tissue capsule, which sends in fine processes to support a mass of convoluted tubes, between which course a few blood-vessels; these tubes possess an outer nucleated basement-membrane, and are lined with a single layer of more or less cylindrical epithelium, which entirely fills the tube; hence the tubes possess no lumen. The tubes are from 0·04 to 0·08 mm. in diameter; the cells are clear or granular, and possess distinct, rounded nuclei.

e. The **Cerebral Hemispheres** and **Olfactory Lobes.** The cerebral hemispheres (*Lobi hemisphaerici*, Stieda; *Lobi cerebrales*, Reissner; Centralmasse des Geruchssinns, Carus; Hemisphaeren des grossen Hirns, Tiedemann; Grosse Hemisphaeren, Schiess; Prosencephalon, Huxley). The olfactory lobes (*Tubercula olfactoria*, Stieda; *Lobi olfactorii*, Reissner; Riechkolben, Schiess; Rhinencephalon, Huxley).

a. **External form** (Figs. 98, 102, 103 *Hc* and *L.ol*). The two cerebral hemispheres form together the largest section of the brain; from above they are seen to be separated by a dorsal longitudinal fissure, which is here well marked : each hemisphere is an ovoid body with the smaller end directed forwards and continuous with the corresponding olfactory lobe; the posterior end forms one half of the anterior boundary of the thalamencephalon. The olfactory lobes are two elongated, rounded bodies directly continuous with the corresponding cerebral hemispheres, and likewise partially separated in the median line by a dorsal longitudinal fissure : at the point of union of the cerebral hemispheres and olfactory lobes is a faintly marked transverse depression.

Fig. 106.

Section through the lower division of the pituitary body (magnified 360 times); from Stieda.
a Tubes lined with epithelium.
b Blood-vessels.

On the ventral surface the parts are again marked off from one another by a corresponding ventral longitudinal fissure and a transverse groove; the two longitudinal fissures being continuous, anteriorly, between the olfactory lobes. The cerebral hemispheres appear to be more widely separated behind (Fig. 102) than is the case on the dorsal surface, and in the space so formed is the *lamina terminalis* (*Lt*). Seen from the side, the slight depression of the upper surface, between the cerebral hemispheres and the olfactory lobes, is seen to be continued downwards and slightly backwards to join the corresponding groove on the inferior surface.

The longitudinal fissures are shallow and do not meet, except at one point, at about the middle of the cerebral hemispheres (Fig. 105). The olfactory bulbs arise superficially (Figs. 102, 103 *I'* and *L.ol*) from the whole length of the olfactory lobe, between the anterior extremity (*I'*) and the posterior (*L.ol*), where they are also attached to the cerebral hemispheres.

β. **Internal structure.** The cerebral hemispheres and olfactory lobes are hollow, the common cavity of each side being known as the lateral ventricle (*Ventriculus lateralis*); these ventricles communicate with each other, and with the third ventricle (Fig. 105). The narrow aperture by which the lateral ventricles communicate is known as the **Foramen of Monro** (*MF*); it communicates with the third ventricle posteriorly, and with the space between the cerebral hemispheres anteriorly, and thus forms

a common cavity (*Ventriculus communis loborum hemisphaericorum*, Stieda). www.libtool.com.cn

In general terms, each ventricle may be said to be a semilunar cavity, prolonged backwards and forwards (Fig. 107 *c*); the outer

Transverse section through the hinder portion of the cerebral hemispheres; from Stieda.

c Lateral ventricle.
c' Common ventricle of Stieda.
d Longitudinal fibres.
f Anterior prolongation of the third ventricle.

wall is always more or less concave, while the inner varies according to the part of the hemisphere examined. At the anterior and posterior extremities the inner wall is convex and bulges into the cavity (Fig. 107); in the middle portion of the cavity the inner wall presents a longitudinal groove (*Ventriculi lateralis cornu internum*, Reissner), (Fig. 108 *d*), and consequently the inner wall has here two rounded masses, an upper and a lower (*Corpus striatum*, Wiedersheim), projecting into it. By tracing them backwards and forwards, the lower swelling is seen to increase at the expense of the upper, while at the same time the lateral grooves disappear; the outline of the cavity shown in Fig. 107 is then

obtained. The roof of the ventricle is arched and broader than the floor, which, in the middle part, exists only as a vertical slit (Fig. 108), (*Ventriculi lateralis cornu inferius*, Reissner): towards the anterior and posterior extremities it widens and becomes shallower (Fig. 107).

Fig. 108.

Transverse section near the middle of the cerebral hemispheres.

c Lateral ventricle.
d Groove on the inner wall.

The cerebral hemispheres and olfactory lobes are composed of a fine granular matrix, enclosing spindle-shaped, rounded, or pear-shaped nerve cells and nuclei, and containing very fine fibres. The cells (Fig. 109 *b*) are more numerous towards the ventricle, and somewhat sparse towards the superficial surface. The cells are of two chief sizes, the smaller and more numerous average 0·004 mm. to 0·008 mm. in diameter; they are found chiefly in the deeper portions of the section, but also form a very thin irregular

layer beneath the *pia mater*: the larger cells have an average diameter of 0·010 mm. to 0·012 mm., and are placed towards the periphery, especially in the dorsal part of the inner wall.

In this irregular collection of cells the following centres have been described : (1) The nucleus, through which the *corpus callosum* passes (Köppen); (2) the lower internal or median cell-area

(Osborne), situated above the foregoing nucleus in the posterior and middle portions of the hemispheres; (3) the upper internal cell-area (Osborne) is the area of large cells in the dorsal part of the inner wall; (4) the *Corpus striatum* (Osborne) is a mass of cells between the *corpus callosum* and the *commissura anterior*; Köppen doubts the correctness of Osborne's opinion, and suggests that a group of cells found in the wall of the third ventricle in front of ' Meynert's band ' may perhaps be a *corpus striatum*.

Fig. 109.

From a transverse section through one of the cerebral hemispheres; from Stieda.
(Magnified 360 times.)

a   Epithelium of lateral ventricle.
b   Nerve cells.
c   Connective-tissue processes from the Pia mater.

A bundle of longitudinal medullated nerve-fibres, the ' round bundle,' is found on either side of the median line (Fig. 107 *d*), and near the lower border in the posterior portion of this region; these fibres can be traced from the posterior section of the thalamencephalon; they diminish in number as they course·through the base of the cerebral hemispheres, and are ultimately lost in the lower anterior part of the outer walls. A second strand of longitudinal fibres is the continuation of that of the *Tuber-cinereum* above described, which can be followed to the outer wall of the posterior part of the ventricles, and to the anterior commissure.

The commissures are: (1) The *corpus callosum*, a large bundle of transverse fibres, seen best in a transverse section, at the point of junction between the *lamina terminalis* and the cerebral hemispheres, forming an arch over the roof of the anterior prolongation of the third ventricle. The fibres course to the inner and anterior parts of the hemispheres, and are situated chiefly behind the *foramen Monroi*. To this commissure must be added those fibres which unite the two olfactory lobes, and possibly the fibres (*Commissura posterior*) found in the roof of the third ventricle (Köppen). (2) The *Commissura anterior* (Stieda), a smaller set, found immedi-

ately under the floor of the common ventricle, forming in their course outwards in a curve, with the concavity directed downwards. This commissure connects the 'round bundles' of opposite sides, and those fibres coursing with the 'round bundles' to the olfactory lobes constitute the *pars olfactoria* of the *commissura anterior*. To this commissure must also be added some fibres found on the ventral surface of the *commissura anterior* and connecting the two strands of the *Tuber-cinereum*; an unusually coarse strand of these fibres can be traced to the inner wall of the ventricle, and is termed the *pars olfactoria interna* by Osborne.

The general structure of the olfactory lobes resembles that of the hemispheres; the olfactory nerves arise each by two roots, an outer and inner. The outer root arises from the outer wall near the groove between the corresponding hemisphere and olfactory lobe; the inner or anterior root arises from the anterior surface of the olfactory lobe. Both roots have a peculiar method of origin from the extremely fine fibrillar network of the matrix (Nerve-fibre-conglomerate, Köppen), in which are rounded dark bodies known as 'glomeruli;' in the 'glomeruli' dark points and nuclei are seen, between larger and smaller bands of nerve-fibres. Köppen holds that all the sensory nerves of the brain arise in a similar manner.

A decussation takes place between the two inner roots of the olfactory nerves; possibly the external roots are connected by means of the *commissura anterior*.

Very little **pigment** exists in the cerebral hemispheres or olfactory lobes, the greater portion is found in the upper part of the inner walls of the cerebral hemispheres.

The **epithelium** of the **ventricles of the brain**, like that of the central canal of the **spinal cord**, consists of conical cells with their bases directed towards the cavity, and their apices directed peripherally and prolonged into distinct processes (Figs. 104, 109 *a*). In such situations, as the choroid plexuses, where nervous tissue is absent and the cavity is completed by *pia mater* alone, the epithelial cells are flattened. Everywhere else it is ciliated[1] and possesses distinct round nuclei which are as broad as the cells themselves. The epithelium is somewhat irregularly and sparsely pigmented; the ventral parts of the central canal of the spinal cord, of the fourth ventricle, and of the Sylvian aqueduct are always more pigmented than the dorsal parts.

---

[1] Schmidt (*l. c.*) states that the epithelium of the central canal of the spinal cord is not ciliated.

PLAN OF THE ARRANGEMENT OF THE NERVE-FIBRES OF THE CENTRAL NERVOUS SYSTEM, ACCORDING TO KÖPPEN.

	NERVE-FIBRE STRANDS IN THE WHITE MATTER.	NERVE-FIBRE STRANDS IN THE GREY MATTER.	COMMISSURES.	NERVE-FIBRES WHICH CONNECT THE STRANDS OF WHITE FIBRES.
The spinal cord.	1. The ventral columns, including the strand of coarse fibres. 2. The lateral columns. 3. The dorsal columns, including Goll's column.	1. Longitudinal fibres in the dorsal portion of the grey matter.	1. The ventral commissure. 2. The dorsal commissure (rudimentary).	
The medulla oblongata.	1. The ventral columns, including the strand of coarse fibres and dorsal longitudinal strand. 2. The lateral columns, which give off an ascending (recurrent) vagus-root. 3. The dorsal columns. a. Ascending trigeminal root. b. Auditory root. c. Descending auditory root.	1. Longitudinal fibres of the Substantia gelatinosa Rolandi, and which give off ascending vagal and trigeminal roots.	1. The ventral commissure : a. Dorsal portion. b. Ventral portion. 2. (The dorsal commissure is wanting.)	1. The fibrae arcuatae.
The cerebellum and the pars commissuralis.	1. The ventral columns, including the dorsal longitudinal strand (the strand of coarse fibres has disappeared). 2. The lateral columns (each receives a strand from the cerebellum). 3. The dorsal columns. a. Large ascending trigeminal root. b. Descending auditory root.	1. Longitudinal fibres of the grey matter. Small ascending trigeminal root.	1. The ventral commissure. 2. The dorsal commissure, cerebellar commissure and trochlear decussation.	1. The fibrae arcuatae.
The optic lobes.	1. The ventral and dorsal columns, including the dorsal longitudinal strand. 2. (The lateral columns cannot now be distinguished from the ventral columns.) 3. The dorsal columns: two ascending opticus-roots.	(Wanting.)	1. The ventral commissure. 2. The dorsal commissure. a. Commissura posterior. b. Marginal commissure.	1. The fibrae arcuatae.
The thalamencephalon and the cerebral hemispheres.	1. The ventral and dorsal columns. a. Fibres from the optic lobes. b. The 'round bundle.' c. The 'Thalamus-Tuber-cinereum strand.'	(Wanting.)	1. The ventral commissure : a. Commissura transversa Halleri. b. Commissura anterior. 2. The dorsal commissure, the corpus callosum.	1. The fibrae arcuatae.

M

C. THE COVERINGS OF THE BRAIN AND SPINAL CORD.

1. The *Pia mater* closely invests the whole of the brain and spinal cord; it may, in fact, be regarded as the flattened, outermost layer of the connective-tissue material which supports the nervous elements; fine processes (Fig. 109 *c*) pass radially from its inner surface to join the general connective-tissue matrix or neuroglia. It is usually pigmented, those portions covering the optic lobes and spinal cord being especially deeply pigmented: on the cerebral hemispheres it contains very little pigment; at times, indeed, in *R. temporaria*, pigment is absent from this part.

The *pia mater* is continued on to the choroid plexuses and pituitary body, and on to the pineal body by means of the pedicle; the membrane is very vascular, and forms, especially for the cerebral hemispheres and the olfactory lobes, a very important source for the direct supply of blood-vessels.

2. The *Dura mater*, or lining membrane of the cranial cavity and vertebral canal, is a connective-tissue membrane containing many very much branched, pigmented cells. This membrane is not so deeply pigmented as the *pia mater*, except in that portion covering the cerebral hemispheres and the olfactory lobes, which is much darker than the corresponding portion of the *pia mater*.

3. The **arachnoid** membrane is the layer of endothelial cells covering the inner surface of the *dura mater*: by means of the blood-vessels and nerves, etc., it is continued on to the *pia mater* of the spinal cord and brain, which it in like manner closely invests. Masses of **calcareous crystals** are found between the epineurium and the arachnoid (Wiedersheim) on each spinal nerve at its exit from the intervertebral foramen, also on the trigeminal nerves in the cranium. Additional smaller and more irregular masses are found on the dorsal part of the *dura mater* of the spinal cord.

D. THE VESSELS OF THE BRAIN AND SPINAL CORD. (Fig. 110.)

The arteries of these organs are derived from the internal carotids and the *arteriae vertebrales*. As soon as the internal carotid arteries reach the cranial cavity each divides into two branches, an anterior (*Ramus anterior*, Schöbl[1]) and a posterior (*Ramus posterior*, Schöbl); the anterior branches course forwards on the lower part of

---

[1] These names are those adopted by Schöbl for corresponding vessels in the newt, the translator has accepted them as being suitable, with slight modification, to the vessels of the frog.

the surface of the brain as far as the anterior portion of the tha-
lamencephalon, where they again divide; one division, *arteria
lobi hemisphaerici inferior externa* (Schöbl), continues forwards along
the outer surface of the cerebral hemisphere and of the olfactory
lobe as far as the olfactory bulb, where it may still be distinctly
seen; it gives off branches to the adjacent parts in its course for-
wards. The vessels of the two sides communicate with each other
by means of delicate transverse vessels (*Arteriae communicantes ante-
riores*). The second division, *arteria lobi hemisphaerici superior in-
terna* (Schöbl), of the *ramus anterior* courses on the thalamencephalon
to the dorsal surface, gives a large branch to the choroid plexus of
the fourth ventricle, and runs forwards in the dorsal longitudinal
fissure; it supplies vessels to all the neighbouring parts.

The *rami posteriores* converge as they course backwards, and ulti-
mately unite to form an *arteria basilaris*, which is continued in the
median line of the under surface of the spinal cord as the *arteria
spinalis anterior*. The *ramus posterior* gives off, in its course, many
small vessels to the neighbouring parts, and two larger vessels on
either side, one of which, the *arteria lobi optici* (Schöbl), is distributed
to the optic lobes, while the other passes to the pituitary body.

The branches of these vessels form a network in the *pia mater*,
from which the nervous tissue is supplied; they also send numerous
branches directly into the brain and cord, and these have a similar ar-
rangement for all parts of the brain with the exception of the cerebral
hemispheres and olfactory lobes; more or less vertical branches arise
from the posterior parts of the upper borders of the *rami anteriores*,
from the whole of the *rami posteriores*, and from the *arteria basi-
laris*; these course upwards from their place of origin into the corre-
sponding part of the brain, give off a few branches in the white
matter, and then branch freely, and at somewhat sharp angles,
in the grey matter. In the *pars commissuralis* a large branch may
be traced from the *ramus posterior* on either side upwards into the
cerebellum almost to its upper border. The vessels of the cerebral
hemispheres and olfactory lobes seem to possess no other definite
arrangement than that described above. The grey matter seems,
on the whole, to be more vascular than the white; the vessels of
the latter are chiefly arranged radially to the surface, and run in
courses which are more or less straight; the vessels of the grey
matter are more irregular and sinuous.

The *Arteria spinalis anterior* courses along the whole length of
the spinal cord, giving off lateral branches and communicating with

rami spinales (branches of the *Arteria vertebralis*). These branches form a plexus in the *pia mater*, from which vessels pass at irregular points into the cord ; one set of small vessels, described by Reissner, pass in a straight course from the superior longitudinal sinus towards the *substantia reticularis,* where they divide. Other branches pass directly from the *arteria spinalis anterior,* through the ventral longitudinal fissure, and there divide; the twigs as a rule avoiding the *septum medium* and passing in greater part towards the ventral horns. The vessels in the white matter are for the most part radial and straight, while in the more vascular grey matter they are irregular and more sinuous in their course.

Fig. 110.

Diagram to show the *Vena spinalis posterior,* the *Venae spinales superiores,* and the origin of the *Vena jugularis interna.*

H   Hemispheres.
ji   Internal jugular.
op   Optic lobes.
mo   Medulla oblongata.
spp   Vena spinalis posterior.

The choroid plexus of the third ventricle (*Plexus choroideus ventriculi tertii,* Reissner) lies, as already described, on the roof of the third ventricle; it is somewhat triangular in form (*Plexus venosus triangularis,* Schöbl), and is evidently a prolongation of the *pia mater,* with an increased supply of vessels. It receives, at its anterior angle, veins from the cerebral hemispheres and the adjacent parts. The under surface is covered with a layer of ciliated pavement epithelium. At the posterior angles of the plexus the veins communicate on either side (Fig. 110) with the anterior lateral prolongation of the *vena spinalis superior,* and with the internal jugular vein. The small body usually named the pineal body, and placed on the roof of the ventricle, is only a small thickened portion of the plexus, and consists of a group of convoluted blood-vessels. This plexus sends a considerable bunch of vessels into the upper part of the third ventricle. The choroid plexus of the fourth ventricle (*Plexus choroideus ventriculi quarti,* Reissner) is a triangular membrane, slightly attached to the borders of the fourth ventricle. Its upper surface is flat and bounded at either side by a large vein, the *vena spinalis superior;* anteriorly it is bounded by the *cerebellum.* The under surface is not flat; in the middle line is a slight furrow corresponding to the position of a median vessel, which may, when injected, be seen from the dorsal surface; from it a number of

short vessels pass outwards and slightly backwards to the outer border. The connective-tissue between these vessels is pushed down into the cavity; in this manner one obtains a double row of flattened villous-looking bodies, which frequently have their tips pigmented. The under surface of the plexus is clothed with flattened, ciliated epithelium.

On either side of the pituitary body is another small venous plexus (*Plexus lateralis*, Schöbl); it communicates above with the posterior angle of the choroid plexus of the third ventricle; externally, with the internal jugular vein; and internally with its fellow of the opposite side by more or less irregular transverse vessels, which, together with a median vein from the fissure between the cerebral hemispheres, form an irregular *circulus venosus* around the pituitary body. These plexuses receive blood from the lower part of the cerebral hemispheres, the thalamencephalon, the optic lobes, and from the pituitary body. The veins of the spinal cord open into the dorsal, *vena spinalis posterior* (Fig. 110 *spp*), which bifurcates at the posterior angle of the fourth ventricle, one division passing to either side and forming, as already described, the outer border of the choroid plexus; anteriorly it opens into the internal jugular vein (Fig. 110 *ji*).

The blood-vessels, both arteries and veins, are irregularly pigmented, both on the surface and in the interior of the central nervous system; those of the cerebral hemispheres and olfactory lobes have very little or no pigment.

Fig. 111. Dorsal view of the orbit, etc.; deep dissection.

c	Course of the palatine nerve.	II	Optic nerve.
db	Fibrous plate.	III	Motor oculi nerve.
dm	M. depressor maxillae.	IV	Trochlear nerve.
cf	Terminal branches of the ophthalmic nerve.	Vb	R. palatinus
F	Facial with R. anterior of the glossopharyngeal.	Vc	R. maxillo-mandibularis } of the trigeminal nerve.
g,g,g	Terminal twigs of the ophthalmic nerve.	Vc'	R. maxillaris
h	Muscular twigs of the Ram. maxillaris.	Vd	R. mandibularis
ics	M. intertransversar. capitis superior.	Ve (VII)	Facial nerve.
ii	Twigs of upper eyelid.	Vg	Gasserian ganglion.
K	Terminal twigs of the Ram. maxillaris.	VN	Trigeminus.
la	M. levator anguli scapulae.	V8	Sympathetic nerve.
pt	M. pterygoideus.	VI	Abducens nerve.
sc	M. sterno-cleido-mastoideus.	VII'	Facial nerve.
Sp	Sympathetic nerve.	VIII	Auditory nerve.
t	M. temporalis.	X1	Ram. anterior of the glossopharyngeal.
tr	Nasal branch.	X2	Glossopharyngeal nerve.
*	Union of facial nerve with Ram. anterior of the glossopharyngeal nerve.	X3	Pneumogastric nerve.
		XG	Ganglion nervi vagi.
I	Olfactory nerve.	XI	Accessory nerve.

Fig. 112. Dorsal view of the orbit, etc.; superficial dissection.

e	External branch of the ophthalmic nerve.	Va	Ophthalmic nerve.
f	Internal branch of the ophthalmic nerve.	Vc	R. maxillo-mandibularis.
g,g,g	Terminal twigs of the ophthalmic nerve.	Vc'	R. maxillaris of the trigeminal nerve.
II	Optic nerve.	Vd	R. mandibularis of the trigeminal nerve.
III	Motor oculi nerve.	VI	Abducens nerve.
IV	Trochlear nerve.	VI'	Ciliary nerves.

Fig. 113. View of roof of mouth; mucous membrane, etc., removed.

a	Branch of the Ram. palatinus to the Harderian gland.	ri	M. rectus internus.
		ri'	M. rectus inferior.
b	Branch of the Ram. palatinus to the inter-maxillary gland.	sc	M. sterno-cleido-mastoideus.
		uk	Mandible.
c	Inosculating-branch of the Ram. palatinus.	t	Terminal branch of Ram. palatinus.
Ch	Internal naris.	*	Union of facial nerve with Ram. anterior of the glossopharyngeal.
d	Cutaneous branch of the Ram. palatinus.		
db	Fibrous plate.	III	Motor oculi nerve.
F	Ramus mandibularis of the facial nerve.	Vb	Ramus palatinus of trigeminal nerve.
Gl	Intermaxillary gland.	Vc	Ramus maxillo-mandibularis of the trigeminal nerve.
HD	Harderian gland.		
l	Eyeball.	Vc'	Ramus maxillaris of the trigeminal nerve.
m	M. masseter.	Vd	R. mandibularis.
Ms.ob.i.	M. obliquus inferior.	Ve (VII)	Facial nerve.
OK	Upper jaw.	X	Pneumogastric nerve.
r	M. retractor bulbi.	X1	Glossopharyngeal nerve.

Fig. 114[1]. Lateral dissection of head, etc., to show the cranial nerves, etc.

c	Cardiac nerve.	pp	Pharyngeal branches of the pneumogastric nerve.
F	Union of facial and Ram. anterior of the glossopharyngeal nerve.		
		tt'	M. temporalis.
h	Ram. hyoideus of the glossopharyngeal nerve.	us	Muscular twigs of the Ram. mandibularis of the trigeminal nerve.
la	M. levator angi scapulae.		
lgd	M. longissimus dorsi.	Z	Tongue.
m	M. masseter.	Va	Terminal twigs of the ophthalmic nerve.
mt	Ram. mandibularis of the glossopharyngeal nerve.	Vc	Ram. maxillaris of the trigeminal nerve.
		Vd	Ram. mandibularis of the trigeminal nerve.
M1	Hypoglossal nerve.	Ve (VII)	Facial nerve.
M2	Brachial nerve.	X1	Ram. anterior of the glossopharyngeal nerve.
Oh	Anterior cornu of the hyoid bone.	X2	Glossopharyngeal nerve.
oi	M. obliquus internus.	X3	Pneumogastric nerve.
ph1	M. petrohyoideus I.	X3g	Ram. gastrici of the pneumogastric nerve.
ph2	M. petrohyoideus II.	X3l	Ram. laryngeus.
ph3	M. petrohyoideus III.	X3p	Ram. pulmonales of the pneumogastric nerve.
ph4	M. petrohyoideus IV.	XI	Accessory nerve of the pneumogastric nerve.

Fig. 115. Dissection of the floor of the mouth.

dm	M. depressor maxillae.	ph2	M. petrohyoideus II.
F	United facial nerve and Ram. anterior of the glossopharyngeal nerve.	ph3	M. petrohyoideus III.
		ph4	M. petrohyoideus IV.
gh } gh' }	M. geniohyoideus.	sc	M. sterno-cleido-mastoideus.
		sh	M. sterno-hyoideus.
h	Ram. hyoideus of the glossopharyngeal nerve.	sm	M. mylohyoideus (submaxillaris).
H	Heart.	smt	M. submentalis.
Lg	Lung.	TT	Thyroid.
m'	Ram. mandibularis of the glossopharyngeal nerve.	uk	Mandible.
		us	Muscular twigs of the Ram. mandibularis.
M1	Hypoglossal nerve.	X2	Glossopharyngeal nerve.
M2	Brachial nerve.	X3	Pneumogastric nerve.
Oh	Anterior cornu of the hyoid bone.	X3c	Rami cardiaci of pneumogastric nerve.
oh	Momohyoideus.	X3l	Ram. laryngeus of the pneumogastric nerve.
ph1	M. petrohyoideus I.	X3p	Ram. pulmonalis of the pneumogastric nerve.

[1] The branches of the vagus which are represented in this figure as crossing the petrohyoid muscles ought to be underneath them.—*Trans.*

II. THE PERIPHERAL NERVOUS SYSTEM.

E. THE CRANIAL NERVES.

(To facilitate reference the original arrangement of this part
has been altered.)

[There are ten pairs of cranial nerves in the frog, which are numbered in order from before backwards. The mode of origin of these nerves, and their deeper relations with the respective parts of the brain to which they belong, have already been described.]

1. The **olfactory nerve** (*N. olfactorius*), [(Figs. 97, 98, 102, 103, 111 *I*) runs a very short course only a few lines in length, and escapes from the cranium by an opening in the cartilage of the sphenethmoid into the nasal cavity, where it divides into two branches, each of which breaks up into a brush of filaments, to be distributed in the olfactory mucous membrane. The nerve contains no white fibres]. (See organ of smell, p. 385.)

2. The **optic nerve** (*N. opticus*), (Figs. 97, 102, 103, 111 *II*) [arises, as already described, by the optic tract, and joins with its fellow at the optic chiasma or commissure, where part of the fibres pass over to the opposite side (according to Michel all the fibres cross). Each optic nerve then courses outwards, piercing the cartilage of the cranium and so reaching the eyeball]. (See organ of sight, p. 408.)

3. The **motor oculi** (*N. oculomotorius, Oculo-motor, Motor communis*), (Figs. 102, 111, 112, 113 *III*). From its origin it courses outwards and forwards, perforating with a slight obliquity the cartilaginous wall of the cranium, just in front of the Gasserian ganglion (Fig. 116, *III*); on reaching the orbit it divides into two branches, between the *Levator bulbi* and the *Rectus internus* and *inferior*. One branch, *Ramus superior*, runs over and parallel to the *Ramus ophthalmicus Trig.* and enters the under surface of the *Rectus superior*; the second, lower branch, *Ramus inferior*, supplies filaments to the *Rectus internus* and *inferior* and to the *Obliquus inferior*. Apparently it exchanges fibres with the ophthalmic division of the trigeminal nerve.

[That portion of the motor-oculi between its branch to the *Rectus superior* and to that to the *Rectus internus* contains a number of nerve cells; according to Schwalbe (*l. c.*, p. 235 and Pt. XII, Fig. 4) these cells are arranged in four groups or ganglia;

the second group forms a very slight prominence, and is covered by
a very fine layer of nerve fibres, it also gives off some extremely fine
nerves to the eyeball; this is perhaps a ciliary ganglion (*Ganglion
ciliare*, Schwalbe). Beard, however, names it 'mesocephalic gan-
glion.' The other three groups are simply clusters of cells between
the fibres of the nerve.]

4. The **pathetic or trochlear nerve** (*N. trochlearis, patheticus*),
(Figs. 102, 103, and 112 *IV*). From its origin it courses forwards
with and then crosses the motor-oculi; it perforates very obliquely
the cartilaginous lateral wall of the cranium, in front of the
motor oculi but above and very slightly behind the optic foramen
(Fig. 116); it runs parallel to and in company with the *Ramus
opthalmicus trigemini*, and appears to exchange a few fibres with it,
which, however, according to de Watteville, Stannius, Cuvier, and
Wyman, is not really the case. In this course it lies first to the inner,
then to the outer side of the ophthalmic, over which it passes to
supply the *Rectus superior*. [The pathetic and ophthalmic nerves
are sometimes enclosed in a common sheath (de Watteville).]

5. The **trigeminal nerve** (*N. trigeminus*), (Figs. 97, 102, 103,
111, 112, 113, and 114 *V*) is the largest of the cranial nerves in
the frog; from its origin it runs outwards and forwards to the skull
wall, and just before reaching this enters the large *Gasserian
ganglion*. It then passes through the cranial wall immediately in
front of the auditory capsule, and divides at once into two main
branches (Fig. 111 *Vg*, etc.), the *Ramus ophthalmicus* and the *Ramus
maxillo-mandibularis*.

The Gasserian ganglion is a large, yellow, oval ganglion placed
in a depression in the outer wall of the cranium; it is covered by a
'periganglionic gland,' which is similar in structure to that of
a spinal 'periganglionic' gland (see p. 180), the fibrous capsule
being stronger. This ganglion receives three other nerves besides
the trigeminal, *viz.* the sixth and seventh nerves, and branches of
the sympathetic.

According to de Watteville, these nerves are arranged on the
lower surface of the ganglion, so that the sympathetic is below,
the sixth above it, then the seventh, while the fifth is uppermost;
the sympathetic splits into several bundles which join the various
branches of the ganglion; the sixth divides into two bundles, one of
which usually joins the ophthalmic, while the other makes its exit
independently; the seventh splits into two bundles, one of which

leaves the ganglion as the hyomandibular branch, the other gives some fibres to the palatine branch of the trigeminal nerve, and is then continued as the palatine branch of the facial.]

a. The *Ramus ophthalmicus* (*Ramus nasalis*, Fischer ; Ophthalmic or Orbital Branch, Wyman ; Orbito-nasal or Ophthalmic Nerve, de Watteville), (Figs. 111 and 112 *Va*). After leaving the Gasserian ganglion the nerve is directed forwards parallel to the side of the cranium, between this and the eyeball. It lies beneath the *Rectus superior*, but above all the other muscles of the eyeball and the optic nerve. At the anterior end of the orbit it divides into two branches (*e* and *f*) which pass through apertures (*Foramen pro ramo nasali*) in the cartilage of the sphenethmoid, to reach the nasal cavity, where they lie between the cartilage and mucous membrane. In this position the nerves supply branches to the mucous membrane and then pierce the skull to appear on the surface (Figs. 111, 112 *g,g,g*, 114 *Va*), the skin of which they supply. The branches inosculate with each other and communicate with the anterior twigs of the *Ramus maxillaris* (Fig. 114 *Vc*) and with those of the *Ramus palatinus* (Fig. 113 *Vb*).

In its course through the orbit the *Ramus ophthalmicus* gives off :—

(1) Near the Gasserian ganglion one, two, or three small branches, which communicate with the trochlear nerve, and may then be traced to the sclerotic of the eyeball ; some of the twigs enter near the optic nerve, others nearer the cornea. They are regarded as *Ciliary nerves* (*Nervi ciliares*).

(2) A large branch, the **palatine nerve** (*Ramus palatinus*), (Figs. 111 and 113 *Vb, b*). This nerve, after receiving the palatine branch of the facial, descends on the inner border of the *Levator bulbi* to the mucous membrane of the mouth, to which it gives numerous filaments ; it then runs parallel and near to the median line, lying on the base of the skull ; and near the front of the orbit it divides into three branches. The smallest (*a*) supplies the Harderian gland (*IID*) ; the second (*b*) continues in the course of the original nerve, pierces the vomer, and divides, giving filaments to the mucous membrane in its whole course, while the terminal twigs supply the intermaxillary gland (*Gl*) and the surrounding structures. One of these (†) ascends on the anterior border of the sphenethmoid to the intermaxillary (internasal, Born) space to supply the numerous glands and to inosculate by one or two twigs with the nasal branch (*tr*) of the trigeminal.

The third branch of the palatine nerve (c) curves directly outwards, just behind the palatine bone, to the inner surface of the maxillary bone; it then courses backwards, pierces the fibrous plate (db) between the eyeball and the pterygoid bone, and ultimately unites with superior maxillary division of the trigeminal nerve (Vc'). Just before piercing the fibrous plate it gives off a tolerably large nerve (d) to the mucous membrane, and in its whole course it gives off twigs to the mucous membrane and surrounding structures; many of these twigs inosculate with other terminal twigs of the trigeminal.

[This nerve has been minutely described by Stirling and Macdonald; these observers find that the branches form a very fine and close plexus in the mucous membrane, etc.; fibres were traced to blood-vessels, glands, etc., and ganglion cells were found scattered along the nerves. The fibres are both medullated and non-medullated, and many of the cells are described as 'spiral cells' (see page 201), such as those described by Arnold in the sympathetic system of the frog.]

b. The *Ramus maxillo-mandibularis* (*Ramus maxillaris*, Ecker and Hoffmann; Supra-maxillary, Humphry; Upper Maxillary Branch, Wyman), (Figs. 111, 112, and 113 Vc). This nerve is the largest division of the trigeminal; it runs directly outwards behind the eyeball, in front of the auditory capsule, and between the temporal and pterygoid muscles. After a very short course it divides into the maxillary and mandibular nerves. The nerve gives off before its division a few fine filaments (i, i) to the hinder half of the upper eyelid and to the surrounding skin, also a branch (k) [not correctly drawn in Fig. 111] which divides to supply twigs to the temporal and pterygoid muscles.

(1) The *Ramus maxillaris* (*Ramus supramaxillaris*, Ecker; *Ramus maxillaris superior*, Hoffmann; Upper Maxillary Branch, Wyman; Supramaxillary, Humphry and de Watteville), (Figs. 111, 112, 113, and 114 Vc) runs outwards and then forwards, between the eyeball and the outer wall of the orbit, to the margin of the upper jaw (K); a large portion terminates in a number of small branches for the supply of the skin of the lower eyelid, the upper lip, and of the parts between the tympanic membrane and the external nares. Some of these twigs inosculate with twigs of the palatine and ophthalmic nerves. The second portion of the nerve unites with the palatine nerve, as already described.

(2) The *Ramus mandibularis* (*Ramus maxillaris inferior*, Hoff-mann; Mandibular or Lower Jaw Branch, Wyman; Inframaxillary, Humphry and de Watteville), (Figs. 111, 112, 113, 114, and 115 *Vd, us*). As far as the outer margin of the eyeball, this nerve runs parallel to and behind the *Ramus maxillaris*, in which course it supplies branches to the temporal and pterygoid muscles; it then curves backwards, outwards, and downwards to the under surface of the squamosal bone, where it supplies a twig to the *Depressor maxillae*, and then perforates the *Masseter*: in this manner it reaches the outer surface of the mandible, just behind the insertion of the temporal muscle; it then courses forwards, under the skin, to the *Symphysis menti*. In this course the nerve gives off numerous branches to the skin and surrounding parts, it also supplies the mylo-hyoid and submental muscles; one branch (Figs. 114 and 115 *us*) is larger than the rest, and supplies the under surface of the floor of the mouth and lower lip.

6. The **abducens nerve** (*Nervus abducens*, Ecker and Hoffmann; included in the trigeminal, Wyman), (Figs. 111 and 112 *VI*). This very slender nerve courses along the inner wall of the cranium from its origin to the Gasserian ganglion (*q.v.*) which it joins, and leaves this in contact with the ophthalmic division of the trigeminal nerve: the nerve then bifurcates in the orbit; the outer branch supplies the *Rectus externus*, the inner inosculates with small twigs of the ophthalmic division of the trigeminal, and then gives off a number of small ciliary nerves, already described, and one special branch to the *Retractor bulbi*.

7. The **facial nerve** (*N. facialis*, Ecker and Hoffmann; *Facialis* (*Portio dura*), Wyman; Facial or Jugular Nerve, Stannius), (Figs. 111, 113, and 114 *Ve VII*) arises immediately behind the trige-minal, and runs forwards, first in company with the auditory nerve, then alone, to the Gasserian ganglion (*q.v.*), with which it unites; it again appears at the posterior angle of the ganglion, and escapes from the cranium in company with, and immediately behind, the *Ramus mandibularis* of the trigeminal, and divides at once into two branches.

a. The *Ramus palatinus* at once unites with the palatine branch of the ophthalmic division of the trigeminal nerve. Wiedersheim doubts this arrangement, and holds that the two portions arise in common from the Gasserian ganglion; neither has Wyman (*Rana pipiens*) described this branch of the facial.

[De Watteville states that the *Ramus palatinus* and the palatine branch of the ophthalmic nerve are separated by the carotid artery. In urodeles the two nerves are distinct.]

.b. The *Ramus hyomandibularis* (*Ramus jugularis*, Hoffmann; Facial Nerve, Wyman), (Figs. 113 and 114, *Ve VII*). The nerve is directed outwards and backwards so as to pass around the bony wall of the auditory capsule, it then crosses over the inner end of the columella, with which it is in close contact, and is then joined, under cover of the *sterno-cleido-mastoideus* (*sc*), by a branch (*Ramus communicans*) of the glossopharyngeal (see Fig. 111 *). The single trunk (*F*) so formed is directed downwards in the posterior wall of the Eustachian tube to just above the angle of the mandible, where it divides into three branches, or sometimes into two, in which case a third nerve is supplied by one of the others, usually by the *Ramus hyoideus*.

(1) The *Ramus mandibularis* (*Ramus mentalis*, Hoffmann; Third Trunk of the Facial, Wyman), (Figs. 114 *mt* and 115 *m'*) passes inside the angle of the jaw and courses forwards, between the skin and mylo-hyoid muscle, parallel to the *Ramus mandibularis* of the trigeminal nerve, as far as the symphysis. It supplies small twigs to the neighbouring parts of the mucous membrane of the mouth.

(2) The *Ramus hyoideus* (*Ramus jugularis*, Hoffmann; Second Trunk of the Facial, Wyman), (Figs. 114, 115 *h*) is the largest division of the facial; it courses forwards subcutaneously over the *deltoideus* and the hinder fibres of the *mylo-hyoideus* to the anterior cornu of the hyoid bone, supplying its muscles and the skin of the throat and sternal region.

(3) The *Ramus auricularis* (First Trunk of the Facial, Wyman); is a small branch, directed outwards; it supplies a branch to the walls of the tympanic cavity, and is finally distributed in the skin under the tympanic membrane and behind the angle of the mouth.

8. The **auditory nerve** (*N. acusticus*, Ecker, Hoffmann; Auditory Nerve, Wyman). This nerve has a very short course in the cranium; it reaches the auditory organ by a foramen (Fig. 116 *VIII*) in the auditory capsule, and is then distributed in the ear, with which it will be described.

9. The **glossopharyngeal nerve** (*N. glossopharyngeus*, Ecker; *Ramus glosso-pharyngeus*, Hoffmann; Glossopharyngeal, Wyman;

Glossopharyngeal of the Vagus, Müller), (Figs. 102 and 103 X, 111, 113, 114, and 115 X^2) arises in common with the pneumogastric nerve, and quits the skull with it through an opening (*Canalis nervi vagi*) immediately behind the auditory capsule, and at once divides into two branches; both of which lie under the *MM. intertransversarii capitis* and are covered by the *Depressor mandibulae*.

a. The *Ramus anterior* (Verbindungsast des Glossopharyngeus, Wiedersheim; *Ramus communicans*, Hoffmann; Uniting Branch, Wyman; Laryngeal Branch of the Vagus, Volkmann; *Communicans ad facialem*, de Watteville), (Figs. 111, 113, and 114 X^1). This nerve curves downwards and forwards around the auditory capsule and beneath the *Depressor mandibuli* to join the facial nerve, as already described.

b. The *Ramus posterior* (*N. glossopharyngeus*, Wiedersheim; *Ramus lingualis*, Hoffmann), (Figs. 111, 113, and 114 X^2). This nerve runs downwards and forwards to the ventral surface of the pharynx, dips underneath the *Petrohyoideus IV*, to appear again, after a short interval, by piercing the *Petrohyoideus II* or *III*, courses parallel to and behind the anterior cornu of the hyoid bone, and thus reaches the floor of the mouth. The nerve then runs forwards in a very sinuous course, close to the median line, and between the *Geniohyoideus* and *Hyoglossus*; in its course on the floor of the mouth it crosses the hypoglossal nerve. It supplies the petrohyoid muscles, and gives numerous small branches to the mucous membrane of the pharynx (*Ramus pharyngeus*, Hoffmann).

10. The **pneumogastric** or **vagus nerve** (*Vagus*; *Ramus intestinalis nervi vagi*, Fischer, Hoffmann; Vagal Trunk, Wyman; Vasosympathetic, Gaskell), (Figs. 111, 113, 114, and 115 X^3). This nerve arises in common with the glossopharyngeal; the two nerves leave the skull together by an opening in the exoccipital bone (*Canalis nervi vagi*); immediately outside the skull they acquire a ganglionic enlargement (*Ganglion condyloideum, Ganglion nervi vagi*), (Fig. 111 XG); in this course the glossopharyngeal lies in front of the pneumogastric, which it then leaves. The pneumogastric lies first upon the *M. levator anguli scapulae*, then running backwards and downwards along the hinder border of the *Petrohyoideus IV* it comes to the side of the pharynx; it is covered by the trapezius, and passes between the hypoglossal nerve and the *Aorta ascendens*; arriving at the *Arteria pulmonalis*, it gives off its terminal branches.

[Gaskell has proved that this nerve contains both sympathetic and vagal elements, and that it is therefore really a vago-sympathetic.]

Fig. 116.

Right half of skull of *Rana esculenta*, seen from within.

II	Optic nerve.
III	Motor oculi nerve.
IV	Trochlear nerve.
VN	Root of the trigeminal nerve.
Vg	Gasserian ganglion.
VS	Sympathetic nerve.
VI	Abducens nerve.
VII¹	Facial nerve.
VIII	Auditory nerve.
X¹⁻³	Pneumogastric and glossopharyngeal nerves.

The branches and communications of the pneumogastric nerve are :—

a. Communications between the ganglion of the pneumogastric and the sympathetic system (Fig. 111 *Sp*), which again connect it with the Gasserian ganglion of the trigeminal nerve (Fig. 111 *VS, Vg*); (see sympathetic system).

b. [The *Ramus cutaneus dorsalis* (Fischer) is considered by Stannius and Fürbringer to be the homologue of the *Ramus auricularis*; it passes outwards between the *digastricus* and *temporalis* to be distributed in the skin of the suprascapular region. This nerve is the persistent portion of the *N. lateralis nervi vagi* of the tadpole.]

c. During its course over the *petrohyoidei* the vagus gives off a few twigs (Fig. 114 *pp*), which form a fine plexus to supply these muscles and the pharynx [also a twig to the trachea, according to Hoffmann].

d. The *Ramus accessorius* (Fürbringer, Hoffmann, Ecker), (Fig. 114 *XI*) is usually a single small nerve which runs between the *intertransversarii* muscles and the *trapezius*: it supplies the under surface of the latter muscle.

e. The *Ramus scapularis* (Hoffmann) is a very slender nerve arising near the *Ramus accessorius*; it passes along the under surface of the *trapezius* to the inner surface of the *interscapularis*, which it supplies.

f. The *Ramus laryngeus* (*Recurrens vagi*), (Figs. 114 and 115 *X3l*) runs for some distance parallel to the pneumogastric, separated from it by the *petrohyoideus IV*; arriving at the hinder cornu of the hyoid bone the nerve loops round the *Arteria pulmonalis*, and divides into two branches for the supply of the larynx.

g. The *Rami gastrici* (Fig. 114 *X3g*) are usually two in number: they pierce the partial diaphragm formed by the anterior fibres of the *M. obliquus internus* and terminate in the walls of the stomach.

h. The *Rami pulmonales* (Figs. 114 and 115 *X3p*) also perforate the partial diaphragm, and then course along the pulmonary arteries to the lungs.

i. The *Ramus cardiacus* (Figs. 114 and 115 *X3c*). This nerve is usually smaller on the right side than on the left; it passes along the dorsal surface of the pulmonary artery and *Vena cava superior* to the *Sinus venosus*; in this course it gives off two or three twigs to the roots of the lungs: the two nerves communicate just before reaching the heart and pass on to the auricular septum, whence they are distributed to the heart.

j. A slender **Laryngeal nerve** arises from the vagus alongside the *Ramus cardiacus*; it courses along the hinder end of the greater cornu of the hyoid to the outer side of the pharynx, which it pierces to pass to the larynx.

F. The Spinal Nerves.

I. **General description.** Ten pairs of nerves arise, as already described (p. 135), from the spinal cord; each nerve has two roots, a ventral or anterior, and a dorsal or posterior, which unite at their points of exit from the intervertebral foramen: just before, and for a short distance beyond this union, each dorsal root bears a ganglionic enlargement.

1. The length and direction of the various **Nerve-roots** vary greatly; the roots of the anterior spinal nerves run a very short course, almost transversely outwards, from their points of origin to the intervertebral foramina: the roots of the middle and posterior nerves, in consequence of the vertebral column being considerably longer than that part of the cord belonging to it, pass obliquely backwards to the foramina, the hinder nerves of the *Cauda equina* running for a considerable distance in the vertebral canal (Fig. 116). The relations of these roots are as follows:—

(1) The roots of the first nerve (*N. hypoglossus*) arise from the spinal cord at a point between the first and second vertebrae ; they run transversely outwards to escape between the first and second vertebrae.   The dorsal root is extremely slender.

Fig. 117.

(2) The roots of the second nerve ·(*N.*

The nervous system of *Rana esculenta*, from the ventral surface. (From Icones physiologicae by A. Ecker. Pl. XXIV, Fig. 1.)

F	Facial nerve.
G	Ganglion of pneumogastric nerve.
He	Cerebral hemisphere.
Lc	Optic tract.
Lop	Optic lobe.
M	Boundary between medulla oblongata and spinal cord.
M1–10	Spinal nerves.
MS	Connection between fourth spinal nerve and sympathetic chain.
N	Nasal sac.
Ni	Sciatic nerve.
No	Crural nerve.
o	Eyeball.
S	Trunk of sympathetic.
S1–10	Sympathetic ganglia.
SM	Rami communicantes of the same.
Sp	Continuation of sympathetic into head.
I	Olfactory nerve.
II	Optic nerve.
III	Motor oculi nerve.
IV	Trochlear nerve.
V	Trigeminal and facial nerves.
Va	Ramus ophthalmicus.
Vc	Ramus maxillaris.
Vd	Mandibular branch of trigeminal.
Ve	Hyomandibular branch of facial.
Vg	Gasserian ganglion.
Vs	Upper end of sympathetic trunk in connection with Gasserian ganglion.
VI	Abducens nerve.
VII	Facial nerve.
VIII	Auditory nerve.
X	Glossopharyngeal and pneumogastric nerves.
X1	Ramus anterior of glossopharyngeal.
X2	Ramus posterior of glossopharyngeal.
X3, 4	Branches of pneumogastric.

brachialis) arise at the level of the second vertebra and leave the vertebral canal between the second and third vertebrae.

(3) The roots of the third nerve arise from the cord between the second and third vertebrae, and pass out between the third and fourth vertebrae.

(4) The fourth nerve arises by its two roots at the level of the fourth vertebra, and quits the vertebral canal between the fourth and fifth vertebrae.

(5) The fifth nerve arises opposite the fourth vertebra, and passes outwards and slightly backwards to the foramen between the fifth and sixth vertebrae.

(6) The roots of the sixth nerve are attached to the cord opposite the fourth vertebra, and leave the vertebral canal between the sixth and seventh vertebrae.

(7) The seventh nerve arises from the cord at a point between the fourth and fifth vertebrae, and leaves the canal between the seventh and eighth vertebrae.

(8) The eighth nerve quits the cord at a point opposite the articulation between the fifth and sixth vertebrae, then runs backwards to the eighth vertebra, and escapes between this and the ninth vertebra.

(9) The ninth nerve arises at the level of the sixth vertebra, and passes out between the sacrum (ninth vertebra) and the urostyle.

(10) The tenth nerve (*N. coccygeus*) arises from the cord immediately behind the ninth nerve and opposite the sixth vertebra, and courses alongside the terminal filament to pass out through a foramen in the urostyle (*canalis coccygeus*).

b. [The **Spinal ganglia** (*Ganglia intervertebralia*).

At their exit from the intervertebral foramen the two roots of each nerve unite and bear a ganglionic enlargement, which is in intimate connection with the dorsal root, but is merely in contact with the ventral root. The ganglia lie [1] in the large intervertebral depressions, upon the under surface of the *Proc. obliqui*, above and behind, being in relation with the bodies of the vertebrae internally, and the *Musculi intertransversarii* externally (Fig. 119); ventrally the ganglia are, more or less, covered by the ' periganglionic glands.' The ganglia vary much in size; that of the first spinal nerve is the

---

[1] The *Gangl. coccygeum* is in the urostyle.

smallest.   The ganglion is not attached to the dorsal root alone but is prolonged a short distance beyond the point of union of the two roots ; this is best seen in the nerves of the lumbar plexus.

Each ganglion is a yellowish-white rounded or oval body, with an outer thick (sometimes 0·15 mm. thick) sheath of connective - tissue, connected by the epineurium of the nerve roots with the *Dura mater*. This sheath is composed of bundles of parallel, wavy, white, connective-tissue fibres, which enclose a large number of connective-tissue corpuscles, and here and there contains brown pigment.

By means of longitudinal and transverse sections it may be seen that the ganglion surrounds the ventral root, but that it forms a thinner layer on that side, where the dorsal root joins the ventral ; although at this point the two roots and the ganglion are firmly united together, the thick fibrous sheath of the ganglion prevents any communication between the nervous elements of the ventral root and those of the ganglion.

Fig. 118

Ventral view of the brain and spinal cord, to show the points of exit of the spinal nerves.

*M*1–10 Spinal nerves.
VG Trigeminal ganglion.
*W*1–10 Vertebrae.
XG Ganglion of vagus.

The sheath contains nerve-cells and fibres, and sends in a few fine processes to support these structures. The fibres of the posterior root enter and pass out of the ganglion without suffering any changes, except that the nerve fibres are slightly separated by the presence of a few nerve-cells, and that a distinct increase in the number of nerve fibres takes place. The nerve-cells, of which the ganglion is chiefly composed, and upon the number of which its size directly depends, are arranged chiefly around the fibres of the dorsal root; such few as lie between the fibres are smaller than the rest and vary more in their relative numbers; at times one or two isolated cells are found in the capsule or even in the adjoining 'periganglionic gland.' The cells near the capsule are somewhat smaller than the deeper cells [1]. Each of these cells, which are usually pear-shaped, possesses only one process; the cell membrane is thick, resistant, and possessed of

Fig. 119.

Ventral view of the spinal ganglia; on the right side they are still hidden by the 'periganglionic glands.'

an external nucleated, endothelial covering, the space around being probably a pericellular lymph-space; it often contains one to three small fat-globules; the protoplasm of these has, according to v. Lenhossék, a concentric fibrillation; the nucleus is round, clear, and distinct, and relatively larger the smaller the nerve-cell; it is usually placed in the centre of the cell.

In that portion of the cell towards the process is a portion brighter and less easily stained than the rest of the cell (Polarkernen, Courvoisier); this apparently possesses one or two nuclei, and is regarded as a cell by Lenhossék (Polarzellen); the process of each cell soon acquires a medullated sheath, and after

Fig. 120.

Schema of spinal ganglion.
A Ventral root.
C Ramus communicans.
G Ganglion.
O Dorsal division.
P Dorsal root.
R Ventral division.

[1] Larger cells of deeper layer 80 μ to 90 μ in diameter, sometimes one or two as large as c.1 mm. v. Lenhossék.

N 2

a short course, 0·09 mm. to 0·35 mm., divides usually about the third constriction (Lenhossék). These processes all pass peripherally, even those which appear at first to pass in the opposite direction curve round again; it is chiefly due to these fibres that the spinal nerve is larger than its two roots.

In addition to the above, smaller, irregular cells from 5 μ to 7 μ in length are found; Rawitz regards them as young cells, Lenhossék as cells capable of (entwicklungsfähige) developing into nerve-cells. The ganglia contain only few blood-vessels.]

The above description is founded upon that of Lenhossék, and has been confirmed by the translator in every particular, except that only very indistinct and unsatisfactory indications of the concentric fibrillation so clearly delineated by Lenhossék were obtained; the structure of the Gasserian ganglion was found to correspond exactly with the description here given of the structure of the spinal ganglia. The nucleus was oftener at the side than at the centre of the cell.

c. The 'Periganglionic Glands' (Periganglionäre Kalkdrüsen, v. Lenhossék; Kalksäckchen, Ecker, and others; Crystal capsules, Wyman; Calcareous Sacs or Masses, of other writers), (Fig. 119). These bodies are found on the ganglia of all the spinal nerves and on the Gasserian ganglion of the trigeminal nerve; they have recently been carefully investigated by v. Lenhossék. According to his description there are usually two to each ganglion, lying on its sides and ventral surface; each consists of a connective-tissue capsule which sends in a few fine trabeculae to support a system of glandular tubes: these usually run parallel to the long axis of the gland, and are about 14 μ to 15 μ in diameter; each tube is lined with a single layer of somewhat columnar epithelium, the cells of which have sharp, distinct outlines and oval nuclei.

A *membrana propria* was not made out with certainty; the lumen of the tubes is wide and contains a milky fluid, which gives the whole structure its characteristic appearance; it has long been known (Blasius, 1681, mentions the fact, *l. c.*, p. 291) that this fluid contains calcareous matter, which effervesces and dissolves in the presence of hydrochloric acid; the crystals vary in form but are chiefly oval (Wyman).

These glands bear no definite proportion to the size of the nerves to which they are attached (Fig. 118); they already contain calcareous matter during the tadpole stage before the limbs are developed (Stannius, Wyman). No ducts have been traced to

these glands. This description, founded upon that of Lenhossék, can be confirmed by the translator in every particular; his sections, however, would lead him to believe that the glands are far more vascular than the description and the drawings of Lenhossék imply.]

d. The **Branches** of the complete spinal nerves formed by the union of the dorsal and ventral roots with the ganglion (Fig. 120) are usually described as two, a dorsal and a ventral branch, which latter at once gives off a *Ramus communicans* to the sympathetic system; these two branches are given off almost immediately beyond the ganglion.

II. The Individual Nerves.

A. The Dorsal Branches (Fig. 121).

The dorsal branches are smaller than the ventral; they pass upwards between the inner borders of the *Musc. intertransversarii* and the articular processes of the vertebrae to reach the under surface of the *M. longissimus dorsi*; the general course of these nerves is very similar for all; each nerve gives off—

(*a*) A twig to the *Musc. intertransversarius* and then divides into two branches.

(*b*) A *Ramus muscularis* (Fig. 121 *rm*), which passes outwards to supply the *M. longissimus dorsi*.

(*c*) A *Ramus cutaneus* (Fig. 121 *rc*); this nerve continues under the extensor muscle of the back, running on the arch of the vertebra towards the middle line; it then pierces the muscle and Fascia dorsalis to reach the large dorsal lymph-sac (*Sacc. cranio-dorsalis*), through which it courses to end in the skin. In its course through the sac the nerve is connected with a small artery and vein by a small amount of connective-tissue, the whole being enclosed

Fig. 121.

Dorsal branches of the spinal nerves. The *Fascia dorsalis* is dissected, removed from the left side.

rc   Rami cutanei.
rm   Rami musculares.

in a sheath of endothelium continuous with that of the general cavity. www.libtool.com.cn

The three anterior cutaneous nerves pierce the *Fascia dorsalis* near the spinous processes, the fourth a little to the side, the fifth perforates the *M. coccygeo-iliacus* at about the junction of its anterior and middle thirds; the sixth and seventh perforate the same muscle, but more posteriorly. There are seven of these *Rami cutanei*, the first coming from the second spinal nerve, the rest from the succeeding six spinal nerves.

B. The Ventral Branches.

The ventral branches of the spinal nerves are larger than their corresponding dorsal branches : each nerve gives off immediately a *Ramus communicans* to the sympathetic system (Figs. 117 *SM*, 120 *C*); these *Rami communicantes* will be described with the sympathetic system ; the remaining portions of the ventral divisions of the original spinal nerves are usually known as the spinal nerves ; they will be described as such in detail.

1. The **hypoglossal nerve** [1] (*N. hypoglossus, N. spinalis I*), (Figs. 114, 115, and 117 *M*1), or first spinal nerve, is of small size ; it leaves the vertebral canal between the first and second vertebræ to lie between the *Musculi intertransversarii* and the pharynx, where it has in front the *Arteria vertebralis*, behind the *Arteria* and *Nervus brachialis* ; passing under the *Levator anguli scapulae*, it touches the *Aorta ascendens* and crosses the *Vagus* and the Carotid-gland, and thus reaches the space between the *Musculi sterno-hyoidei* and the *Petro-hyoideus* ; then curving forwards sharply it turns under the *Mylo-hyoideus* to course between the fibres of the *Genio-hyoideus* to the root of the tongue, where it ends. It first lies to the inner and then to the outer side of the glossopharyngeal nerve. In its course the nerve gives off the following branches :—

(a) One or two communicating twigs (Figs. 114 and 122) to the second spinal nerve.

---

[1] [Observers have differed considerably as to the relations of this nerve : Volkmann describes it as the first nerve of the neck, and describes a ganglion on its dorsal root ; Vogt denies the presence of this ganglion, and regards it as a true cranial nerve ; Stannius asserts that no ganglion exists, and holds the nerve to represent the first two spinal nerves ; Wyman describes the two roots and regards it as a spinal nerve ; Hoffmann regards this nerve as the second spinal (N. spinalis II) : Fürbringer as the representative of two spinal nerves ; de Watteville describes two roots and names it first spinal nerve.—TRANS.]

(*b*) Muscular twigs to the *Longissimus dorsi, Intertransversarii capitis, Levator anguli scapulae,* and the *Retrahens scapulae.*

(*c*) When near the glossopharyngeal it supplies twigs to the *Geniohyoideus, Sternohyoideus,* and *Omohyoideus,* where it bifurcates.

(*d*) One of the branches passes inwards to supply the *Hyoglossus.*

(*e*) The other terminal branch passes forwards with the *Ramus lingualis* and the glossopharyngeal, between the fibres of the *Genio-hyoideus,* which it partially supplies, and sends twigs to the neighbouring parts.

(*f*) [Hoffmann describes a communicating branch to the pneumogastric nerve, which the translator has not been able to discover, and which no other observer has mentioned.]

2. The **second spinal** or **brachial nerve** (*N. brachialis, N. spinalis II*), (Fig. 122) is a large nerve, leaving the vertebral canal between the second and third vertebrae ; it then accompanies the *Art. axillaris* along the anterior border of the transverse process of the third vertebra, over the hinder end of the *Musc. levator scapulae* and the anterior end of the *m. transverso-scapularis major,* to the inner border of the *Musc. subscapularis,* under which it passes into the arm.   In this course it gives off or receives the following branches :—

(*a*) It first receives a branch from the second spinal nerve.

(*b*) It gives off a large branch, the *N. coraco-clavicularis* (Fig. 122 *Cc*), which first accompanies a branch of the *Art. axillaris* on the *Musc. levat. scapulae,* then courses forwards and outwards over the *Musc. subscapularis* to pass from above into the *Foramen ovale* between the clavicle and coracoid bones.   It gives off two branches :

(1) One immediately beyond its origin, which runs backwards over the *Musc. subscapularis* to supply the *Musc. obliq. abdominis internus* (Fig. 122 *Cc'*).

(2) While in the *Foramen ovale,* the *N. coraco-clavicularis* bifurcates ; the anterior twig runs forwards and outwards to the *deltoideus* and also supplies a recurrent filament to the *Musc. sterno-radialis* ; the posterior twig enters the upper surface of the *Musc. sterno-radialis.*

(*c*) At the outer extremity of the *Musc. transverso-scapularis* the brachial nerve gives off a posterior branch, which at once bifurcates :

(1) The first branch passes into the under surface of the *Musc. latissimus dorsi* (*ld*), giving a twig to the *Infraspinatus.*

(2) The second is the *Ramus cutaneus axillaris* (*IIc*) ; it passes on

the under surface and posterior border of the *Musc. latissimus dorsi*
to the skin of axilla and dorsal surface of the upper arm.

(*d*) Several small branches are given off from the upper and an-
terior surfaces of the brachial nerve near the *Foramen ovale*; they
accompany an artery to pass forwards and upwards between the
Musc. subscapularis and the *M. transverso-scapularis* on the one side,

Fig. 122.

The brachial plexus.

Cc	N. coraco-clavicularia	ss	Musc. subscapularis.
Cc'	Nerve to musc. obliq. abdom. internus.	S I	First spinal nerve.
d	Deltoid muscle.	S II	Second spinal nerve.
la	Musc. lev. ang. scap.	S III	Third spinal nerve.
ld	Musc. lat. dorsi.	IIc	Ramus cutaneus axillaris.
oi	Musc. obliq. abdom. intern.	IIIc	Ramus cutaneus abdominalis.
sc	Musc. sterno-mastoid.		

and the long head of the *M. triceps brachialis* on the other, and are
lost in the *M. deltoideus* and the *M. infraspinatus*.

The *N. brachialis* continues its course by passing between the
long and inner heads of the *M. triceps*, reaches the arm and splits
into two nerves, the *N. ulnaris* and the *N. radialis*.

[**I.**] The *N. ulnaris* (Fig. 123 *U*) escapes from cover of the long
head of the *M. triceps* and runs obliquely over its inner head

towards the outer side of the *Plica cubiti* ; in this course it supplies four branches —

a. The *Ramus subscapularis* passes dorsally to the *M. subscapularis.*

β. A *Ramus pectoralis* (Fig. 123 *up*), passes forwards to the *M. abdomino-pectoralis* and to the skin of the pectoral region (*R. cutaneus pectoralis*).

Fig. 123.

γ. The *N. cutaneus antibrachii superior s. medialis* (*uc*) passes to the skin of the inner side of the forearm ; this and the two following nerves are given off near the *Plica cubiti.*

Nerves of the ventral surface of the arm. The hand pronated.

rc	Upper cutaneous branch of the N. radialis.
rc′	Lower cutaneous branch of the N. radialis.
U	N. ulnaris.
uc	R. cutan. sup. of the N. ulnaris.
uc′	R. cutan. inf. of the N. ulnaris.
up	R. pectoralis of the N. ulnaris.

δ. The *N. cutaneus antibrachii inferior s. dorsalis s. musculo-cutaneus* (*uc′*) at once supplies branches to the *M. flexor carpi radialis*[1], and then runs downwards upon the muscle and bifurcates :—

[1] The *R. lateralis* is distributed, by two twigs, in the *M. flexor carpi ulnaris* and in the skin of the second finger, to which it supplies the *Rami digitales volaris* and *dorsalis.*

[2] The *R. dorsalis,* after giving a cutaneous twig to the second finger, is distributed by numerous twigs to the skin of the dorsal surface of the hand.

The *N. ulnaris* then passes between the *M. flexor carpi radialis* and the tendon of the *M. sterno-radialis,* sinks deeply into the *Plica cubiti,* where it lies between the *M. flexor carpi radialis* and the *Flexor carpi ulnaris,* then between the latter and the *Flexor antibrachii medialis* on the one side and the *Flexor digitorum communis* on the other : it supplies branches to all these muscles, and while still in the forearm divides into two terminal branches :—

a. The *R. ulnaris medialis* is the smaller ; it runs inwards,

---

[1] As this muscle increases in size during the breeding season, it would be interesting to know whether a corresponding change takes place in the nerve.

passes under the tendon of the *M. extensor carpi ulnaris* into the palm of the hand and ends as the *N. volaris digiti V medialis.*

β. The *R. ulnaris lateralis* passes near the thumb-rudiment, covered by the *M. abductor pollicis*, deeply into the palm of the hand, and supplies by bifurcating branches the adjacent sides of the second, third, fourth, and fifth fingers (*R. volares*); it also gives twigs to the muscles of the palm.

Fig. 124.

Nerves of the ventral surface of the arm. The hand supinated, and the superficial layer (Flex. carpi rad. and uln., Flex. dig. commun.) has been removed.

R	N. radialis.
u	N. ulnaris.
uc	R. cutan. inf. of the N. ulnaris.
um	Bifurcation of the N. ulnaris.

[**II.**] The *N. radialis* (Figs. 123, 124, and 125 *R*) passes immediately beyond its origin from the *N. brachialis*, between the humerus and the *M. triceps*, runs along the bone to its outer side; in this course it gives off :—

α. *Rami musculares* to the separate parts of the *M. triceps.*

β. The *Ramus cutaneus superior* (Fig. 125 *rc*) to the skin of the outer surface of the upper arm and forearm.

The nerve then sinks deeply under the origins of the *M. extensor carpi ulnaris* and the *M. extensor digitorum communis*, where it bifurcates after giving off some small twigs :—

Fig. 125.

The N. radialis.

ec	M. extensor carpi ulnaris.
ed	M. extensor digit. comm.
R	N. radialis.
R₁	R. lateralis.
R₂	R. medialis.
rc	R. cutaneus superior.
rc′	R. cutaneus inferior.

γ. Small muscular twigs to the extensor muscles of the hand and fingers.

δ. The *R. radialis medialis* (*R2*), the

smaller terminal branch, supplies a branch to the *M. extensor digit. comm. longus* and the skin over the carpus (*Ramus cutaneus inferior, rc'*), and ends on the muscles of the little finger as the *R. dorsalis digiti V medialis*.

ε. The *R. radialis lateralis* (*R*), the larger of the two branches, supplies the extensor muscles of the fingers and gives bifurcating branches, *Rami digitales dorsales*, to the adjacent sides of the second, third, fourth, and fifth fingers (the *Ramus dorsalis lateralis* of the second finger is supplied by the *N. ulnaris*).

3. The **third spinal nerve** (*N. spinalis III*) (Fig. 122 *SIII*) leaves the vertebral canal by the foramen between the third and fourth vertebrae, and runs outwards and forwards upon the large transverse process of the third vertebra to the brachial nerve (*N. spinalis II*). Its behaviour at this point is subject to considerable variation ; at times it joins the brachial nerve completely, at other times the two nerves are simply in contact ; or lastly, it may send a small twig to the brachial nerve. Externally to this point the two nerves supply a number of small branches, which may belong almost entirely to either one nerve or the other ; these nerves again inosculate in a variable manner, to form an axillary plexus. The more constant branches are :—

(1) One or more twigs to the *Musc. transverso-scapularis major*.

(2) Several branches, usually two larger and one smaller ; they course in the *M. obliq. abdom. internus* (Fig. 122 *oi*) to the *M. rectus*, where they give off branches, then pierce the muscle to reach the skin (*R. cutaneus abdominalis*), (Fig. 122 *IIIc*).

4. The **fourth spinal nerve** (*N. spinalis IV*) (Fig. 126 *M4*) appears between the fourth and fifth vertebrae ; it runs on the ventral surface of the transverse process of the fifth vertebra and upon the *Musc. intertransversarius* obliquely outwards and downwards, and reaches the deeper surface of the *Musc. obliquus internus*, into which it descends, about opposite the articulation between the eighth and ninth vertebrae ; it then bifurcates into :—

(1) A *Ramus cutaneus abdominalis*, which pierces the muscle and supplies the skin.

(2) A *Ramus muscularis*, which supplies the broad abdominal muscle and the *M. rectus abdominis*.

5. The **fifth spinal nerve** (*N. spinalis V*) (Fig. 126 *M5*) emerges through the foramen between the fifth and sixth vertebrae, runs

obliquely downwards and outwards over the transverse processes of the sixth and seventh vertebrae and the corresponding *M. inter-transversarii*, and at a point nearly opposite the middle of the uro-style pierces the *M. obliquus internus.*

The rest of its course corresponds exactly with that of the fourth spinal nerve.

Fig. 126.

Ventral view of the brain and spinal cord, to show the points of exit of the spinal nerves.

M1-10 Spinal nerves.
VG Trigeminal ganglion.
W1-10 Vertebrae.
XG Ganglion of the vagus.

6. The **sixth spinal nerve** (*N. spinalis VI*) (Fig. 126 *M6*), after escaping from the ver-tebral canal between the sixth and seventh vertebrae, runs ob-liquely downwards and outwards on the under surfaces of the trans-verse processes of the seventh, eighth, and ninth vertebrae, then under the iliac bone to a point opposite the hinder half of the uro-style, where it descends under cover of the *M. obliquus abdom. internus.* In the rest of its course it repeats the corre-sponding courses of the fourth and fifth spinal nerves.

7, 8, 9, and 10. The seventh, eighth, ninth, and tenth **spinal nerves** (*Nervi spinales VII, VIII, IX, and N. spinalis X s. N. coccygeus*) (Figs. 126 and

127 M7, M8, M9, and M10) are best described together, as they are intimately associated to form the sciatic plexus (*Plexus ischiadicus, Plexus cruralis*).

Within the vertebral canal the roots of these nerves form the *Cauda equina*; the seventh nerve leaves the canal between the seventh and eighth vertebrae, the eighth nerve between the eighth and ninth vertebrae, the ninth between the sacrum or ninth vertebra and the urostyle, and the tenth by the *Canalis coccygeus* in the urostyle; from these points the four nerves run obliquely on the ventral surface of the *M. ilio-coccygeus* to the pelvis, where they form the sciatic plexus. Although subject to some variation, the usual arrangement is that the seventh and eighth nerves unite to form a trunk, which then receives the ninth nerve; the large nerve so formed is the sciatic nerve: a branch of the tenth usually then joins either the sciatic plexus or the sciatic nerve; the plexus gives off or receives the following branches :—

(*a*) Like other spinal nerves, these nerves give off *Rami communicantes* (see Sympathetic System).

(*b*) The *M. ilio-hypogastricus* (Fig. 127 M7*a*). This arises from the seventh spinal nerve, before its union with the eighth spinal nerve; it runs obliquely outwards and downwards on the *Musc. ilio-coccygeus* and under the border of the *M. obliquus abdom. internus*, where it bifurcates :—

(1) One branch, the *Ramus cutaneus abdominalis*, pierces the *M. obliq. abdom. internus* in the same fashion as the cutaneous branches of the fourth, fifth, and sixth spinal nerves; it supplies the skin of the abdomen.

(2) The second or *Ramus muscularis* supplies the flat abdominal muscles and the *M. rectus abdominis*.

(*c*) The *M. cruralis* (Fig. 127 M7*b*) also arises from the seventh spinal nerve at or just beyond its point of union with the eighth spinal nerve. It accompanies the *A. cruralis* on the pelvic wall to the thigh, where it lies upon the *M. ilio-psoas* in a triangle between the *M. rectus fem. anterior* and the *M. adductor longus*, and divides into two main branches :—

(1) Muscular twigs to the *M. ilio-psoas*, *M. rectus femoris anticus*, *MM. adductores longus* and *brevis*.

(2) The *Ramus cutaneus femoris*, which runs downwards in the hinder wall of the Lymph-sac (*Saccus iliacus*), and supplies the skin of the under and outer surfaces of the thigh.

(d) The *Ramus dorsalis* is a very small nerve; according to Waldeyer it possesses only twenty nerve-fibres. It arises from

Fig. 127.

The sciatic plexus, from a drawing by Wiedersheim.

a	Communicating nerve from the ninth spinal nerve.	*Ao*	Aorta.
		Com	Point of union of nerves *a* and *cc*.
a'	Nerve to musc. lev. ani.	*Is*	Ischium.
b	Nerve to oviduct.	*M5*	Fifth spinal nerve.
c	Urostyle.	*M6*	Sixth spinal nerve.
cc	Communicating twig from the ninth spinal nerve.	*M7*	Seventh spinal nerve.
		M8	Eighth spinal nerve.
ci	M. coccygeoiliacus.	*M9*	Ninth spinal nerve.
c.l	M. coccygeosacralis.	*M10*	Tenth spinal nerve.
d	Nerve to bladder.	*M7a*	M. iliohypogastricus.
d'	Twig to the m. iliacus.	*M7b*	M. cruralis.
e	Twig from sciatic plexus to coccygeal plexus.	*Ni*	Sciatic nerve.
i	M. intertransversarius.	*Ovd*	Oviduct.
i	M. ilio-coccygeus.	*Rect'*	Rectum.
ip	M. ilio-psoas.	*S7, S8, S9, S10*	Rami communicantes of seventh, eighth, ninth, and tenth spinal nerves.
lev	M. lev. ani.		
oi	M. obliq. abdom. internus.	*Ves*	Bladder.
t'	Transverse process of sacrum.	*8, 9*	Eighth and ninth vertebræ.

the coccygeal nerve immediately beyond the *Canalis coccygeus*, perforates the *M. ilio-coccygeus*, and runs on its dorsal surface obliquely over the lymph-heart, without supplying it; the nerve then pierces the fascia to supply the skin of the back and thigh.

(*e*) The *Ramus abdominalis* also arises from the coccygeal nerve; it is larger than the *R. dorsalis*, and arises at the same point; the nerve runs on the ventral surface of the *M. ilio-coccygeus* towards the lymph-heart, and inosculates with the sympathetic. It is from this nerve that the branch to the sciatic plexus is usually given off; it further supplies a varying number of branches, which with branches derived directly or indirectly from the sciatic nerve, form a plexus (*Plexus coccygeus*); the two plexuses may together be regarded as a *Plexus ischio-coccygeus* or a *Plexus sacro-coccygeus*.

(*f*) In addition to the *Rami communicantes* given off by the spinal nerves near the vertebral column, the sciatic plexus supplies a few twigs, usually two (Fig. 127).

(*g*) Other small twigs pass from the sympathetic system forwards and outwards to join the sciatic plexus or the sciatic nerve. According to Waldeyer two of these are very constant.

(*h*) Branches to the oviduct (Fig. 127 *b*).

(*i*) Branches to the rectum (Fig. 127 *cc*).

(*k*) Branches to the bladder (Fig. 127 *d*).

(*l*) Branches to the *M. levator ani* (Fig. 127 *a'*).

(*m*) A branch to the lymph-heart, which runs along the anterior border of the *M. lev. ani*, on to its dorsal surface, and then direct to the lymph-heart.

Variations in the **sciatic plexus.** The arrangement of the nerves in the sciatic plexus is subject to many variations; according to Wiedersheim most of these variations belong to two chief classes: either the *N. coccygeus* inosculates directly with the ninth spinal nerve by one or several branches, or it joins the ninth nerve indirectly by uniting with its branches. A case of the latter arrangement is seen in Fig. 127, and is thus described by Wiedersheim:—

' After cutting through the pelvic symphysis and drawing to one side the contained viscera, namely, the hinder end of the oviduct, the rectum, and the bladder, one sees a row of small twigs (*a, b. cc. d*, and *e*) arising from the inner, hinder, and anterior surfaces of the ninth spinal nerve: the first (*a*) runs backwards parallel with

the *N. coccygeus* over the *M. ilio-coccygeus* to join this nerve at the point marked *Com.* The twig *cc* behaves in like manner after receiving a twig from *b*. The twig *b* arises from the inner surface of the ninth nerve between the two foregoing and close to its union with the eighth spinal nerve; from this origin twig *b* passes almost transversely outwards to the hinder extremity of the oviduct ("uterus"), and partly to the rectum, crossing in its course twig *a*, the sciatic nerve, and the urostyle. Its branches form a net-like plexus with the terminal branches of the last sympathetic ganglion and with a branch *cc* from the point of union *Com*.

'A second branch (*a'*), arising from the point of junction *Com*, is a continuation of the *N. coccygeus* (*M*10); it passes vertically downwards towards the hinder end of the cloaca and at the upper border of the *Levator ani*, divides into two branches, which are distributed to the inner and outer surfaces of this muscle and to the cloaca. Other branches pass dorsally to the lymph-hearts, while a third set pass to the hindermost part of the bladder.

'These three sets of nerves, to the *M. coccygeus*, *M. levator ani*, and to the lymph-hearts, are not supplied entirely by the *N. coccygeus*, as this is reinforced by one or more branches (*e*) from the sciatic plexus: this branch (*e*) supplies twigs to the *M. ilio-coccygeus*, which is also supplied anteriorly from the trunk of the *N. coccygeus*.

'The bladder receives a special branch (*d*), which arises from the sciatic plexus at the junction of the eighth and ninth spinal nerves; this nerve gives a twig (*d'*) to the *M. iliacus*.'

I. The **sciatic nerve** (*N. ischiadicus*) (Fig. 128 *I*) is the largest nerve of the body; it passes under the *M. coccygeus*, between the origins of the *M. vastus externus* and of the *M. pyramidalis*: lies then between the *M. biceps* and the *M. pyramidalis*, and later between the *M. biceps* and the *M. semimembranosus*; lastly, it bifurcates under the *M. biceps* to form the *N. tibialis* (*II*) and the *N. peroneus* (*III*). In this course it gives off:—

(*a*) A twig to the *M. coccygeo-iliacus*, while still in the pelvis.

(*b*) The *N. cutaneus femoris posterior* (Fig. 128, 2), which passes between the *M. pyramidalis* and the *M. vastus externus*, to appear behind and beneath the former; it accompanies an artery of like name to supply the skin of the hinder and inner surfaces of the thigh.

(*c*) A little below the foregoing it gives off a collateral branch (Fig. 128, 3), which passes under the *M. pyramidalis* and divides to form—

(1) A branch to the upper third of the *M. semimembranosus*.

(2) A branch to the *Rectus internus minor*. A twig of this branch (*bb*) pierces the muscle transversely in company with the *Arteria cutanea*, and passes to the skin of the middle of the inner surface of the thigh.

(3) Branches to both heads of the *semitendinosus*.

(4) Branches to the *M. adductor magnus*.

(*d*) Branches covered by the *M. pyramidalis* to the *M. quadrat. femoris* and *M. obturator*.

(*e*) A branch (5) forwards to the *M. biceps*.

(*f*) A branch (6) which accompanies the *Art. circum-flexa genu lateralis sup.* forwards to the *M. extensores cruris*, the *M. vastus externus*, and the *M. rectus anterior*.

Fig. 128.

Distribution of the sciatic nerve.

I	The sciatic nerve.
II	N. tibialis.
III	N. peroneus.
1	Branches to the M. pyramidalis.
2	N. cut. fem. posterior.
3	Large collateral branch.
5	Branch to the M. biceps.
6	Branch accompanying the art. circumfl. genu lateralis sup.
7	Branch of tibial nerve to the M. gastrocnemius.
8	N. suralis.
ad'''	M. adductor magnus.
b	M. biceps.
bb	Twig accompanying the art. cutanea.
ci	M. coccygeo-iliacus.
cp	N. cut. cruris lateralis.
ct	R. cut. cruris posterior.
g	M. gastrocnemius.
gl	M. glutaeus.
p	M. pyramidalis.
pe	M. peroneus.
ra	M. rectus anterior.
ri'	M. rectus internus minor.
sm	M. semimembranosus.
st	M. semitendinosus.
ve	M. vastus externus.

O

II. The *Nervus tibialis* (Figs. 128 *II*, 129 *T*) passes backwards and inwards to supply the extensors of the foot and the flexors of the toes. Its branches are :—

(*a*) The *R. cutaneus cruris posterior* (Figs. 128 and 129 *ct*), accompanied by an artery and vein, passes to the skin of the calf.

(*b*) A twig to the upper part of the gastrocnemius (Fig. 129 *g'*).

Fig. 129.

The main nerve, after supplying this twig, bifurcates to form the next two nerves.

(*c*) The *Nervus suralis* (Figs. 128, 8 ; 129 *s*) runs downwards on the inner border of the *M. gastrocnemius* and gives off :—

(1) A twig (*g''*) to the upper third of the muscle.

(2) The *Ramus cutaneus medius* (*cs*) is given off below the middle of the *M. gastrocnemius* ; it passes to the skin of the lower third of the leg. After giving off the latter branch, the *N. suralis* runs downwards along the inner aspect of the *Tendo achillis* to the *Aponeurosis plantaris* of the sole of the foot as far as the calcar, and gives off :—

Nerves of the leg and sole of the foot.

ab5	Branch to the M. abduct. digit. V.
ad5	Branch to the M. adduct. digit. V.
ar	M. rectus anterior.
b	M. biceps.
cs	Ramus cutaneus medius.
ct	Ramus cutaneus cruris posterior.
dvI	Ramus digitalis volaris I.
dvII	Branch supplying R. digit. volaris I and II.
dvIII	Second branch of the N. tibialis.
F5	Branch to the M. flex. brev. digit. V.
flp	Branches to the M. plantaris and the M. flexor digitorum.
g'	Branch to the M. gastrocnemius.
g''	Branch to the M. gastrocnemius.
pc	N. peroneus.
s	N. suralis.
sm	M. semimembranosus.
T, t	Nervus tibialis.

(3) Branches (*flp*) to the *Musc. plantaris* and the *M. flexor digitorum.* www.libtool.com.cn

(4) A branch to the *M. abductor hallucis.*

(5) The *R. digitalis volaris I* (*dvI*) supplies the inner side of the first toe by its terminal twig.

(*d*) The *Nervus tibialis* (Fig. 129 *t*) passes downwards on the hinder surface of the tibio-fibula, sinks into the *M. tibialis posticus* to appear again at its hinder border; it then runs over the ankle-joint into the sole of the foot, where it lies midway in the space between the two *Ossa tarsi* and between the *M. extensor tarsi* and the *M. abductor digiti I longus* ; the nerve then runs downwards in the groove of the small *Os tarsi* and divides to form three branches :—

(1) The first branch (*dvII*) runs to the space between the second and third fingers, where it bifurcates :—

(*a*) The *Rami digital. volaris I* run transversely over the muscles of the second toe, supply the muscles of the first toe, and bifurcate to form the *R. digital. volaris I* and *II.*

(*β*) The *Ram. digit. volar. II* divides in the space between the second and third fingers to supply the *Flex. phalang.* and the adjacent sides of these toes.

(2) The second branch (*dvIII*) runs over the *M. flex. metatarsi* of the third toe to the space between the third and fourth toes, and bifurcates to supply the adjacent sides of these toes and the web between them.

(3) The third branch at once divides to supply :—

(*a*) The *M. transv. metatarsi.*

(*β*) The *MM. lumbricales* of the fourth toe.

(*γ*) The *M. abductor digit. V* (*ab5*), the *M. flexor brevis dig. V* (*F5*), and the *M. adductor dig. V* (*ad5*) ; it then ends as—

· (*δ*) A bifurcating branch forming the *R. digit. volar.* of the fourth and fifth toes.

III. The *Nervus peroneus* (*N. peroneus communis superior*, Ecker), (Fig. 130 *pc*) is the second division of the sciatic nerve; it passes between the outer head of origin of the *M. gastrocnemius* and the tendon of insertion of the *M. biceps*, it then lies on the tibio-fibula between the *M. gastrocnemius* and the *M. peroneus*, where it is accompanied by the *Vena tibialis postica*, then runs downwards upon the *M. extensor cruris* and the *Flexor tarsi ant.*, and passes under the *M. tibial. anticus* and bifurcates ; its branches are :—

a. The *N. cutaneus cruris lateralis* (Fig. 128 *cp*); which, like other cutaneous nerves, runs in a common sheath together with an artery and vein to the skin. It arises close to the sciatic nerve.

b. Muscular branches to the *MM. peroneus, tibialis anticus, extensor cruris brevis*, and the *flexor tarsi anterior*.

Fig. 130.

Distribution of the *N. peroneus.*

A Inner terminal twig of N. peron. comm. inf.
B Outer terminal twig of N. peron. comm. inf.
cpl N. cutaneus dorsi pedis lateralis.
pc N. peroneus.
pci N. peroneus communis inferior
pl N. peroneus lateralis.
pm N. peroneus medialis.

c. The *N. peroneus medialis* (Fig. 130 *pm*) is the smaller of the two terminal branches of the *N. peroneus*; it courses with the *Art. tibialis antica* under the *MM. flexores tarsi anterior* and *posterior* and supplies the latter.

d. The *N. peroneus lateralis* (Fig. 130 *pl*) is the larger terminal branch of the *N. peroneus*; it passes downwards between the heads of the *M. tibialis anticus* to the tendon of origin of the *Flexor tarsi posterior*, where it gives off two branches (Nos. 1 and 2); the nerve then unites with the *N. peroneus lateralis* to form a common stem, the *N. peroneus communis inferior* (Ecker). The *N. peroneus lateralis* gives off :—

(1) The *N. cutaneus dorsi pedis lateralis* (*cpl*), which passes to the skin of the outer side of the dorsum of the foot.

(2) A second branch to the *M. extensor* of the fourth and fifth toes.

e. The *N. peroneus communis inferior* (Fig. 130 *pci*) runs on the dorsum of the foot in company with the *Art. dorsalis pedis*, underneath the *MM. extensores digiti I* and *II*; it supplies several branches and then bifurcates. It gives off :—

(1) Branches to the *MM. extensor longus* and *brevis digiti I*.

(2) *Rami digitales dorsales* to the adjacent sides of the first and second toes. www.libtool.com.cn

(3) Branches to the *MM. extensores digiti II*.

(4) The inner, terminal branch (Fig. 130 *A*) at once divides :—

(*a*) The outer branch runs between the third and fourth toes as far as the commencement of the web, where it bifurcates to form two *Rami cutanei*, which course along the adjacent sides of these toes as far as their apices.

(*β*) The inner branch passes to the extensor muscle, and, in part, to the adjacent sides of the third and fourth toes.

(5) The outer, terminal branch (Fig. 130 *B*) of the *N. peroneus communis inferior* passes to the muscles of the fourth and fifth toes, and supplies *Rami cutanei dorsales* to the outer side of the fourth and inner side of the fifth toes.

Cutaneous branches of the *N. tibialis* supply the outer side of the fifth and inner side of the first toe.

G. THE SYMPATHETIC SYSTEM (*Sympathicus*).

(*Re-written by the translator*.)

The sympathetic cord or chain is a row of nervous ganglia (vertebral or lateral ganglia), connected by nerve-fibres, and lying on either side of the vertebral column (Figs. 117 and 131); with the exception of the last spinal nerve there is usually one sympathetic ganglion associated with each spinal nerve; in the case of the tenth spinal nerve there may be only one ganglion or as many as twelve.

The first ganglion (Figs. 111, opposite *ics*; 117 *S1*) is placed on the hypoglossal nerve just as it emerges from the first intervertebral foramen; it is large, but smaller than the second; its *Ramus communicans* is represented by several fine and very short fibres, which connect the ganglion with the nerve.   This ganglion is connected with the second by two or three nervous threads, between which passes the subclavian artery, a true *Annulus Vieussenii* being thus formed (de Watteville).   The other ganglia are connected by single bands of fibres.   The first ganglion supplies also branches to the axillary artery and to the cardiac plexus.

The second ganglion (Figs. 117 and 131) is the largest, and is closely applied to the brachial nerve; as in the case of the first ganglion and hypoglossal nerve, it is attached to the second spinal nerve without a distinctly marked *Ramus communicans*.

The third ganglion (*Ganglion cardiacum basale*, Gaskell and Gadow) is sometimes fused with the second, but is usually close to the third spinal nerve : it has a short but distinct *Ramus communicans*.

Behind the third ganglion the sympathetic cord is continued backwards along the corresponding aortic arch, then parallel with and close to the abdominal aorta (Figs. 117, 127, and 131), receiving *Rami communicantes*, which are long and well marked, from each of the spinal nerves ; the fourth, fifth, and sixth nerves usually supply each one *Ramus communicans*, the seventh two, and the eighth and ninth each two or three : from the tenth nerve it receives three or more, as many as twelve having been noted. The ganglia are usually more or less spindle-shaped or flattened and triangular ; the hinder part of the cord usually receives in addition two or three branches from the sciatic plexus and twigs from the *R. abdominalis* of the *N. coccygeus*.

Fig. 131.

Sympathetic cord. From Ecker (Icones physiologicae, Pl. XXIV, Fig. 3).

The heart, lungs, and liver have been removed ; the stomach, intestine, kidneys, and testes drawn to the right side ; the left sympathetic cord is thus pulled to the right side to expose the Rami communicantes.

S Sympathetic cord attached to the ganglion of the vagus.

The numbers refer to the ganglia, which are enumerated from before backwards.

The branches and communications of the sympathetic cords are as follows :—

a. Communicating branches between the two cords ; these are extremely numerous and irregular, forming a net-like plexus, which surrounds the abdominal aorta and other adjacent structures, and gives off numerous small twigs to the neighbouring vessels and organs.

b. Communications with the cranial nerves ; these are two branches (Wiedersheim), (Figs. 111 and 116) which pass from the first ganglion to the *Ganglion nervi vagi*, where one terminates, the other leaves the ganglion to pass on to the Gasserian ganglion

(Figs. 111 and 116 *VS*): according to Gaskell a *single* nerve passes from the first ganglion to the *Ganglion nervi vagi*, whence one portion of its fibres is continued to the Gasserian ganglion, the remainder accompanying the pneumogastric nerve without any connection with the ganglion; he therefore names this nerve the vago-sympathetic. (See Gasserian ganglion, p. 168.)

c. Communications with the spinal nerves ; these are :—

(1) The *Rami communicantes*.

(2) Communications between the sympathetic ganglia or their branches and the spinal nerves or their branches (Fig. 117); by means of these connections, fibres of the sympathetic system are conducted by the spinal nerves and their branches to all parts of the body.

d. Branches to the heart, which form the following ganglia :—

(1) A relatively large plexus lies on the auricles in the median plane immediately beneath the division of the *M. hyoglossus*. It supplies a network of fibres to the auricles and the adjacent large vessels. It is said to communicate at various points with the pneumogastric nerve.

(2) A smaller ganglion of oval form, supplies twigs to the neighbouring vessels and a communicating branch to the hypoglossal nerve (Wiedersheim).

e. Branches to the abdominal viscera; these form intricate plexuses by which the organs are supplied : the one best known is the solar plexus (Fig. 131); it is formed chiefly from branches derived from the third, fourth, and fifth ganglia, and supplies the stomach, etc.; other plexuses for the various viscera are known by corresponding names, such are the *Plexus hepaticus, renalis, genitalis, haemorrhoidalis,* and *vesicalis.*

The sympathetic system is characterised by the fact that the branches form intricate plexuses, which include numerous ganglia and which are very irregular ; it is also characteristic that most of its fibres are non-medullated. According to the investigations of Gaskell, the fibres of the sympathetic system arise in mammalia as very fine medullated fibres from the posterior vesicular (Clarke's) columns (Mason has recently described cells in the frog's spinal cord, which he holds to be homologous with the cells of these columns); they leave the cord by both the ventral and dorsal roots of the spinal nerves, and are thus connected with two sets of ganglia, (1) with the ganglia of the dorsal roots, and (2)

through the *Rami communicantes* with the sympathetic ganglia (vertebral or lateral ganglia); these two sets of ganglia Gaskell terms proximal. By means of the branches from the sympathetic ganglia (*Rami efferentes*) part of the fibres pass to another set of ganglia, the solar plexus, etc., which he terms prevertebral or collateral; from these the fibres pass to be distributed to the various viscera and blood-vessels, where a fourth set of very small ganglia (terminal ganglia) is found. The prevertebral and terminal ganglia are together classed as distal ganglia. Gaskell holds that the fine medullated fibres from the cord lose their medullary sheath in one or other of these ganglia according to the function they fulfil.

The inhibitory fibres of the heart and vaso-dilator fibres of the blood-vessels continue as white fibres along the vago-sympathetic and spinal nerves to the distal ganglia (Bidder's ganglion, etc.), where the medullary sheath disappears: whereas the 'augmentor' fibres of the heart and vaso-constrictor fibres of the blood-vessels lose their medullary sheath in the proximal ganglia and pass on as non-medullated fibres. In the same way the nerve-fibres that bring about contraction of the circular muscle fibres of the hollow viscera lose their medullary sheaths in the proximal ganglia, while those fibres, the influence of which negatives the former, become pale fibres in the distal ganglia.

Waters has demonstrated that in the frog the various spinal nerves have each a localised physiological action upon the blood-vessels and muscular walls of various parts of the alimentary canal: he shows that

The third spinal nerve supplies the oesophagus.

The fourth spinal nerve supplies the stomach.

The fifth spinal nerve supplies the upper third of the small intestine.

The sixth spinal nerve supplies the lower two thirds of the small intestine.

The seventh spinal nerve supplies the large intestine.

The eighth spinal nerve supplies the bladder, this supply being, however, not so definite as the others given above.

It has long been known that the branches of the spinal ganglia (ganglia of the posterior roots) are together larger (one-third, Lenhossék), and contain more fibres than the ventral and dorsal roots together; this is supposed to be in part due to an acquisition of new fibres derived from the ganglia. The majority of recent observers hold that each ganglionic cell has only one process, which,

however, soon bifurcates; whether any of the fibres so formed pass
as far as the cord or beyond its blood-vessels is doubted by most ob-
servers, and denied by Gaskell.   These remarks and the description
of the cells of the spinal ganglia (p. 176) hold good for the lateral
or vertebral ganglia and the prevertebral ganglia (solar gan-
glion, etc.) of the sympathetic system; the terminal ganglia will
be described with the organs in which they are found.

H. HISTOLOGICAL NOTES ON THE NERVOUS SYSTEM.

(In order to render the foregoing description of the nervous system more complete,
the following notes have been added by the translator.)

[The histological elements of the nervous system are nerve-cells
and nerve-fibres; of these the nerve-cells have been described with
the parts in which they occur; it may simply be remarked that
later observers have been unable to discover the 'spiral cells' de-
scribed by Beale, Arnold, and others.   The nerve-fibres, as in most
other animals, are of two kinds, medullated and non-medullated.

1. Medullated nerve-fibres or white fibres are found in all cranial
and spinal nerves, with the exception of the olfactory nerves, and
in many of the sympathetic nerves (see Sympathetic System);
also in the white matter of the brain and spinal cord; examined
microscopically the fibres are seen to consist of an external sheath or
neurilemma, a medullary sheath, and an axis-cylinder :—

a. The neurilemma (Sheath of Schwann, Outer or Primitive
Sheath) is a nucleated endothelial layer covering the nerve-fibre;
it is continuous with the corresponding coat of the nerve-cells, and
is uninterrupted throughout the length of the nerve; at the nodes,
however, it dips down towards the axis-cylinder, the circular groove
so formed being filled with cement substance.

b. The medullary sheath (White substance of Schwann); the
presence of this sheath is the chief cause of the whiteness of these
nerves; the thickness of the sheath varies considerably, and towards
the ultimate distribution of the nerve it is entirely lost.   At more
or less regular intervals along the course of the nerve-fibre the
continuity of the medullary sheath is broken, and gives the
fibres the appearance of being constricted at these places; such
constrictions are known as nodes of Ranvier; the portion between
two such nodes being termed an internode.   Each internode
possesses an oval, flattened, granular nucleus at about its middle

and placed between the neurilemma and the medullary sheath ; the nucleus has a nucleolus. In the fresh state the medullary sheath seems to be fluid ; it is of a fatty nature.

Medullary segments are caused by breaks in the continuity of the medullary sheath, which are seen only in nerves which are no longer in their normal condition, and are especially well marked after treatment with osmic acid. The breaks are oblique ; hence the conical end of one segment fits into the funnel-shaped end of the next. How far they correspond to pre-existent structures is uncertain. The segments in the frog vary in length from 0·010 to 0·040 mm.

c. The axis-cylinder is the essential part of every nerve-fibre ; it shows a longitudinal striation corresponding to the fine fibrils (primitive fibrillae) of which it consists ; these fibrils often exhibit minute varicosities : at times it has the appearance of being invested with a very delicate structureless sheath. It is continuous through the nodes of Ranvier.

2. Non-medullated nerve-fibres (Grey or Varicose Fibres ; Fibres of Remak) ; these occur chiefly in branches and plexuses of the sympathetic system ; they consist of a neurilemma and an axis-cylinder, which agree exactly with the corresponding elements found in the medullated fibres.

The nerve-fibres, whether medullated or non-medullated, are bound together by connective-tissue to form nerves. A number of fibres bound together by connective-tissue to form a slender cord is known as a funiculus ; a small nerve may consist of one such funiculus ; the sheath surrounding it is known as the perineurium, and sends in supporting processes between the fibres (endoneurium) : when several funiculi are bound together to form a large nerve the common sheath is known as the epineurium. These sheaths support nerves (*nervi nervorum*) and vessels (*vasa vasorum*) supplying the nervous elements, and their intercellular spaces form lymph-canals. The whole nerve is surrounded by an endothelial coat, which helps to form a lymph-space, which more or less completely surrounds the nerve.

The ultimate distribution of the nerve-fibres will be included in the description of the various organs in which they end.]

SECTION IV.

THE VASCULAR SYSTEM.

THE VASCULAR SYSTEM.

LITERATURE.

———◆———

THE HEART AND BLOOD-VESSELS.

Aeby, Ueber den feineren Bau der Blutcapillaren. Centralbl. f. d. med. Wiss. 1865, p. 209.

Altmann, R., Ueber Corrosion in der Histologie. Centralbl. f. d. med. Wiss. 1878, p. 245.

Aubert, H., Die Innervation der Kreislaufsorgane. Hermann's Handbuch der Physiologie. Leipzig, 1880. Vol. VI, Pt. I, p. 377.

Beck, K., Zur Kenntniss der Herznerven. Arch. f. mik. Anat. 1884. Vol. XXIV, pp. 11–19.

v. Besold, Untersuchungen über die Innervation des Herzens. Leipzig, 1863.

Bidder, F., Ueber functionell verschiedene und räumlich getrennte Nervencentra im Froschherzen. Arch. f. Anat. u. Physiol. 1852, p. 163.

Bidder, F., Zur näheren Kenntniss des Froschherzens und seiner Nerven. Arch. f. Anat. u. Physiol. 1866, p. 1.

Bidder, F., Endigungsweise der Herzzweige des N. vagus beim Frosche. Arch. f. Anat. u. Physiol. 1868, p. 1.

Bidder, F., and **Gregory,** Beiträge zur Physiologie der Herzbewegung beim Frosche. Dorpat, 1865.

Boas, J. E. V., Ueber den Conus arteriosus und die Arterienbogen der Amphibien. Morph. Jahrb. 1881. Vol. VII, pp. 271–273.

Boas, J. E. V., Beiträge zur Angiologie der Amphibien. Morph. Jahrb. 1882. Vol. VIII, pp. 169–187.

Bobretsky, C., Ueber die Entwickelung der Capillargefässe. Centralbl. f. d. med. Wiss. 1885, p. 769.

Bremer, L., Die Nerven der Capillaren der kleinen Arterien und Venen. Arch. f. mik. Anat. 1882. Vol. XXI, p. 663.

Brenner, A., Ueber das Verhältniss des N. laryngeus inferior vagi zu einigen Aortenvarietäten des Menschen und zu dem Aortensystem der durch Lungen athmenden Wirbelthiere überhaupt. Arch. f. Anat. u. Physiol. 1883, pp. 373–397.

Brücke, E., Ueber Mechanik des Kreislaufes des Blutes bei Fröschen. Wiener Sitzungsb. 1851. Vol. VI, p. 61 ; also p. 114.

Brücke, E., Beiträge zur vergl. Anatomie u. Physiologie des Gefässsystems der Amphibien. Denkschriften d. Wiener Academie. 1852. Vol. III, p. 335.

Burdon-Sanderson, J., Circulation of the Blood, in Handb. for the Physiological Laboratory. London, 1873.

Burow, De vasis sanguiferis ranarum. Diss. inaug. Regiomontani, 1834.

Calori, L., Sugli organi della circolazione e della respirazione dei gyrini della Rana esculenta e della Salamandra cristata. Nuov. Ann. delle Scienz. nat. de Bologna. 1838.

Champness, F., The Septum Atriorum of the Frog and the Rabbit. Journ. of Anat. and Physiol. 1874, p. 340.

Chapmann, S. H., Beiträge zur Kenntniss des Baues des normalen und entzündeten Pericardiums der Batrachier. Wiener Med. Jahrbücher.

Chrzonscsewsky, N., Ueber die feinere Structur der Blutcapillaren. Virchow's Arch. 1866. Vol. XXXV, p. 169.

Darwin, F., Contributions to the anatomy of the sympathetic ganglia of the Bladder in their relation to the vascular system. Quart. Journ. Micros. Sci. 1874. Vol. XIV, p. 109.

v. Deen, De differentia et nexu inter nervos vitae animalis et vitae organicae. Diss. inaugur. Lugduni; also in Arch. f. Anat. u. Physiol. 1834, p. 477.

v. Deen, Over de zijelingsche Takken dar zwervende van den Proteus anguinis (includes frog-larva). Bijdragen tot de Naturkundige Wetenschappen. 1834.

Dogiel, J., Die Ganglienzellen des Herzens bei verschiedenen Thieren und beim Menschen. Arch. f. mik. Anat. 1877. Vol. XIV, p. 471.

Dogiel, J., Die Nervenzellen und Nerven des Herzventrikels beim Frosche. Arch. f. mik. Anat. 1882. Vol. XXI, p. 21.

Dumeril, A. M. C., and Bibron, G., Erpétologie générale, ou histoire naturelle complète des reptiles. Paris, 1841.

Eberth, C. J., Ueber den feineren Bau der Blutcapillaren bei den Wirbelthieren. Centralbl. f. d. med. Wiss. 1865, p. 196.

Eberth, Elemente der quergestreiften Muskelfasern, bes. des Herzens. Virchow's Arch. 1866. Vol. XXXVII, p. 100.

Ecker, A., Icones physiologicae. Leipzig, 1851-9.

Engelmann, T. W., Der Bulbus Aortae des Froschherzens. Physiol. Untersuch. in Gemeinsch. mit. J. Hartog und J. J. Verhoff. Pflüger's Arch. f. d. ges. Physiol. 1882. Vol. XXIX, pp. 425-468.

Friedländer, Ueber die nervösen Centralorgane des Froschherzens. Unters. a. d. physiol. Labor. in Würzburg. 1867. Vol. II, p. 159.

Fritsch, G., Zur vergleichenden Anatomie der Amphibienherzen. Arch. f. Anat. u. Physiol. 1869, p. 654.

Gaskell, W. H., On the augmentor (accelerator) nerves of the heart of cold-blooded animals. Journ. of Physiol. 1884. Vol. V, p. 46.

Gaskell, W. H., and Gadow, On the anatomy of the cardiac nerves in certain cold-blooded animals. Journ. of Physiol. 1884. Vol. V, p. 362.

Gastaldi, Neue Untersuchungen über die Muskulatur des Herzens. Würzb. Naturf. Zeitschr. 1862. Vol. III, pp. 6-9.

Gegenbaur, C., Grundzüge der vergleichende Anatomie. 2nd edit., 1870.

Gerlach, L., Ueber die Nervenendigungen in der Muskulatur des Froschherzens. Virchow's Arch. 1876. Vol. LXVI, pp. 187-223.

Golubew, A., Beiträge zur Kenntniss des Baues und der Entwicklungsgeschichte der Capillargefässe des Frosches. Arch. f. mik. Anat. 1869. Vol. V, pp. 49-89.

Gompertz, C., Ueber Herz und Blutkreislauf bei nackten Amphibien. Arch. f. Anat. u. Physiol. Phys. Abt. 1884, p. 242.

Gruby, Sur le système veineux de la grenouille. Annales des Sciences nat. 2nd series. Zool. 1842. Vol. XXVII, p. 207.

Gruby, Recherches anatomiques sur le système veineux de la grenouille. Paris, 1842.

Gscheidlen, R., Zur Lehre v. d. Nervenendigungen in den glatten Muskelfasern. Arch. f. mik. Anat. 1877. Vol. XIV, p. 321.

Heidenhain, Disquisitiones de nervis organisque centralibus cordis. Dissert. inaug. Berol., 1854; and in Arch. f. Anat. u. Physiol. 1858, p. 479.

His, W., Ueber die Endigung der Gefässnerven (in mesentery). Virchow's Arch. 1863. Vol. XXVIII, pp. 427-428.

Hoffmann, C. K., Die Lungengefässe der Rana temporaria. Dissert. Dorpat, 1875.

Hoffmann, C. K., in Bronn's Klassen und Ordnungen des Thierreichs. Leipzig und Heidelberg, 1873-1878. Vol. VI, pp. 509-514.

Hoffmann, T., Die Lungen-Lymphgefässe der R. temporaria. Dissert. Dorpat, 1875.

Huizinga, D., Untersuchungen über die Innervation der Gefässe in der Schwimmhaut des Frosches. Pflüger's Arch. f. d. ges. Physiol. 1875. Vol. XI, p. 207.

Huschke, Ueber die Carotidendrüse einiger Amphibien. Zeit. f. Physiol. von Friedmann u. Treviranus. 1831. Vol. IV, p. 113.

Hyrtl, J., Vorläufige Anzeige über gefässlose Herzen. Wiener Sitzungsb. 1859. Vol. XXXIII, p. 572.

Hyrtl, J., Ueber die sogenannten Herzvenen der Batrachier. Wiener Sitzungsb. 1864. Vol. L, Pt. II, p. 42.

Hyrtl, J., Ueber das Verhalten der Leberarterie zur Pfortader bei Amphibien u. Fischen. Wiener Sitzungsb. 1864. Vol. XLIX, Pt. I, p. 167.

Jantschitz, J., Materialien zur Anatomie der Nerven des Pericardiums. Rudneff's Journ. f. normale und patholog. Histologie u. klinisch. Med. St. Petersburg, 1874, pp. 417-442.

Klug, F., Ueber die Beschleunigungsnerven des Froschherzens. Centralbl. f. d. med. Wiss. 1881, p. 945.

Klug, F., Ueber die Herznerven des Frosches. Arch. f. Anat. u. Entwicklungsgesch. 1881, pp. 330-346. Abstract in Centralbl. f. d. med. Wiss. 1882, p. 259.

v. Kölliker, A., Handbuch der Gewebelehre. 5th edit.

Küttner, Beitrag zu den Kreislaufsverhältnissen in der Froschlunge. Virchow's Arch. Vol. LXI, p. 21.

Lahousse, P., Die Structur des Nervenplexus in der Vorhofscheidewand des Froschherzens. Arch. f. Anat. u. Physiol. 1886, pp. 191-196.

Lambotte, H. A., Observations anatomiques et physiologiques sur les appareils sanguins et respiratoires de Batraciens anourés. Mém. cour l'Acad. de Bruxelles. 1838.

Langer, C., Ueber das Lymphgefässsystem des Frosches. Wiener Sitzungsb. 1866. Vol. LIII, Pt. I, p. 395 ; 1867. Vol. LV, Pt. I, p. 593 ; 1868. Vol. LVIII, Pt. I, p. 198.

Langerhans, P., Notiz zur Anatomie des Amphibienherzens. Zeit. f. wiss. Zool. 1873. Vol. XXIII, p. 457.

Langerhans, P., Zur Histologie des Herzens. Virchow's Arch. 1873. Vol. LVIII, pp. 65-83.

Lavdowsky, M., Das Säugadersystem und die Nerven der Cornea. Arch. f. mik. Anat. 1872. Vol. VIII, p. 538.

Lavdowsky, N., Ueber die Fortsätze der Nervenzellen in den Herzganglien. Arch. f. mik. Anat. 1887. Vol. XXIX, p. 609.

Lehmann, Ueber die Nervenendigungen und das Vorkommen von mikroskopischen Ganglien in den Gefässwandungen. Zeit. f. wiss. Zool. 1864. Vol. XIV, pp. 346-352.

Levschin, Ueber das Lymph- und Blutgefässsystem. Wiener Sitzungsb. 1870. Vol. LXI, Pt. I, p. 67.

Leydig, Anatomisch-histologische Untersuchungen über Fische und Amphibien. 1853.

Leydig, F., Ueber Organe eines sechsten Sinnes. Nova Acta Acad. Caes. 1868. Vol. XXXIV, pp. 1-102.

Leydig, Lehrbuch der Histologie. 1857.

Löwit, M., Beiträge zur Kenntniss der Innervation des Herzens. Pflüger's Arch. f. d. ges. Physiol. Chapters I and II, 1880, Vol. XXIII, p. 313. Chapters III, IV, and V, 1881, Vol. XXV, pp. 399-496. Chapter VI, 1882, Vol. XXVIII, p. 312. Chapter VII, 1882, Vol. XXIX, p. 469.

Löwit, M., Ueber die Gegenwart von Ganglienzellen im Bulbus aortae des Froschherzens. Pflüger's Arch. f. d. ges. Physiol. 1883. Vol. XXXI, pp. 88-94.

Ludwig, C., Ueber die Herznerven des Frosches. Arch. f. Anat. u. Physiol. 1848, p. 139.

Marshall, A. M., The Frog. Manchester and London. 1885, pp. 22–31.

Marshall, C. F., Structure and Distribution of striped and unstriped muscle. Quart. Journ. Micros. Sci. 1887. Vol. XXVI.

Meckel, J. F., System der vergleichenden Anatomie. Halle, 1833.

Milne-Edwards, Leçons sur la Physiol. et l'Anat. comparée. Vol. II, p. 407.

Namias, M., Suiganglii miocardici della Rana. Osservazione ed esperienzi in Lo Spallanzani. 1881. Vol. X, pp. 402–419.

Nicolsky, P., Ueber Flimmerendothel beim Frosche (in pericardium). Centralbl. f. d. med. Wiss. 1880, p. 641.

Oellacher, J., Ueber die erste Entwickelung des Herzens und der Pericardial- oder Herzhöhle bei Bufo cinereus. Arch. f. mik. Anat. 1871. Vol. VII, p. 157.

v. Openchowski, T., Beitrag zur Kenntniss der Nervenendigungen im Herzen. Arch. f. mik. Anat. 1883. Vol. XXII, p. 408.

Owen, R., Comparative Anatomy. Vol. I, p. 517.

Owen, R., On the structure of the heart in the perennibranchiate Batrachia. Trans. Zool. Society, 1834. Vol. I, p. 212.

Pihlermann, R., Untersuchungen über die angeblich präformirten Verbindungswege zwischen den Blut- und Lymphgefässen des Frosches. Dissert. Dorpat, 1876.

Pohl-Pincus, Ueber die Muskelfasern des Froschherzens. Arch. f. mik. Anat. 1884. Vol. XXIII, p. 500.

Prévost and Lebert, Mémoire sur la formation des organes de la circulation et du sang dans le batraciens. Annales des Sciences nat. 1844 ; Vol. I, p. 193; and in Compt. rend. 1844 ; Vol. XVIII, p. 88 ; and in Froriep's Notizen, 1844, Vol. XXX, cols. 337–340.

Ranvier, L., Leçons d'anatomie générale. Paris, 1880, p. 469.

Ranvier, L., Appareils nerveux terminaux des muscles de la vie organique ; cœurs sanguins, cœurs lymphatiques ; œsophagus ; muscles lisses. Leçons d'anatomie générale au Collége de France. Paris, 1880. Vol. VII, p. 350.

Rawitz, B., Ueber den Bau der Spinalganglien. Arch. f. mik. Anat. Vol. XXI, p. 244.

Reich, M., Einige microscopische Studien mit Silbersalpeterlösung besonders an Gefässen des Auges und anderen Organen. Wiener Sitzungsb. 1873. Vol. LXVII, Pt. III, pp. 81–96.

Rokitansky, C. Ueber die Scheidewand der Vorhöfe. Wiener Med. Jahrb. 1871, p. 340.

Rosenberger, De centris motuum cordis disquisitiones anatomico-physiologicae. Dorpat, 1850.

Rouget, C., Mémoire sur le développement, la structure et les propriétés physiologiques des capillaires sanguins et lymphatiques. Arch. de physiol. normale et pathologique. 1873, pp. 662–664.

Rusconi, M., Observations sur le système veineux de la grenouille. Annales des Sciences nat. 2nd series. Zool. 1845. Vol. IV, p. 283.

Sabatier, Etudes sur le cœur dans la série des vertébrés. Montpellier, 1873 ; also Ann. Sci. nat. 1873, Vol. XVIII, art. 4 ; also Revue Cours. Scient. 1873, pp. 163–165.

Schmuziger, F., Ein Beitrag zur Auswanderung der Blutkörperchen aus den Gefässen des Frosches. Arch. f. mik. Anat. 1873. Vol. IX, pp. 709–711.

Schöbl, D. J., Ueber die Blutgefässe des cerebrospinalen Nervensystems der Urodelen. Arch. f. mik. Anat. 1882. Vol. XX, p. 87. Also in Sitzungsb. d. k. b. Gesell. d. Wiss. in Prag. 1878, p. 25.

Schöbl, D. J., Ueber Wundernetze und divertikelbildende Capillaren bei nackten Amphibien, etc. Arch. f. mik. Anat. 1885. Vol. XXV, p. 89.

Schraeder, M. E. G., Ueber das Hemmungscentrum des Froschherzens. Strassburg, 1886.

Schutz, C. H., Das System der Circulation. Stuttgart and Tübingen, 1836.

Schweigger-Seidel, Das Herz, in Stricker's Handbuch d. Gewebelehre.

Sokoloff, Ueber die Saftkanälchen (Lymphkanälchen) in den quergestreiften Muskeln des Frosches. Rudneff's Journ. f. normal u. patholog. Histologie und Klin. Med. St. Petersburg, 1873, pp. 456–459.

Stirling, W., and Macdonald, The minute structure of the palatine nerves of the Frog and the termination of nerves in blood-vessels and glands. Journ. of Anat. and Physiol. 1884. Vol. XVII, p. 273.

Stricker, S., Untersuchungen über die capillaren Blutgefässe in der Nickhaut des Frosches. Wiener Sitzungsb. 1865. Vol. LI, Pt. II, pp. 16–26.

Stricker, S., Studien über den Bau und das Leben der capillaren Blutgefässe. Wiener Sitzungsb. 1866. Vol. LII, Pt. II, pp. 379–394.

Trevianus, G. R., Ueber die Karotidendrüse einiger Amphibien. Tiedemann's Zeitschr. 1831. Vol. IV, p. 113.

Trevianus, C. R., Beobachtungen aus der Zootomie u. Physiologie, nach dessen Tode herausgegeben von L. C. Treviranus. Bremen, 1839.

Verhoeff, J. J. W., Histologische en physiologische bijdragen tot de kennis van den bulbus aortae van het kikvorschhart. Onderzoekingen gedaan in het Phys. Laborat. VII, aflev 2. Utrecht, 1882.

Vignal, Recherches sur l'appareil ganglion nerve du cœur des vertébrés. Labratoire d'histologie du Collége de France. Travaux de l'année 1881, p. 186; and in Arch. de Physiol. norm. et path. 1881, pp. 673–694 and 910–934.

Virchow, H., Ueber die Kopfgefässe des Frosches. Sitzungsb. Würzburg, 1880. Vol. XV, p. xxxiv.

Virchow, H., Ueber die Gefässe im Auge und die Umgebung des Auges beim Frosche. Zeit. f. wiss. Zool. 1881. Vol. XXXV, p. 247.

Volkmann, Nachweise der Nervencentra, von welchen die Bewegung der Lymph- und Blutgefässherzen ausgeht. Arch. f. Anat. u. Physiol. 1844, p. 419.

Wagner, R., Lehrbuch d. vergleichenden Anatomie. Leipzig, 1834–35.

Wagner, R., Icones Zootomicae. Leipzig, 1841.

Weismann, Ueber die Muskulatur des Herzens beim Menschen und in dem Thierreiche. Arch. f. Anat. u. Physiol. 1861, p. 42.

Wyman, J., On the heart and respiration of the Menobranchus and Batrachians. Proc. of the Boston Soc. of Nat. History. 1856. Vol. V, p. 51.

Zimmermann, W., Ueber circumvasale Safträume der Glaskörpergefässe von Rana esculenta. Arch. f. mik. Anat. 1886. Vol. XXVII, p. 410.

THE LYMPHATIC SYSTEM.

Bacculo, B., Nuove ricerche intorno l'apparecchio ganglionare intrinsico dei cuori linfatici. Naples, 1885.

Eckhard, C., Zeitsch. f. rat. Med. 1850. Vol. IX.

Eckhard, C., Beiträge zur Anat. u. Physiol. 1855, Vol. I, p. 53; 1858, Vol. II, p. 145; 1863, Vol. III, p. 167.

Eckhard, C., Experimentale Physiologie des Nervensystems. Giessen, 1867, p. 208.

Goltz, Centralbl. f. med. Wiss. 1863, pp. 17, 497; 1864, p. 690.

Heidenhain, Disquisitiones de nervis cordis cordiumque lymphaticorum. Berlin, 1854.

His, W., Ueber die Wurzeln der Lymphgefässe in den Häuten des Körpers und über die Theorien der Lymphbildung. Zeit. f. wiss. Zool. 1863. Vol. XII, p. 223.

Hoffmann, T., Die Lungen-Lymphgefässe der R. temporaria. Dissert. Dorpat, 1875.

Hüter, C., Ueber den Kreislauf und die Kreislaufstörungen in der Froschlunge. Centralb. f. med. Wiss. 1873, Nos. 5 and 6.

Jourdain, S., Sur les sacs sous-cutanés et les sinus lymphatiques de la région céphalique dans la Rana temporaria. Compt. rend. 1881. Vol. XCIII, pp. 597–600.

Jourdain, S., Sur le système lymphatique des têtards de grenouilles. Compt. rend. 1883. Vol. XCVI, pp. 271–273.

Jourdain, S., Recherches sur le système lymphatique de la R. temporaria. Montpellier, 1883; Extr. de la Revue de Sci. nat. Montpellier, 1884.

Kahrhel, G., Studien über Innervation der Lymphherzen. Medic. Jahrb. 1886, pp. 392–420.

Key and Retzius, Studien in der Anatomie des Nervensystems. Arch. f. mik. Anat. 1873. Vol. IX, p. 308.

Klein, E., On the lymphatic system of the skin and mucous membranes. Quart. Journ. Micros. Sci. 1881. Vol. XX, pp. 379–406.

Langendorff, O., and Boll, F., Zur Kenntniss der Lymphherzen. Arch. f. Anat. u. Physiol. 1883, p. 329.

Langer, C., Ueber das Lymphgefässsystem des Frosches. Wiener Sitzungsb. 1866, Vol. LIII, Pt. I, p. 395; 1867, Vol. LV, Pt. I, p. 593; 1868, Vol. LVIII, Pt. I, p. 198.

Levschin, Ueber das Lymph- und Blutgefässsystem. Wiener Sitzungsb. 1870. Vol. LXI, Pt. I, p. 67.

Luchsinger, B., Zur Lehre der Innervation der Lymphherzen. Pflüger's Arch. f. d. ges. Physiol. 1880. Vol. XXIII, p. 304.

Meyer, J., Systema amphibiorum lymphaticum. Diss. Berol., 1845.

Müller, J., Beiträge zur Anatomie und Naturgeschichte der Amphibien. Tiedemann's Zeitschr. 1831. Vol. IV, pp. 190–275.

Müller, J., On the existence of four distinct hearts having regular pulsations connected with the lymphatic system in certain amphibious animals. Phil. Trans. 1833. Pt. I, pp. 89; also in Arch. f. Anat. u. Physiol. 1834, p. 296.

Müller, J., Bemerkungen über die Structur der Lymphherzen und der Lymphgefässe. Arch. f. Anat. u. Physiol. 1839, p. 176.

Obersteiner, H., Ueber einige Lymphräume im Gehirne. Wiener Sitzungsb. 1870. Vol. LXI, Pt. I, p. 57.

Pagliani, Ueber die Funktion der Herzganglien. Moleschott's Untersuchungen. 1876. Vol. XI, p. 358.

Panizza, B., Sopra il sistema linfatico dei retelli. Ricerche Zootomiche. Pavia, 1833.

Panizza, B., Ueber die Lymphherzen der Amphibien. Arch. f. Anat. u. Physiol. 1834, p. 300.

Pihlermann, R., Untersuchungen über die angeblich präformirten Verbindungswege zwischen den Blut- und Lymphgefässen des Frosches. Dissert. Dorpat, 1876.

Priestly, J., An account of the anatomy and physiology of the batrachian lymphhearts. Journ. of Physiol. 1878. Vol. I, p. 1.

Ranvier, L., Appareils nerveux terminaux des muscles de la vie organique; cœurs sanguins, cœurs lymphatiques; œsophagus; muscles lisses. Leçons d'Anatomie générale faites au Collége de France. Paris, 1880. Vol. VII, p. 350.

v. Recklinghausen, Die Lymphgefässe und ihre Beziehung zum Bindegewebe. 1862.

Remak, R., Ueber blutlehre Gefässe (Lymphgefässe) im Schwanze der Froschlarve. Arch. f. Anat. u. Physiol. 1849, p. 102.

Robinson, C., Ueber die Lymphgefässe der Abdominaleingeweide der Frösche, sowie deren Lymphbehälter. Froriep's Notizen, 1846. No. 807, col. 225.

Rusconi, M., Lettre du docteur Rusconi à M. Breschet sur le système lymphatique de la Salamandra commune. Arch. f. Anat. u. Physiol. 1840, p. 8.

Rusconi, M., Ueber die Lymphgefässe der Amphibien. Arch. f. Anat. u. Physiol. 1843, p. 241.

Busconi, M., Einige historische Notizen die Lymphgefässe der Amphibien betreffend. Arch. f. Anat. u. Physiol. 1843, p. 244.

Busconi, M., Sur les vaisseaux lymphatiques. Annales des Sci. nat. Series II. Zool. 1841. Vol. XV, p. 249.

Busconi, M., Riflessioni sopra il sistema linfatico dei Rettili. Pavia, 1845.

Scherkey, M. L., Ueber die Feststellung und Bedeutung der Centren der Lymphherzen im Rückenmark. Dissert. Berlin, 1878.

Scherkey, M. L., Zur Lehre der Innervation der Lymphherzen. Arch. f. Anat. u. Physiol. 1879, p. 227.

Schweigger-Seidel, F., and Dogiel, J., Ueber die Peritonealhöhle bei Fröschen und ihren Zusammenhang mit dem Lymphgefässsysteme. Arbeiten aus d. physiol. Anstalt. Leipzig, 1867, pp. 68–76; Abstract in Centralbl. f. d. med. Wiss. 1867, p. 287.

Suslowa, N., Beiträge zur Physiologie der Lymphherzen. Centralbl. f. d. med. Wiss. 1867, p. 832.

Suslowa, Beiträge zur Physiol. der Lymphherzen. Dissert. Zürich, 1867; also in Zeitsch. f. rat. Med. 3rd series. 1868. Vol. XXXI, p. 224.

Waldeyer, W., Anatomische und physiologische Untersuchungen über die Lymphherzen der Frösche. Zeitsch. f. rat. Med. 3rd series. 1864. Vol. XXI, pp. 103–124; Abstract in Centralbl. f. d. med. Wiss. 1864, p. 73.

Waldeyer, W., Zur Anatomie und Physiologie der Lymphherzen von Rana und Emys europea. Studien des physiol. Instituts zu Breslau. 1865, pp. 71–96; Abstract in Centralbl. f. d. med. Wiss. 1865, p. 321.

Weber, E. H., Ueber die Lymphherzen der Amphibien von Panizza. Arch. f. Anat. u. Physiol. 1834, pp. 300–304.

Weber, J., Beiträge zur Anatomie und Physiologie. Bonn, 1832.

THE BLOOD AND LYMPH.

Aly, W., Ueber die Vermehrung der rothen Blutkörperchen bei Amphibien. Dissert. Halle, 1884.

Arndt, R., Beobachtungen an roten Blutkörperchen der Wirbelthiere. Virchow's Arch. Vol. LXXVIII, p. 1.

Beale, L. S., Observations upon the nature of the red blood-corpuscle. Quart. Journ. Micros. Sci. 1864, pp. 32–43.

Bissozero, G., Ueber die Teilung der roten Blutkörperchen. Centralbl. f. d. med. Wiss. 1881, p. 129.

Bissozero, G., Ueber die Teilung der roten Blutkörperchen. Centralbl. f. d. med. Wiss. 1882, p. 577.

Bissozero, G., and Torre, A. A., Ueber die Entstehung der roten Blutkörperchen bei den verschiedenen Wirbelthierklassen. Virchow's Arch. 1884. Vol. XCV, pp. 1–25.

Brücke, E., Ueber den Bau der rothen Blutkörperchen. Wiener Sitzungsb. 1867. Vol. LVI, Pt. II, pp. 79–91.

Donders and Moleschott, Holländische Beiträge. 1848, p. 361.

Eberth, C. J., Ueber die Vermehrung der rothen Blutkörperchen nach Untersuchungen von W. Aly. Fortschritte d. Med. 1885. Vol. III, pp. 1–7.

Fuchs, E., Beitrag zur Kenntniss des Froschblutes und der Froschlymphe. Virchow's Arch. 1877. Vol. LXXI, p. 78.

Gaule, J., Beobachtungen der farblosen Elemente des Froschblutes. Arch. f. Anat. u. Physiol. 1880, pp. 375–392.

Gulliver, G., Measurements of the red blood-corpuscles of Batrachians. Proc.
    Zool. Soc. London. 1873, p. 162.

Hewson, W., On the figure and composition of the red Particles of the Blood, com-
    monly called Globules. Phil. Trans. 1773. Vol. LXIII, Pt. I, p. 303.

Home, E., On the changes the blood undergoes in the act of coagulation. Phil.
    Trans. 1818, p. 172.

Kollmann, J., Bau der rothen Blutkörperchen. Zeitschr. f. wiss. Zool. 1874. Vol.
    XXIII, p. 462.

Kusnesoff, F., Ueber blutkörperhaltige Zellen der Milz. Wiener Sitzungsb. 1873.
    Vol. LXVII, Pt. III, pp. 58-67.

Moriggia, A., Ueber den Durchtritt der farblosen Blutkörperchen durch die Blut-
    gefässwandungen, etc. Moleschott's Untersuchungen. 1876. Vol. XI, p. 470.

Neumann, E., Zur Histologie der rothen Blutkörperchen. Centralbl. f. d. med.
    Wiss. 1865, p. 481.

Owsjannikow, P., Zur Histologie der Blutkörperchen. Bullet. de l'acad. science
    de Pétersbourg. 1865. Vol. VIII, pp. 561-572.

Peremeschko, Ueber die Theilung der rothen Blutkörperchen bei Amphibien.
    Centralbl. f. d. med. Wiss. 1879, pp. 673-675.

Ranvier, L., Traité technique d'histologie, pp. 148-224.

Rollett, A., Versuche und Beobachtungen am Blute. Wiener Sitzungsb. Vol.
    XLVI, Pt. II, pp. 65-98.

Stricker, Beobachtungen über die Entstehung des Zellkernes. Wiener Sitzungsb.
    1878. Vol. LXXVI, Pt. III, p. 7.

Thoma, R., Die Ueberwanderung farbloser Blutkörperchen von dem Blut in das
    Lymphgefässsystem. Heidelberg, 1873.

Welcker, H., Grösse, Zahl, Volum, Oberfläche und Farbe der Blutkörperchen bei
    Menschen und Thieren. Henle u. Pfeuffer's Zeitschr. 1864. Vol. XX,
    pp. 258-307.

PART 1.

THE HEART AND BLOOD-VESSELS.

I. THE HEART.

(The original arrangement of this section has been modified.)

THE heart is situated in the middle line above the central portion of the shoulder-girdle and *M. sternohyoideus,* and below the oesophagus; the apex is directed backwards and lies between the lobes of the liver, the base is directed forwards and lies a short distance behind the larynx. The heart is surrounded by the pericardium.

A. The **Pericardium** [is a very thin membranous sac, which completely encloses the heart; it is attached, at some distance, to the large vessels passing to and from the heart, and has inserted into it some fibres of the *M. obliquus abdominis internus* (see page 70). A fold of the pericardium extends from the dorsal surface to the truncus arteriosus, and through it courses the vena cardiaca.

The pericardium is a connective-tissue membrane, and is lined on either side with endothelium, which is in part ciliated (Leydig); the endothelium of the inner surface is continued on to the heart

Fig. 132.

The heart and blood-vessels, seen from the ventral surface; after Howes.

AC.	Left anterior caval vein.
C'.	Carotid arch.
LA.	Left auricle.
P'.	Right pulmo-cutaneous arch.
RA.	Right auricle.
S'.	Left systemic arch.
TA.	Truncus arteriosus.
V.	Ventricle.

and so forms a closed lymph-sac. The pericardium is more or less pigmented, and contains both vessels and nerves; it may contain fat-cells].

B. The Heart.

[The heart is a hollow muscular organ, composed of : (1) two auricles, forming the wider anterior portion ; (2) the ventricle, placed behind the auricles ; (3) the sinus venosus, situated dorsally; and (4) the truncus arteriosus, lying ventrally. Examined while still living, the auricles are seen to be much darker in colour than the ventricle, due to the blood being seen through their thinner walls; between the auricles and the ventricle is a distinct groove, the auriculo-ventricular groove. The whole organ is more or less pigmented, especially the ventricle (*R. temporaria* has much less pigment).]

Fig. 133.

The heart, seen from above, and dissected to show the opening from the Sinus venosus to the right auricle ; after Howes.

C'.	Right carotid arch.
IC.	Posterior caval vein.
LA.	Left auricle.
P'.	Right pulmo-cutaneous arch.
PV.	Pulmonary vein.
RA.	Right auricle.
S'.	Right systemic arch.
SV.	Sinus venosus.
SV'.	Opening of Sinus venosus into the right auricle.
V.	Right anterior caval vein.

a. The **Sinus venosus** (*Sinus venarum cavarum*), (Fig. 133 *SV*.) is a thin-walled sac lying on the dorsal surface of the heart, and very slightly to the right side (Hoffmann). It is somewhat triangular in form, receiving an anterior caval vein at each anterior angle (*V*.), and the posterior caval vein (*IC*.) at the posterior angle. The ventral wall has a transverse opening (*SV'*.), by which it communicates with the right auricle ; the opening possesses two valves, an anterior and a posterior, and is placed close to the auricular septum.

b. The **auricles** [are not always separated, as the septum which usually brings about the separation is in some cases incomplete, and in rare instances appears to be absent (Hoffmann)]; according to Ecker, the auricular septum is sometimes placed so far to the left side that it

appears to be absent (Fig. 135). The septum is attached to the walls of the auricles so as to form two distinct cavities, which communicate at the auriculo-ventricular opening, where the septum has a free concave border (Fig. 134). The right auricle is much larger than the left, and receives the systemic venous blood from the sinus venosus by the opening (Figs. 133 and 134 *SV.*) already described. The left auricle receives the blood from the lungs by the pulmonary vein (Fig. 133 *PV.*), which opens into the auricle near the septum (Fig. 134 *PV.*): [the openings from the sinus venosus and from the pulmonary vein may be so closely approximated as to be separated by the septum only. The septum is much thinner than the auricular walls]. Both auricles open into the ventricle by the auriculo-ventricular opening (Fig. 134).

Fig. 134.

The frog's heart seen from the ventral surface, and dissected so as to show its structure. The ventral walls of the truncus arteriosus and of the auricles and ventricle have been removed. From a drawing by Mr. Hurst.

A. Auriculo-ventricular aperture and valve.
B. Aperture leading from ventricle to truncus arteriosus.
C. Left carotid arch.
LA. Left auricle.
P. Left pulmo-cutaneous arch.
P'. Style passed down right pulmo-cutaneous arch into the truncus arteriosus, *T.*
PV. Opening of pulmonary vein.
RA. Right auricle.
S. Left systemic arch.
SA. Septum atriorum.
SV. Opening of Sinus venosus into right auricle.
V. Ventricle.

c. The **ventricle** (Figs. 132, 134, and 136 *V.*), examined while still living, is seen to be bluntly conical in shape and darker on the left side than on the right; this is due to the ventricular wall of the right side, near the truncus arteriosus, being somewhat thinner. The inner wall is not smooth but possesses muscular ridges (*Trabeculae*). At its base the ventricle communicates with the auricles by the auriculo-ventricular opening (Figs. 134 and 136), and with the truncus arteriosus by a separate opening (Fig. 134 *A.*). The ventricle is lined by a layer of endocardial endothelium.

Fig. 135.

Dissection of a case in which the auricular septum is placed more to the left than is normal.

S Septum.
SS Left auricle.
V Opening into the Sinus venosus.

The **auriculo-ventricular opening** (Fig. 134 *A.*) is a large aperture guarded by two valves, a dorsal and a ventral : each valve is formed by a reduplication of the endothelium, and contains a small amount of connective-tissue ; its free margin is bound down by a number (about twelve) of fibrous cords, the *chordae tendineae,* which are attached by their posterior extremities to the trabeculae.

Fig. 136.

Dissection of the heart from the left side ; after Howes.

A.	Auriculo-ventricular opening.
AC,	Anterior caval veins.
IC.	Posterior caval vein.
LA.	Left auricle.
PV.	Pulmonary vein.
RA.	Right auricle.
SV.	Sinus venosus.
TA.	Truncus arteriosus.
V.	Ventricle.

d. The **truncus arteriosus** (Figs. 132 *TA.,* 134 *A.*) arises at the base of the ventricle, on the right side of its ventral surface, then passes forwards and to the left, across the auricles, to reach their anterior border near the median line, where it divides to form two vessels.

Internally it is incompletely divided into two compartments by a spiral valve (Fig. 134) ; the valve is attached to the dorsal surface and is free ventrally : when the vessel is fully dilated (artificially), the valve extends two-thirds of its diameter. The opening of the vessel into the ventricle is guarded by two semilunar valves (Fig. 134 *A.*), the free margins of which are bound to the inner surface of the tube by *chordae tendineae.* The distal extremity has a semilunar valve in the left compartment (Fig. 134), which is attached by a delicate band to the spiral valve (Ecker).

C. The minute structure of the Heart.

[The heart consists chiefly of muscle, but possesses also nerve-fibres, nerve-cells, endothelium, and connective-tissue ; the truncus arteriosus has in addition, blood-vessels.

a. The **muscular structure** of the heart.

(1) The **arrangement** of the **muscle-fibres** varies in the different portions of the heart. That of the ventricle will be easily understood

by reference to Fig. 137. A layer of circular fibres (*CM*) extends round the whole ventricle, and from it more or less radial or trans-

Fig. 137.

I. Transverse section through the junction of the hinder and middle thirds of the ventricle of *R. temporaria.* II. Transverse section through junction of middle and anterior thirds of the same heart. Occ. I, Syst. 1, Leitz. The heart was freely distended [1] with dilute spirit, and so hardened.—G. H.

CC	Central cavity.
CM	Circular muscle.
LM	Longitudinal muscle.
TM	Transverse muscle.

verse bands (*TM*, also Fig. 138 *TM*) pass inwards; these, in the apical portion of the ventricle, seem to extend almost transversely across; towards the base they are directed onwards and forwards towards the auricles. Of these bands some, near the apex, can be traced directly to the opposite side, others join the wall more anteriorly, and still others join bands of muscular fibres (*LM*), which may be described as longitudinal, and form the *Musculi papillares.* In the anterior portion of the ventricle the same arrangement holds good, but is modified to form a central cavity; still more anteriorly, at the junction of auricles and ventricle, the trabecular structure is much less apparent, the fibres being closer and mainly circular.

In the auricles the muscular fibres are chiefly arranged in circular rings which cross one another; on the inner surface, however, traces of an arrangement similar to that in the ventricle may be . made out. In the heart, from which the sections in Fig. 137

---

[1] The base of the ventricle measured, when distended, 8 mm. by 5 mm.

were drawn, transverse bands (cut longitudinally), 0·33 mm. in length, were numerous; their central ends terminated in bands, the fibres of which were cut transversely. The auricular septum (Fig. 141 a *M*) also possesses muscular fibres which cross one another in its substance.

The fibres of the truncus arteriosus resemble those of an ordinary artery; those of the sinus venosus are arranged in rings, mostly transverse, but others oblique, and a few longitudinal.]

(2) The **structure** of the **cardiac muscle-fibres** (Figs. 138 and 141 a).

[The cardiac muscle of the frog consists of spindle-shaped cells, which as Pohl-Pincus pointed out, are of two kinds; the main difference between the two being in the size of the nucleus, which is much broader in one than in the other.

Fig. 138.

Portion of a transverse section through the middle of the ventricle of *R. temporaria*. From same heart as the sections in Fig. 136. Oc. I, Syst. 7, Leitz.—G. H.

A	Rod-shaped nuclei of muscle fibre.
B	Oval nuclei of muscle fibre.
CM	Circular layer of muscle.
CT	Connective-tissue.
E	Endothelium of the epicardium.
TM	Transverse bands of muscle.

α. Cells with a broad nucleus (Fig. 138 *B*): the nucleus is lenticular or egg-shaped, 4 to 7 μ broad, 8 to 14 or 18 μ long; the ratio of length to breadth being 1 : 2.

β. Cells with a narrow nucleus (Fig. 138 *A*): the nucleus is

rod-shaped, 2·5 to 3·5 μ broad and 25 to 43 μ in length. The ratio of length to breadth varying from 1 : 8 to 1 : 16. These cells are more frequent in the right half of the base of the ventricle than the former variety. In the trabeculae the second variety is more numerous (Pohl-Pincus).

The muscle-fibre may be simple (Fig. 141 a *M*) or possess branches (Fig. 138); the fibres are all more or less spindle-shaped, and striated transversely and longitudinally, but possess no sarcolemma. The protoplasmic contents of the cell are finely granular; the nucleus much more coarsely granular and possessing one or more distinctly marked nucleoli. The striations are due to the presence of a network, which has been carefully described by Messrs. B. Melland and C. F. Marshall[1], and is similar to that of ordinary voluntary muscle (see histology of muscle).]

b. The **nerves** of the **heart.**

The nervous supply of the heart is derived from the sympathetic system and from the cardiac branches of the pneumogastric nerve ; the course of which has already been traced (page 175) to the roots of the anterior caval veins, where they form a simple plexus by means of a connecting link (Fig. 139). The plexus possesses nerve-cells and sends off two nerves into the auricular septum ; the one (*d*) lies dorsally and is shorter and thicker than the other (*v*), which lies ventrally in the septum. They course backwards to the posterior border of the septum, and there distribute fine branches to the base of the ventricle and surrounding parts.

[In the whole of their course in the heart they have numerous nerve-cells, either imbedded between their fibres or attached to the nerves and their branches.

The nerve-fibres are both medullated and non-medullated. The nerve-cells (Figs. 139, 140, 141)

Fig. 139.

Course of the cardiac nerves in the auricular septum.

d Dorsal nerve.
v Ventral nerve.

---

[1] I have had opportunity of examining Mr. Marshall's slides and have convinced myself of the correctness of his observations.

are usually oval, and are unipolar or rarely bipolar; sometimes two cells exist in the same envelope, forming the 'twin-cells' of

Fig. 140.

Group of nerve-cells on the cardiac nerve, from the auricular septum. Stained with picrocar-mine. Occ. III, Syst. 3, Hartnack; after Dogiel.

F Fibres of the cardiac nerve.
G Nerve-cells.

Dogiel (Fig. 141 b II). According to the recent observations of Lavdowsky and Dogiel each cell receives one medullated fibre and gives off a fine non-medul-lated fibre; the two run together for a short distance, after which the non-medullated fibre sepa-rates to supply muscle-fibres.

Two large clusters of nerve-cells have received special names.

Remak's ganglion is a large group of nerve-cells in the wall of the sinus venosus.

Bidder's ganglion is formed, collectively, by groups of cells in the auriculo-ventricular groove, the chief groups being attached to the two cardiac nerves.

No nerve-cells have been dis-covered behind that portion of the ventricle near the auriculo-ventricular groove, nor has a direct connection between the cells or their processes with the fibres of the pneumogastric nerve been made out.

Nerve-fibres have been described as existing in all parts of the ventricle and being connected with the muscle-fibres (Openchowsky and others); this cannot, as yet, be accepted as proved.

The truncus arteriosus also possesses nerve-fibres and nerve-cells (Pagliani, Löwit, and others), but their arrangement seems to be very irregular. Löwit did not succeed in finding the nerve-cells in all cases examined; and Engelmann denies their occurrence.]

c and d. [The **endothelium** and **connective-tissue** of the heart.

The connective-tissue of the heart exists only in very small quantity. A fine layer on the outer surface of the ventricle, especially towards the auriculo-ventricular groove, can easily be seen (Fig. 138 CT); the various valves, the auricular septum, and more particularly the truncus arteriosus, all contain connective-

tissue. In the latter part the spiral valve is wholly formed of this tissue. www.libtool.com.cn

Fig. 141 a.

Small group of nerve-cells from the auricular septum. Stained with picrocarmine and silver nitrate, after Dogiel.

E	Endothelium (endocardium).
G	Nerve-cells.
M	Muscle-fibres.
N	Nucleus.
N'	Nucleolus.

The whole of the inner surface is lined with endothelium

Fig. 141 b.

Isolated nerve-cells from frog's heart. I. Usual form of nerve-cell. II. 'Twin-cell.'

C	Capsule.
N	Nucleus.
N'	Nucleolus.
P	Process.

Fig. 142.

Arteries and veins of the Truncus arteriosus of Bufo vulgaris, after Hyrtl.

a   Arteria bulbi.
b   Truncus arteriosus.
h, i Hepatic portal veins.
t   Right and left synangium.
v   Vena bulbi anterior.
vi   Left innominate vein.
vc   Vena bulbi posterior (V. cardiaca).
A   Right auricle.
A'   Left auricle.
V   Ventricle.

(endocardium), which covers the various trabeculae ; the external surface of the heart is likewise covered with an epicardial layer of endothelium (Fig. 138 E).]

e. The blood-supply to the heart.

With the exception of the *truncus arteriosus*, no part of the heart possesses blood-vessels (Hyrtl). [The *truncus arteriosus* (Fig. 142 *b*) has a rich anastomosis, which receives its blood by the *arteria bulbi* (*a*), a branch of the carotid arch. Two veins connect this anastomosis with the systemic veins, and with the hepatic portal veins : the former, *vena bulbi anterior* (*v*), passes over the auricles to open into the left innominate vein (*vi*) ; the latter, the *vena bulbi posterior* (*vc*) or *vena cardiaca*, as it is more usually named, passes from the *truncus arteriosus* in a fold of pericardium, and then courses backwards to open into the anterior-abdominal vein.]

II. THE ARTERIES.

(The original arrangement of this section has been modified.)

The *Truncus arteriosus* divides to form two vessels (Figs. 132, 134) ; each of these is divided by two partitions into three compartments, which after a short course together separate to form three distinct vessels, the carotid, systemic, and pulmo-cutaneous arches.

1. The **carotid arch** (*Canalis carotico-lingualis*, Brücke ; *Ductus caroticus*), (Fig. 143 *I*) is the most anterior of the three arches : it winds round the side of the oesophagus as far as the carotid gland, where it divides to form two branches ; the right carotid arch gives off a small branch to the *Truncus arteriosus*, the *Arteria bulbi* (see above).

The **carotid gland** (Fig. 144 c') is a dilated portion of the vessel. The interior contains bands or trabeculae of muscle, which give its

Fig. 143.

Schema of the arterial system of *Rana esculenta*.

A	Dorsal aorta.	*ov*	Occipito-vertebral artery.
c	Cutaneous artery.	*P*	Pulmonary artery.
ca	Carotid artery.	*s*	Subclavian artery.
d	Carotid gland.	*T*	Truncus arteriosus.
ic	Iliac arteries.	*ug*	Urinogenital arteries
ie	External iliac artery.	*v*	Vertebral artery.
ii	Internal iliac artery.	*I*	Carotid arch.
J	Mesenteric artery.	*II*	Systemic arch.
l	Lingual artery.	*III*	Pulmo-cutaneus arch.
o	Occipital artery.		

walls a more or less spongy structure; the muscle-fibres are not transversely striated (Hoffmann).

a. The **lingual artery** (*Arteria lingualis, Arteria hyoidea-lingualis, Arteria hyoidea*), (Figs. 143 *l*, 144 *L*) arises by two roots from the inner surface of the carotid gland, and courses forwards and inwards, supplying branches to the thyroid gland and the *Musculi geniohyoidei*, to the ventral surface of the hyoid; another continues forwards on the outer border of the *M. hyoglossus* to supply branches to the hyoid and tongue.

b. The **carotid artery** (*Arteria carotis communis*), (Figs. 143 *ca*, 144 *c''*) arises by several roots from the outer wall of the carotid gland; and passes over the *Musculus petrohyoideus* I to the anterior end of the oesophagus, round which it courses towards the vertebral column, and then runs forwards to the base of the skull. The artery then courses forwards, lying immediately above the mucous membrane and underneath the transverse arm of the parasphenoid, which it crosses about midway between its back and external end; [at this point the artery gives off two palatine arteries, then ascends in the orbit to the origin of the *M. pterygoideus*, and divides into two branches, the internal carotid artery and the ophthalmic artery]. The branches are :—

Fig. 144.

Right carotid gland.

c   Carotid arch.
c' Carotid gland.
c'' Carotid artery.
L Lingual artery.

(1) The pharyngeal artery (*Arteria pharyngea ascendens*), (Fig. 145 *p*) which runs towards the opening of the Eustachian tube, distributes branches to the pharynx, and anastomoses with the *Arteria pharyngeo-maxillaris* of the cutaneous artery, and with the *Ramus inframaxillaris* of the occipital artery.

(2) [The posterior palatine artery (*Arteria palatina posterior*, Virchow) immediately divides into a number of small twigs to supply the mucous membrane of the hinder and outer parts of the gums.]

(3) The anterior palatine artery (*Arteria palatina anterior*, Virchow; *Arteria palatina*, Ecker), (Fig. 145 *p'*) runs forwards, between the *Musc. levator bulbi* and the mucous membrane, with the *Ramus palatinus* of the trigeminal nerve. [On reaching the palatine bone, it curves outwards to the outer anterior angle of the orbit, where it gives off a branch backwards along the upper jaw to the hinder portion of the orbit.] In its course it supplies twigs

to the surrounding tissues, but chiefly to the mucous membrane and Harder's gland.

Fig. 145.

Arterial system of *Rana esculenta*.

A	Dorsal aorta.	*m*	Mesenteric artery.
Ad	Right systemic arch.	*M*	Stomach.
As	Left systemic arch.	*M'*	Spleen.
c (opposite fore-limb) Carotid artery.		*o*	Ophthalmic artery.
c (in abdomen) Coeliac artery.		*p*	Pharyngeal artery.
cm	Cutaneous artery.	*p'*	Anterior palatine artery.
e	Lingual artery.	*S*	Subclavian artery.
H	Heart.	*I*	Carotid arch.
H'	Harderian gland.	*II*	Systemic arch.
L	Liver.	*III*	Pulmo-cutaneous arch.
Lu	Lung.		

(4) The internal carotid artery (*Art. cerebralis*, Virchow); see Arteries of Brain, p. 162.

(5) The ophthalmic artery (*Art. ophthalmica*), (Fig. 145 *o*) [is larger than the internal carotid artery at this point; it crosses the origins of the *M. rectus externus* and of the *M. retrahens bulbi* and reaches the optic nerve; the artery then runs forwards along the under surface of this nerve and of the eyeball, lying close to the sclerotic coat as far as a little beyond the equator, where it pierces the sclerotic coat so obliquely that the choroid coat is only

Q

reached at the ciliary processes. In its course the artery supplies :—

a. Muscular branches, given off at the point where the artery reaches the eyeball.

β. Two arteries (*AA. ciliares*) to the choroid, given off at the same point as the foregoing.

γ. Two arteries to the iris.

δ. The *Art. hyaloidea*, the terminal portion of the ophthalmic artery. (For further description of these vessels, see Eye.)].

2. The **systemic arch** (*Ductus aorticus*), (Figs. 132, 143, and 145 *II*) is the middle arch of the three; it arises from the middle canal of the *Ductus arteriosus*, and winds obliquely round the oesophagus between the *MM. petrohyoidei I* and *II* towards the vertebral column, which it reaches at about the level of the sixth vertebra. The right systemic arch is continued as the dorsal aorta, the left arch communicates with it merely by a small opening, and is then continued as the coeliaco-mesenteric artery.

Branches of the systemic arch :—

a. The **laryngeal artery** (*Arteria laryngea*), (Fig. 146 *lg*) arises from the inner border of the systemic arch before it reaches the oesophagus; it passes forwards and inwards to be distributed in the larynx and pharynx. According to Brücke this artery possesses a valve at its point of origin.

Fig. 146.

Transverse section at level of the larynx.

C Carotid gland.
G Glottis.
lg Laryngeal artery.
S Subclavian artery.
I Carotid arch.
II Aortic arch.

b. The **oesophageal arteries** (*Arteriae oesophageae*) pass from the upper part of the arch to the dorsal surface of the oesophagus.

c. The **occipito-vertebral artery** (Ecker), (*Art. occipito-vertebralis*), (Fig. 147 *o, v*) [arises from the systemic arch immediately in front of the transverse process of the second vertebra, and ascends immediately in contact with the body of the first vertebra, which it separates from the *MM. intertransversarii capitis* and the sympathetic cord]. Immediately under the most anterior portion of the *M. longissimus dorsi* the artery divides into two branches, the vertebral and occipital arteries :—

(1) The **vertebral artery** (*Arteria vertebralis* or *supra-vertebralis*

(Fig. 147 v) courses backwards lying on the transverse processes of the vertebrae and on the M.M. intertransversarii, under cover of the M. longissimus dorsi. In this course it is close to the oblique pro-

Fig. 147

Dissection to show the occipito-vertebral and the cutaneous arteries.

The skin of the back has been divided by a median incision and drawn to either side; the right arm dislocated and removed through the opening in the skin (at A). On the left side the extensor muscles of the back have been removed.

c.m.   Cutaneous artery.
c.p.   Arteria cutanea pectoris.
o   Occipital artery.
s   Scapular artery.
v   Vertebral artery.

cesses, and may even be partially covered by these; it extends beyond the sacrum, and gives off:—

a. The *Rami spinales*, which pass through the intervertebral foramina to the spinal cord (see Arteries of Spinal Cord, p. 162).

β. The *Rami dorsales*; these supply the muscles of the back and send branches to the skin, which accompany the cutaneous branches of the spinal nerves through the *Saccus lymphaticus cranio-dorsalis*.

γ. The *Rami intercostales* are distributed in part to the *MM. intertransversarii*; other twigs pass ventrally to the periganglionic glands; the longest branches accompany the anterior divisions of the spinal nerves to the muscles and skin of the belly (Fig. 145).

(2) The **occipital artery** (*Arteria occipitalis*), (Figs. 147 and 148 *o*), the anterior branch of the occipito-vertebral artery, pierces the *M. longissimus dorsi*; then courses forwards under cover of the *Fascia dorsalis* and upon the *M. temporalis*, and divides, behind the eyeball [at the anterior .border of the *M. temporalis*, Virchow], into two branches :—

a. The *Ramus orbito-nasalis* (Fig. 148 *on*) accompanies the ophthalmic nerve along the wall of the cranium, and passes through the sphenethmoid, with the nasal branch of the ophthalmic nerve, to the nose, where it divides into two branches supplying the mucous membrane of the nose. In its course through the orbit the artery supplies branches to the Harderian gland and neighbouring parts, and anastomoses with the ascending branch of the *Arteria palatina*.

β. The *Ramus maxillaris communis* (*Art. temporalis*, Virchow), (Fig. 148 *m*) runs downwards and outwards along the anterior border of the *M. temporalis*, and passes under the anterior arm of the squamosal bone to course backwards on the upper jaw. At this point the *Ramus maxillaris superior* (*m'*) is given off. The main artery continues its backward course to the tympanic membrane, where it divides into its three terminal branches :—

[(1) The *Ramus maxillaris superior* (*AA. maxillares superiores*, Virchow), usually not a single artery but a number of small twigs, which supply the space between the eye and the upper jaw.

(2) A small ascending branch to the tympanic membrane (Virchow).

(3) A *Ramus auricularis* (Virchow), which forms a rich anastomosis on the hinder wall of the tympanic cavity, and supplies a twig to the tympanic membrane. This passes

Fig. 148.

Branches of the occipito-vertebral and cutaneous arteries in the head ; side view. The skin (*H*) has been reflected downwards.

c.m. Cutaneous artery.
l.a. M. levator scapulae.
m Art. maxillaris communis.
m' Art. maxillaris superior.
m'' Art. maxillaris inferior.
o Occipital artery.
on Art. orbito-nasalis.
p.m. Art. pharyngo-maxillaria.
v Vertebral artery.

from the upper border of the membrane to the point of attachment of the *Columella auris* (extrastapedial), round which it forms a circular anastomosis. The *Ramus auricularis* also anastomoses with the cutaneous artery.

Fig. 149.

Dissection to show the occipito-vertebral and the cutaneous arteries.

The skin of the back has been divided by a median incision and drawn to either side ; the right arm dislocated and removed through the opening in the skin (at *A*). On the left side the extensor muscles of the back have been removed.

c.m. Cutaneous artery.
c.p. Arteria cutanea pectoris.
o   Occipital artery.
s   Scapular artery.
v   Vertebral artery.

(4) A branch passing inwards to the fat-body, and lying immediately in front of the deltoid muscle (Virchow).

(5) A small branch running on to the inner surface of the angle of the jaw and then forwards (Virchow).

(6) A larger vessel, the *Ramus maxillaris inferior* (Fig. 148 *m″*), which arises from the *Ramus maxillaris superior* under cover of the tympanic membrane, and accompanies the *Ramus mandibularis* of the trigeminal nerve through the *M. masseter*, or between this muscle and the *M. temporalis* to the mandible, and then courses forwards to the chin. A large cutaneous branch is given off half-way along the floor of the mouth. The artery gives off many small twigs to supply the neighbouring structures.]

3. The **pulmo-cutaneous arch** (*Ductus pulmo-cutaneus*), Figs. 132, 143, and 145 *III*) is the hindmost (fifth embryonic) of the three persistent arches; it passes upwards and forwards on the oesophagus, and at the level of the carotid gland divides into two branches, the pulmonary artery and the cutaneous artery.

a. The **pulmonary artery** (*Arteria pulmonalis*) runs backwards to the root of the lung, along the outer surface of which it is continued in a sinuous course. It supplies the lung.

b. The **cutaneous artery** (*Arteria cutanea magna*), (Fig. 149 *c.m.*) [passes along the deeper surface of the *M. petrohyoideus III* until near the prootic bone; in this course it travels forwards, outwards, and upwards, crosses the outer border of the muscles, and appears between the *M. levator anguli scapulae* and the *M. sternocleidomastoideus*. At this point the artery curves sharply round to reach the angle of the jaw, the hinder border of the *M. depressor maxillae inferioris*. The curve so formed and the descending limb are covered by the *M. depressor maxillae inferioris*. The artery then passes backwards to form a rich anastomosis in the skin almost as far as the posterior end of the trunk. It supplies the following branches :—

(1) The *Ramus dorsalis* (Virchow) arises immediately in front of the curve of the main artery; it ascends behind the *M. temporalis*, and passes along the anterior border of the *M. depressor maxillae* to the skin, where it curves backwards. It supplies small twigs forwards as far as the eyelids.

(2) The *Ramus auricularis* (Virchow) also arises in front of the curve in the cutaneous artery; sometimes it arises from the *Ramus dorsalis*. The artery winds around the *M. petrohyoideus III* near its insertion, and so reaches the posterior wall of the tympanic cavity, where it anastomoses with the *R. auricularis* of the *Ramus maxillaris communis*.]

(3) The *Arteria pharyngo-maxillaris* (Fig. 148 *p.m.*) is a small branch running forwards and outwards to supply the mucous membrane of the larynx, Eustachian tubes, gums, the lower jaw, and

the skin under the mouth. It forms a rich anastomosis with branches of the *Ramus maxillaris inferior* of the occipital artery, and with others from the pharyngeal branch of the carotid artery; a large branch passes forwards to supply the skin of the throat and floor of the mouth.

(4) The *Arteria cutanea pectoris* (Fig. 149 *c.p.*) is distributed to the skin of the breast.

4. The **subclavian artery** (*Arteria subclavia*), (Fig. 150 *s*). The subclavian artery arises from the systemic arch immediately behind the occipito-vertebral artery at the level of the second or third vertebra. The artery then runs outwards alongside and in front of the brachial nerve, between the *M. subscapularis* and the *M. triceps* to the arm, where it is known as the brachial artery; in its course it gives off :—

a. The *Arteria costo-cervicalis* (Fig. 150, 1). This artery arises near the systemic arch, and runs backwards, parallel to the vertebral column, over the brachial nerve, and across the transverse processes of the vertebrae. It is distributed more especially to the *M. obliquus internus.*

b. The *Arteria coraco - clavicularis* (Fig. 150, 2) arises more externally than the last artery; it accompanies the coraco-clavicular nerve on the dorsal surface of the ventral portion of the shoulder-girdle, and passes between the *M. deltoideus* and *M. subscapularis* into the *Foramen ovale,* where it divides to supply these muscles and the *M. pectoralis.*

Fig. 150.

Subclavian artery of the left side.

A	Systemic arch.	*s*	Subclavian artery.
A'	Dorsal aorta.	*U*	Ulnar artery.
c	Arteria cutanea medialis superior.	1	Arteria costo-cervicalis.
c'	Arteria cutanea medialis inferior.	2	Arteria coraco-clavicularis.
ls	M. levator scapulae.	3	Arteria scapularis posterior.
o.v	Occipito-vertebral artery.	4	Arteria scapularis superior.
p	Arteria pectoralis.	5	Cutaneous artery.
R	Radial artery.	6	Arteria subscapularis.

c. The *Art. scapularis posterior* (Fig. 150, 3), a small branch arising opposite at the tip of the second transverse process and passing backwards over the *MM. transverso-scapulares*, to which it is distributed.

d. The *Art. scapularis superior* (Fig. 150, 4) accompanies several nerves between the *M. subscapularis, M. transverso-scapularis major*,

Fig. 151.   Fig. 152.

Arteries of the palmar surface of the hand.

B	Ulnar artery.
ci	R. cutaneus medialis inferior.
d	Digital branches.
F	M. flexor digitorum communis.
II	Thumb.
V	Fifth finger.

Arteries of the dorsal surface of the hand.

B	Ulnar artery.
cri	R. cutan. rad. inferior.
R	Radial artery
II	Thumb.
V	Fifth finger.

and the long head of the *M. triceps* towards the dorsal surface, where it is distributed to the *MM. infraspinatus, latissimus dorsi*, etc.

e. The *Ramus cutaneus maxillaris*.

f. The *Art. subscapularis* (Fig. 150, 6) is distributed in the subscapular muscle.

A. The **brachial artery** (*Arteria brachialis*), (Fig. 150) accompanies the brachial nerve under cover of the long head of the *M. triceps* and over its inner head to the *Plica cubiti*, into which it sinks near the tendon of the *M. sternoradialis*; beyond this point it is continued as the ulnar artery.   In its course the brachial artery gives off :—

a. The *Arteria pectoralis* (Fig. 150 *p*).

· b. The *Arteria cutanea medialis superior* (Fig. 150 *c*).

c. The **radial artery** (*Arteria radialis*), (Fig. 150 *R*) which winds

round the humerus with the radial nerve between the muscles of the outer side of the forearm, to which it gives branches : in the palm of the hand it passes between the *M. extensor carpi ulnaris* and the *M. flexor antibrachii* to the dorsal surface of the hand, where it anastomoses with the ulnar artery.   In its course it supplies :—

(1) Muscular branches to the surrounding muscles.

(2) The *Ram. cut. radialis inferior,* which arises from the radial artery towards the distal end of the forearm, and passes underneath the *M. flexor carpi ulnaris* to the skin.

B. The **ulnar artery** (*Arteria ulnaris*), (Figs. 150 *U,* 151 *B*) accompanies the ulnar nerve towards the hand, passes between the *M. flexor digitorum communis* and the *M. anconeus* to the palm of the hand, and then winds round the outer side to the dorsal surface of the carpus to form its terminal branches.   The branches are :—

(1) The *Ram. cutan. med. inferior* (Fig. 151 *ci*); it arises near the wrist-joint and supplies (*a*) twigs to the skin of the inner surface; (*β*) a branch downwards, which courses along the inner side of the second finger to its tip; and (*γ*) a branch which passes upwards to anastomose with the *R. cutaneus medialis superior.*

(2) In the palm of the hand a branch (Fig. 151 *d*) is given off, which divides to form *Arteriae digitales volares* : one for the second finger, two for the third finger, two for the fourth finger, and one for the fifth finger.

(3) Given off on the dorsum of the hand (Fig. 152) it supplies branches corresponding exactly with those of the palmar surface.

5. The **dorsal aorta** (*Aorta communis s. abdominalis* (Fig. 153 *A*). The two systemic arches unite at about the level of the sixth vertebra to form the dorsal aorta : as already mentioned the union is very incomplete, the dorsal aorta being practically a continuation of the right systemic arch, and only communicating with the left by means of a small opening.   The branches are as follows :—

a. The **coeliaco-mesenteric artery** (*Arteria intestinalis communis*), (Fig. 153), the true continuation of the left systemic arch, at once divides to form the gastric and mesenteric arteries.

(1) The **gastric artery** (*Arteria gastrica s. coeliaca*) (*c*) immediately divides into two branches :—

a. The *Ramus dexter s. anterior ;* this artery gives off the *Arteria hepatica* to the liver and gall-bladder and passes to the right (anterior) surface of the stomach, running along the attachment of the

mesentery and supplying branches forwards to the oesophagus and backwards towards the intestine.

β. The *Ramus sinister s. posterior* passes to the left (posterior) surface and behaves like the *Ram. dexter*.

(2) The **mesenteric artery** (*Arteria mesenterica superior* and *inferior*, and the *Arteria splenica*), (Fig. 153 *m*) supplies :—

α. The superior mesenteric artery, which supplies the upper part of

Fig. 153.

Arterial system of *Rana esculenta*.

A	Dorsal aorta.	*m*	Mesenteric artery.
Ad	Right systemic arch.	*M*	Stomach.
As	Left systemic arch.	*M'*	Spleen.
c opposite fore-limb) Carotid artery.		*o*	Ophthalmic artery.
c (in abdomen) Coeliac artery.		*p*	Pharyngeal artery.
cm	Cutaneous artery.	*p'*	Anterior palatine artery.
e	Lingual artery.	*S*	Subclavian artery.
H	Heart.	*I*	Carotid arch.
H'	Harderian gland.	*II*	Systemic arch.
L	Liver.	*III*	Pulmo-cutaneous arch.
Lu	Lung.		

the intestine, and gives off a recurrent branch to the stomach, which anastomoses with the gastric arteries.

β. The splenic artery to the spleen.

γ. The inferior mesenteric artery to the lower part of the intestine.
All the arteries to the intestine course in lymph-spaces.

b. The **urinogenital arteries** (*Arteriae urino-genitales*), (Fig.
154 *ug*) are four to six small arteries arising from the ventral
surface of the aorta between the kidneys : they immediately divide
into right and left branches to supply the kidneys, fat-bodies,
reproductive organs, and their ducts (see kidney).

c. The **lumbar arteries** (*Arteriae lumbales*), are small paired vessels
to the neighbouring muscles, and send branches through the in-
tervertebral foramina to the vertebral canal. Sometimes these
arteries arise from the *Art. spinalis* or *Art. vertebralis*, etc.; in the
former case they pass outwards from the vertebral canal to the sur-
rounding structures.

d. The **haemorrhoidal artery** (*Art. mesenterica inf. s Art. hae-
morrhoidalis superior*) is a small median artery running from the pos-
terior end of the aorta to the large intestine.

**6. Bifurcation of the aorta. The
iliac arteries** (*Arteriae iliacae commu-
nes*). Opposite the middle of the uro-
style the aorta bifurcates to form the
iliac arteries; each of these courses
on the corresponding sciatic plexus to
the thigh, beyond which it is con-
tinued as the sciatic artery. The
branches of the iliac artery are :—

a. The **vesico-epigastric artery**
(*Arteria epigastrico-vesicalis*), (Fig. 155
ev); it arises near the bifurcation,
passes outwards on the plexus, and
divides into two branches :—

(1) The epigastric artery (*Arteria
epigastrica*) (*e*) immediately gives off
a recurrent branch to the iliac bone
and the *M. ilio-coccygeus*; it then
continues to the ventral muscles of the abdominal wall, where it
runs forwards on the deeper surface of the *M. obliquus internus*, and
is distributed more especially to this muscle.

(2) The hypogastric artery (*Arteria vesicalis*) (*v*) winds downwards
around the sciatic plexus to reach the mesentery, along which it
courses to the bladder, where it forms a rich anastomosis.

Fig. 154.

The urinogenital arteries.

A Dorsal aorta.
H Testis.
N Kidney.
ug Urinogenital arteries.

b. The **femoral artery** (*Arteria femoralis s. cruralis*), (Fig. 155 *f*) is the representative of the femoral artery of man, although it does not perform the same functions. The artery passes under the hinder free border of the *M. obliquus internus* to the thigh, where it lies upon the *M. ilio-psoas*, and sends twigs to the neighbouring muscles, the skin, and lymph-sac (*Lamina inguinalis*), and then divides into :—

(1) A twig, which runs forwards on the ventral surface of the iliac bone and is covered by the epigastric artery.

(2) A twig, running forwards and downwards on the *MM. ilio-psoas, vastus internus*, and *sartorius*, to send branches to the hip-joint.

c. The **spermatic artery** (*Arteria spermatica*), which arises, in males, from the iliac artery, and ascends to the *Vesicula seminalis*.

Fig. 155.

Bifurcation of the aorta and the iliac arteries.

e   Epigastric artery.
cv   Vesico-epigastric artery.
f   Femoral artery.
o   Internal oblique muscle.
v   Vesical artery.

7. Arteries of the hinder extremity.

A. The **sciatic artery** (*Arteria ischiadica*), (Fig. 156 *i*) is the continuation of the iliac artery; it leaves the pelvis between the hinder (outer) border of the *M. coccygeo-iliacus* and the inner surface of the origin of the *M. ilio-psoas*, then lies between the former muscle and the origin of the *M. vastus externus*. It appears on the thigh between the *M. vastus externus* (in front) and the *M. pyriformis* (behind); it is the main arterial trunk for the hinder extremity. The artery courses backwards, lying upon the sciatic nerve and between the *M. biceps* and the *M. semimembranosus*; in this course it runs in a lymph-space placed in the *Septum femorale superius* (see page 259). Arrived at the popliteal space the artery bifurcates to form the peroneal and tibial arteries; near the pelvis it gives off two branches (a) and (b), and in its course along the thigh two branches (c) and (d).

a. The *Art. haemorrhoidalis inferior* (*h*) runs backwards and

inwards under the *M. pyriformis* to be distributed in the *M. sphincter ani* and the skin of the anus.

b. The *Art. cutanea femoris posterior v. superior* (*cf'*) runs with the corresponding nerve and the *M. pyriformis*, and over the *M. semimembranosus* to the skin of the inner and hinder surfaces of the thigh.

c. The *Rami musculares* supply the *M. semimembranosus*, the *M. biceps*, and the *MM. extensores auris*; the branch to the *M. rectus inferior major* pierces the muscle in company with the nerve, and is continued as :—

d. The *Art. cutanea femoris media* (*cf''*) to the skin of the middle of the inner surface of the thigh. Several small twigs pierce the *M. rectus internus minor*, reach the skin, and communicate with this artery.

Fig. 156.

Arteries of the hinder extremity.

cc	Art. cutanea calcanei.
cf	Cutaneous branch of the femoral artery.
cf'	Art. cutanea fem. post. superior.
cf''	Art. cutanea femoris media.
cgl	Art. cut. genu lateralis superior.
cgl'	Art. circumflexa genu lateralis inferior.
cgm	Art. circumflexa genu superior medialis.
cgm'	Art. circumflexa genu inferior medialis.
ci	M. coccygeo-iliacus.
g	M. gastrocnemius.
gl	M. gluteus.
h	Art. haemorrhoidalis inferior.
i	Sciatic artery.
ml.	Art. malleolaris lateralis.
mm	Art. malleolaris medialis.
p	Art. peronea.
p'	Muscular branch to the M. peroneus.
P	M. pyramidalis.
ra	M. rectus anterior.
ri''	M. rectus internus.
sm	M. semimembranosus.
su	Art. suralis.
t	Tibial artery.
to	Aperture in tibio-fibula.
tr	Art. tarsea.
ve	M. vastus externus.

B. The **peroneal artery** (*Art. peronea*), (Fig. 156 *p*) runs out-

wards under cover of the tendon of the *M. biceps femoris*, and accompanies the peroneal nerve downwards to give off :—

a. The *Art. circumflexa genu lateralis superior*, which runs forwards on the outer side of the knee, gives a twig to the joint, and is continued as :—

b. The *Art. cutanea genu lateralis superior* (*cgl*) to the skin of the anterior and outer sides of the knee. It anastomoses with branches of the *Arteriae circumflexae genu mediales* to form a rich anastomosis (*Rete articulare genu*) : other branches pass upwards to inosculate with the *Art. cutanea femoris anterior* (*cf*), and others downwards to anastomose with the next artery.

c. The *Art. circumflexa genu lateralis inferior* (*cgl'*) runs under the tendon of origin of the gastrocnemius to the outer side of the knee, and terminates in the skin as the *Art. cutanea genu lateralis inferior*. Some of the cutaneous twigs pass upwards to anastomose with the *Art. cut. genu lat. superior*, others downwards to anastomose with the *AA. malleolares*.

d. A muscular branch (*p'*) for the *M. peroneus* ; it is the real continuation of the peroneal artery, and runs behind the outer tendon of origin of the gastrocnemius to be distributed in the *M. peroneus*.

C. The **tibial artery** (*Arteria tibialis*), (Fig. 156, *t*), arises at the bifurcation of the sciatic, and runs inwards, meeting the tibial nerve between the tendons of origin of the *M. gastrocnemius*, and deep in the popliteal space under cover of the calf-muscles. It then pierces the *M. tibialis posticus*, and leaves this to perforate the tibio-fibula (see p. 50), appearing again on the anterior surface as the anterior tibial artery. Before meeting the tibial nerve this artery gives off the following branches :—

a. The *Art. circumflexa genu superior medialis* (*cgm*), which winds round to the front of the knee-joint, and gives off a cutaneous branch, the *Art. cutanea genu medialis superior*, which is distributed in the skin of the inner side of the knee and anastomoses above with the *Art. cutanea femoris media*, below with the following branches (**b**, **c**, and **d**).

b. The *Art. circumflexa genu inferior medialis* (*cgm'*) supplies twigs to the knee-joint, and passes to the skin of the knee and inner surface of the calf as the *Art. cutanea inferior medialis*.

c. Muscular twigs to the *M. gastrocnemius*.

d. The *Art. suralis* (*su*); this accompanies the *N. suralis* downwards along the calf-muscle, and is distributed in the skin of the inner side of the heel.

e. While passing between the fibres of the *M. tibialis posticus*, the tibial artery gives off muscular twigs; one larger than the rest is known as the *Ramus descendens*.

D. The **anterior tibial artery** (*Arteria tibialis antica*), (Fig. 157 *t.a.*) is the continuation of the tibial artery after piercing the tibio-fibula. It runs downwards on the anterior surface of the leg, then between the two heads of the *M. tibialis anticus* to the dorsum of the foot, where it is continued as the *Arteria dorsalis pedis*. It supplies :—

a. *Rami musculares* to the *M. peroneus*, *M. extensor cruris*, and to the *M. flexor tarsi anterior.*

b. The *Art. cutanea cruris inferior* (*c.c.i.*) passes between the two heads of the *M. tibialis anticus* to the skin of the anterior and outer sides of the leg.

c. The *Art. cutanea calcanei* (*c.c.*) is given off at the ankle-joint; it runs outwards on the lower end of the

Fig. 157.

Arteries of the dorsal surface of the foot.

c.c.	Art. cutanea calcanei.
c.c.i.	Art. cutanea cruris inferior.
Ft'	M. flexor tarsi.
h	Art. cutanea hallucis.
i₁	Art. interossea dorsalis I.
i₂	Art. interossea dorsalis II.
i₃	Art. interossea dorsalis III.
i₄	Art. interossea dorsalis IV.
ml	Art. malleolaris lateralis.
m.m.	Art. malleolaris medialis.
t.a.	Anterior tibial artery.
ta*	Bifurcation of the dorsalis pedis artery.
tr	Art. tarsea.

tibio-fibula, giving branches to the joint, then backwards between

the tibio-fibula and the *M. peroneus* to be distributed to the skin of the heel. Above it anastomoses with the *A. circumflexa genu inf. lateralis*, and below with the malleolar arteries.

d. The *Art. malleolaris lateralis* (*ml*) arises a little beyond the last artery; it runs outwards under the origin of the *M. flexor tarsi*, gives branches to the joint and muscles, and terminates in the skin of the outer border and dorsal surface of the foot.

e. The *Art. malleolaris medialis* (*m.m.*) arises at about the same level as the *Art. malleolaris lat.* from the inner border of the anterior tibial artery. It supplies branches to the joint, gives numerous branches to the skin, which anastomose with the *Art. suralis*, and passes to the inner border of the foot, where it ends by distributing branches to the *M. plantaris*, the extensor aponeurosis, and, as the *Art. cutanea plantaris*, to the skin of the sole of the foot.

E. The **dorsal artery** of the foot (*Art. dorsalis pedis*), (Fig. 157 *t.a.*) runs under the *M. flexor tarsi posterior* to the point *ta**, where it is superficial; the artery then bifurcates; the branches are :—

Fig. 158.

Arteries of the sole of the foot.

i   Art. interossea.
pf   Rami perforantes.

a. The *Art. tarsea* (*tr*) which arises from the dorsal artery of the foot while under cover of the *M. flexor tarsi posterior*; it passes to the *M. extensor digiti V* and to the skin of the dorsum and outer border of the foot. One branch courses along the outer border of the fifth toe to its tip; another passes upwards to anastomose with the neighbouring vessels.

b. The inner branch, formed by the bifurcation of the dorsal artery of the foot, at once divides to form :—

(1) The *Art. cutanea hallucis* (*h*) to the supplemental great toe.

(2) The *Art. interossea dorsalis I* (*i¹*), which at once bifurcates to form two *Rami digitales* for the first and second toes; these inosculate with the *Art. cutanea plantaris*, and send twigs to the skin of the inner border of the foot.

c. The outer branch formed by the bifurcation of the dorsal artery divides to form the *Arteriae interossei dorsales II, III,* and *IV* (*i²*, *i³*, *i⁴*); they are distributed in a rich anastomosis to the web.

d. The *Arteria interossea* (Fig. 158 *i*) arises from the dorsal artery of the foot at the tarsus, and perforates the membrane between the astragalus and calcaneum to reach the sole of the foot. It forms a rich subcutaneous plexus on the calcar, and anastomoses with the *Rami perforantes* (Fig. 158 *pf*), which pass above the upper borders of the *Musculi interossei* to reach the plantar surface, where they give off small *Rami interossei volares* to anastomose with the *AA. interosseae dorsales*.

III. THE VEINS.

(The arrangement of this section has been modified.)

The blood, distributed to the body by means of the arteries, is returned to the heart by the veins, which conduct the blood directly or indirectly to the auricles. The pulmonary vein opens directly into the left ventricle, the three *Venae cavae* open into the *Sinus venosus*.

A. **Vein opening into the left auricle.**

The **pulmonary vein** (*Vena pulmonalis communis*), (Fig. 159 *vp*). The blood returning from each lung is gathered into a vessel lying along the inner side of the root of the lung. That of the right side is somewhat longer than the left; the two vessels (*Venae pulmonales dextra et sinistra*) run above the corresponding anterior caval veins to form a common trunk, the pulmonary vein, which opens into the left auricle (see p. 215).

B. **Veins opening into the *Sinus venosus*.**

The veins opening into the *Sinus venosus* are the three caval veins; of these the two anterior open into the anterior angles of the *Sinus venosus*, the posterior into the posterior angle.

1. The **Anterior Caval Veins** (*Vena cava superior*), (Figs. 133 *V*, 159 *C a*) are a pair of large veins opening into the *Sinus venosus* and returning to it blood from the fore-limbs and sides of the head. Each vein is formed by the union of a small vein, the external jugular, with two large veins, the innominate and the subclavian veins.

a. The **external jugular vein** (*Vena jugularis externa*), (Fig. 159 *je*) is formed, at the outer border of the hyoid bone, by the union of two veins :—

(1) The lingual vein (*Vena lingualis*) (Fig. 161 *l*). This originates at the tip of the tongue and passes in a very tortuous course along the ventral surface of the hyoid; it receives numerous branches from the tongue and hyoid muscles.

R

(2) The mandibular vein (*Vena maxillaris inferior*), (Fig. 161 *m*) runs along the insertion of the *M. submaxillaris*, and turns inwards at its hinder border to join the lingual vein.

b. The innominate vein (*Vena anonyma*), (Fig. 160 *A*) is formed by the union of the internal jugular and the subscapular veins. By tracing the innominate vein upwards between the suspensorium and the shoulder-girdle, the internal jugular vein will be seen to receive the vertebral vein at the outer border of the *M. levator scapulae*. The left innominate vein receives the *Vena bulbi anterior* from the *Truncus arteriosus* (p. 222).

Fig. 159.

Schema of the veins of *Rana esculenta*.

a	Subclavian vein.
ab	Anterior abdominal vein.
Ad	Right auricle.
As	Left auricle.
Ca	Anterior vena cava.
Cp	Posterior vena cava.
cm	Cutaneous vein.
d	Vena dorso-lumbalis.
D	Intestine.
f	Femoral vein.
i	Sciatic vein.
ic	Vena communicans iliaca.
je	External jugular vein formed by lingual and maxillary veins *l* and *m*.
ji	Internal jugular vein.
L	Hepatic veins.
N	Kidney.
o	Oviducal veins.
P	Hepatic portal vein.
ral	Renal portal vein.
ralI	Secondary renal portal veins.
re	Renal veins.
s	Subscapular vein.
SC	Sinus venosus.
va	Innominate vein.
vc	Vena bulbi posterior (cardiac vein
vp	Pulmonary veins.

(1) The **internal jugular vein** (*Vena jugularis*), (Fig. 160 *J*), can be traced from the border of the *M. levator scapulae* upwards and forwards to the hinder part of the prootic bone : it then passes forwards under the lateral process of the prootic, in a groove on the anterior surface of the same bone, towards the hinder angle of the orbit, where it receives the veins from the cranial cavity (see vessels of brain, p. 165), and also a branch from the orbit.

Fig. 160.

Distribution of the internal jugular vein and the anterior portion of the cutaneous vein.

A	Innominate vein.	*o*	Vena orbitalis posterior.
c.m.	Cutaneous vein.	*P*	Lateral process of the prootic bone.
f	Nasal vein.	*S*	Subscapular vein.
h	Harderian gland.	*S'*	Shoulder-girdle.
H	Skin, reflected downwards.	*T*	Tympanic membrane.
J	Internal jugular vein.	*V*	Vertebral vein.
L	Anterior lymph-heart.	2	Transverse process of the second vertebra.
l	M. levator scapulae.	3	Transverse process of the third vertebra.
O	M. obliquus internus.	4	Transverse process of the fourth vertebra.
o	Vena orbitalis anterior.		

a. [The *Vena orbitalis media* (Virchow); it arises from the anterior internal angle of the orbit, from the Harderian gland, the nasal cavity, or from other veins on the anterior wall of the orbit. The vessel lies close to the cranium, immediately underneath the *Arteria nasalis,* and sinks under the *M. rectus superior* to join the internal jugular vein. It its course it receives the *Vena bulbi superior* (see eye), and near its termination communicates with the *Vena orbitalis posterior.*]

β. The *Vena vertebralis* (Fig. 160 *V*) arises posteriorly and runs forwards over the transverse processes of the vertebrae, the *Musculi intertransversarii*, and the *M. levat. scapulae*, to join the internal jugular vein. In its course it receives branches (*Venae spinales*) from the vertebral canal through the intervertebral foramina, and cutaneous branches which accompany the corresponding arteries and nerves through the dorsal lymphatic sac. The vein pulsates in consequence of its connection with the anterior lymph-heart (Müller).

(2) The **subscapular vein** (*Vena subscapularis*), (Fig. 160 *S*). This vein arises in the transverse abdominal muscles and the muscles of the shoulder girdle; it unites with the internal jugular vein under the shoulder-girdle.

Fig. 161.

The anterior caval vein and its branches.

a	Innominate vein.	*l*	Lingual vein.
c.m.	Cutaneous vein.	*m*	Mandibular vein.
c.x.	Anterior cava vein.	*s*	Brachial vein.
i	Internal jugular vein.	*s.c.*	Subscapular vein.
i'	External jugular vein.		

c. The **subclavian vein** (*Vena subclavia*), (Fig. 159). passes backwards from the anterior caval vein on the dorsal surface of the coracoid bone and the clavicle, and then under cover of the *Portio sternalis* of the *M. pectoralis major*, to the internal border of the *Portio abdominalis* of the *M. pectoralis major*, where it is formed by the union of the cutaneous vein and the brachial vein.

(1) The cutaneous vein (*Vena cutanea magna*, Ecker; *Vena*

musculo-cutanea, Gruby), (Figs. 160, 161, and 162 *c.m.*). This vein arises by small branches in the head ; these are :—

a. The *Vena nasalis* (Virchow); it arises by an upper and a lower branch from around the nostril, and courses backwards along the superior maxillary bone to about the middle of the orbit, where it joins the facial vein.

β. The *Vena orbitalis anterior* (Virchow), (*Vena ophthalmica anterior*, Ecker), (Fig. 160 *o*) commences at the Harderian gland from a rich anastomosis, receives branches from the floor and anterior wall of the orbit, and joins the facial vein with the *Vena nasalis*.

γ. The *Vena orbitalis posterior* (Virchow), (*Vena ophthalmica posterior*, Ecker), (Fig. 160 *o'*) arises on the posterior wall of the

Fig. 162.

Course of the cutaneous vein as seen from the side.

c.m. Cutaneous vein.
d   M. depressor maxillae.
i   M. infraspinatus.

orbit on the *M. pterygoideus* ; it passes under the *Processus zygomaticus* to join the facial vein, and in its course receives the *Vena ophthalmica* (see eye), and communicates with the *Vena orbitalis medialis* and the internal jugular vein.

δ. The *Vena facialis* (Fig. 160) is formed about the middle of the orbit by the union of the *Vena nasalis* and the *Vena orbitalis anterior*; it courses backwards towards the angle of the jaw. On reaching the *M. depressor maxillae*, about 4 mm. in front of the angle of the jaw, it passes on to the skin. It receives in its course the *Venae palpebrales* (Fig. 162) and the *Vena orbitalis posterior*.

The musculo-cutaneous vein is the direct continuation of the *Vena facialis* after this has left the upper jaw; it immediately receives one or more twigs (*Venae tympanicae*), (Fig. 162) from the tympanic membrane and the tympanic cavity.

The vein then courses backwards in the outer wall of the lateral lymph-sac as far as the middle of the trunk, where it passes, by means of the *Septum abdominale*, to the outer border of the *Portio*

abdominalis of the *M. pectoralis*; here the vein curves round to pass forwards between the fibres of this muscle to its inner border where it terminates by joining the brachial vein. In the whole of this lengthy course the vein receives numerous branches from the neighbouring parts.

Fig. 163.

Veins in the region of the kidney.

a   Renal portal vein.
a'   Dorso-lumbar veins.
abd. Anterior abdominal vein.
d   Intestine.
f   Femoral vein.
i   Sciatic vein.
N   Kidney.
o   Right ovary, drawn to the left.
o'   Oviduct.
ov   Oviducal veins.
p   Mesenteric veins.
r   Renal veins.
V   Bladder.
v.c.i. Posterior vena cava.
Vv   Vesical veins.

(2) The **brachial vein** (*Vena brachialis*) is formed in the *Plica cubiti* by the union of two veins.

a. The **radial vein** (*Vena radialis*) arises on the dorsum of the hand from a venous arch, the distal convexity of which receives the *Venae digitales dorsales* : the vein courses superficially along the outer side of the forearm to the elbow.

β. The **ulnar vein** (*Vena ulnaris*) arises from the veins in the palm of the hand, and courses towards the elbow, lying deeply between the muscles of the inner and outer surfaces of the forearm. In the elbow the vein becomes superficial near the tendon of the *M. sterno-cleidoradialis*, and joins the radial vein to form the brachial vein.

The cutaneous veins of the fore-limb follow courses corresponding with those of the arteries.

2. The **Posterior Caval Vein** (*Vena cava inferior*), (Fig. 159 *Cp*, 163 *v.c.i.*).

The posterior caval vein is a median vein which, commencing between the kidneys, runs forwards to open into the posterior end of the *Sinus venosus*. It receives the hepatic, renal, and ovarian or spermatic veins.

a. The hepatic veins (*Venae hepaticae*), (Fig. 164 *v.h.*) are two in number, one from either side of the liver; they open into the posterior caval vein near the *Sinus venosus*.

b. The **renal veins** (*Venae renales* or *Venae revehentes*), (Fig. 163 *r*) are four or five small vessels on each side; they pass from the inner border of the kidney inwards and forwards, to form, by their union, the posterior caval vein. The most anterior receive branches from the fat-bodies (see kidney).

c. The **spermatic** or **ovarian veins** are four or five in number on each side; they open into the posterior caval vein between the renal veins.

3. The **Portal Systems.**

[There are, in the frog, two portal systems; the renal and the hepatic. Each of these receives vessels which are derived, directly or indirectly, from the veins of the hinder extremity.

The femoral vein on entering the pelvis divides to form two branches; an iliac vein placed dorsally, and a pelvic vein placed ventrally; the two pelvic veins converge to the middle line of ventral wall of the abdomen, where they unite to form the anterior abdominal vein.]

a. The **renal portal vein** (*Vena renalis advehens princeps*), (Fig. 163 *a*). This vein is formed by the union of the sciatic and the iliac veins; it courses forwards to the outer border of the kidney, and is distributed, by numerous branches, to that organ, chiefly on its dorsal surface. It receives the following veins :—

(1) The **iliac vein** (*Vena iliaca externa*); this is the dorsal branch formed by the bifurcation of the femoral vein.

(2) The **sciatic vein** (*Vena ischiadica*), (Figs. 163 and 165 *i*) arises at the popliteal space, courses upwards in company with the sciatic nerve between the *M. semitendinosus* and the *M. biceps*, then passes, still with the nerve, between the *M. vastus externus* and the *M. pyramidalis* into the pelvis. It continues forwards to join the iliac vein. At the root of the thigh this vein communicates with the femoral vein by the *Ramus communicans iliacus*.

(3) The **dorso-lumbar vein** (*Vena dorso-lumbalis*), (Fig. 163 *a'*) is a vein (or more usually several) arising by twigs in the dorsal and outer walls of the abdomen ; it joins the renal portal vein opposite the kidney.

(4) The **oviducal veins** (Fig. 163 *ov*) are irregular veins from the oviducts, which open either into the dorso-lumbar vein, or into the renal portal vein.

b. The **hepatic portal system**.

The liver receives blood from two sources : (1) from the hind-limbs by means of the anterior abdominal vein, and (2) from the alimentary canal by the hepatic portal vein.

The **anterior abdominal vein** (*Vena abdominalis*), (Figs. 159 *ab*, 164 *Va*) is formed, a little in front of the symphysis pubis, by the union of the two pelvic veins. It courses forwards along the middle line of the ventral body-wall until opposite the liver, where it ascends and divides into three branches, of which two enter the right and left lobes of the liver respectivey1. The third, the *Ramus descendens*, joins the hepatic portal vein. The anterior abdominal vein receives the following veins :—

Fig. 164.

Veins of the liver.

A A	Auricles.	*P*	Hepatic portal vein.
aa	Right and left branches of	*P'*	Intestinal veins.
	anterior abdominal vein.	*P''*	Gastric veins.
b	Ramus descendens.	*S*	Sinus venosus.
c	Vena bulbi (Vena cardiaca).	*V*	Ventricle.
D	Intestine.	*Va*	Anterior abdominal
G	Gall-bladder.		vein.
L.l.	Left lobe of liver.	*V.c.i.*	Posterior vena cava.
L.r.	Right lobe of liver.	*v.h.*	Hepatic veins.

a. The **vesical vein** (*Vena vesicalis*), (Fig. 163 *Vv*) ; a median vein arising in the groove between the lobes of the bladder from lateral branches, which extend outwards on the bladder. This vein

communicates above with other vesical twigs which open into the haemorrhoidal vein.

β. Parietal veins, which join the anterior abdominal vein in its course along the ventral body-wall.

γ. A cardiac vein (*Vena cardiaca*), (Figs. 142, 159 *vc*, 164 *c*), which joins the anterior abdominal vein just before its division (see p. 222).

The **hepatic portal vein** (*Vena portarum*), (Figs. 159, 164 *P*) is formed by the union of the gastric, intestinal, splenic, and one of the haemorrhoidal veins. The large vein so constituted passes forwards towards the liver, receives the *Ramus descendens* from the anterior abdominal vein, and then passes into the left lobe of the liver. Its branches are the following :—

(1) The **gastric veins.** The stomach has three veins :—

a. [The *Vena coronaria ventriculi,* which receives blood from the hinder end of the oesophagus and anterior portion of the stomach.

β and *γ.* Two other veins which form an *Arcus coronarius* on the concave surface of the stomach; the hinder receiving in addition the small *Venae pancreaticae* and the *Vena duodenalis*; the trunk so formed receives the *Vena coronaria ventriculi* (Hoffmann).

(2) The **intestinal veins**; the veins of that portion of the alimentary canal between the middle of the duodenum and the anterior end of the large intestine open into a common vein which joins the hepatic portal vein.

(3) The **splenic vein** joins either the hepatic portal vein or one of the intestinal veins.

(4) The **haemorrhoidal veins** are three in number; the anterior opens into the splenic vein, the remaining two into the portal veins through the agency of the intestinal veins.]

4. The Veins of the Hinder Extremity.

The hinder extremity has two venous trunks, the sciatic vein and the femoral vein.

a. The **femoral vein** (*Vena femoralis*), (Fig. 165 *f*) is the larger venous trunk of the hinder extremity. It arises in the popliteal space as a direct continuation of the posterior tibial vein, courses upwards in company with the sciatic artery and nerve, then leaves these to wind forwards and outwards, and appears between the origins of the *M. vastus externus* and of the *M. rectus anterior.*

The vein here gives off the *Ramus communicans iliacus* to the sciatic vein, and turns forwards and downwards around the *M. glutaeus maximus* to reach the floor of the pelvis, near the femoral artery. The vein then bifurcates to form the pelvic and iliac veins.

Fig. 165.

(1) The *Ramus communicans iliacus* (Fig. 165 *c.i.*) forms a communication with the sciatic at the base of the thigh.

(2) The posterior tibial vein (*Vena tibialis postica*), of which the femoral is a continuation, arises on the dorsal surface of the toes and foot. It runs superficially on the *M. extensor longus digiti primi* over the ankle-joint, courses upwards and winds round the outer surface of the tibio-fibula to the flexor surface. It receives, in its course, muscular branches, and at the knee a large cutaneous branch.

b. The **sciatic vein**: this vein has already been described (see p. 247), but the vein from which it arises requires description.

Veins of the hinder extremity, half schematic.

c.i. Vena communicans iliaca.
f Femoral vein.
i Sciatic vein.
f' Vena cutanea cruris medialis.
r.a. M. rectus anterior.
s.m. M. semimembranosus.
v.e. M. vastus externus.

The **anterior tibial** vein (*Vena tibialis antica*) arises on the dorsum of the foot by twigs from the toes; it courses under the *M. extensor longus digiti primi*, then upwards on the anterior surface of the leg, and enters the canal in the tibio-fibula to appear on its hinder surface. The vein then

receives twigs from the *M. peroneus*, the *M. tibialis posticus*, the *M. gastrocnemius*, and a large cutaneous branch.

a. The *Vena cutanea cruris medialis* (Fig. 165 *i'*) receives branches from both above and below, and enters the popliteal space to join the anterior tibial vein.

β. The anastomosis on the dorsum of the foot, from which the anterior tibial vein arises, receives perforating twigs from the plantar surface.

PART II.

THE LYMPHATIC SYSTEM.

(The arrangement of this section has been considerably altered.)

[The lymphatic system of the frog may, for descriptive purposes, be advantageously treated of in four parts :

1. The subcutaneous lymph-sacs.

2. The lymph-hearts.

3. The lymph-spaces of the body, and those lying between the various organs.

4. The lymph-vessels of the separate organs.

The first two parts will be described in this section ; the remainder with the organs or parts of the body with which they are more intimately associated. The spleen will be described with the abdominal viscera.

1. The Subcutaneous Lymph-Sacs.

A number of large spaces exist between the skin and the muscles, in which there is no direct attachment between these parts. These spaces are separated from each other by thin connective-tissue septa, stretched between the muscles and the skin, and by attachments of the skin to the underlying structures.

Joh. Müller first demonstrated that these spaces were connected with the lymphatic system, and that the contained fluid was lymph. Although this fact was contradicted by Meyer it received confirmation from Stannius, Leydig, and especially from Recklinghausen, who showed that the fluid of the lymph-sacs was carried away by the lymphatics, and that later it entered the blood-stream.

A. The Lymph-sacs of the Head and Trunk.

a. The septa. The connective-tissue septa themselves contain sinuses which occupy the space between their two surfaces (Fig. 166): these septal sinuses receive the contents of the cutaneous lymph-vessels and forward their contents into lymph-vessels situated in the septa. Such a sinus is shown in transverse section in Fig. 166, which is a section of the ventral septum. The same sinus, in plan, is seen in Fig. 167.

(1) The **dorsal septum** (*Septum dorsale*), (Figs. 169 and 171 *d*) of each side commences at the tympanic membrane; it is then attached to the *M. depressor maxillae*, *M. infraspinatus*, and *M. longissimus*

Fig. 167.

Fig. 166.

Transverse section of a sep-
tum with the attached
skin, its contained sinus
injected with blue injec-
tion mass.

H Skin.
s Septum.
S Sinus contained in the
septum.

The *sinus abdominalis lateralis* (Ecker) injected
with blue mass.

H Skin with its lymph-vessels.
S Sinus of the septum with lymph-vessels
opening into it.
s The septum cut parallel with the skin.

dorsi; and continued backwards over the *M. obliquus abdominis externus* to the anterior end of the *M. glutaeus*, whence it extends along the iliac bone, where it is connected with the posterior lymph-heart and the *M. pyriformis*, to the tip of the urostyle. At the tip of the *M. glutaeus* it is joined by the iliac septum. The posterior part of the septum is horizontal, and forms the roof of the iliac lymph-sac.

(2) The **ventral septum** (*Septum abdominale*), (Figs. 169, 170, and 171 *a*), commencing at the *Symphysis pubis*, runs forwards and out-wards, on either side, along the outer border of the *M. rectus abdom-inis* to the *Portio abdominalis* of the *M. pectoralis* (*p'''*), where it is attached, at a right angle, to the pectoral septum; it then extends forwards, after attachment to the axillary septum, to the outer

angles of the maxillary septum. At the root of the anterior extremity it divides to enclose the root of the limb, and so form the axillary septum.

(3) The **pectoral septum** (*Septum pectorale*), (Figs. 170 and 171 *p*) is attached to the superficial surface of the *M. pectoralis* (*Portio sternalis, anterior* and *posterior*); it runs transversely across the body, and is attached at its outer end to the ventral and to the maxillary septa. The septum passes obliquely backwards and downwards to be attached to the skin, and so forms a very acute angle with the *M. cutaneus pectoris* (*cp*) : a vertical band of connective-tissue, broad behind, narrow in front, extends in the middle line from the septum to the body wall; from it a certain amount of loose connective-tissue extends in all directions, and forms open lymph-spaces between the *MM. cutanei pectorales* and the vertical septum.

(4) The **perineal septum** (*Septum perineale*), (Fig. 170 *pe*). This median septum extends from the attachment of the dorsal septum to the tip of the urostyle, backwards to the symphysis pubis, where it joins the ventral septa. In its attachment it follows the middle line of the perineum.

(5) The **maxillary septum** (*Septum maxillare*), (Figs. 170, 171 *m*) is attached by either extremity to the dorsal septum, near the tympanic membrane, is continued downwards to unite with the

Fig. 168.

Sinus thoracicus transversus (Ecker).

cp M. cutaneus pectoralis.
H Skin reflected forwards.
s Sinus with its afferent vessels.

anterior end of the ventral septum, and then runs across the anterior pectoral region, forming a curve with the convexity forwards. It has inserted into it fibres of the *M. submaxillaris*. The septum is formed of very loose tissue, and frequently contains deposits of fat; it encloses a well-marked septal sinus, the *Sinus thoracicus transversus* (Ecker).

(6) The **iliac septum** (Figs. 169, 172 15, 173 *S'*) is a septum extending from the dorsal septum to the inguinal septum. It is attached to the dorsal septum opposite the anterior end of the *M. glutaeus*, and extends outwards and downwards to the inguinal

Fig. 169[1].

septum. In it the *M. cutaneus iliacus* passes from the trunk to the skin.

(7) The **inguinal septum** (*Lamina inguinalis*, Ecker), (Figs. 169, 171, the dotted line near 15, Fig. 172, separates the belly from the thigh ; on the ventral surface it is attached to the groove which

The lymph-sacs of *Rana esculenta*, seen from the dorsal surface.

1 Dorsal lymph-sac.
3 Lateral lymph-sac.
7 Brachio-radial lymph-sac.
9 Femoral lymph-sac.
10 Suprafemoral lymph-sac.
11 Interfemoral lymph-sac.
12 Crural lymph-sac.
13 Dorsal lymph-sac of the foot.
14 Plantar lymph-sac of the foot.
15 Iliac lymph-sac.
a Ventral septum.
d Dorsal septum.
f' Superior femoral septum.
f''' Intermediate femoral septum.
i Inguinal septum.
s Posterior brachial septum.
s''' Anterior brachio-radial septum.
V Vocal sac.

[1] In Figs. 168, 169, and 170 the dotted lines denote the boundaries of the various lymph-sacs.

forms the boundary between the belly and thigh; on the dorsal surface it is more posterior, and is attached to the dorsal surface of the muscles of the thigh at some little distance from the trunk. It completely surrounds the root of the hinder limb. It has attached to it the ventral, dorsal, and iliac septa, together with the septa of the thigh.

b. The lymph-sacs.

(1) The **dorsal lymph-sac** (*Saccus cranio-dorsalis*), (Figs. 169 and 171 1). This is a large lymph-sac, extending from the tip of the snout to the tip of the urostyle; it is bounded in front by the attachment of the skin to the premaxillary bones; the line of attachment is continued, on either side, along the inner border of the external nares, then forms a pouch towards the jaw and in front of the eye, and runs backwards along the upper border of the orbit, where it is attached to the upper eyelid, to the inner border of the tympanic membrane. In this course the skin is firmly attached to the underlying parts. The lateral boundary of the lymph-sac, behind this point, is formed by the dorsal septum, which separates it from the lateral lymph-sac.

(2) The **ventral lymph-sac** (*Saccus abdominalis*), (Figs. 170, 171 2) is triangular in form, with the base forwards at the breast, and the apex behind at the pelvic symphysis; it occupies the space between the skin below and the belly muscles and part of the *M. pectoralis* above. It is bounded anteriorly by the pectoral septum (*p*) and laterally by the ventral septa (*a*).

(3) The **lateral lymph-sac** (*Saccus lateralis*), (Figs. 169, 170, and 171 3) exists on either side; below, the sac is bounded by the ventral septum (*a*), above by the dorsal septum (*d*), anteriorly by the maxillary septum (*m*), and posteriorly by the inguinal septum (*i*) and the wall of the iliac lymph-sac.

(4) The **submaxillary lymph-sac** (*Saccus submaxillaris*), (Figs. 170 and 171 4) is a space between the *M. submaxillaris* and the skin; the sac is bounded behind by the maxillary septum, which separates it from the pectoral lymph-sac, and more laterally from the lateral lymph-sac. In front and at the sides the skin is firmly attached to the margin of the mandible.

(5) The **pectoral lymph-sac** (*Saccus thoracicus*), (Figs. 170 and 171 5) lies between the submaxillary and ventral lymph-sacs. The

Lymph-sacs of *Rana esculenta*, seen from the ventral surface.

2	Ventral lymph-sac.	a	Ventral septum.	m'	Attachment of maxillary septum to skin.
3	Lateral lymph-sac.	a'	Anterior division of ventral	p	Pectoral septum.
4	Submaxillary lymph-sac.		septum.	p'''	Port. abdom. of the M. pectoralis.
5	Thoracic lymph-sac.	a''	Posterior division of ventral		
6	Brachio-ulnar lymph-sac.		septum.	pe	Perineal septum.
8	Anterior brachial lymph-sac.	cf	Intermediate femoral septum.	r	M. rectus abdominis.
		cp	M. cutaneus pectoris.	ri''	M. rectus internus minor.
9	Femoral lymph-sac.	f''	Inferior femoral septum.	s''	Anterior brachio-ulnar septum.
11	Interfemoral lymph-sac.	i	Inguinal septum.		
12	Crural lymph-sac.	i'	Attachment of inguinal	s'''	Anterior brachial-radio septum.
13	Dorsal lymph-sac of the foot.		septum to skin.		
14	Plantar lymph-sac of the foot.	m	Maxillary septum.	sm	Musc. submaxillaris.

sac is bounded behind by the pectoral septum (*p*), and in front by the maxillary septum (*m*).

(6) The iliac lymph-sac (*Saccus iliacus*), (Figs. 171 and 172 15, 173) does not really belong to the subcutaneous lymph-sacs, as it does not lie directly under the skin except by a very narrow border. It is bounded in front by the iliac septum, above by the dorsal septum, and posteriorly by the inguinal septum. By these boundaries a space is enclosed, which lies under the dorsal septum and dorsal sac, and at the same time partly under the lateral sac. In this sac the *M. glutaeus*, the anterior ends of the *M. vastus externus*, *M. rectus anterior*, and *M. cutaneus iliacus*, lie free together

Fig. 171.

The lymph-sacs of *Rana esculenta*. seen from the side.

1   Dorsal lymph-sac.
2   Ventral lymph-sac.
3   Lateral lymph-sac.
4   Submaxillary lymph-sac.
5   Pectoral lymph-sac.
9   Femoral lymph-sac.
10 Suprafemoral lymph-sac.
12 Crural lymph-sac.
15 Iliac lymph-sac.
a   Ventral septum.
d   Dorsal septum.
i   Inguinal septum.
m   Maxillary septum.
m' Attachment of M. submaxillaris to the skin.
p   Pectoral septum.
sm M. submaxillaris.
v   Vocal sac.

with the hindmost part of the *M. obliquus abdominis externus*, and the hinder portion of the posterior lymph-heart. Anteriorly the floor is depressed between the *M. obliquus abdominis* and the *M. glutaeus*, the depression leading to a canal, which communicates with the abdominal cavity.

B. The Lymph-sacs of the Anterior Extremity.

a. The **septa**.

(1) The **axillary septum** (*Septum axillare*), (Figs. 170 *a'*, *a''*, 171) is practically a portion of the ventral septum, which divides at the root of the arm to enclose it. The dorsal and ventral portions of this circular septum have received special names.

Fig. 172.

Transverse section through the trunk in the region of the iliac lymph-sac.

c   Urostyle.
c'   Skin.
o   Muscles of abdominal wall.
1   Dorsal lymph-sac.
3   Lateral lymph-sac.
15   Iliac lymph-sac.

a. The dorsal axillary septum (*Septum axillare dorsale*) crosses the *M. triceps* and joins the pectoral septum.

β. The ventral axillary septum (*Septum axillare dorsale*) passes through the axilla and joins the pectoral septum.

The circular axillary septum has attached to it the following :—

(2) The **posterior brachial septum** (*Septum brachiale posticum* (Fig. 169 *s*); it is attached along the middle line of the extensor surface of the arm (long head of the *M. triceps*) to the elbow and to the forearm (*MM. anconaei*), then passes obliquely over the volar surface of the hand to the fourth finger.

(3) The **anterior brachio-ulnar septum** (*Septum brachiale anticum ulnare*), (Fig. 170 *s''*) commences at the same point as the foregoing, passes obliquely over the outer head of the *M. triceps*, and is continued over the *M. flexor antibrachii lateralis, M. supinator longus,* and *M. extensor digitorum communis*, to the dorsal surface of the fourth finger.

(4) The **anterior brachio-radial septum** (*Septum brachiale anticum radiale*), (Fig. 170 *s'''*) passes from the outer angle of the wall of the pectoral lymph-sac, over the inner head of the *M. triceps* and *M. flexor carpi radialis* to the thumb.

b. The **lymph-sacs** are enclosed by these three septa ; they are four in number :—

(1) The **brachio-ulnar lymph-sac** (*Saccus brachialis ulnaris*), (Fig. 170 6) is situated between the first and second septa along the extensor and ulnar surfaces.

(2) The **brachio-radial lymph-sac** (*Saccus brachialis radialis*), (Fig. 169 7) is placed along the extensor and radial surfaces.

(3) The **anterior brachial lymph-sac** (*Saccus brachialis anticus*), (Fig. 170 8) lies on the flexor surface between the second and third septa; it is a long cavity and interrupted by connective-tissue bands, in which the tendon of the *M. sterno-radialis* and the nerve and vessels are situated.

(4) The **axillary lymph-sac** (*Saccus axillaris*) corresponds to the iliac lymph-sac; it is bounded by the divisions of the ventral septum.

In the hand no large lymph-space exists; the skin is attached by numerous bands to the underlying structures.

C. The Lymph-sacs of the Hinder Extremity.

a. The septa.

(1) The **superior femoral septum** (*Septum femorale superius*), (Figs. 169 and 175 *f'*) is attached above to the inguinal septum near the posterior lymph-heart; and is continued, from this point, over the *M. vastus externus* and along the *M. triceps* to the knee.

(2) The **inferior femoral septum** (*Septum femorale inferius*), (Figs. 170 and 175 *f''*) runs from the inguinal septum near the point of insertion of the *M. rectus abdominis*, along the *M. rectus internus minor* to the knee.

(3) The **intermediate femoral septum** (*Septum femorale intermedium*), (Figs. 169 and 175 *f'''*) passes from near the posterior lymph-heart over the *M. semimembranosus* and the *M. rectus internus minor* to join the inferior femoral septum.

Fig. 173.

Dissection to show the iliac lymph-sac.

g   M. glutaeus.
i.c. M. ilio-coccygeus.
m.c. M. cutaneus iliacus.
o   M. obliq. abdom. externus.
r   M. rectus.
S   Dorsal septum.
S' Iliac septum.
S''' Portion of dorsal septum, which forms the roof of the iliac lymph-sac.
v   M. vastus externus.
*   Aperture, by which the iliac lymph-sac communicates with the abdominal cavity.

Fig. 174.

Plan of attachments of the inferior femoral, inguinal, and perineal septa.

(4) The **tibio-femoral septum** (*Septum femoro-crurale*) is a circular band, separating the lymph-sacs of the thigh from the leg sac.

(5) The **septa** of the foot. At the ankle joint the skin is closely attached all round to the underlying parts. Along the outer border of the foot a septum is attached to the skin externally, and to the underlying parts, especially the *M. abductor longus digiti primi*, internally. A similar but weaker band is attached along the outer border of the foot, especially to the *M. adductor digiti quinti*.

b. The lymph-sacs.

(1) The **femoral lymph-sac** (*Saccus femoralis*), (Figs. 169, 170, 171, 175 9) covers the lower and outer surfaces of the thigh; it is bounded by the superior femoral and inferior femoral septa, and in front by the inguinal septum.

Fig. 175.

Transverse section of the thigh.

b	M. biceps.
f'	Superior femoral septum.
f"	Inferior femoral septum.
f'''	Intermediate femoral septum.
H	Skin.
ri'	M. rectus internus major.
ri'''	M. rectus internus minor.
s	M. Sartorius.
sm	M. semimembranosus.
ve	M. vastus externus.
9	Femoral lymph-sac.
10	Suprafemoral lymph-sac.
11	Interfemoral lymph-sac.

(2) The **suprafemoral lymph-sac** (*Saccus suprafemoralis*), (Figs. 169, 171, 175 10) lies on the upper surface of the thigh, between the superior and intermediate femoral septa; above it is bounded by the inguinal septum.

(3) The **interfemoral lymph-sac** (*Saccus interfemoralis*), (Figs. 169, 170, 175 11) is a narrow sac on the inner surface of the thigh, between the inferior femoral septum and the intermediate femoral septum. It covers the *M. rectus internus minor*, and is interrupted by numerous bands of tissue which pass from the surface of the muscle to the skin. It is, therefore, not a simple sac, but a very wide-meshed trabecular structure of connective-tissue. The sac is triangular in shape, with the base directed forwards at the inguinal septum.

(4) The **lymph-sac** of the **leg** is a simple sac enclosing the whole leg, bounded above by the tibio-femoral septum, and below by the attachment of the skin to the ankle.

(5) The **lymph-sacs** of the **foot**. On the dorsum of the foot the skin is free, and there is consequently a lymph-sac. On the plantar surface the skin is attached by numerous connective-tissue bands and thread-like tendons, particularly to the flexor tendons. The

skin of the dorsal and plantar surfaces meet on the web and enclose a very rich anastomosis of lymph-capillaries.

2. The Lymph-Hearts.

The frog has two pairs of lymph-hearts, one pair anterior, the other posterior.

A. The **anterior lymph-hearts** (Fig. 176). These organs lie, one on each side, behind the broad transverse processes of the third vertebra (Müller, Panizza, Priestley), in a deep triangular space formed by the separation of the fibres of the *M. intertransversarius*, between the transverse processes of the third and fourth vertebrae. Each heart is a rounded sac, slightly elongated anteriorly where

Fig. 176.

Fig. 177.

The anterior lymph-hearts.

L   The left anterior lymph-heart.
l.s.   M. levator scapulae.
N   Brachial nerve.
t.s.   M. transverso - scapularis maior.
1–4   Vertebrae numbered from before backwards.

The posterior lymph-hearts.

gl   M. glutaeus.
ic   M. ilio-coccygeus.
L   Posterior lymph-hearts.
p   M. pyriformis.
r   M. rectus.
ve   M. vastus externus.

it is connected with the subscapular vein. [The hearts receive lymph from the anterior part of the body and the surrounding parts, and empty their contents into the vertebral vein. Each of these hearts is supplied by a branch from the second spinal nerve (Volkmann, Eckhard, Schiff, Priestley).]

B. The **posterior lymph-hearts** (Fig. 177) are situated on either side of the urostyle in the triangular spaces (Müller, Panizza, Priestley), bounded externally and above by the *M. glutaeus*,

internally and above by the *M. coccygeo-iliacus*, below and exter-
nally by the origin of the *M. vastus externus*, and below by the
M. pyramidalis. Each posterior heart is about two lines long and
one broad, with its long axis placed antero-posteriorly; the outer
surface is uneven and appears to be unequally dilated. The lymph-
heart is closely attached to the surrounding parts, especially to
the fascia covering the *M. ilii-coccygea*, and posteriorly to the
M. levator ani and the *M. pyramidalis*. [The posterior lymph-hearts
receive lymph from the parts surrounding them, and from the
hinder extremities, and forward it into the *V. iliaca communicans*.

The posterior lymph-hearts are each supplied by a branch from
the corresponding coccygeal nerve (Waldeyer) by its dorsal branch.
The lymph-hearts are also in close connection with the sympathetic
system (Waldeyer).]

PART III.

THE BLOOD, LYMPH, AND HISTOLOGY OF THE VESSELS.

[The parts described in this section will be considered very
briefly, and only from an anatomical point of view.

A. The **blood** [1].

The blood varies in colour, according as it is obtained from an
artery or from a vein; from an artery it has a bright red or scarlet
colour; from a vein a darker shade: in the pulmonary vessels these
colours are reversed. The blood consists of a fluid plasma which
contains red and white corpuscles: the whole forming a slightly
alkaline, opaque, and somewhat sticky fluid.

a. The **plasma** or *liquor sanguinis* is a transparent, clear, slightly
yellow fluid, faintly alkaline in reaction.

---

[1] Mr. Hurst has noticed a frog (R. temporaria) in which the blood was perfectly
colourless.

b. The **corpuscles** are of two kinds, colourless and coloured.

(1) The colourless or white corpuscles are subspherical masses of protoplasm, endowed with the power of spontaneous motion. They are much fewer than the red corpuscles, though the proportion of white to red varies considerably. Three chief varieties of colourless corpuscles can be distinguished, all of which are true cell forms, and behave like other cells with staining or other reagents. They have no cell-wall, but are simply nucleated masses of protoplasm. These corpuscles possess the power of passing through the walls of the blood-vessels, and are then known as migratory cells; such migratory cells can be found in nearly all tissues, but more especially in the connective-tissues.

α. Ordinary large colourless corpuscles are large transparent masses of protoplasm containing one or two nuclei, rarely three or more. The cell contains few granules, and usually has one or more vacuoles or clear spaces containing fluid.

β. Granular corpuscles are less numerous than the foregoing, but larger, and are distinguished by the numerous large dark granules which they contain. The processes such a corpuscle sends out are hyaline.

γ. Smaller corpuscles also occur varying much in form: they may consist of a nucleus with a very small amount of hyaline or granular protoplasm, or of several nuclei with an extremely small amount of protoplasm.

(2) The **coloured corpuscles** are much more numerous than the colourless corpuscles; each is a bi-concave, oval disc, about 0·0255 mm. in length, and 0·017 mm. in breadth (Gulliver)[1] (R. temporaria, 0·0235 and 0·0145 mm. respectively). Each corpuscle possesses an oval nucleus (Hewson)[2], which projects into either concave surface of the whole corpuscle. These corpuscles do not possess the power of spontaneous movement; and have no cell-wall. The corpuscles are of a reddish-yellow colour, and give the blood its characteristic hue. The colouring matter is haemoglobin, and when separated it crystallizes in prisms (Preyer). The corpuscles show a well-marked intracellular and intranuclear network.]

---

[1] Gulliver, Proc. Zool. Soc. London, 1845, Vol. XIII, p. 93 seq.
[2] Hewson, Phil. Trans. 1773, Vol. LXIII, p. 310 seq.

B. [The **Lymph** and **Chyle**.

The **lymph** is that portion of the blood which has filtered from the blood-vessels, through the tissues, into the lymphatics. It is a clear, transparent fluid, containing colourless corpuscles, which agree in all particulars with the colourless corpuscles of the blood. During digestion the lymph from the alimentary canal contains particles of fatty matter, and is then known as **chyle**.] The colourless corpuscles of the lymph frequently contain portions of red corpuscles or granules of pigment. Non-nucleated masses of protoplasm and decolourised red corpuscles (slightly diminished in size) have also been described as occurring frequently in the lymph (Fuchs[1]).]

C. [Histological Remarks on the Vascular System.

a. The **heart** has already been described (pp. 216–222).

b. The **blood-vessels** present the same structure as the corresponding vessels in higher animals. The *arteries* and *veins* have each the three walls or layers usually described—*Tunica adventitia*, *Tunica media*, and *Tunica intima*. The only characteristic to be mentioned is that the *Tunica adventitia* contains branched, pigmented corpuscles. The *Nervi vasorum*, especially of the smaller arteries, are arranged in two plexuses, one in the *Tunica adventitia* (His)[2], the second in the muscular coat (J. Arnold)[3]. The fibres of both plexuses are non-medullated, and have the usual beaded appearance; they communicate freely with each other. The **capillaries** present, as a rule, the usual structure: such special arrangements of the capillaries or peculiarities in structure as occur will be described with the organs in which they are found.

c. The **subcutaneous lymph-sacs** are lined with a layer of endothelium resembling the endocardium shown in Fig. 149; the endothelial layer possesses stomata (see peritoneum), through which the lymph-sacs communicate with the underlying lymphatics. The endothelium is continued on to the vessels, nerves, etc., which course through the sacs, and excludes these from the cavities. As a rule an artery, vein, and nerve are enclosed in a common sheath.

d. The **lymph-hearts** are small saccular bodies with thin transparent walls, which contain obscurely striated muscle-fibres. The vessels communicating with the hearts appear to possess valves

---

[1] Fuchs, Virchow's Arch. 1877, Vol. LXXI, p. 78 seq.

[2] His, Virchow's Arch. 1863, Vol. XXVIII, p. 427.

[3] Arnold, in Stricker's Handbuch d. Gewebelehre, p. 137.

(Müller). The walls of the hearts are formed of three layers; an external, compared by Waldeyer to an *adventitia*, a muscular layer, and an endothelial lining. The muscular fibres form a close inter-lacing mass, the fibres being small, branched (Leydig), and pos-sessed of many nuclei. Among the muscular fibres are pigmented corpuscles, together with medullated and non-medullated nerve-fibres, but no ganglion-cells (Volkmann, Waldeyer, Priestley). The *adventitia* is a connective-tissue layer with many pigment cells (Leydig, Hyrtl, Waldeyer).]

SECTION V.

THE ALIMENTARY TRACT WITH ITS APPENDAGES, THE SPLEEN, AND THE PERITONEUM.

THE ALIMENTARY TRACT, ETC.

LITERATURE.

----&----

THE MOUTH.

(Except the mucous membrane of the tongue, for which see organ of taste.)

Ducrotay de Blainville, H. M., Ostéographie ou description iconographique comparée du squelette et du système dentaire des cinq classes d'animaux vertébrés. Paris, 1841.

Erdl, Ueber den Bau der Zähne bei den Wirbelthieren, etc. München, 1841.

Fixen, C., De linguae raninae structura. Dorpat, 1857.

Heinoke, F., Untersuchungen über die Zähne niederer Wirbelthiere. Zeitsch. f. wiss. Zool. 1873. Vol. XXIII, p. 495.

Hertwig, O., Ueber das Zahnsystem der Amphibien, etc. Suppl. to Vol. XI, Arch. f. mik. Anat. 1874.

Hoffmann, C. K., Bronn's Thierbuch. Leipzig and Heidelberg, 1873-1878. Vol. VI, p. 379.

Holl, M., Zur Anatomie der Mundhöhle von Rana temporaria. Wiener Acad. Sitzungsb. 1887. Vol. XCV, Pt. III, p. 47.

Hoyer, Ueber die Epithelzellen der Froschzunge, sowie über den Bau der Cylinder- und Flimmerepithelien und ihr Verhältniss zum Bindegewebe. Arch. f. Anat. u. Physiol. 1858, p. 163; also Deutsche Klinik, 1857.

Langer, C., Ueber das Lymphgefässsystem des Frosches. Wiener Acad. Sitzungsb. 1867. Vol. LV, Pt. I, pp. 614-621.

Leydig, Die Anuren Batrachier der deutschen Fauna. Bonn, 1877.

Owen, R., Odontography. London, 1840-1845, p. 187.

Reichel, P., Beiträge zur Morphologie der Mundhöhlendrüsen der Wirbelthiere. Leipzig, 1882; also in Morph. Jahrb. 1882, Vol. VIII, pp. 1-72.

Santi Sirena, Untersuchungen über den Bau und die Entwicklung der Zähne bei den Amphibien und Reptilien. Verhandl. d. phys.-med. Gesellsch. in Würz-burg, 1872. Vol. II, new series, p. 125.

Schöbl, J., Ueber divertikelbildende Capillaren in der Rachenschleimhaut nackter Amphibien. Sitzungsb. d. k. b. Gesellsch. d. Wiss. in Prag. 1878, p. 25; also in Arch. f. mik. Anat. 1885, Vol. XXV, p. 89.

Schultze, F. E., Das Drüsenepithel der schlauchförmigen Drüsen des Dünn- und Dickdarms und die Becherzellen (of the pharyngo-oral cavity). Centralbl. f. d. med. Wiss. 1866, p. 61.

Schultze, F. E., Epithel- und Drüsen-Zellen. Arch. f. mik. Anat. 1867. Vol. III, p. 137.

Smith, W. J., Beitrag zur differentiellen Diagnose der Rana fusca s. platyrrhinus und Rana arvalis s. oxyrrhinus auf Grund der an den Gaumenzähnen nachweis-baren Unterschiede. Pflüger's Arch. f. d. ges. Physiol. 1883. Vol. XXXII, pp. 581-588.

Tomes, C. S., On the development of the teeth of the newt, frog, slowworm, and green lizard. Phil. Trans. 1874, p. 285.

Török, Untersuchungen über die Entwickelung der Mundhöhle, etc. Wiener Sitzungsb. 1866. Vol. LIV, Pt. I, p. 75.

Waller, A., Microscopic examination of the principal tissues of the tongue, etc. Phil. Mag. 1846, pp. 273–290.

Waller, A., On the development of the mouth and tongue of the frog. Phil. Mag. 1850. Vol. I, pp. 38–43.

Zeller, A., Die Abscheidung des indig.-schwefelsauren Natrons in den Drüsen (Intermaxillary gland). Virchow's Arch. 1878. Vol. LXXIII, p. 257.

THE OESOPHAGUS AND STOMACH.

Biedermann, Untersuchungen über Magenepithel. Wiener Acad. Sitzungsb. 1875. Vol. LXXI, Pt. III, p. 377.

Bischoff, Ueber den Bau der Magenschleimhaut. Arch. f. Anat. u. Physiol. 1838, p. 503.

Bleyer, E., Magenepithel und Magendrüsen der Batrachier. Dissert. Königsberg, 1874.

Braun, Zum Vorkommen von Flimmerepithel im Magen. Zool. Anzeiger. 1880. No. 69, p. 568.

Brinton, in Cyclopaedia of Anat. and Physiol., edited by R. B. Todd. 1859. Vol. I, p. 320.

Cobelli, Le gliandole acinose del cardia. Wiener Acad. Sitzungsb. 1866. Vol. LIII, Pt. I, p. 251.

Ebstein, W., Beiträge zur Lehre vom Bau und den physiologischen Funktionen der sogenannten Magenschleimdrüsen. Arch. f. mik. Anat. 1870. Vol. VI, p. 515.

Ecker, A., Ueber die Drüsen der Magenschleimhaut. Zeitsch. f. rat. Med. 1852, p. 243.

Foster, M., On some points in the epithelium of the frog's throat. Journ. of Anat. and Physiol. 1869. Vol. IV, p. 394.

Frerichs, On the Stomach, in Wagner's Handwörterbuch d. Physiol. 1848. Vol. II, p. 748.

Glinsky, A., Zur Kenntniss des Baues der Magenschleimhaut der Wirbelthiere. Centralbl. f. d. med. Wiss. 1883, p. 225.

Gonjaew, K., Die Nerven des Nahrungsschlauches. Arch. f. mik. Anat. 1875. Vol. XI, pp. 479–496.

Hebold, O., Ein Beitrag zur Lehre von der Sekretion und Regeneration der Schleimzellen. Dissert. Bonn, 1879, pp. 21–27.

Heidenhain, R., Untersuchungen über den Bau der Labdrüsen. Arch. f. mik. Anat. 1870. Vol. VI, p. 368.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs. Leipzig und Heidelberg. 1873–1878. Vol. VI, pp. 408–412.

Just, A., Zur Histologie und Physiologie des Flimmerepithels. Breslauer ärztliche Zeitsch. 1885. No. 18, pp. 205–206.

Klein, E., Darmkanal, in Stricker's Gewebelehre, p. 388, etc.

v. Kölliker, A., Mikroskopische Anatomie, 1854. Vol. II, p. 147.

Langley, J. N., and Sewall, H., On the changes in pepsin-forming glands during secretion. Journ. of Physiol. 1880. Vol. II, pp. 261, 281.

Langley, J. N., On the histology and physiology of pepsin-forming glands. Phil. Trans. 1881. Vol. CLXXII, Pt. III, pp. 663–712.

Langley, J. N., On the structure of secretory cells and on changes which take place in them during secretion. Internat. Monatschr. f. Anat. u. Histol. Vol. I, pp. 69-76.

Leydig, Lehrbuch der Histologie. 1857.

Nussbaum, M., Ueber den Bau und die Thätigkeit der Drüsen. Arch. f. mik. Anat. 1882, Vol. XXI, p. 296; 1882, Vol. XXVIII, p. 296; 1877, Vol. XIII, p. 721.

Partsch, C., Beiträge zur Kenntniss des Vorderdarmes einiger Amphibien und Reptilien. Arch. f. mik. Anat. 1877. Vol. XIV, p. 179.

Begéozy, E. N., Ueber die Epithelzellen des Magens. Arch. f. mik. Anat. 1880. Vol. XVIII, pp. 408-411.

Robinson, C., Ueber die Lymphgefässe der Abdominaleingeweide des Frosches, etc. Froriep's Notizen, 1846. No. 807, col. 225.

Rollett, Bemerkungen zur Kenntniss der Labdrüsen und der Magenschleimhaut. Untersuch. in d. Institut f. Physiol. u. Histol. zu Graz. 1871.

Schultze, F. E., Epithel- und Drüsenzellen. Arch. f. mik. Anat. 1867. Vol. III, p. 174; abstract in Centralbl. f. med. Wiss. 1866, No. 4.

Schmidt, C., Ueber eigenthümliche aus dem Flimmerepithel hervorgehende Gebilde. Arch. mik. Anat. 1881. Vol. XX, p. 123.

Sewall, H., A note on the processes concerned in the secretion of the pepsin-forming glands of the frog. Studies in the Biol. Laborat., Johns Hopkins Univers. Vol. II, pp. 131-134.

v. Swiecioki, H., Untersuchungen über die Bildung und Ausscheidung des Pepsins bei den Batrachiern. Pflüger's Arch. f. d. ges. Physiol. 1876. Vol. XIII, p. 444.

Trinkler, N., Zur Kenntniss des feineren Baues der Magenschleimhaut, insbesondere der Magendrüsen. Centralbl. f. med. Wiss. 1883, pp. 161-163.

Trinkler, N., Ueber den Bau der Magenschleimhaut. Arch. f. mik. Anat. 1885. Vol. XXIV, p. 74.

Trütschel, Ueber die Endigung der Nerven in der Schleimhaut des Magens. Centralbl. f. d. med. Wiss. 1870, p. 115.

Valatour, Recherches sur les glandes gastriques et sur les tuniques musculaires du tube digestif dans les poissons osseux et les Batraciens. Annales de Sc. nat. 1861. Series IV. Vol. XVI, p. 219.

THE INTESTINE.

Arnstein, C., Ueber Becherzellen, etc. Virchow's Arch. 1867. Vol. XXXIX, p. 527.

Arnstein, C., and Gonjaew, K., Ueber die Nerven des Verdauungskanals. Pflüger's Arch. f. d. ges. Physiol. 1874. Vol. VIII, pp. 614-615.

Auerbach, L., Fernere vorläufige Mittheilung über den Nervenapparat des Darmes. Virchow's Arch. 1864. Vol. XXX, p. 457.

Auerbach, L., Untersuchungen über Lymph- und Blutgefässe. Virchow's Arch. 1865. Vol. XXXIII, p. 340.

Auerbach, L., Organologische Studien.

Billroth, T., Ueber die Epithelzellen der Froschzunge; der Bau, Cylinder- und Flimmerepithel und ihr Verhältniss zum Bindegewebe. Arch. f. Anat. u. Physiol. 1858, p. 159.

Billroth, T., Einige Beobachtungen über das ausgedehnte Vorkommen von Nervenanastomosen im Tractus intestinalis. Arch. f. Anat. u. Physiol. 1858, p. 148.

Brettauer und Steinach, Untersuchungen über das Cylinderepithelium. Wiener Akad. Sitzungsb. 1857. Vol. XXIII, p. 303. Moleschott's Zeitsch. 1857. Vol. III, p. 57.

Darsch, O., Beiträge zur Kenntniss des feineren Baues des Dünndarmes. Wiener Sitzungsb. 1880. Vol. LXXXII, Pt. III, p. 168.

Dönitz, Ueber die Schleimhaut des Darmcanals. Arch. f. Anat. u. Physiol. 1864, p. 367.

Dönitz, Ueber Darmzotten. Arch. f. Anat. u. Physiol. 1866, p. 757.

Eberth, C. J., Ueber den feineren Bau der Darmschleimhaut. Würzb. naturw. Zeitschr. 1864. Vol. V, p. 23.

Eimer, T., Zur Fettresorption, etc. Virchow's Arch. 1867. Vol. XXXVIII, p. 428.

Eimer, T., Ueber Becherzellen. Virchow's Arch. 1868. Vol. XLII, p. 490.

Eimer, T., Zur Geschichte der Becherzellen. Dissert. 1867.

Eimer, T., Die Wege des Fettes in der Darmschleimhaut bei seiner Resorption. Virchow's Arch. 1869. Vol. XLVIII, p. 119.

Eimer, T., Zur Becherfrage. Virchow's Arch. 1867. Vol. XL, p. 282.

Erdmann, Die Resorptionswege in der Schleimhaut des Dünndarms. Dissert. Dorpat, 1867.

Fries, E., Ueber die Fettresorption und die Entstehung der Becherzellen. Virchow's Arch. 1867. Vol. XL, p. 519.

Gerlach, L., Ueber den Auerbachschen Plexus mysentericus. Arbeiten aus d. physiol. Anstalt. Leipzig. 1872, pp. 102–112.

Gonjaew, K., Die Nerven des Nahrungsschlauches. Arch. f. mik. Anat. 1875. Vol. XI, pp. 479–496.

Gruby and Delafond, Résultats des recherches faites sur l'anatomie et les fonctions des villosités intestinales, etc. Compt. rend. 1843. Vol. XVI, p. 1194.

Grugenhagen, A., Ueber Fettresorption und Darmepithel. Arch. f. mik. Anat. 1887. Vol. XXIX, p. 139.

Heidenhain, R., Die Absorptionswege des Fettes. Moleschott's Untersuchungen. 1858. Vol. IV, p. 251.

Henle, J., Symbolae ad anatomiam villorum intestinalium impr. eorum epithelii et vasorum lacteorum. Berolini, 1837.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs. Leipzig und Heidelberg, 1873–1878. Vol. VI, pp. 412–424.

Klein, E., Der Darmkanal in Stricker's Gewebelehre, Article XVI.

Klein, E., Contributions to the anatomy of Auerbach's Plexus in the intestine of the frog and toad. Quart. Journ. Micros. Sci. 1873. Vol. XIII, p. 377.

Klein, E., and Verson, E., Der Darmcanal, in Stricker's Gewebelehre, 1871, p. 355.

Klein, E., Der neue Nervenapparat v. Thanhoffer's. Centralbl. f. d. med. Wiss. 1883, p. 82.

v. Kölliker, A., Nachweis eines besonderen Baues der Cylinderzellen des Dünndarms. Verhandl. d. phys.-med. Gesells. Würzburg, 1856. Vol. VI, p. 153.

v. Kölliker, A., Handbuch der Gewebelehre.

Lambl, Ueber die Epithelialzellen der Dünndarmschleimhaut. Wiener med. Wochenschr. 1859. Nos. 24 and 25.

Langer, C., Ueber das Lymphgefässsystem des Frosches. Wiener Acad. Sitzungsb. 1866. Vol. LIII, Pt. I, p. 395.

Letzerich, L., Ueber die Resorption der verdauten Nährstoffe im Dünndarm. Virchow's Archiv. 1866, Vol. XXXVII, p. 232 ; 1867, Vol. XXXIX, p. 435.

Lipsky, A., Beitrag zur Kenntniss des feineren Baues des Darmcanals. Wiener Akad. Sitzungsb. 1865. Vol. LV, Pt. I, p. 183.

Oeffinger, Einige Bemerkungen über die sogenannten Becherzellen. Arch. f. Anat. u. Physiol. 1867, p. 337.

Partsch, C., Beiträge zur Kenntniss des Vorderdarmes einiger Amphibien und Reptilien. Arch. f. mik. Anat. 1877. Vol. XIV, p. 179.

Remak, R., Ueber peripherische Ganglien an den Nerven des Nahrungsrohrs. Arch. f. Anat. u. Physiol. 1858, p. 189; also in Zeit. d. Vereins f. Heilkunde in Preussen. 1840.

Renzoni, Osservazioni e ricerche sul epitelio intestinale. Rendiconti dell Acad. di Napoli. 1868.

Rusconi, Riflessioni sopra il sistema linfatico dei rettili. Pavia, 1845.

Sachs, J., Zur Kenntniss der sogenannten Vacuolen oder Becherzellen im Dünndarm. Virchow's Arch. 1867. Vol. XXXIX, p. 493.

Schultze, F. E., Das Drüsenepithel der schlauchförmigen Drüsen des Dünn- und Dickdarms und die Becherzellen. Centralbl. f. d. med. Wiss. 1866, p. 160.

Schultze, F. E., Epithel- und Drüsen-Zellen. Arch. f. mik. Anat. 1867. Vol. III, p. 145.

Thanhoffer, L., Beiträge zur Fettresorption und histologischen Structur der Dünndarmzotten. Pflüger's Arch. f. d. ges. Physiol. 1874. Vol. VIII, pp. 391–443.

v. Thanhoffer, L., Ein neuer Nervenapparat im Dünndarm. Centralbl. f. d. med. Wiss. 1883, p. 33.

v. Thanhoffer, L., Antwort auf Herrn Prof. Klein's ' Der neue Nervenapparat etc.,' betitelte Bemerkungen. Centralbl. f. d. med. Wiss. 1883, p. 176.

Valatour, M. M., Recherches sur les glandes gastriques et sur les tuniques musculaires du tube digestif dans les poissons et les Batraciens. Annales des Sci. nat. 4th Series, Vol. XVI. Zool. 1861, pp. 219–285.

Watney, H., The minute anatomy of the alimentary canal. Phil. Trans. 1877. Vol. CLXVI, Pt. II, p. 451.

Wiegandt, Untersuchungen über das Dünndarmepithel. Dissert. Dorpat, 1860.

v. Wittich, Beiträge zur Frage über Fettresorption. Virchow's Arch. 1857. Vol. XI, p. 37.

THE LIVER, GALL-BLADDER, AND PANCREAS.

Barfurth, D., Vergleichend-histochemische Untersuchungen über das Glycogen. Arch. f. mik. Anat. 1885. Vol. XXV, p. 369.

Brot, J., and Wagenmann, C. A., De amphibiorum hepate et glandularum ductu excretio carentium structura deque earundem functionibus experimenta. Berolini, 1841.

v. Brunn, A., Flimmerepithel in den Gallengängen des Frosches. Zool. Anzeiger. 1883. No. 148, p. 483.

Eberth, C. J., Die Pigmentleber der Frösche und die Melanämie. Virchow's Arch. 1867. Vol. XL, p. 305.

Eberth, C. J., Zur Kenntniss der Verbreitung glatter Muskeln. Zeitschr. f. wiss. Zool. 1863. Vol. XII, p. 360.

Eberth, C. J., Ueber den feineren Bau der Leber. Centralbl. f. d. med. Wiss. 1866, p. 897.

Eberth, C. J., Untersuchungen über die Leber der Wirbelthiere. Arch. f. mik. Anat. 1867. Vol. III, p. 423.

Eberth, C. J., Untersuchungen über die normale und pathologische Leber. Virchow's Arch. 1867. Vol. XXXIX, p. 70.

Eberth, C. J., Ueber die Pigmentleber der Frösche. Virchow's Arch. 1862. Vol. XXIX, p. 70.

Gerlach, L., Ueber die Nerven der Gallenblase. Centralbl. f. d. med. Wiss. 1873, p. 562.

Hering, E., Ueber den Bau der Wirbelthierleber. Wiener Acad. Sitzungsb. 1886. Vol. LIV, Pt. I, p. 335.

Hering, E., Ueber den Bau der Wirbelthierleber. Arch. f. mik. Anat. 1867. Vol. III, p. 88.

Hering, E., On the liver. Stricker's Gewebelehre. 1872, p. 429.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs. Leipzig und Heidelberg, 1873-1878. Vol. VI, p. 424.

Jones, C. H., On the structure and development of the liver. Phil. Trans. 1849. Pt. I, p. 122.

Langley, J. N., On variations in the amount and distribution of fat in the liver-cells of the frog. Proc. Roy. Soc. 1886. Vol. XXXIX, p. 234.

Leydig, F., Lehrbuch der Histologie. 1857.

Leydig, F., Die Leber der Fische und Batrachier.

Nussbaum, M., Ueber den Bau und die Thätigkeit der Drüsen (Pancreas). Arch. f. mik. Anat. 1877. Vol. XIII, p. 752.

Popoff, M., The nerves of the gall-bladder (in Russian). Rudneff's Journ. f. normal. u. pathol. Histol., etc. 1872.

Remak, R., Ueber runde Blutgerinnsel und über pigmenthaltige Zellen. Arch. f. Anat. u. Physiol. 1852, p. 115.

Weber, E. H., Ueber die periodische Farbenänderung welche die Leber der Hühner und Frösche erleidet. Bericht von Verhandl. K. Sächs Gesell. Leipzig, 1850, p. 15.

Zeller, A., Die Abscheidung des indig.-schwefelsauren Natrons in den Drüsen (Pancreas). Virchow's Arch. 1878. Vol. LXXIII, p. 257.

THE SPLEEN.

Billroth, T., Beiträge zur vergleichenden Anatomie der Milz. Arch. f. Anat. u. Physiol. 1857, p. 88.

Billroth, T., Beiträge zur vergleichenden Anatomie der Milz. Virchow's Arch. 1861, Vol. XX, p. 410, and 1862, Vol. XXIII, p. 457; also Zeitschr. f. wiss. Zool. 1862, Vol. XI, p. 325.

Ecker, Blutgefässdrüsen, in Wagner's Handwörterbuch der Physiologie. 1849. Vol. IV.

Gray, H., On the structure and use of the spleen. London, 1854.

Hoffmann, C. K., Bronn's Thierbuch. Leipzig und Heidelberg, 1873-1878. Vol. VI, p. 509.

v. Kölliker, A., Ueber den Bau und die Verrichtungen der Milz. Mittheil. d. naturf. Gesell. in Zürich, 1847. Vol. I, p. 120.

Kusnesoff, F., Ueber blutkörperchenhaltige Zellen der Milz. Wiener Sitzungsber. 1873. Vol. LXVII, Pt. III, pp. 58-67.

Müller, W., Ueber den feineren Bau der Milz. Leipzig und Heidelberg, 1865.

Remak, R., Ueber runde Blutgerinnsel und über pigmenthaltige Zellen. Arch. f. Anat. u. Physiol. 1852, p. 115.

Schweigger-Seidel, F., Untersuchungen über die Milz. Virchow's Arch. 1862. Vol. XXIII, p. 526.

Stieda, L., Zur Histologie der Milz. Dorpat, 1862.

THE PERITONEUM.

Alltmann, R., Ueber die Veränderungen des serösen Epithels am blosgelegten Froschmesenterium. Arch. f. mik. Anat. 1878. Vol. XVI, p. 111.

Arnold, J., Ueber die Durchtrittsstellen der Wanderzellen durch entzündete seröse Häute. Virchow's Arch. 1878. Vol. LXXIV, p. 245.

Batelli, A., Dello addaltamento di alcune cellule endotiali nelle membrane serose. Lo Sperimentale. 1884, p. 132.

Cyon, Ueber die Nerven des Peritoneum. Bericht über d. Verhandl. d. Kön. Sächs. Gesell. d. Wiss. z. Leipzig, 1868. Vol. XX, p. 119. Leipzig, 1869.

Grunau, H., Ueber das Flimmerepithel auf dem Bauchfell des weiblichen Frosches und über den Eileiterbau desselben. Dissert. Königsberg, 1875.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs. Leipzig und Heidelberg, 1873-1878. Vol. VI.

Hoffmann, T., Die Lungen-Lymphgefässe der Rana temporaria. Dissert. Dorpat, 1875.

Kapff, Untersuchungen über das Ovarium und dessen Beziehungen zum Peritoneum. Arch. f. Anat. u. Physiol. 1872, p. 553.

Klein, E., On Remak's ciliated vesicles and corneous filaments of the peritoneum of the frog. Quart. Journ. Mic. Sci. New Series, 1872. Vol. XII, p. 43.

Klein, E., On the peripheral distribution of non-medullated nerve-fibres (nerves of the peritoneum). Quart. Journ. Micros. Sci. 1872. Vol. XII, p. 32.

Leydig, Lehrbuch der Histologie. 1857, p. 325.

Mayer, Ueber die Flimmerbewegung. Froriep's Notizen, 1836. Vol. XLVII, p. 179.

Neumann, E., Die Beziehungen des Flimmerepithels der Bauchhöhle zum Eileiterepithel beim Frosch. Arch. f. mik. Anat. 1875. Vol. XI, pp. 354-377.

Nicolsky, P., Ueber das Flimmerepithel beim Frosche. Centralbl. f. d. med. Wiss. 1880, p. 641.

Paladino, G., Dell' endotelio vibratile nei Mammiferi ed in generale di alcuni dati sulla fisiologia delle formazioni endoteliche. Estr. dal Giornale intern. delle Scienze Mediche. 1882. Vol. IV.

Schweigger-Seidel and Dogiel, Ueber die Peritonealhöhle der Frösche. Arbeiten aus d. physiol. Anstalt zu Leipzig. 1866, p. 68.

Solger, B., Ueber einige Entwicklungsstadien des Peritonealepithels der Amphibienlarven. Manusc. d. Naturf. Versamml. zu Freiburg. 1884.

Thiry, Ueber das Vorkommen eines Flimmerepitheliums auf dem Bauchfell des weiblichen Frosches. Göttinger Nachrichten. 1862, pp. 171-174.

Tourneux, Recherches sur l'épithelium des sereuses. Journ. de l'anat. et de la physiol. 1874.

Waldeyer, Eierstock und Ei. Leipzig, 1870, pp. 72 and 122.

Wolff, W., Ueber freie sensible Nervenendigungen. Arch. f. mik. Anat. 1882. Vol. XX, pp. 377-381.

THE ALIMENTARY TRACT, ETC.

I. THE ALIMENTARY TRACT.

THE alimentary tract consists of the mouth or pharyngo-oral cavity, the oesophagus, the stomach, the small intestine and the large intestine; these together forming a tube extending from the mouth to the cloaca. From the commencement of the oesophagus, at the entrance to the larynx, to the end of the cloaca, the length of the tube is about 31·5 cm., that of the various parts being:

From glottis to pylorus	5·5 cm.
From pylorus to large intestine	22·0 cm.
Large intestine to end of cloaca	4·0 cm.
Total length	31·5 cm.

A. The **Mouth.**

The mucous membrane covering the tongue will be described with the sense-organs (see organ of taste).

a. General description. The mouth of *R. esculenta,* as in all other amphibia, with the exception of the lowest (*Siren, Proteus,* etc.), is of considerable width, and extends backwards as far as the middle of the tympanic membrane. The upper margin of the mouth possesses a lip or fold of the skin (*SS¹*), which projects sufficiently to prevent the teeth being seen from the front or from the sides. This lip-like rim is most prominent in the premaxillary and superior maxillary regions, but can be traced along the whole length of the upper jaw, and on to the lower jaw, by means of a well-marked fold at the angle of the mouth. Beyond this point the lip is absent, as the skin is closely attached to the bony mandible.

On the **roof** of the **mouth** the following structures can be made

out: immediately within the lip is a deep, well-marked groove, the outer boundary formed by the lip, the inner by a fold of the mucous membrane (Fig. 178 F); this fold increases from behind forwards as far as the premaxillary bones, where it forms two prominences (F^1, F^1) with an interval between. These correspond to the palatine processes of the premaxillary bones: immediately behind them are openings of the ducts of the intermaxillary glands.

In the groove so formed are placed a single row of simple teeth, which, though subject to many variations, are usually about fifty in number.

A little further back and to either side of the median line is a small group of vomerine teeth (Vo); each group has from five to ten teeth; external to these is on each side a transversely-placed oval opening, the posterior nares (Cho). These apertures are directed outwards and backwards into a shallow groove, bounded anteriorly by a fold of mucous membrane.

According to Wiedersheim the mucous membrane immediately around the vomerine teeth is supplied with taste-bulbs; the epithelium surrounding these being non-ciliated.

Fig. 178.

The roof of the mouth.

Cho   Posterior naris.
ID   Opening of intermaxillary glands.
F   Fold of mucous membrane.
F1, F1 Prominences of mucous membrane.
K   Muscles.
O   Floor of the orbit.
S   Lip.
S1   Lip.
T   Eustachian tubes.
Vo   Vomer.

The roof of the mouth underneath the parasphenoid is somewhat vaulted and on either side depressed by the eyeballs, which project downwards more or less prominently (O, O). Still further back are the openings of the Eustachian tubes (Fig. 178 T), one on each side, and almost surrounded by the limbs of the pterygoid bones.

On the **floor** of the **mouth** (Fig. 179) the tongue (Z, Z^1) forms the most prominent object; its shape varying according to the state of contraction of its muscles. Behind it, in the middle line, is a transverse groove (†), corresponding to the posterior border of the hyoid bone, and still further back is the opening to the larynx (L),

a longitudinal slit about 3 mm. in length. The mucous membrane to either side of the tongue is only slightly folded, and a little in front of the angle of the mouth is depressed into an aperture (*S*), opening into the vocal sac. This opening is surrounded by small radiating folds of mucous membrane, and is oval in shape.

Towards the oesophagus the mucous membrane of both the roof and the floor of the mouth is thrown into numerous longitudinal folds.

b. The minute structure of the several parts.

(1) The **mucous membrane** of the mouth. At the junction of the skin and the mucous membrane there is a gradual transition from the stratified epithelium of the skin to a single layer of **columnar epithelium.** On the floor of the mouth this condition is reached at the tongue; on the roof the transition takes place more quickly. The columnar epithelium of the mouth (that of the tongue is excluded from this description) is ciliated; scattered cells, which are not ciliated, are found here and there irregularly, but are not numerous. The cylindrical cells are very finely granular in their upper parts, clearer in the middle portion, more coarsely and darkly granular in their deeper portions; each cell is possessed of a large, well-defined, oval nucleus, which contains one or sometimes two nucleoli. The non-ciliated cells usually present a sharply differentiated, structureless, hyaline, free border (Schultze). The epithelium towards the margin of the mouth, where it is stratified, is also ciliated.

Fig. 179.

The floor of the mouth.

K Muscles.
L Opening to larynx.
M Mandible.
S Opening to voice-sac (in males only)
Sm Chin.
Z Tongue.
*Z*1 Left cornu of bifid tongue.
† Folds opposite hinder border of the hyoid.

Goblet-cells occur in every part of the epithelium, whether ciliated or non-ciliated, and their forms vary very greatly.

[The **submucous layer** is a fibrous connective-tissue matrix, very rich in nerves and blood-vessels. The capillaries are arranged in small, somewhat polygonal meshes (Fig. 180), and are peculiar, with those of the anterior part of the oesophagus, in having small

dilatations. This arrangement was first [1] described by Langer, and later by Schöbl. The dilatations are placed quite irregularly on the capillaries, sometimes only on one side, sometimes on both sides of the vessel ; a slight constriction occurs at the neck of each dilatation, where it opens into the capillary [2]. The nerves of the mucous membrane underneath the orbits have nerve-cells attached to them (Stirling and Macdonald, page 170). The lymphatics are very numerous, and for the most part follow the course of the blood-vessels to their finest twigs, beyond which they follow an independent course (Langer).]

(2) The **teeth** are wanting in the lower jaw; on the roof of the mouth they are found in two situations : as a single row in the groove within the lip, and a group on each vomer. Each tooth has the form of an elongated cone, which in the case of the jaw-teeth is curved, in that of the vomerine teeth straight. The teeth are fixed to the jaw so as to project upwards and slightly inwards, those at the front of the mouth projecting backwards, and those on the vomers project backwards. Each tooth has a small, sharp projection, or secondary crown on its outer surface (Fig. 181), placed near the mucous membrane. The teeth are fixed to the bones by means of Crusta petrosa, which is again united to the bones of the mandible by a matrix of spongy bone, continuous for the several teeth. Between the tooth and the mucous membrane is a layer of flattened epithelium (*H*), which extends more deeply on the inner side of the tooth than on the outer; the layer is continuous with the epithelium of the mouth, and is two to three cells in thickness. Each tooth has fine longitudinal grooves on the basal part of its outer surface, and consists of two parts, a crown and a root. The teeth possess large cavities, the wall being thin and almost of even thickness, except on the inner surface of the basal portion of the root, where the wall is wanting, and so forms a large aperture to the root.

The general skeleton of the tooth is formed of dentine, this is covered on the crown by a layer of enamel, and the *Cuticula dentis* on the socket by a layer of *Crusta petrosa*.

---

[1] Beale, Phil. Trans., 1863, p. 153, shows dilatations in his drawing, but makes no reference to them in the text.

[2] The vascular supply of the mucous membrane of the dorsal surface of the mouth and oesophagus is shown (after Schöbl) in Plate II, Fig. 180, I. Arteries red, veins blue. II. in the same figure represents the dilatations on the capillaries; after Schöbl.

a. The **dentine** is a homogeneous substance pierced by numerous tubules (*D*), which arise at the pulp-cavity and course in a parallel direction to the surface of the dentine, where they form a rich network with irregular, interglomerular spaces. The inner surface of the dentine is rough, through the presence of numerous small, dark tubercles.

β. The **enamel** covers the dentine on the apical portion of the tooth. It has tubes coursing through it, which are continuous with those of the dentine, and presents also circumferential striations (Fig. 181 III).

γ. The **tooth cuticle** (*Cuticula dentis*) is colourless and covers the enamel. It is highly refractive, very transparent, and very resistant to chemical reagents. From the apex, towards the *Crusta petrosa*, it thins very rapidly, but is continued sufficiently far to cover a portion of the *Crusta petrosa.*

Fig. 181.

I. Transverse section of the premaxillary bone to show attachment of the teeth ; after Hertwig. Magnified 22 times.
II. Dentine and enamel ; after Hertwig. Magnified 500 times.
III. Enamel : after Hertwig. Magnified 500 times.

A   Blood-vessel of the pulp-cavity.
C   Crusta petrosa.
D   Dentine.
F   Processus dentalis.
H   Layer of epithelium.
O   Tooth cuticle.
R   Reserve.
S   Enamel.
X   Cutaneous glands.

δ. The *Crusta petrosa* resembles bone, except that it contains no Haversian canals ; it possesses cells which resemble bone corpuscles, and are usually somewhat rounded or oval and communicate with each other by their processes ; for the most part it is homogeneous and free from cells (Hertwig).

ε. The **pulp-cavity** contains a connective-tissue very rich in cellular elements ; those cells adjacent to the dentine are arranged in a layer (*Membrana eboris*) which has somewhat the appearance of a layer of epithelium. The cells (odontoblasts) of this layer are spindle-shaped, and send processes (dentinal fibres) into the dentinal tubules. A small blood-vessel can be traced into each cavity, but as yet no nerve has been found in the pulp-cavities.

[Smith (*l. c.*) has, after careful investigation, come to the conclusion that the teeth of *R. esculenta* and *R. temporaria* are practically alike, therefore the methods of differentiating the two species by means of the teeth, as given by Leydig, are not to be relied on.]

(3) The **intermaxillary glands** (*Glandula intermaxillaris*) consist of a mass of convoluted tubes, lying chiefly between the pre-maxillary bones and the capsule of the nose, and opening by about twenty to twenty-five ducts at the fore-part of the mouth (Fig. 178 *ID*). A portion of the glands extends high into the nasal cavity (Born), while dorsally another portion lies under the skin and the *M. dilatator* and *M. lateralis narium*, which together act as compressors to the subjacent glands : a small, elastic, cartilaginous rod, placed between the anterior margin of the nasal capsule and the under surface of the ascending limb of the premaxilla, opposes these muscles on either side by its spring-like action (Wiedersheim).

In a fresh skull the openings of the ducts can easily be seen after washing away the mucous secretion ; they are, however, seen to better advantage by treatment with Müller's fluid and subsequent staining with carmine. With sufficient magnifying power, they are then seen as a row of bright dots. The tubules are of uniform thickness, placed closely side by side, and surrounded by a nervous plexus, which contains numerous branching nerve-cells. The epithelium of the tubules is cylindrical, with a rounded, finely granular nucleus ; processes from the peripheral ends of the cells are continued to a *Membrana propria*. The ducts are lined with columnar, ciliated epithelium.

The **secretion** of the glands is remarkably adhesive, and is wiped off by the tongue when it is projected ; by this means the tongue becomes a particularly efficacious instrument for capturing prey. The glands are, both histologically and chemically, pure mucous glands. In urodeles the homologous glands are placed in the hollow septum of the nose, between the nasal cavities.

(4) The **tongue** (Figs. 179, 182, 183) is a broad, fleshy flap on the floor of the mouth, to which it is attached by the anterior half of its ventral surface as far forwards as the chin. Seen from above it has a wedge-like form, being narrow in front and wider behind, where it is prolonged at each angle to form two cornua.

By raising the tongue one obtains a view of a portion of the

M. hyoglossus. The two *MM. hyoglossi* arise (see page 66) some distance apart, and run forwards and towards each other to meet on the ventral surface of the hyoid bone ; they now assume a longitudinal direction, and course forwards parallel to each other until they reach the *M. genio-glossus* (Fig. 182 *G*). Each muscle now divides to form coarse bundles, which ascend on either side of the *M. genio-glossus* towards the dorsum of the tongue. In this course they are encircled by a strong, elastic, connective-tissue sheath. The sheath is incomplete at the hinder end of the *M. genio-glossus*, where it possesses rounded apertures, through which the glossopharyngeal nerves (*N, N*) disappear, to be distributed, after a sharp curve backwards, in the substance of the organ.

The *M. genio-glossus* arises, in two parts on either side, at the side of the chin. One part (Fig. 182 *G*) is dorsal and median, the other (Fig. 182 *G¹*) ventral and external.

The first part, with its fellow of the opposite side, forms an arched commissure in the form of muscular rings, which decrease in

Fig. 182.

Muscles of the tongue, seen from the ventral surface.

G   Median portion of M. genio-glossus.
G¹ Lateral portion of M. genio-glossus.
H   Hyoid.
Hy M. hyoglossus.
L   Larynx.
M Mandible.
N Glossopharyngeal nerve.

size from before backwards, and so form a pear-shaped mass : the second, external portion, extends backwards, with a slight obliquity, as a thin, fan-like expansion, to the mucous membrane, where it is inserted. This arrangement can easily be seen after dissecting away the sheath (Fig. 183 *Hy*); the hindermost fibres curve sharply into the tongue (*Hy¹*); the anterior fibres pass obliquely forwards and blend with the straight fibres of the dorsal portion of the *M. genio-glossus* (Fig. 183 *Gg*). The arcuate fibres of the *M. genio-glossus* pass, for the most part, upwards and outwards to the tips of the posterior bifid border of the tongue; in this course they lie as a rule above the *M. hyoglossus*, but here and there the two muscles intermix (Fig. 183 *Gg¹*), and it is by no means easy to separate them.

Fig. 183.

www.libtool.com.cn

Muscles of the tongue, from the ventral
surface.

G   M. genio-glossus.
Gg   Straight fibres of the M. genio-glossus.
*Gg*1 Curved fibres of the M. genio-glossus.
Hy and *Hy*1 M. hyoglossus.
Z   Borders of the tongue.

The *M. hyoglossus* is the retractor
of the tongue, the *M. genio-glossus*
the protractor.

(For mucous membrane of the
tongue, see organ of taste. The
vocal sacs are described with the
organs of voice and respiration.)

B. The **Oesophagus** and **Stomach**
(Figs. 184, 185, 189, 194, 195,
199).

a. **General description.** The
oesophagus is not separated from the
pharyngo-oral cavity by a sharp line
of demarcation. It has a length of
only a few mm. in medium-sized
frogs (Fig. 184 *Oe*), and lies in the
middle line of the body, supported
on either side by the cornua of the
hyoid bone. The oesophagus lies on
the dorsal wall of the larynx, is smooth externally, and is thrown
into well-marked longitudinal folds internally.

The transition from oesophagus to stomach is somewhat indefi-
nitely marked by a slight dilatation of the tube, often scarcely per-
ceptible, still it can always be recognized by an abrupt curvature to
the left (Fig. 184 *M*), which becomes more prominent when the
stomach is distended. Externally the stomach is seen as an elon-
gated, slightly curved cone, smooth externally and of equal diameter
throughout.

The oesophagus and stomach are held in position by folds of
peritoneum (mesentery), which attaches them to the dorsal wall of
the abdominal cavity, to the lungs, pericardium, and liver; and by
the blood-vessels.

b. **Minute structure.** The walls of these viscera are composed
of four layers or coats.

(1) The **serous coat** (Fig. 186) is a layer of endothelium, lying
on a very thin stratum of connective-tissue; the whole derived
from the peritoneum, which encloses the organs.

(2) The **muscular coat** (Fig. 186 *LM* and *TM*) is arranged in

two layers, one (*LM*) longitudinal, the other (*TM*) transverse. The longitudinal layer is thicker in the oesophagus, and thins as it is continued to the pyloric end of the stomach. The circular layer, on the other hand, gains in thickness; both layers are of unstriated muscular fibre.

(3) The **submucous coat** (Fig. 186 *A*, *B*, and *SM*) is better developed in the stomach than in any other part of the alimentary canal. It is formed of a wide-meshed, loose connective-tissue, which supports numerous blood-vessels and lymphatics. Towards the mucous coat it possesses a well-differentiated *Muscularis mucosa*, which is arranged in two layers, a longitudinal (*B*) and a transverse (*A*).

(4) The **mucous coat** is possessed of numerous tubular glands, which vary in structure according to the part of the membrane examined. They have been the subject of much investigation (Heidenhain, Nussbaum, Partsch, Langley, and others), and are best described in three groups: those of the oesophagus, of the first part of the stomach, and of

Fig. 184.

The alimentary canal.

A	Opening of large intestine into cloaca.
Cl	Cloaca.
D	Small intestine.
Du	Duodenum.
HB	Urinary bladder.
M.	Stomach.
Mz	Spleen.
Oe	Oesophagus.
Py	Pylorus.
R	Large intestine (rectum).
†	Junction of small and large intestine.

the pyloric end of the stomach respectively; between each pair of groups are transitional forms.

a. [The oesophageal glands are complete tubular glands lined by a single layer of epithelium, which very closely resemble the

glandular cells of the fundus of the stomach (Plate II, Fig. 187).
The cells are conical or cylindrical, the protoplasmic contents

Fig. 185.

The abdominal viscera of *Rana esculenta* (female).

D	Small intestine.	*L¹*	Right lobe of liver.
Du	Duodenum.	*L²*	Middle lobe of liver.
EE	Ovaries.	*Lg*	Left lung.
H	Heart.	*Lg¹*	Right lung.
HB	Urinary bladder.	*M*	Stomach.
L	Left lobe of liver.		

granular, the granules being larger than those of the corresponding
cells in the stomach (Langley).   Mucous cells are found among
the true secretory cells.   The cells of the ducts are sometimes,
but rarely, ciliated (Langley).]

β. [The glands of the fundus of the stomach[1] are not so complex as the typical glands of the oesophagus. The cells at the mouth of the gland are continued into fine processes (Fig. 187), and their outer parts contain mucigen. The cells of the neck of the gland are more cubical, and towards the lower part of the neck are mucous cells. The cells of the body of the gland are of irregular shape, and so placed that the nucleus of one cell faces the junction of two cells on the opposite side (Langley). These cells are very finely granular.]

γ. [The glands of the pyloric end of the stomach have been compared with the mouths and necks of the glands of the fundus (Partsch, Langley). The cells are of two kinds only (Fig. 188). The cylindrical cells of the surface of the stomach are continued into the gland, where they become shorter and sub-cubical; these form the greater part of the gland. The cells at the

Fig. 186.

Transverse section through one of the longitudina folds of stomach of *Rana temporaria*. To show general arrangement of the walls.—G. H.

A Transverse layer of muscularis mucosae.
B Longitudinal layer of muscularis mucosae.
LM Longitudinal muscular coat.
M Mucous membrane.
SM Submucous coat.
TM Transverse muscular coat.

deepest portion of the gland are more rounded, and resemble the mucous cells in the neck of the glands of the fundus.]

δ. [Between these well-marked groups of glands are various transitional forms. The transition from oesophageal to gastric glands is not a continuous one, as glands resembling those of the stomach can be found nearer the oesophagus than other glands, which

---

[1] A transverse section through the mucous membrane of the fundus of the stomach of *Rana esculenta* is shown in Plate II, Fig. 187. Alcohol preparation, doubly stained with carmine and anilin blue. After Biedermann. (Obj. II, Syst. 7, Hartnack.)

more nearly resemble oesophageal glands.   At the same point the
mucous membrane is thinner than either in front or behind.   In

Fig. 188.

Transverse section through the
mucous membrane of the
pyloric end of the stomach
of *Rana esculenta.*   After
Partsch. (Obj. II. Syst. 7,
Hartnack.)

the same way an intermediate zone exists
between the typical glands of the fundus
and pylorus of the stomach.]

In both oesophagus and stomach the
mucous membrane is thrown into longi-
tudinal folds when the organs are empty.
The epithelium of the surface of the
oesophagus is mostly ciliated, and possesses
numerous goblet cells ; according to Klein
the cells are not set vertically on the sub-
jacent submucosa, but obliquely.

[The epithelium of the surface of the
stomach is, at least in part, ciliated (Re-
géczy, Trinkler, and others), and has nu-
merous goblet-cells (Schultze, Heidenhain,
Bleyer, Eimer, Oedmonson, and others).]

(5) [The **nerves** of these organs, accord-
ing to Gonjaew, contain both medullated and non-medullated fibres,
which have nerve-cells attached to them.   From these fine branches
pass, either with the blood-vessels or alone, to the mucous coat,
losing their medulla on the way.   In this course they inosculate
very freely, and are then distributed as very fine, beaded fibrils to
the glands and epithelium, which are very richly supplied.]

(6) [The **blood-vessels** and **lymphatics** very closely resemble the
corresponding structures in the small intestine (p. 290) ; the blood-
vessels form a rich anastomosis in the submucous membrane ; the
lymphatics are arranged in two systems, one under the serous coat,
and a larger system in the mucous and submucous coats.   The
oesophagus lies free in a peri-oesophageal lymph-sac (Robinson).]

C. The **Small Intestine.**

a. General description.   The small intestine commences behind
the middle of the abdomen at the pyloric end of the stomach, from
which it is marked off by a slight constriction.   The first portion
of the small intestine is the duodenum (Figs. 184 and 194 *Du*) ; by
means of an abrupt turn it winds directly forwards, parallel to the
long axis of the stomach ; the pancreas is placed in the loop so
formed.

The whole of this portion of the intestine, together with the

greater part of the stomach, is, in the normal condition, under cover
of the liver (Figs. 185, 194) while under the liver the intestine
is firmly attached to the deep surface of that organ by a short
but strong *Ligamentum hepato-duodenale*; it then turns suddenly
backwards, increases in size, and by means of numerous convo-
lutions occupies a considerable portion of the right half of the
abdomen (Fig. 184 *D*). It is held in position by a well-developed
mesentery.

b. **Minute structure.** Like other portions of the alimentary
canal, the small intestine is formed of four layers :—

(1) The **serous coat** presents no peculiarities; it consists simply
of a layer of endothelial cells, with a small amount of sub-endothe-
lial connective-tissue.

(2) The **muscular coat** is in two layers, the outer longitudinal
layer being very thin, the inner circular layer thick.

(3) The **submucous layer** resembles that of the stomach, but is
not so thick; the *muscularis mucosae* is well developed and arranged,
as in the stomach, in two layers.

(4) The **mucous coat** (Fig. 189) is thrown into folds, which differ
in various parts of the tube.

The longitudinal folds of the stomach are compressed together
towards the pyloric end of the stomach (*a*) and diminish in size; at
the commencement of the duodenum they end abruptly (*a¹*), but
without any indication of a valvular arrangement.

Immediately beyond the pylorus the mucous membrane is folded
so as to form an irregular network of folds which inclose irregular
alveoli; the folds are thicker on the concave surface of the duo-
denum, and form a longitudinal ridge (*b*); in this ridge the
alveolar spaces are much smaller than those to either side. The
irregular folding extends through two to three cm., when a more
regular arrangement commences in the form of two adjacent series
of transverse folds (*c, c¹*). Each fold is semi-lunar in shape, with
the convexity attached to the wall of the tube and directed forwards,
while the concave free border and pocket-like space enclosed are
directed backwards.

The arrangement of these folds reminds one of the semi-lunar
valves of the human heart, and probably one of their functions is
to prevent the regurgitation of the chyme (Wiedersheim).

The corresponding valves of opposite sides meet at each end at
an angle, the apex of which is directed away from the stomach. On

Fig. 189.

Mucous membrane of the pyloric end of the stomach and the duodenum.

a   Mucous membrane of the stomach.
*a*¹   Commencement of duodenum.
b   Duodenal mucous membrane arranged in irregular net-work.
c } Semi-lunar folds of the
*c*¹ }   mucous membrane.
d   Longitudinal folds of the mucous membrane.

these folds and between them are smaller, secondary folds, partly irregularly arranged, partly longitudinal (*d d*).

Towards the middle of the small intestine this valvular arrangement is lost, to be replaced by an irregular net-like folding; beyond this longitudinal folds arise, which proceed in a sinuous course towards the large intestine.

The whole mucous membrane, both on the folds and otherwise, is covered with a simple layer of columnar epithelium, which is continued into numerous simple follicles (glands of Lieberkühn) found throughout the mucous membrane of the small intestine. The cells are placed on a basement membrane, which rests on a thin layer of loose connective-tissue, intervening between the epithelial coat and the *muscularis mucosae*. The epithelial cells are intermixed with a large number of goblet-cells, and have between them fine processes from the connective-tissue corpuscles of the subjacent layer; many of these processes extend to or even beyond the free margin of the epithelial cells.

The individual cells are columnar, possessed of a well-marked cell-wall, and have distinct, large, oval nuclei, containing one or more nucleoli. The protoplasmic contents are granular, and with proper treatment show a very distinct intra-cellular network. The free margins of the cells are sharply marked off from the cell-contents, and are more firmly attached to the corresponding portions of adjacent cells than the rest of the cell-wall. This margin has a longitudinal striation, which owing to the important function performed by this part of the intestine, namely, absorption of the fat, has been the subject of many important investigations.

[In the following brief summary of the earlier researches on the minute structure of the intestinal epithelium, in which the intestine of the frog was chiefly used, the memoirs in which these investigations are recorded are referred to in the order of time.

1837. Henle first described the border as a thickened, highly refractive portion of the cell-wall.

1855. Kölliker and Funke, after independent research, described the longitudinal

striation : Funke offered no explanation of the fact, while Kölliker considered it due to the presence of fine tubules. Later Funke gave a modified support to Kölliker's view by admitting the presence of tubules around the circumferential part of the border.

1856. Donders gave a description corresponding with that of Henle.

1857. Brettauer and Steinach gave it as the result of their investigations that the border was composed of closely-applied fine rods : v. Wittich first showed that the borders of adjacent cells were more firmly attached than the rest of the cell ; he admitted the presence of apertures, but considered the whole appearance to be due to post-mortem changes.

Welcker and Friedreich agreed with the views of Brettauer and Steinach, but traced the striation throughout the length of the cells, in fact traced the tubules to the connective-tissue below.

1858. In this year Heidenhain published his results ; he held the striation to be due to the presence of fine rods, and was the first to show that processes of the connective-tissue corpuscles passed up between the epithelial cells ; he found fat globules in the epithelial cells, in the connective-tissue, and in the lacteals.

Friedreich described the striation as continued through the whole length of the cells, and as due to tubules.

1859. Lambl denied the presence of the rods, and considered the whole phenomenon an optical appearance due to the cell-wall ; in this view he was supported by Vlakovich of Padua and Amici of Florence.

1860. Wiegandt held the border to be an independent covering, and the striation to be due to folding or wrinkling.

Col. Balogh described the border as formed of rods, but denied that these existed except when brought about by the action of fats ; in support of this view he showed that the striation was wanting when fat was absent.

1865. Lipsky held the border to be composed of rods.

1866. Henle described the cells as in his former work, but now held the border to be composed of rods, in fact to represent a ciliated border.

1867. Erdmann described the border as being of two layers, an upper, thicker layer, with both longitudinal and transverse striation, and a lower, thinner layer, the true cell-wall. The upper layer he described as capable of splitting in the directions of both striations.

Schultze described the border as not being in intimate connection with the protoplasm of the cell. Arnstein and Wiegandt supported Heidenhain's description.

1868. Albini e Renzoni described the part as resembling resting cilia.

1869. Eimer traced fat-globules into all the parts, epithelium, connective-tissue, and vessels ; and held that the fat could pass from a lacteal to a branch of the Vena porta.

1870. Heidenhain, after further investigation, supported his earlier views.

1874. Thanhoffer described the membrane as perforated, and the protoplasm of the cells as actively sending protoplasmic processes through these apertures ; this he had seen in frogs in which all connection with the spinal nerves had been severed.

1875. Benjamins could not find the striation to be a constant occurrence, and failed to find the processes described by Thanhoffer.

1876. Krause found rod-like bodies round the margin of the border.

1877. Fortunatow supported Thanoffer's view.

1881. Landois observed appearances in Spelerpes fuscus, which led him to support Thanoffer's views.

1883. Wiedersheim supported Thanhoffer's views.

1884. Wiemer supported Thanhoffer's observations.

1888. Paneth failed to find any contractile protoplasmic processes, and asserts that the circumference of the border, when examined under certain conditions, is composed of rods.

From the same causes the goblet- or chalice-cells, already mentioned, have been the subject of much speculation and investigation.

1846. Frerichs drew and described these cells as empty cells.

In 1848 these cells were first described as epithelium capitatum by Gruby and Delafond.

In 1856 Donders described the cells as being open, and as discharging their contents into the canal; the cell-walls being then pressed together by the neighbouring cells, and the cell-contents being then gradually reformed.

In the same year Kölliker published results closely agreeing with those of Donders, and he traced the various stages of the process.

1857. Brettauer and Steinach held them to be cells which had lost their contents, and as the 'cuticular border' was absent, concluded that the cell-contents were in closer connection with the 'border' than with the rest of the cell-wall.

1865. Lipsky and Sachs both doubted the presence of such cells, and considered them due to the action of reagents or post-mortem change.

1866. Letzerich described the cells as open, and regarded them as the commencement of the lacteal system, while Dönitz thought the whole appearance due to reagents.

1867. Schultze and Eimer, independently, described them as unicellular glands. Erdmann, however, again denied their occurrence under normal conditions.

Oeffinger held the goblet-cells to be modified ordinary cylindrical epithelium cells; in which view he was supported by Arnstein.

1868. Schultze and Eimer, after renewed investigations, reiterated their former opinions.

1869. Eimer described the goblet-cells as secreting mucin, and as capable, by division, of throwing out pus-like cells.

1876. Krause described the cells as containing granular contents, which under certain conditions are thrown out.

1877. Tolldt considered them artificial productions. Edinger asserted that they are formed from the cylindrical cells.

1877-1885. Partsch (1877), Klein and Hebold (1879), Stöhr (1880), Patzelt (1882), Haller (1883), Holl (1885), support the last view.

1878. Hoffmann supported Schultze's views.

1886. List describes these organs as unicellular mucous glands.

1887. Paneth described them as secreting mucous and as being derived from the cylindrical cells.]

(5) [The **blood-vessels** of the small intestine (p. 234) have been described by Langer; he finds the vessels arranged in networks, one a subserous network, placed underneath the serous coat, and formed of elongated, irregular, four-cornered meshes. When the intestine is distended the meshes are rectangular.

The vessels to the mucous membrane divide and anastomose very freely in the submucous layer, and then form an irregular network on the inner surface of the *Muscularis mucosa*; this network follows all the foldings of the mucous membrane, and thereby supplies a double layer to each villous fold of the mucous membrane. The meshes are usually four-sided or five-sided.]

(6) [The **lymphatics** of the small intestine (Figs. 190, 191). The lymphatic vessels on reaching the intestine usually bifurcate; the two branches, as a rule, follow and enclose an arterial twig. From the serous layer they receive the contents of a very fine lymphatic plexus, the lumens of which are slightly greater than that of the corresponding capillaries; from the mucous layer they receive the contents of the lacteals: between these two layers the lymphatics anastomose very freely by means of numerous branches (Langer).

The lacteals are lined with an epithelioid layer and traversed by connective-tissue trabeculae, which have a like covering. The

lacteals are not simple but in the form of a coarse network (Fig. 189), (Langer).

(7) [The **nerves** of the small intestine (p. 200) usually follow the arteries to the muscular coats, between which they form a plexus (Auerbach's plexus); from this numerous twigs are given off, which course alone or in company with vessels to the mucous coat, where a second plexus (Meissner's plexus) is formed. Auerbach's

Fig. 190.

Isolated fold of mucous membrane of small intestine of *Rana temporaria*; after Langer. Forty times natural size. Blood-vessels striped, lacteals shaded.

plexus, according to Klein, consists of bands of nervous fibrils in endothelial sheaths; they branch and inosculate, and thus form a plexus. Where several such branches meet, a more or less complicated decussation of the bands of fibres takes place. Along these nervous bands are ganglion cells, either isolated or in groups. The cells are large, generally spherical, and contain a sharply outlined nucleus with a single or double nucleolus. The smaller cells generally appear to possess only one process, which can be traced from the protoplasm of the cell between the fibrils of the nerve-trunk. The larger cells are distinctly multipolar, their protoplasm being provided with a number of fine processes, or, as is oftener the case, with one large and several small processes. In many instances Klein was able to distinguish around the ganglion-cells a capsule of a spherical or ovoid shape. In these cases the body, as well as the processes of the ganglion-cell, were lying within the capsule. This system of ganglion-cells is in connection with the individual bundles within the nerve-trunks.

Fig. 191.

Transverse section of a fold of the mucous membrane of *Rana temporaria*; after Langer. Sixty times natural size.

A   Lacteals with transverse trabe-culae.
B   Circular muscular layer.
C   Longitudinal muscular layer. Blood-vessels striped.

U 2

Klein describes a second system of ganglion-cells, situated in meshes, which are formed by the nerve-trunks of the plexus itself. These ganglion-cells are much larger than the former, and are multipolar; their protoplasm, which is distinctly fibrillar, with granules between the fibrils, is provided with one or two long, thick processes and several short and thin ones; generally the processes are branched. The general shape of the cells is oblong, the thick, long processes being commonly at the two opposite poles. The cells are generally isolated, sometimes situated in the centre of a mesh, or more commonly near a nerve-trunk that borders the mesh on one side. Each ganglion-cell is connected with a nerve-trunk of the plexus by at least one process. In a few of the nerve-trunks of the general plexus, isolated medullated nerve-fibrils are seen to pursue an almost straight course from one trunk into another and divide into two. There is no connection between these medullated fibres and the ganglion-cells.

Fig. 192.

From a transverse section of the large intestine of *Rana temporaria*, moderately distended. —G. H.

A   Denser portion of submucous coat.
B   Looser portion of submucous coat.
C   Artery, cut obliquely.
D   Circular muscle-layer.
E   Longitudinal muscle-layer.

Auerbach's plexus is a much finer plexus than that just described, and the ganglia are much smaller. It supplies twigs to the *Muscularis mucosa*; these break up into fine fibrils, which follow the direction of the muscle-fibres; other twigs supply the blood-vessels, with which they can be traced into the bases of the folds of mucous membrane. Thanhoffer has recently (*l. c.*) described nerve-fibrils, which terminate in the mucous epithelium.]

D. The **Large Intestine** (Fig. 184 *R*).

a. **General description.** The large intestine is a flask-shaped viscus, lying in the median line. The small intestine opens into it

by an abrupt curve at its anterior end. The large intestine is the widest part of the alimentary canal, is thin-walled, and diminishes in width towards its hinder end, where it opens into the cloaca above the opening of the bladder.

b. [**Minute structure.**

(1) The **serous coat** resembles that of the small intestine, etc.

(2) The **muscular coats** resemble those of the small intestine, but are thinner; the longitudinal layer is, however, proportionally thicker (Wiedersheim).

(3) The **submucous coat** (Fig. 192) resembles that of the small intestine in its general structure; the portion lying immediately beneath the mucous membrane (*B*) is denser in structure.
This layer has no *Muscularis mucosa.*

(4) The **mucous coat** (*A*) is a simple layer of large, columnar, epithelial cells, with large oval nuclei. The cells have a hyaline free border, but this possesses no stri-ation. The mucous membrane is usually described as possessing numerous simple follicles (glands of Lieberkühn); in those specimens which I have exa-mined they have been entirely absent (Figs. 192, 193). At six to eight points in a transverse section of a rectum moderately distended the sub-mucous coat is thinner, and so throws the mucous coat into slight, longitudinal grooves; but these do not in the least resemble the glands of Lieberkühn.

(5) The epithelium possesses goblet- or chalice-cells (Hoffmann), the number of which probably depends upon the period of the year and the state of digestion. In the rectum, from which the section for the figures 192 and 193 were cut, not one goblet-cell was found in a complete series of sections.

Fig. 193.

Transverse section of large intestine of *Rana esculenta*; the mucous mem-brane thrown into longitudinal folds in consequence of the organ being contracted. Arteries injected with carmine.—G. H.

A Large circular vessels within the muscular coats.

B Fine anastomosis to the mucous coat.

If the rectum be contracted, the mucous membrane is thrown into longitudinal folds.

(6) The **blood-vessels** (Fig. 193) have a simple arrangement. The arteries are large, and form oblique loops around the intestine, lying under the peritoneum ; from these branches are given off to form a series of rings in the submucous membrane (Fig. 193 *A*) ; from these fine twigs are given off to form a fine anastomosis under the mucous membrane (*B*).

(7) The **lymphatics** of the large intestine are arranged in two chief systems : one under the serous coat resembles the corresponding system of the small intestine. The second set forms a network of rounded loops in the submucous coat, which give rise to a secondary set of smaller vessels towards the mucous membrane ; this secondary system forms a sort of trellis-work standing on the rounded loops, and so maps out small blocks of the thick submucous coat. Towards the cloaca the arrangement is simpler ; the secondary lymphatics are lost, while the primary lymphatics tend to form elongated, longitudinal loops (Langer).]

II. THE GLANDS CONNECTED WITH THE INTESTINAL CANAL.

A. The **Liver** and **Gall-bladder**.

a. **External form**.

(1) The **liver** (Figs. 185, 194) is a large, reddish-brown organ, occupying a large part of the anterior abdominal region. It consists of three or more lobes, which present many individual variations ; as a rule there are two larger lateral lobes (*L* and *L¹*), and a smaller median lobe (*L²*). Each lobe has a superficial or ventral surface, which is convex, and a deep or dorsal surface, which is concave and directed towards the other abdominal viscera lying above the liver. The two surfaces of each lobe meet to form a sharp border around the lobe, except where the three lobes are more intimately attached, opposite the apex of the heart (Figs. 185, 194) ; at this place each lobe possesses a small, flat, or slightly concave anterior surface.

The left lobe (*L*) hides the greater portion of the stomach, and has near its inner border a deep fissure, which runs forwards and

so marks off a more or less well-marked fourth lobe.   The anterior portion of the left lobe is attached to the corresponding portion of the right lobe by a narrow commissure.

The median lobe (L^2) extends backwards as far as the pylorus, and covers the commencement of the intestine together with the pancreas; these organs can, therefore, not be seen until this lobe is displaced.   A fifth lobe is sometimes found on the dorsal surface of the median lobe, and to it or to the dorsal surface of the median lobe the small intestine is attached by the *Ligamentum hepato-duodenale* (Fig. 195 *Lhp*).   The *Vena portarum* enters the liver behind this ligament.

The right lobe extends much further dorsalwards than the left lobe, and even comes in contact with the lung, the vessels of which sometimes indent its surface in spirit specimens. This lobe is also in contact with the base of the fat-body, and in females with the oviduct.

By drawing the lobes of the liver to either side and displacing the heart towards the head, the posterior caval vein is seen passing from the liver to the heart, and the hepatic commissure joining the lateral lobes is brought into view.

(2) The **gall-bladder** (Fig. 195 *G*) is placed on the dorsal surface of the liver in the deep niche between the right and left lobes; it is attached to the liver by connective-tissue and peritoneum.

The gall-bladder is round or oval in form; when moderately full it has a smooth, outer wall, which is thin and allows the green colour of the bile to be seen.   It possesses a duct (*Dcy*), the cystic duct (*Ductus cysticus*), which bifurcates near its origin.

The two cystic ducts (Fig. 195 *Dcy*) join the larger hepatic ducts, as shown in the figure, and so form a simple anas-

Fig. 194.

The liver, seen from the ventral surface.

Du   Duodenum.
H   Heart.
L   Left lobe of liver.
L¹   Right lobe of liver.
L²   Middle lobe of liver.
M   Stomach.

tomosis, from which three branches (3) of varying size unite at the anterior extremity of the pancreas to form the common bile-duct

Fig. 195.

The pancreas and bile-canals. The liver has been displaced towards the head.

Dc   Common bile-duct.
Dc¹   Common bile-duct after leaving the pancreas.
Dc²   Opening of the common bile-duct into the duodenum.
Dcy   Cystic ducts.
Dh   Hepatic ducts.
Dh¹   Supplementary hepatic ducts from the middle lobe of the liver.
Du   Duodenum.
G   Gall-bladder.
L   Left lobe of the liver.
L¹   Right lobe of the liver.
L²   Middle lobe of the liver.
L³   Fourth lobe of the liver.
Lhp   Gastro-hepatic ligament.
M   Stomach.
P   Pancreas.
Py   Pylorus.
P¹   Ducts of the pancreas.

(*Ductus choledochus, Dc*). The common bile-duct runs through the whole length of the pancreas, receiving near its origin additional hepatic ducts (*Dh¹*) from the middle lobe of the liver. In this course the duct lies either on the ventral surface of the pancreas or under a thin layer of the glandular tissue; it receives the ducts of the pancreas and leaves that organ at its posterior border as a round and strong canal (*Dc¹*). The duct courses in the gastro-duodenal ligament, and reaches the dorsal surface of the duodenum at a very acute angle; it then pierces the wall obliquely and terminates with a slit-like or elongated oval opening.

b. [Minute structure.
(1) The liver is composed of various tissues: it possesses a peritoneal covering, a fibrous covering, which supplies trabeculae to support the

various other tissues, blood-vessels, hepatic cells or true liver parenchyma, and bile-canals.

a. The peritoneal covering of the liver encloses the organ almost completely, the only exceptions being where the various

attachments of the liver are found (see peritoneum). The peritoneal covering of the liver is for the most part composed of flattened, ciliated cells (Neumann and Grunau); on the middle lobe these are, however, more or less replaced by non-ciliated cells. The thickness of these cells varies considerably, according to the amount of distension to which the liver is subjected.

β. The **fibrous covering** of the liver is very thin and very difficult to demonstrate ; it consists of connective-tissue fibres with very few corpuscles. This covering is prolonged into the liver along the portal canals, where traces of connective-tissue can always be made out.

From these processes and from the whole of the inner surface of the general connective-tissue capsule are given off fine trabeculae, in which it is very difficult to find any nuclei ; these trabeculae are everywhere extremely delicate and difficult to demonstrate ; nowhere do they form distinct boundaries between lobuli : the structure closely resembles the sustentacular tissue of a lymphatic gland (Eberth).

γ. The **blood-vessels** to the liver are the portal vessels (p. 249), the hepatic veins (p. 247), and the hepatic artery[1] (p. 233).

(1) The portal vessels pass into the liver on its ventral surface ; they divide into branches which course along the middle parts of each lobe and give off smaller branches in all directions towards the periphery ; the interlobular branches (Fig. 196 I) forming a very complex capillary network. As compared with the hepatic veins (Fig. 196 II), the interlobular veins do not give off their capillaries so abruptly, but tend to supply these from small lateral branches. The portal veins are accompanied in their course by branches of the hepatic artery, and often by larger bile-ducts, and thus form portal canals. In no part do the portal (interlobular) veins or their branches limit the lobules by distinct rings of vessels, as seen in many higher animals. The interlobular veins and intralobular veins simply interdigitate with each other.

---

[1] See Plate II, Fig. 196.

  I. Partial injection of the liver from the portal vein (blue) : *Rana esculenta.*—G. H.
  II. Partial injection of the liver from the hepatic vein (red) : *Rana esculenta.*—G. H.
 III. Complete injection of the liver from the hepatic artery (red) and from the portal vein (blue) : *Rana esculenta.*—G. H.

      A Portal (interlobular) veins and their branches.
      B Hepatic (intralobular) veins and their branches.
      C Hepatic arteries and their branches.

(2) The hepatic veins (Fig. 196 I and II) also course chiefly in the middle parts of the lobes of the liver; they branch, and ultimately supply intralobular veins which interdigitate with the interlobular veins (I and II). The capillaries arise very abruptly from an intralobular vein, and form a network of vessels communicating very freely with the corresponding capillaries of the interlobular veins.

(3) The hepatic arteries (Fig. 196 III) break up into small branches which, as a rule, course along the portal canal until near the surface of the liver, when they leave the portal veins and pass to the surface to supply the coverings of the liver. In their course along the portal canals they supply a few very small twigs to the structures forming the canals. At the surface of the liver the branches of the hepatic artery form capillaries, which empty themselves into the general capillary anastomosis beneath (Fig. 196 III).

δ. The **liver-cells** (Figs. 197, 198) are large, and of compressed spheroidal or polygonal shape. They possess no cell-wall, have usually one but sometimes two large nuclei, each with a distinct nucleolus. The cells often contain granules of glycogen or fat-globules. The main fibrillae of the intercellular network are arranged so as to extend between a bile-capillary and a blood-capillary (Fig. 197).

ε. The **bile-ducts** (Fig. 198) commence as fine tubes between the liver-cells, where they are simply small spaces enclosed by the hepatic cells; they are usually enclosed by three or four cells, possibly sometimes by only two cells (Hering). Such bile-capillaries are usually separated from a blood-capillary by the thickness of one liver-cell only (Fig. 198).

As a number of such bile-capillaries run together to form a larger duct, the cells enclosing them change their character, becoming flattened and broader; these cells may, however, be traced continuously into the true hepatic cells (Hering and Eberth). The bile-duct so formed then obtains a slight covering of fibrous tissue, which rapidly increases in quantity, courses along a portal canal, and receives other ducts on the way; the epithelium lining it gradually becomes more elongated, and ultimately resembles that found in the common bile-duct or the gall-bladder.

In the larger ducts the epithelium is, according to v. Brunn,

ciliated ; they also possess a layer of unstriated muscle-fibre (Eberth).

ζ. The **pigment** of the liver varies very much in amount and character, according to the time of the year and state of health of the animal. According to Eberth the pigmentary masses are of about the same size as the white blood-corpuscles, and are possessed of the power of amoeboid movement (in young animals). The cells possess two

Fig. 197.

Liver-cells, after Kupffer.

to seven nuclei and vary much in colour and distribution. As a rule the larger the amount of pigment in a given liver the

Fig. 198.

The bile-capillaries ; natural injection with sulphindigotate of sodium: v v v represent blood-capillaries.—G. H.

smaller is the number of fat-globules found in the individual liver-cells (Eberth).]

(2) [The **gall-bladder** and **bile-ducts**. The gall-bladder has four coverings.

a. A serous coat of peritoneal endothelium.

β. A muscular coat, containing unstriated muscle-fibres and connective-tissue.

γ. A sub-mucous coat of areolar-tissue.

δ. An internal lining of columnar epithelium.

ε. The walls of the gall-bladder are richly supplied with blood-vessels from the cystic arteries (p. 233); these form a close network in the submucous coat.

ζ. The muscular and submucous coats also possess a rich nervous plexus, which contains ganglia and resembles Auerbach's plexus of the intestine (Popoff, Gerlach).]

B. The **Pancreas** (Fig. 199 P).

a. **General description.** The pancreas is a flattened, light yellowish-brown organ, placed in the loop of the duodenum between this latter and the stomach. The whole organ is within the gastro-duodenal ligament, and is attached to the liver; hence it is little influenced by changes in the amount of distension of the stomach or intestine.

Fig. 199.

The pancreas and bile-canals. The liver has been displaced towards the head.

Dc   Common bile-duct.
Dc¹   Common bile-duct after leaving the pancreas.
Dc²   Opening of the common bile-duct into the duodenum.
Dcy   Cystic ducts.
Dh   Hepatic ducts.
Dh¹   Supplementary hepatic ducts from the middle lobe of the liver.
Du   Duodenum.
G   Gall-bladder.
L   Left lobe of the liver.
L¹   Right lobe of the liver.
L²   Middle lobe of the liver.
L³   Fourth lobe of the liver.
Lhp   Gastro-hepatic ligament.
M   Stomach.
P   Pancreas.
P¹   Ducts of the pancreas.
Py   Pylorus.

The organ may be completely exposed by either of two methods: in the former, the liver, stomach, and duodenum are drawn towards the head and

the dorsal surface of the organ so exposed. In the second method the liver is drawn backwards, the various peritoneal folds which connect the duodenum with the posterior border of the liver cut through, and the three organs then separated; the pancreas can then be conveniently examined.

The size and shape of the pancreas are subject to great variations in different specimens. The usual shape of the organ is somewhat triangular (Fig. 199), the left border being usually unbroken, while the other two shorter borders are broken into lobes. The longest lobe stretches as far as the pylorus (Py), to which it is attached by connective-tissue : the opposite extremity of the gland is attached to the liver.

The excretory duct of the pancreas (*Ductus Wirsurgianus*) opens into the common bile-duct at about the middle of the pancreas (P^1); other smaller ducts may open into the same canal.

b. **Minute structure.** [The pancreas consists of a number of lobes loosely held together by connective-tissue; each lobe is composed of a number of lobules attached to each other much more intimately. The lobules are made up of tubes lined by a single layer of glandular epithelium. This epithelium is, as a rule, broadly columnar, but in the smaller tubes may be cubical or polygonal. Each cell has a cell-wall, nucleus, and very granular protoplasm; the latter shows two zones (in the inactive condition), a granular zone near the lumen, and an outer, clear, and finely striated zone (Nussbaum). The lumen of each alveolus is very small, and in many cases difficult to make out.

The smallest ducts have no special lining, and are therefore bounded by the glandular cells; the larger ducts have a flattened, cubical epithelium, which when seen from the surface has an appearance as if the individual cells were widely separated from one another; these ducts have a considerable layer of connective-tissue around them. The largest ducts are lined with a layer of columnar, ciliated epithelium; the cilia are very long, usually of about the same length as the cell, sometimes appearing to be even longer. This epithelium is continuous with the ciliated, epithelial layer of the common bile-duct, which it resembles. These largest ducts have an extremely thick layer of connective-tissue around them.

The pancreas and its ducts are very richly supplied with vessels and nerves ; the nerves forming everywhere a fine plexus, the larger strands of which usually, but not always, course with the larger

blood-vessels. The larger ducts have an especially rich supply of nerves, of which fibrils may be traced towards the ciliated epithelium ; an anatomical connection between the two has not, however, been made out.]

III. THE SPLEEN.

a. General description. Although the spleen belongs to the lymphatic system, it is considered here in order to complete the description of the abdominal viscera. It is a small, rounded-oval body, of a reddish-brown colour, suspended in the mesentery near the anterior end of the large intestine (Fig. 184 *Mz*). In medium-sized animals the longer diameter is about 6 mm., and is parallel with the long axis of the body; the shorter diameter is about 5 mm., and the thickness varies from about 3 mm. to 4 mm. The dorsal surface is flat or slightly concave (*Hilus lienis*), and receives the relatively large afferent and efferent vessels ; the rest of the organ is smooth and rounded, and with its greatest convexity directed towards the left side.

b. [**Minute structure.** The structure of the spleen resembles that of higher animals. It possesses a **serous coat** of peritoneum, under which is a **fibrous coat** ; the latter sends in trabeculae, which divide and form a fine meshwork of supporting-tissue ; the finest trabeculae are formed by the processes of the connective-cells of the sustentacular structure. According to Hoffmann, the thickness of the fibres averages 0·001 to 0·011 mm.; the intervening spaces measure 0·002 to 0·012 mm. The spaces are filled by the spleen pulp, which consists of true spleen-corpuscles, blood-corpuscles, and pigment-corpuscles.

The **spleen-corpuscles** have an average diameter of 0·006 mm., and are round or of a rounded oval form. Each consists of a nucleus, with a very small amount of adherent protoplasm ; the nucleus possesses one or two nucleoli. Some of these cells contain a brownish or black pigment in granules, but most of them are colourless (Hoffmann).

The **pigment-cells** equal the white blood-corpuscles in size, and exactly resemble the corresponding pigment-cells of the liver.

The **blood-corpuscles** are found in various stages of disintegration and regeneration.

The **arteries**, on entering the spleen, at once break up into branches which pass in all directions, giving off twigs on all sides and at varying angles; from these capillaries are supplied, which traverse the parenchyma in all directions. The capillaries empty themselves partly into veins, partly into the splenic spaces.

The **veins** commence either as capillaries in connection with the arteries or by communicating with the splenic spaces. This communication is brought about by small twigs of about o·015 mm. diameter, which have incomplete walls, and so open into the splenic spaces (Hoffmann).

Malpighian bodies are represented by collections of splenic cells on various arterial twigs; they are, however, not so sharply defined as is the case in some higher animals.]

IV. THE PERITONEUM.

a. General description. The **peritoneum** is a thin, pigmented membrane lining the abdominal cavity. Tracing it forwards from the ventral wall of the abdomen (*Peritoneum parietale*), it can be followed along the deeper surface of the muscles to the pericardium. The middle portion leaves the abdominal wall by accompanying the anterior abdominal vein; the lateral portions are continued further forwards, and then ascend on the pericardium and the deeper surfaces of the lateral walls in the thoracic region.

The peritoneum passes thence to the ventral surface of the liver (*Ligamentum coronarium*), covers this surface and passes on to the dorsal surface of the organ, which, together with the gall-bladder, it completely encloses. The membrane thus reaches the dorsal wall (*Ligamentum suspensorium hepatis et pericardii*); from the lateral borders of the liver it passes upwards to the dorsal wall, and thus forms a pocket-like pleuro-peritoneal cavity on either side.

From the dorsal wall and above the attachment of the coronary ligament of the bladder the peritoneum reaches the root of the lung on each side, and completely invests the organ: while in the middle line it covers the outer surface of the oesophagus and attaches it to the dorsal wall, thus forming the first part of the mesentery

Just behind the root of the lung, the peritoneum, in female speci-
mens, has an opening on each side (*Ostium abdominale tubae Fallo-
piae*), by which the oviduct communicates with the peritoneal cavity.

Tracing the peritoneum backwards, it passes over the ventral sur-
face of the kidneys so as to exclude them from the peritoneal sac:
in the middle line, between the kidneys, the peritoneum descends to
form the mesentery for the small intestine. At the inner borders
of the kidneys, the testes or ovaries are pushed into the abdominal
sac, and so possess well-marked mesenteries; the mesovarium be-
comes longer towards the cloaca, but attains its greatest develop-
ment in the breeding season, when it is arranged in numerous folds.
Along the outer borders of the kidneys, in females, the peritoneum
again descends into the abdominal cavities to enclose the oviducts,
which have broad mesenteries. Towards the rectum these mesen-
teries are shorter and attached to either side of the bladder by a
well-marked free border: as the middle line of the bladder is
attached by the peritoneum to the rectum, two distinct pouches
(*Cava recto-vesicalia*) are formed, which descend deeply into the
pelvic cavity. The upper walls of these pouches are pushed in be-
tween the urostyle and the rectum, and together form a strong
meso-rectum, which is longer near the *Valvula Bauhinii* and con-
tinuous with the mesentery of the small intestine. The hinder
portion of this mesentery is very short, and only covers the lateral
walls of the rectum.

With the exception of a small portion of its dorsal surface, which
is attached to the rectum, the whole surface of the bladder is covered
with peritoneum.

The mesentery of the alimentary canal commences in connection
with the oesophagus between the roots of the lungs; it is attached
to the dorsal surface of the liver, covering the posterior caval vein,
and is attached to the gall-bladder. From this point it extends, as
a free, arched fold, to the concave right border of the stomach,
which is completely surrounded by peritoneum.

The gastro-duodenal fold (*Ligamentum gastro-duodenale*) extends
from the stomach to the pylorus and includes the pancreas. The
hepato-duodenal fold (*Lig. hepato-duodenale*) extends from the portal
fissure of the liver to the duodenum.

The mesentery of the small intestine is broad and arranged in
folds, which follow the curves of the intestine; and is attached in
the middle line, immediately beneath the vertebrae, where it encloses
the aorta.

The various folds and mesenteries carry the blood-vessels and nerves to the different organs ; in this course the vessels are surrounded by large lymphatics, which communicate with each other.

Fig. 201.

Preparations from the peritoneum of *Rana esculenta.*—G. H.

I. From peritoneum of the ventral wall of abdomen, stained with silver and logwood (Hartnack, Oc. I, Syst. 7).
II. From mesentery of small intestine of *Rana esculenta*, stained with silver (Hartnack, Oc. I, Syst. 7).
III. Preparation to show ciliated cells between non-ciliated cells ; after Neumann.
IV. Vertical section at border of liver to show ciliated epithelium ; after Neumann.

A Stoma.
B Pigment-cells.
C Ciliated cells.
D Non-ciliated cells.

b. Minute structure (Fig. 201).

[The peritoneum is a serous membrane, formed for the most part of a layer of irregular endothelial cells, arranged on a thin layer of subserous, connective-tissue (Fig. 201 I, II, and III).

The endothelial cells are attached to each other by cement-substance, easily stained by silver nitrate. The cells covering the general surface of the peritoneal cavity are larger and broader than those covering the mesentery of the small intestine (compare I and II, Fig. 201).

At various points stomata are found, bordered by smaller and more deeply staining epithelium (I, *A*). The membrane covering the general cavity is also much more pigmented than that covering the mesentery (compare I and II).

Various portions of the peritoneal surface possess ciliated cells,

x

and these cells are usually thicker than the surrounding non-ciliated cells. Such cells are found especially near the openings of the oviducts and on the liver. The dimensions of the cells vary; according to Neumann the average dimensions of ciliated cells on the liver are: 0·006 mm. depth (without the cilia); nucleus, 0·012 mm. long and 0·003 mm. broad. The cells are five- or six-sided and bounded by straight sides (Neumann).]

SECTION VI.

THE LARYNX, LUNGS, VOCAL SACS, THYMUS AND THYROID GLANDS, AND THE LYMPHATIC GLANDS (TONSILS?) OF THE HYOID REGION.

THE LARYNX, LUNGS, VOCAL SACS, ETC.

LITERATURE.

THE LUNGS AND LARYNX.

Arnold, J., Zur Histologie der Lungen des Frosches. Virchow's Arch. 1863. Vol. XXVIII, p. 433.

Auerbach, L., Ueber den Bau der Blutcapillaren in den Lungen des Frosches und an einigen andern Orten. Amtlicher Bericht über die vierzigste Versammlung deutscher Naturforscher und Aerzte. 1886, p. 241.

Brittan, Brit. and Foreign Medico-chirurgical Review, 1857. Vol. XX.

Eberth, C. J., Ueber den feineren Bau der Lunge. Zeitschr. f. wiss. Zool. 1863. Vol. XII, p. 427.

Eberth, C. J., Ueber den Bau und die Entwicklung der Blutcapillaren. Würzburger naturw. Zeit. 1866-67. Vol. VI, pp. 27-32.

Egorow, W., Ueber die Nerven der Lungen. Centralbl. f. med. Wiss. 1879, p. 305.

Elenz, E., Ueber das Lungenepithel. Würzburger naturw. Zeit. 1864. Vol. V, pp. 66-84.

Frommann, C., Ueber die spontan, wie durch Durchleiten inducirter Ströme, an den Blutzellen v. Salamandra maculata und an den Flimmerzellen von der Rachenschleimhaut des Frosches eintretenden Veränderungen. Jenaische Sitzungsb. 1880.

Gegenbaur, C., Ueber Drüsenzellen in der Lungen-Schleimhaut bei Amphibien. Arch. f. Anat. u. Physiol. 1863, p. 157.

Griffini, L., Contribuzione alla patol. del tessuto epiteliale cilindrico. Arch. per le scienze mediche. 1884. Vol. VIII, pp. 1-43.

Grützner, Physiologie der Stimme und Sprache. Hermann's Handb. d. Physiol. Vol. I, Pt. II, p. 146.

Henle, J., Vergleichende Anatomische Beschreibung des Kehlkopfes. Leipzig, 1839.

Hoffmann, C. K., in Bronn's Klassen und Ordnungen des Thierreichs. Leipzig und Heidelberg, 1873-78. Vol. VI, pp. 514-531.

Hoffmann, T., Die Lungengefässe der Rana temporaria. Dissert. Dorpat, 1875.

Holmgren, F., Upsala Läkareförenings Förhandlingar, 1867. Vol. III, pp. 389-399.

Howes, G. B., On a hitherto unrecognised feature in the larynx of the anurous amphibia. Proc. Zool. Soc. London, 1887, p. 491.

Hüter, C., Ueber den Kreislauf und die Kreislaufstörungen in der Froschlunge. Centralbl. f. med. Wiss. 1873. Nos. 5 and 6.

Kandaraski, M., Ueber die Nerven der Respirationswege. Arch. f. Anat. u. Phys. 1881, p. 1.

Küttner, Beitrag zu den Kreislaufsverhältnissen in der Froschlunge. Virchow's Arch. 1874. Vol. LXI, p. 21.

Leydig, Anatomische-histologische Untersuchungen über Fische und Reptilien. 1853.

Malpighi, De pulmonibus. Oper. omn. Lugd. Batav. 1687. Vol. II, p. 328.

Müller, H., Ueber das Vorkommen glatter Muskelfasern in den Lungen der Amphibien. Würzburger naturw. Zeit. 1861.

Pertik, O., Untersuchungen über Nervenfasern. Arch. f. mik. Anat. 1881. Vol. XIX, p. 183.

Ranvier, L., Leçons sur l'histologie du système nerveux. Vol. I, pp. 98–101.

Schestopol, A., Ueber die Durchlässigkeit der Froschlunge für gelöste und körnige Farbstoffe. Virchow's Arch. 1879. Vol. LXXV, p. 199.

Schultze, F. E., Epithel und Drüsenzellen. Arch. f. mik. Anat. 1867. Vol. III, p. 145.

Schultze, F. E., Die Lungen, in Stricker's Handbuch der Gewebelehre.

Stirling, W., On the nerves of the lungs of the newt. Journ. of Anat. and Physiol. 1882, p. 96.

Treviranus, C. R., Beobachtungen aus der Zootomie u. Physiologie; nach dessen Tode herausgegeben von L. C. Treviranus. Bremen, 1839.

THE THYMUS GLAND.

Ecker, Blutgefässdrüsen, in Wagner's Handwörterbuch der Physiologie, 1853. Vol. IV, p. 114.

Fleisch, E., Ueber den Bau einiger sogenannten Drüsen ohne Ausführungsgänge. Wiener Akad. Sitzungsb. 1870. Vol. LX, Pt. II, p. 55.

Gegenbaur, Vergleichende Anatomie.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreiches. 1873–1878. Vol. VI, p. 503.

Leydig, Lehrbuch der Histologie. 1857, p. 422.

Tolldt, Ueber lymphoide Organe der Amphibien. Wiener Acad. Sitzungsb. 1868. Vol. LVIII, Pt. II, p. 171.

Watney, H., The minute anatomy of the thymus. Phil. Trans. 1882. Vol. CLXXIII, p. 1100.

THE THYROID GLAND.

Baber, E. C., Researches on the minute anatomy of the thyroid gland. Phil. Trans. 1881. Pt. III, p. 577.

Ecker, Blutgefässdrüsen, in Wagner's Handwörterbuch der Physiologie, 1853. Vol. IV.

Fleisch, E., Ueber den Bau der sogenannten Schilddrüse des Frosches. Wiener Acad. Sitzungsb. 1868. Vol. LVIII, p. 57.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreiches. 1873–1878. Vol. VI, p. 503.

Huxley and Martin, Practical Biology. 4th edit., 1877, p. 181.

Leydig, Lehrbuch der Histologie. 1857, p. 376.

Müller, J., Ueber die Entwicklung der Schilddrüsen des Frosches. Wiener Sitzungsb. 1871. Vol. VI, pp. 428–553.

Müller, W., Ueber die Entwicklung der Schilddrüse. Jenaische Zeitschr. 1871. Vol. VI, p. 438.

Ponicaré, Zur Anatomie der Glandula thyroidea. Journ. de l'anat. et de la physiol. 1877. Vol. XIII, pp. 123–143.

Rolleston, Forms of Animal Life. 2nd Edit. 1888, p. 77.

Zeiss, O., Mikroskopische Untersuchungen über den Bau der Schilddrüse. Dissert. Strassburg, 1877.

THE LARYNX, LUNGS, VOCAL SACS, ETC.

I. THE LARYNX.

THE larynx (Fig. 202) is a short wide tube placed between the posterior cornua of the hyoid, to which it is attached by connective-tissue. The long axis of the tube lies in the median line and almost horizontally, but the posterior end is on a slightly lower level than the anterior, when the animal is in the natural sitting position (Fig. 202). The anterior end of the larynx opens into the mouth by a longitudinal slit (Fig. 179 *L*), and is placed in a slight depression caused by the folding of the mucous membrane; the posterior end communicates with the cavities of the lungs.

The larynx is

Fig. 202.

Dissection to show the position and relations of the larynx. The animal (*Rana esculenta*) is in the natural sitting position; the toes of the fore-foot are, however, too much flexed.—G. H.

B	Brain.
C	Gall-bladder.
E	Opening of Eustachian tube.
Eo	Oesophagus.
F	False vocal cords.
G	Epiglottis.
H	Heart.
L	Liver.
V	True vocal cords.

lined with mucous membrane, which is continuous, in front with that of the mouth, behind with that of the lungs. The organ has a skeleton of cartilage, and possesses special muscles,

by which the supply of air to the lungs, and the voice can be regulated.

a. **The cartilages of the larynx.**

The cartilages of the larynx are five in number, of which four are paired and one is single.

(1) The **cricoid cartilage** (Figs. 203, 204) is an oval ring of cartilage with various processes. The ring-like portion of the cartilage is placed in a plane which is almost vertical, but which is directed slightly upwards anteriorly, and slightly downwards posteriorly (the animal being in the usual sitting position).

Fig. 203.

The cartilaginous skeleton of the larynx.

I. Seen from in front ; the spinous process would normally be more curved.
II. Seen from the left side ; the spinous process should be more curved.

Ca	Right arytenoid cartilage.	SR Opening to larynx.
Ca^1	Left arytenoid cartilage.	* * * The two outer asterisks are above the two
$C.l.^1$–$C.l.^4$ Cricoid cartilage.		apices of the left arytenoid cartilage ; the
P	Lateral plate of cricoid cartilage.	middle one above the pre-arytenoid carti-
Sp	Spine of cricoid cartilage.	lage.

The sides of the ring are slightly curved inwards on the anterior surface, and possessed of irregular enlargements ($C.l.^1$–$C.l.^4$), the space enclosed by this portion of the cartilage is occupied by a membrane (M), which forms the floor of the body of the larynx.

From each side of the body of the cartilage, a process ($C.l.^2$) is given off, which curves backwards and inwards to join its fellow of the opposite side, the two forming a blunt spinous process (Sp), which projects backwards, and is intimately attached to the oesophagus. Between these processes and the lower portion of the body of

the cricoid cartilage are the apertures of the roots of the lungs (Fig. 203), which, by their attachments to these cartilages, are kept open.

(2) The **arytenoid cartilages** (Fig. 203 I, II, Ca, Ca^1) are a pair of cartilages placed in front of the cricoid cartilage, one on each side. Each cartilage is semilunar in shape, concave internally, and convex externally. The cartilages are placed almost vertically, with their posterior borders or bases parallel to the body of the cricoid cartilage. The superior borders (Fig. 204) are directed upwards and forwards, the inferior downwards and forwards. The superior and inferior borders are separated by a semicircular notch, bounded by two sharp apices. The superior and inferior angles of the two cartilages are close together, and movably attached to each other by connective-tissue.

These cartilages vary very greatly in the two sexes. In the males they are thick, strong, and large; in the female the cartilages are very thin, more hollowed and much smaller.

Fig. 204.

The larynx and surrounding parts, seen from the ventral surface.

Ca^1 Arytenoid cartilages.
$Cl^1–Cl^4$ Cricoid cartilage.
G, G^1 Fibrous tissue connecting the larynx with the posterior cornua of the hyoid.
H Lesser cornua of the hyoid.
HH Greater cornua of the hyoid.
Lg Right lung.
Lg^1 Left lung.
M Fibrous membrane filling the ring-like cricoid cartilage.

Ph^4 The M. petrohyoideus tertius.
S Part of tendon of M. petrohyoideus tertius.
SB, SB^1 Mucous membrane bulging from the anterior ventricle of the larynx.
Sp Spinous process of the cricoid cartilage.
ZK Body of the hyoid.

(3) [The **pre-arytenoid cartilages** (Fig. 206 I, *P*) are two small elongated cartilages placed in the semicircular notch between the superior and inferior borders of the arytenoid cartilages. They are subject to much variation in size, sometimes being merely a very slender rod, at others a moderately thick oval mass. In female specimens they appear to be, at times, absent, or to unite with the arytenoid cartilages, as in these cases a third very small apex is found on each arytenoid cartilage; but it is always much smaller than the two neighbouring apices.]

b. The **attachments** of the **cartilages** to each other.

The cartilages do not articulate directly with each other, but are connected by connective-tissue only; there are, therefore, no synovial sacs.

Fig. 205.

The muscles of the larynx.

A.l.	Aperture between the arytenoid cartilages.	*HH* Greater cornua of the hyoid.
C.l.	Cricoid cartilage.	*Jt* Fibrous tissue into which the two constrictions are inserted.
C.a.[1]	Superior angle of the arytenoid cartilage.	
C.a.l.	M. constrictor aditus laryngis.	*Ph2* Second petrohyoid muscle (M. petrohyoid. I).
C.o.l.	M. hyo-arytenoideus anterior.	*Ph3* Third petrohyoid muscle (M. petrohyoid. II).
C.o.l.[1]	M. hyo-arytenoideus posterior.	*Ph4* Fourth petrohyoid muscle (M. petrohyoid. III).
D.l.	M. dilatator laryngis.	
G	Connective-tissue.	*S,S1,S2* Tendon of the fourth petrohyoid muscle.
G1	Connective-tissue.	*Sp* Spinous process of the cricoid cartilage.
H	Smaller posterior cornua of the hyoid.	*ZK* Body of the hyoid.

c. The **muscles** of the larynx [1].

The muscles of the larynx appear in the following order, when dissected from the mouth :—

---

[1] The nomenclature adopted is that of Henle and Hoffmann.

(1) The *M. dilatator aditus laryngis* (Henle), (Fig. 205 *D.l.*) arises on either side from the hinder end of the larger posterior cornu of the hyoid : the fibres diverge slightly to be inserted into the middle portion of the outer surface of the arytenoid cartilage; a smaller bundle of fibres is attached to the deeper-lying constrictor muscle and to the cricoid cartilage.

(2) The *M. constrictor aditus laryngis* (Henle), (Fig. 205 *C.a.l.*), arises on either side from the hinder half of the dorsal surface of the posterior cornu of the hyoid. The two muscles enclose the larynx, and are inserted into a median tendinous raphe on the under surface of the larynx (*Jt*). The raphe is connected with the skeleton of the larynx by connective-tissue.

(3) The *M. hyo-arytenoideus anterior* (Fig. 205 *C.o.l.*) arises on each side from the inner border of the anterior end of the cornu of the hyoid ; the muscle lies close to the anterior border of the arytenoid cartilage, and is inserted into a fibrous lamella on the dorsal surface of the larynx. The *M. petrohyoideus tertius* is also partially inserted into this lamella.

(4) The *M. petrohyoideus tertius* (Fig. 205 *Ph*[4]), (see also p. 66). The greater part of this muscle is inserted into the end of the posterior cornu of the hyoid (*HH*); a smaller portion (*S, S*[2]) is prolonged to be inserted into the cricoid cartilage and into the fibrous lamella into which the *MM. hyo-arytenoidei anteriores* are inserted.

(5) The *M. hyo-arytenoideus posterior* (Fig. 205 *C.o.l.*[1]) arises on each side from the superior angle of the corresponding arytenoid cartilage, under cover of the tendon of the *M. petrohyoideus tertius*. The muscle is inserted into the inferior angle of the arytenoid cartilage.

d. The interior of the larynx (Figs. 202, 206, 207). The cavity of the larynx is constricted at two points : anteriorly it is constricted by the true vocal cords (Figs. 206 *V*, 207 *SB*), posteriorly by the false vocal cords. The whole cavity is lined with mucous membrane, which is continuous with that of the mouth anteriorly, with that of the lungs posteriorly.

(1) The **true vocal cords** are two vertical flat bands of connective-tissue, attached above to the superior angles of the arytenoid cartilages, below to their inferior angles; their anterior borders are thin and free ; near their posterior borders they are attached by mucous membrane to the internal surfaces of the arytenoid cartilages.

The anterior and posterior borders are not parallel but are each concave (Fig. 202 *V*).

Fig. 206.

Three sections through the larynx of *Rana esculenta*.—G. H.

I. Sagittal section near the median plane through the larynx.
II. Oblique transverse section through larynx.
III. Almost horizontal section through larynx.

A Arytenoid cartilage.
C Cricoid cartilage.
E Epiglottis.
F False vocal cords.
G Epiglotidean glands.
H Hyoid.
M Membranous floor of the larynx, cut obliquely.
O Opening into root of lung.
P Pre-arytenoid cartilage.
V Vocal cord.

The anterior border is thin, the posterior thick and rounded.

Seen from in front (Fig. 206), the opening between the cords (*Rima glottidis*) is slightly wider at each end than in the middle. The ends of the concave posterior border are prolonged backwards and enclosed in a fold of mucous membrane. Part of the tissue enclosed is unstriated muscular fibre, which may be traced to the cricoid cartilage.

(2) [The **false vocal cords** (Figs. 202 and 206 *F*) are simply folds of mucous membrane, which extend vertically on each side of the larynx behind the true vocal cords; they do not extend so far towards the median plane as do the true vocal cords.]

(3) [The **ventricles** of the larynx (Figs. 202 and 206) are two on each side. The anterior ventricles are between the true vocal cords and the arytenoid cartilages; they are open anteriorly, and closed by mucous membrane posteriorly.

The posterior ventricles open towards the median plane, each presenting an oval opening (Fig. 202), which widens outwards into a large cavity (Fig. 206 *II*). The cavity is bounded in front by the base of the true vocal cord, and the mucous membrane attached to it; posteriorly by the false vocal cord, and externally by the cricoid cartilage and the connective-tissue capsule of the larynx.]

(4) [The **mucous membrane** of the larynx varies in structure in various parts of the organ. From the anterior opening of the larynx to the posterior borders of the vocal cords it is lined with stratified epithelium, which is firmly attached to the underlying structures by a small amount of sub-epithelial

tissue. This is especially well marked on the vocal cords themselves. www.libtool.com.cn

Behind the vocal cords the mucous membrane is much more loosely attached to the surrounding structures by an extremely vascular areolar tissue. The epithelium is arranged in a single layer of columnar cells, among which are numerous goblet-cells. In the more external parts of the posterior ventricles, the mucous membrane is thrown into deep folds and so forms polygonal acini. In the median line of the floor of the larynx and behind the false vocal cords is a vertical fold of mucous membrane, which increases in height and breadth as it proceeds backwards towards the roots of the lungs. The mucous membrane behind the true vocal cords is extremely vascular, in the most posterior portion of the larynx the blood-vessels form a capillary network exactly like that of the lungs.]

Fig. 207.

The Rima glottidis, seen from the front.

G Rima glottidis.
SB Vocal cords.

e. [The **epiglottis** (Fig. 206 *E*) is a small bilobed fold of mucous membrane placed on the floor of the mouth in the median plane and immediately in front of the aperture to the larynx. Between it and the mucous membrane covering the arytenoid cartilages are a number of large mucous glands (*G*). The epiglottis does not contain cartilage; it is, however, constant in its appearance and sharply marked off from the surrounding mucous membrane.]

II. THE LUNGS.

a. General description. The lungs are two large thin-walled sacs (Figs. 185 and 204 *Lg* and *Lg*[1]). The roots of the lungs are contracted at their origin from the larynx and then expand to form two ellipsoid sacs, which terminate posteriorly in bluntly-pointed ends. With the exception of their roots they lie entirely free in the pleuro-peritoneal cavity, and are covered by the pleuro-peritoneal membrane. In the recent state they have a bright red colour due to the large supply of blood-vessels.

b. Minute structure.

(1) The **muscular tissue** of the lungs is for the most part arranged in large bands, which form a coarse network on the deeper

surface of the organ; when seen in section [1] (Pl. II, Fig. 208 *A*, *B*) these bands are found to be composed of well-developed involuntary muscular fibres. Between the larger bands are smaller bands having a similar arrangement. From these networks of muscular bands finer processes of muscular tissue pass peripherally towards the surface of the organ, and are attached to the thin and incomplete muscular layer found in the wall of the lung (*C*).

(2) The **connective-tissue** of the lungs is present in only small quantity, but is still sufficient to fill in the spaces between the various muscular bands and the surface of the lung, and to invest the whole of that surface. There is thus formed a series of pits, the mouths of which open into the general cavity of the lung, while their bases are at the surface. Through this connective-tissue course the blood-vessels, nerves, and lymphatics. It contains numerous yellow elastic fibres.

(3) The **blood-vessels** of the lungs. The pulmonary artery courses along the outer surface of the lung to the apex, giving off, at right angles, lateral branches in the whole of its course; these show a tendency to be alternately larger and smaller. The lateral branches divide and form a rich capillary network (T. Hoffmann).

The capillary network has very small meshes; the diameter of a given mesh being frequently less than that of the capillary bounding it. The meshes are rounded or polygonal in shape.

The pulmonary vein arises by lateral branches from this capillary network; the branches join, at right angles, the main vein, which courses from the apex of the lung along its inner surface to the root of the organ.

(4) The **epithelium** of the lungs. Externally the lungs are covered with a layer of endothelium derived from the peritoneum. Internally the surface is covered with an epithelium which varies considerably in different positions.

On the free borders of the muscular trabeculae forming the

---

[1] See Plate II, Fig. 208.

Two sections from the lung of *Rana temporaria*; stained with borax carmine.—G. H.

I. The lung dilated (Hartnack, Oc. I, Syst. 3).
II. The lung contracted (Hartnack, Oc. I, Syst. 7).

A Band of muscle cut transversely.   *B* Band of muscle cut longitudinally.
C Muscular layer of surface.

borders of the alveoli is a short columnar ciliated epithelium (Fig. 208); such epithelium is also found in the root of the lung; it contains goblet-cells.

The alveoli, for the most part, are lined with a single layer of tesselated epithelium; the cells are polygonal in outline, with finely granular contents and a distinct nucleus: the average diameter of the cells is from 0·0074 to 0·0108 mm., that of the nucleus 0·0054 mm., that of the nucleolus 0·0009 mm.; four to eight of such cells occupy the space enclosed by one mesh of the capillary network (Eberth).

The epithelium rests on a structureless basement membrane, which is continuous over the whole inner surface of the lung, whereas the epithelium does not pass over the capillaries, and is therefore only found in isolated patches in the areas enclosed by the capillaries (Eberth).

In various isolated spots, small groups of short columnar or goblet-cells are found in the tesselated epithelium (Eberth, Hoffmann).

(5) [The **lymphatics** of the lungs have been described by T. Hoffmann; they form a network of vessels surrounding the larger blood-vessels: from this branches are given off, which form a network of fine canals through the whole of the lung; part of this secondary network accompanies the blood-capillaries, but other portions run a separate course. They communicate with the pleuro-peritoneal cavity.

(6) The **pigment-cells** are very numerous, branched, and large; they accompany the lymphatics, and not the blood-vessels (T. Hoffmann).

(7) The **nerves** of the lungs (p. 172) course along the larger blood-vessels, under the serous coat; the fibres are chiefly medullated fibres (Egorow, Kandarazki). Non-medullated branches, which form a plexus in each alveolus, are given off. The branches have small triangular enlargements (ganglia), where they unite. The nerves are accompanied by nerve-cells, which occur either singly or in groups.

Egorow describes the nerves as being distributed in three networks: one for the mucous membrane and muscular trabeculae; a second for the superficial muscular layer; and a third for the serous membrane.]

III. THE VOCAL SACS.

a. General description. The vocal sacs are a pair of sacs which open in the floor of the mouth (Fig. 179 *S*); they are found only in the males.   When the animal croaks these sacs are dilated and act as resonators; when so dilated the sacs force up the skin under the angle of the mouth and tympanic membrane.   In well-developed specimens they are about as large as an average sized cherry. The skin covering the sacs is extremely elastic, but is not directly attached to the sacs.

b. Minute structure. The sac consists of connective-tissue, with a large proportion of yellow elastic fibre.   Internally it is lined with a flattened epithelium, and externally is covered with a layer of striated muscular fibre, derived from the mylo-hyoid muscle (Fig. 209 *My*, *My*¹).

Fig. 209.

Dissection to show the vocal sac of the right side.

HH   Larger posterior cornua of the hyoid.
*HH*¹   Smaller posterior cornua of the hyoid.
My   Mylo-hyoid muscle.
*My*¹   Mylo-hyoid muscle continued on to the vocal sac.
Thy   Thyroid glands.
VH   Anterior cornua of the hyoid.
Z   Body of the hyoid.

IV. THE THYMUS GLAND.

a. General description. The thymus gland (Fig. 210 *Th*) is placed on each side behind the angle of the jaw; it is best exposed by removing the skin behind the tympanic membrane and the angle of the jaw, and then reflecting the *M. depressor mandibulae* (*D.m.*).   The gland is then found as an elongated, oval body, not quite 3 mm. long, lying in the space between the *M. depressor mandibulae* and the *M. sternocleidomas toideus* (*St*); it extends slightly beyond the posterior border of the former muscle.   The space also includes connective-tissue, fat, and numerous vessels.

In *Rana temporaria* this gland is spherical, much smaller, and placed further behind on the *M. sternocleidomastoideus*, between the *M. latissimus dorsi* and the *M. deltoideus* (Wiedersheim).

b. **Minute structure** (Fig. 211).

[The gland is surrounded by a connective capsule, which is indented on the inner surface to form a hilus through which blood-vessels course into the organ.

Fig. 210

The capsule sends in numerous fine trabeculae, which form a connective-tissue skeleton such as is found in all lymphatic glands. The corpuscles of the trabeculae possess elongated nuclei from 0·019 to 0·028 mm. in length, and 0·010 to 0·015 mm. in breadth (Tolldt). The trabeculae support a network of blood-vessels.

The meshes of this sustentacular tissue are filled with **cells**; these are:

Dissection to show relations of the thymus gland.

De. M. deltoideus.
D.m. M. depressor mandibulae.
L.d. M. latissimus dorsi.
St M. sternocleidomastoideus.
Tf Tympanic membrane.
Th Thymus gland.

(a) Lymphoid cells, rounded or oval, possessing a round nucleus and nucleolus, and an extremely small amount of adhering protoplasm; the size of the nucleus is from 0·011 to 0·015 mm. (Tolldt).

Fig. 211.

From various sections from the thymus gland of *Rana esculenta*. —G. H.

I. Complete gland (Hartnack, Oc. I, Syst. 3).
    a Pigment-cells.
II. Portion of a section (Hartnack, Oc. I, Syst. 7) showing small corpuscles of Hassall.
III. Portion of a section showing lobules with degenerating cells.
    a Capsule of lobe.
    b Lobules.
    c Large corpuscle of Hassall, surrounded by normal tissue.
IV. Nerve-cell? (corpuscle of Hassall), after Fleischl.

(β) Corpuscles of Hassall (Fig. 211 II, III, and IV) are, as a rule, large bodies, but are subject to much variation in size. Their

general appearance is seen in Fig. 211 III; they show a concentric striation and usually enclose one or more smaller cells. They therefore closely resemble similar corpuscles found in higher animals.

(γ) In many frogs the cellular structure of at least a part of the gland seems to have undergone a degenerative stage (III). In such cases the connective-tissue is increased in quantity, and marks off portions of the section into small lobules (III) which are filled with cells containing mucus or sometimes fat (III). Under what conditions this degeneration, if such it be, takes place has not yet been determined[1].

(δ) Large branched pigment-cells are found in the course of the larger blood-vessels.

(ε) Watney describes also four varieties of 'granular cells:' 1. polygonal or rounded; 2. vacuolated; 3. spheroidal masses; 4. club-shaped masses attached to the blood-vessels. I have, however, not been able to distinguish them.]

[Tolldt (*l. c.* 1868) described the lymphoid tissue and the blood-vessels of this gland but did not find the corpuscles of Hassall.

Fleischl (*l. c.* 1870) disputed Tolldt's description; he evidently found the corpuscles of Hassall (see Fig. 211 IV), but he held them to be nerve-cells, and described them as such. He was also of opinion that the blood-vessels open into the intercellular spaces (as in the spleen). This has not been found to be the case by any other observer. Watney (*l. c.* 1882) first described the concentric corpuscles of Hassall as such.

Most writers describe the parenchyma as arranged in lobules. This I have only seen in a part of the gland and under what I believe to be pathological conditions.]

V. THE THYROID GLAND.

a. **General description.** A thyroid gland (Fig. 209 *Thy*) is found on either side as a small, triangular, or oval, reddish-coloured body on the dorsal surface of the *M. sternohyoideus*, just before it passes between the *MM. genio-hyoidei*. It lies in the angle formed between the larger and smaller posterior cornua of the hyoid (*HH, HH¹*). It is easily found by the presence of a large number of vessels in its neighbourhood, and especially by the large jugular vein, to the ventral surface of which it is intimately attached.

[1] Only winter-frogs were at my disposal (translator).

Not uncommonly several smaller supplemental glands are found in the rich anastomosis surrounding the organ.

The dorsal surface of the gland is lobulated, the ventral surface flatter and convex. The glands of opposite sides are seldom symmetrical.

b. Minute structure (Fig. 212 I and II). [The gland possesses a connective-tissue capsule, which sends in trabeculae to support the vesicles of which the gland is composed.

The vesicles (I and II), which vary greatly in size, are closed cavities, usually of a rounded or oval form, but sometimes branched (Baber). Each vesicle is lined with a single layer of cubical or slightly columnar epithelium (II, *a*), which rests on a delicate basement-membrane of connective-tissue, placed between the epithelium and the surrounding lymphatics (Baber).

Zeiss describes a delicate reticulum between the epithelial cells.

The vesicles always contain mucus (*b*), and are surrounded by a fine anastomosis of blood-vessels (*c*).]

Fig. 212.

Minute structure of the thyroid gland of *Rana esculenta.*—G. H.

I. Section through the gland (Hartnack, Oc. I, Syst. 3).

II. Small portion of above (Hartnack, Oc. I, Syst. 7).

  a Epithelium lining the vesicles.
  b Mucus.
  c Blood-vessels, injected with blue mass.

VI. THE LYMPHATIC GLANDS OF THE HYOID REGION (TONSILS?).

a. [General description. These are two oval, reddish-coloured, soft lymphatic glands, placed one on each side of the larynx. Frequently they are divided into two or three lobes by more or less

deep fissures.   They are constant in their occurrence, and are frequently supplemented by one or more smaller glands; each gland has the larynx on its inner side, the *Vena jugularis* externally, the *M. omohyoideus* in front, and above the mucous membrane of the pharynx (Tolldt).

Fig. 213.

Part of section through the lymphatic gland (tonsil?) of *Rana esculenta* (Hartnack, Oc. I, Syst. 13).—G. H.
a Extremely large lymphoid follicle.

b. **Minute structure.** The glands consist of dense lymphoid tissue (Fig. 213), but possess in addition one or more large bodies (*a*) which resemble lymphoid follicles in structure.   Each is composed of a dense mass of small cells; and the whole follicle is, as in similar follicles of higher animals, sharply differentiated from the rest of the organ.

The glands possess an extremely rich vascular supply, and are frequently pierced by one or more large arterial trunks.

The mucous membrane covering the glands is thinner than that immediately around, but is not perforated.]

[As far as I am aware, Tolldt is the only observer who describes these glands: he makes no mention of the lymphoid follicles.]

SECTION VII.

THE URINO-GENITAL SYSTEM, THE ADRENALS, AND THE FAT-BODIES.

THE URINO-GENITAL SYSTEM, ETC.

LITERATURE.

THE URINO-GENITAL ORGANS.

Adami, J. G., On the nature of glomerular activity in the kidney. Journ. of Physiol. 1886. Vol. VI, p. 382.

Ankermann, De moturo et evolutione filorum spermaticorum. Regimonti, 1854.

Ankermann, Einiges über die Bewegung und Entwicklung der Samenfäden des Frosches. Zeitsch. f. wiss. Zool. 1857. Vol. VIII, p. 129.

Beale, L. S., On very fine nerve-fibres ramifying in certain fibrous tissues, and of trunks and plexuses consisting entirely of fine nerve-fibres in the bladder of the frog. Beale's Archives of Med. 1864. Vol. IV, pp. 19-251.

Bergmann, C. G., De glandulis suprarenalis. Dissert. Göttingae, 1839.

Bidder, Vergleichende Anat. und histol. Untersuchungen über die männlichen Geschlechts- und Harnwerkzeuge der nackten Amphibien. Dorpat, 1846.

Biondi, D., Die Entwicklung der Spermatozoiden. Arch. f. mik. Anat. 1885. Vol. XXV, p. 594.

Bloomfield, J. E., The development of the Spermatozoa. Quart. Journ. Micros. Sci. 1881. New Series. Vol. XXI, p. 415.

Böttcher, A., Ueber den Bau und die Quellungsfähigkeit der Froscheileiter. Virchow's Arch. 1866. Vol. XXXVII, p. 174.

Bouillot, J., Sur l'épithélium sécréteur du rein des Batrachiens. Compt. rend. 1882. Vol. XCV, No. 14, pp. 603-604.

Bourne, A. Gibbs, On certain abnormalities in the common frog, Rana temporaria. Quart. Journ. Micros. Sci. 1884. New Series. Vol. XXIV, pp. 83-86.

Bowman, W., Sur la structure et fonctions des glandules des reins ou corpuscules de Malpighi. Annal. des Sci. Zool. 1843. Series II. Vol. XIX, pp. 108-145.

Bowman, W., On the structure of the Malpighian bodies of the kidney, etc. Phil. Trans. 1842. Pt. I, pp. 57-80.

Bowman, W., Ueber die Structur und den Nutzen der Malpighischen Körper in den Nieren. Froriep's Notizen, 1842. Vol. XXII, No. 21, coll. 321-324.

Bowman, W., Ueber die Structur und Functionen der Malpighischen Körper in den Nieren. Froriep's Notizen, 1843. Vol. XXV, No. 12, col. 177.

Brandt, A., Fragmentarische Bemerkungen über das Ovarium des Frosches. Zeitsch. f. wiss. Zool. 1877. Vol. XXVIII, p. 575.

Budge, Harnreservoir der Wirbelthiere. Mittheil. aus d. naturw. V. v. Neu-Pommern und Rügen. 1875, p. 103.

Carus, C. G., and **Otto, A. W.**, Erläuterungstafeln zur vergleichenden Anatomie. Leipzig, 1840.

Crivelli e Maggi, Alcuni cenni sovra lo studio dei corpi piangiati delle Rane. Rendiconti del Reale Istituto Lombardo di scienze e lettere. 1869. Second Series. Vol. II, p. 716.

Della Chiaje, Esistenza della glandule renala ne Batruci et ne Pisci. Napoli, 1837.

Drasch, O., Ueber das Vorkommen zweierlei verschiedener Gefässknäuel in der Niere. Wiener Sitzungsb. 1878. Vol. LXXVI, Part III, p. 79.

Duncan, J., Ueber die Malpighischen Knäuel in der Froschniere. Sitzungsb. d. Acad. zu Wien, 1867. Vol. LVI, Pt. II, p. 6.

Duval, M., and Wiet, Ueber die Wanderung der Eier in die Bauchhöhle beim Frosche. Gaz. de Paris, 1880. No. 17, p. 219.

Duval, M., Recherches sur la Spermatogénèse chez la grenouille. Revue Sci. nat. Montpellier, 1880. Vol. II, pp. 121-143.

Ecker, Der feinere Bau der Nebennieren, etc. 1846.

Eimer, T., Untersuchungen über den Bau und die Bewegung der Samenfäden. Verhandl. d. phys.-med. Gesell. in Würzburg, 1874. Vol. VI, New Series, p. 93.

Engelmann, Zur Physiologie des Ureter. Pflüger's Arch. f. d. ges. Physiol. 1869. Vol. II, p. 243.

Fürbringer, M., Zur vergleichenden Anat. und Entwicklungsgesch. d. Excretionsorgane der Vertebraten. Morph. Jahrb. Vol. IV.

Fürbringer, M., Zur Entwicklung der Amphibienniere. Heidelberg, 1877.

Gerlach, J., Beiträge zur Structurlehre der Niere. Arch. f. Anat. u. Physiol. 1845, p. 378.

Gibbes, H., On the structure of the Spermatozoon. Quart. Journ. Micros. Sci. 1880. Vol. XX, p. 318.

Goette, A., Entwicklungsgeschichte der Unke. Leipzig, 1875.

Goette, A., Kurze Mittheilungen aus der Entwicklungsgeschichte der Unke. Arch. f. mik. Anat. 1873. Vol. IX, p. 396.

Grunau, H., Ueber das Flimmerepithel auf dem Bauchfell des weiblichen Frosches und über den Eileiterbau desselben. Dissert. Königsberg, 1875.

Grünhagen, A., Untersuchungen über Samenentwickelung. Centralbl. f. d. med. Wiss. 1885. Vol. XXIII, p. 481.

Grünhagen, A., Ueber die Spermatogenese bei Rana fusca (temporaria). Centralbl. f. d. med. Wiss. 1885. Vol. XXIII, p. 737.

Gscheidlen, R., Zur Lehre v. d. Nervenendigung in den glatten Muskelfasern. Arch. f. mik. Anat. 1877. Vol. XIV, p. 321.

Heidenhain, R., Mikroskopische Beiträge zur Anatomie und Physiologie der Nieren. Arch. f. mik. Anat. 1874. Vol. X, p. 1.

Helmann, Ueber die Entwicklung der Spermatozoen der Wirbelthiere. Dissert. Dorpat, 1879.

Henle, J., Zur Anatomie der Niere. Nachrichten v. d. k. Gesell. d. Wissensch. z. Göttingen, 1862. Vol. X, pp. 4-12; and in Abhandlungen, 1861-62, Vol. X, p. 223.

Hoffmann, C. K., in Bronn's Klassen und Ordnungen des Thierreichs. Leipzig and Heidelberg, 1873-1879. Vol. VI.

Hüfner, Zur vergleichenden Anatomie und Physiologie der Harncanälchen. Diss. Leipzig, 1866.

Hyrtl, Ueber die Injection der Wirbelthierniere, etc. Wiener Acad. Sitzungsb. 1863. Vol. XLVII, Pt. I, p. 172.

Jensen, O. S., Recherches sur la spermatogénèse. Archives de Biologie, 1883. Vol. IV.

Jensen, O. S., Ueber die Struktur der Samenkörper bei Säugethieren, Vögeln, und Amphibien. Anat. Anzeiger. 1886.

Knappe, E., Das Bidder'sche Organ. Morph. Jahrb. 1886. Vol. XI, pp. 489-548.

Kolessnikow, N., Ueber die Eierentwicklung bei Batrachiern und Knochenfischen. Arch. f. mik. Anat. 1878. Vol. XV, p. 382.

v. Kölliker, A., Gewebelehre. Fifth Edition.

Langer, C., Ueber das Lymphgefässsystem des Frosches. Wiener Acad. Sitzungsb. 1867. Vol. LV, Pt. I, p. 621.

Lavdowsky, M., Ueber die Endigung der Nerven in der Harnblase des Frosches. Centralbl. f. d. med. Wiss. 1871, p. 33.

Lavdowsky, M., Die feinere Structur und die Nervenendigungen der Froschharnblase. Arch. f. Anat. u. Physiol. 1872, p. 55.

Lereboullet, A., Recherches sur l'anatomie des organes génitaux des animaux vertébrés. Nov. acta Acad. Leop. Car. 1851. Vol. XXIII, pp. 1-226.

Leydig, F., Anatom.-histol. Untersuchungen über Fische und Reptilien.

Leydig, F., Lehrbuch der Histologie des Menschen und der Thiere. Frankfurt, 1857, p. 508.

Leydig, F., Untersuchungen zur Anatomie und Histologie der Thiere. Bonn, 1883.

List, J. H., Ueber Becherzellen im Blasenepithel des Frosches. Wiener Sitzungsb. 1884, Vol. LXXXIX, Pt. III, pp. 186–210; also in Arch. f. mik. Anat. 1887, Vol. XXIX, p. 147.

List, J. H., Ueber Becherzellen im Blasenepithel des Frosches. Zool. Anzeiger, 1884. No. 169, p. 328.

List, J. H., Ueber einzellige Drüsen im Blasenepithele der Amphibien. Biol. Centralbl. 1885. Vol. V, p. 499.

Loos, P. A., Die Eiweissdrüsen d. Amphibien und Vögel. Zeitsch. f. wiss. Zool. 1881. Vol. XXXV, pp. 478–504.

Maier, R., Die Ganglien in den harnabführenden Wegen des Menschen und einiger Thiere. Virchow's Arch. 1881. Vol. LXXXV, pp. 49–71.

Marcussen, J., Ueber die Cloake und Harnblase der Frösche. Bull. der phys.-math. Acad. de St. Pétersbourg, 1853. Vol. XI.

Marshall, A. M., On certain abnormal conditions of the reproductive organs in the frog. Journ. of Anat. and Physiol. 1884. Vol. XVIII, p. 121.

Marshall, A. M., The frog. Manchester and London. 2nd Edit. 1885.

Mecznikow, E., Zur vergleichenden Histologie der Niere. Göttinger Nachrichten, 1866, p. 61.

Meyer, F., Beitrag zur Anatomie des Urogenitalsystems der Selachier und Amphibien. Sitzungsb. d. nat. Gesellsch. Leipzig. 1874, p. 38; published 1875.

Moleschott, Ein histochemischer und ein histologischer Beitrag zur Kenntniss der Nieren.

Miescher, Die Spermatozoen einiger Wirbelthiere. Verhandl. d. naturf. Gesell. in Basel. 1878. Vol. VI.

Neumann, E., Untersuchungen über die Entwickelung der Spermatozoiden. Centralbl. f. d. med. Wiss. 1868. No. 24.

Neumann, E., Untersuchungen über die Entwickelung der Spermatozoiden. Arch. f. mik. Anat. 1875. Vol. XI, p. 292.

Neumann and Grunau, Drüsen der Froscheileiter. Arch. f. mik. Anat. 1875. Vol. XI, p. 372.

Nussbaum, N., Ueber die Niere der Wirbelthiere. Sitzungsber. Bonn, 1870.

Nussbaum, N., Ueber die Endigung der Wimpertrichter in der Anurenniere. Sitzungsb. d. niederrheinischen Gesell. in Bonn, 1877. Vol. XXXIV, p. 122.

Nussbaum, N., Ueber den Bau und die Thätigkeit der Drüsen. Arch. f. mik. Anat. 1886. Vol. XXVII, p. 442.

Nussbaum, N., Ueber die Secretion der Niere und über die Verbindung der Samen und harnbereitenden Drüsenschläuche in den Nieren der Batrachier. Sitzungsb. d. niederrheinischen naturf. Gesell. in Bonn, 1877. Vol. XXXIV, p. 277.

Nussbaum, N., Fortgesetzte Untersuchungen über die Secretion d. Niere. Pflüger's Arch. f. d. ges. Physiol. 1878. Vol. XVII, p. 580.

Nussbaum, N., Ueber die Endigung der Wimpertrichter der Niere der Anuren. Zool. Anzeiger, 1880. No. 67, pp. 514–517.

Nussbaum, N., Zur Differenzirung des Geschlechts im Thierreich. Arch. f. mik. Anat. 1880. Vol. XVIII, p. 73.

Peltier, Sur les zoospermes de la grenouille. L'Institut. 1838. Vol. VI.

Perrault, C., De generatione ranarum fusca et bona dissertatio, in Actis Eruditorum, 1687.

Prévost, Note sur les animalcules spermatiques de la grenouille et de la Salamandre. Mémoires de la société phys. et d'hist. nat. de Genève. Geneva and Paris, 1841–1842. Vol. IX, p. 289.

Rathke, H., Beiträge zur Geschichte der Thierwelt, III Abth. ; and Neueste Schr. d. naturf. Gesell. in Danzig. 1825. Vol. I.

Reger, B., Ueber die Malpighischen Knäuel der Nieren und ihre sogenannten Capseln. Arch. f. Anat. u. Physiol. 1864, p. 537.

Reichert, On kidney. Jahresbericht über Anatomie in Arch. f. Anat. u. Physiol. 1843, p. 220, etc.

Remak, Untersuchungen über die Entwicklung d. Wirbelthiere, p. 128.

Retsius, G., Zur Kenntniss der Spermatozoen. Biol. Untersuchungen. 1881.

Rideward, W. G., On an abnormal genital system in a male of the common frog. Anat. Anz. 1888. Vol. III, p. 333.

Robinson, C., Ueber die Lymphgefässe der abdominal Eingeweide des Frosches. Froriep's Notizen, 1846. No. 807, col. 225.

Rösel, A. J., Historia naturalis ranarum nostralium. 1758, p. 28.

Roth, Untersuchungen über die Drüsensubstanz der Niere. Bern, 1864 ; and Schweiz. Gesellsch. f. Heilkunde, 1864. Vol. III, pp. 1–34.

Schiefferdecker, Ueber einzellige Drüsen in der Blase der Amphibien. Bericht. d. naturf. Ges. in Rostock, 1883.

Schultze, F. E., Das Drüsenepithel der schlauchförmigen Drüsen des Dünn- und Dickdarms und die Becherzellen (Cloaca of frog). Centralbl. f. d. med. Wiss. 1866, p. 161.

Schultze, M., Observationes nonnullae de ovorum ranarum segmentatione. Bonn, 1863.

Schultze, O., Untersuchungen über die Reifung und Befruchtung des Amphibieneies. Zeitsch. f. wiss. Zool. 1887. Vol. XLV, pp. 177–226.

Schweigger-Seidel, F., Ueber die Samenkörperchen und ihre Entwicklung. Arch. f. mik. Anat. 1865. Vol. I, p. 309.

Solger, B., Beiträge zur Kenntniss der Nieren und besonders der Nierenpigmente der niederen Wirbelthiere. Abhandl. d. naturf. Ges. zu Halle, 1882. Vol. XV.

Spengel, J. W., Die Segmentalorgane der Amphibien. Verhandl. d. phys.-med. Gesells. Würzburg. Vol. X, pp. 89–92.

Spengel, J. W., Das Urogenitalsystem der Amphibien. Arbeiten aus d. Zool. Inst. in Würzburg, 1876. Vol. III, pp. 1–114.

Spengel, J. W., Wimpertrichter in der Amphibienniere. Centralbl. f. d. med. Wiss. 1875, p. 369.

Swammerdam, J., Bibblia naturae. Leydae, 1738. Vol. II, p. 796.

Thompson, A., Article 'Ovum' in Todd's Cyclopædia of Anatomy and Physiology, London, 1879. Vol. V, p. 91.

Tolotschinoff, Ueber das Verhalten der Nerven zu den glatten Muskelfasern der Froschharnblase. Arch. f. mik. Anat. 1869. Vol. V, p. 509.

Tornier, O., Ueber Bürstenbesätze am Drüsenepithel. Arch. f. mik. Anat. 1886. Vol. XXVII, p. 181.

v. la Valette St. George, Spermatologische Beiträge. Arch. f. mik. Anat. 1886, Vol. XXVII, p. 385 ; and in Stricker's Gewebelehre, Article 'Hoden.'

Valentin, On kidney. Repertitorium, 1845. Vol. VIII, p. 92.

Waldeyer, W., Eierstock und Ei. Ein Beitrag zur Anatomie und Entwicklungsgesch. der Sexualorgane. Leipzig, 1870.

Weldon, W. F. R., On the suprarenal bodies of vertebrata. Quart. Journ. Micros. Sci. 1885. Vol. XXV, p. 137.

v. Wittich, W., Beiträge zur morphologischen und histologischen Entwicklung der Harn- und Geschlechtswerkzeuge der nackten Amphibien. Zeitsch. f. wiss. Zool. 1853. Vol. IV, p. 152.

Wolff, W., Die Innervation der glatten Muskulatur. Arch. f. mik. Anat. 1882. Vol. XX, p. 361.

THE ADRENALS.

Bergmann, De glandulis suprarenalibus. Dissert. Göttingen, 1839.

Ecker, A., Der feinere Bau der Nebennieren beim Menschen und den vier Wirbel-
thierklassen. Braunschweig, 1846.

Frey, H., On the suprarenal capsules, in Todd's Cyclopædia. London, 1849, p. 827.

Giles, A. E., On the development of the fat-bodies in the frog. Quart. Journ.
Micros. Sci.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs. Heidelberg
und Leipzig, 1873–1878. Vol. VI, p. 506.

v. Kölliker, A., Handbuch der mikroskopischen Anatomie. Leipzig, 1854. Vol. II,
p. 386.

Leydig, Lehrbuch der Histologie. Frankfurt a. M. 1857.

Moers, Ueber den feineren Bau der Nebennieren. Virchow's Arch. 1864. Vol.
XXIX, p. 336.

Nagel, Ueber die Structur der Nebennieren. Arch. f. Anat. u. Physiol. 1830, p. 377.

THE FAT-BODIES.

Carus, Lehrbuch der Zootomie. Leipzig, 1818 (describes the fat-bodies as supra-
renals).

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs. Heidelberg
und Leipzig, 1873–1878. Vol. VI.

Marshall, A. Milnes, The frog. Manchester and London, 1884.

v. Wittich, W., Beiträge zur morphologischen und histologischen Entwicklung der
Harn- und Geschlechtswerkzeuge der nackten Amphibien. Zeitsch. f. wiss. Zool.
1853. Vol. IV, p. 152.

THE URINO-GENITAL SYSTEM, THE ADRENALS, ETC.

THE URINO-GENITAL SYSTEM.

By cutting through the meso-rectum the posterior caval vein is seen, as a large vessel, arising by numerous transverse branches from the ventral surfaces of the kidneys and testes (Fig. 214 *Cv*), lying in the median line between the kidneys; by drawing it to one side the dorsal aorta is brought into view (Fig. 214 *Ao*). The testes are placed on the ventral surface of the kidneys, and together with the fat-bodies conceal the anterior portions of these organs. The posterior portions of the kidneys are covered by peritoneum only, and may by seen without further dissection. The kidneys lie dorsal to the peritoneum, and have this membrane on their ventral surfaces only; their dorsal surfaces are in contact with the lumbo-sacral plexus.

The ureters extend from the anterior border of the eighth vertebra to the middle of the urostyle, where they terminate by two orifices in the dorsal wall of the cloaca (Fig. 184).

The testes are entirely surrounded by peritoneum, except a small part (*Hilus*) of the inner surface, where the vessels and ducts enter.

Fig. 214.

The male urino-genital organs.

Ao Aorta.
Cl Cloaca.
Cv Inferior vena cava.
FK Fat-body.
H Testis.
N Kidney.
S, S¹ Openings of ureters.
Ur Ureter.
Vr Renal veins.
† Appearance of ureters on the ventral surfaces of kidneys.

The urino-genital organs are arranged in the same manner in the two sexes; the ovaries corresponding in position with the

testes (Fig. 214), that is, they are bilaterally symmetrical, and placed on the ventral surfaces of the kidneys.

The oviducts (Fig. 224 *Ov*) lie externally to the kidneys and ovaries, and course through the whole length of the trunk from the roots of the lungs to the cloaca. The size of the ovaries and oviducts varies very greatly according to the season of the year; at times, the kidneys may be entirely hidden by them.

I. THE URINARY ORGANS.

A. The kidneys.

a. General description. Each kidney (Fig. 215) is a reddish-brown, elongated organ, almost semilunar in shape; the inner border being straight and the outer convex.

Fig. 215.

The right kidney, seen from the ventral surface.

The organ is flattened from above downwards, and decreases in thickness towards either end. In animals of average size the kidney is about 16 mm. long, and from 6 to 7 mm. broad. The kidneys lie parallel to the vertebrae.

The outer border is smooth and even, except at its posterior third, where a slight depression for the ureter exists; the inner border has usually two or three well-marked notches, the hindermost of which is the deepest (Fig. 215). Each notch is continued outwards as a groove, traversing the whole breadth of the ventral surface and containing a branch of the renal portal vein. The ventral surface is, as a whole, slightly concave, grooved, and lobulated; the dorsal surface is smooth and slightly convex.

b. [Minute structure. The kidney is enclosed in a thin capsule of fibrous tissue (Fig. 220 *Bg*), which sends in fine trabeculae to support the glandular structures and the blood-vessels.]

(1) The **blood-vessels** of the kidney are the renal veins, the renal arteries, and the renal portal vein.

a. The renal portal vein (p. 247) courses along the outer border of the posterior part of the kidney, and then along the outer margin of the dorsal surface; in this course it gives off large branches, which course inwards and forwards and supply numerous lateral twigs. These anastomose to form a network of vessels on the dorsal surface of the organ, from which very numerous large branches course downwards and somewhat inwards to join corresponding branches of the renal veins (Fig. 216 I).

Fig. 216.

www.libtool.com.cn

The blood-vessels and lymphatics of the kidney.—G. H.

I. Transverse vertical section through kidney. Venous system blue; arteries red (Hartnack, Oc. I, Syst. 3).

-II. Part of a horizontal section through kidney. Venous system blue; arteries red (Hartnack, Oc. I, Syst. 3).

III. Part of a transverse vertical section through kidney; lymphatics blue (Hartnack, Oc. I, Syst. 7).

    A   Ventral surface.
    B   Dorsal surface.
    C   Two arterial twigs uniting before entering the Malpighian body.

β. The renal veins (p. 247) form a coarse plexus on the ventral surface of the kidney, from this numerous large branches (Fig. 216 I) course upwards and outwards.

The venous system between the renal portal veins on the dorsal surface, and the renal veins on the ventral surface, are so large that they can scarcely be named capillaries (Hyrtl).

γ. The renal arteries (p. 233) are distributed to the ventral surface of the kidney; their mode of distribution varies in different parts of the organ. A simple arrangement is that shown in Fig. 216 I, where a branch traverses the breadth of the kidney and gives off branches to the Malpighian corpuscles; in one case (*C*)

I have seen two twigs passing to the same corpuscle; as a rule, however, each Malpighian corpuscle receives only one twig. A more general arrangement is that the artery courses nearer the ventral surface and in a more winding course, several twigs are then given off close together, from the convex surface of one of the curves, and these course to their respective corpuscles.

In the Malpighian corpuscle the arterial twig forms a series of loops and then passes out to open abruptly into one of the branches of the neighbouring venous anastomosis (Hyrtl).

(2) [The **Malpighian corpuscles** and their **capsules** (Figs. 216 I, 218 III). The corpuscles lie nearer the ventral than the dorsal surface. They are rounded oval bodies, formed of loops of an arterial twig, held together by a small amount of connective-tissue. Each corpuscle is enclosed in a capsule, which it incompletely fills (Fig. 217)[1].

The capsules are formed of connective-tissue and lined with a flattened epithelium (Fig. 218 III): according to Duncan the fibrous coat is arranged in two layers (III *a*). Towards the opening of the uriniferous tube the epithelium increases in thickness.

According to Hyrtl, the corpuscles are arranged in two layers, a more superficial one and a deeper one; and are of two sizes, the larger being as a rule the more superficial (ventral).]

(3) [The **uriniferous tubes** (Figs. 217 and 218). Each tube originates at a narrow opening on the dorsal surface of a Malpighian capsule. The tube gradually widens and is lined with a short rounded or cubical epithelium (Roth), (Fig. 218 III); each epithelial cell bearing a small number of extremely small cilia (Bowman, Kölliker, Duncan, and others). The cilia of the cells nearest the capsule are directed towards it (Heidenhain), those of the cells further away have an opposite direction (Spengel). This portion of the tube is known as the neck; it courses dorsalwards.

The second portion of the tube (*Tubulus contortus*), (Fig. 218 III, IX, and XII) has a very tortuous course in the dorsal part of the kidney, and then winds towards the ventral surface. This portion is lined with columnar epithelium, which has granular contents, and possesses large distinct nuclei. The cells of this part

---

[1] See Plate II.

Portions of two transverse vertical sections through the kidney.—G. H.

I. Kidney of *Rana esculenta*, partial injection of the uriniferous tubes with silver nitrate (Hartnack, Oc. I, Syst. 7).

II. Kidney of *Rana temporaria*, stained with borax-carmine (Hartnack, Oc. I, Syst. 7).

Fig. 218.

Various preparations to show the structure of the uriniferous tubes, etc.

I. Three portions of the uriniferous tubes from *Rana esculenta*, from a natural injection with sulphindigotate of sodium (Hartnack, Oc. I, Syst. 3).—G. H.

II. From the third part of a uriniferous tube ; short ciliated epithelium, borax-carmine (Hartnack, Oc. I, Syst. 7).—G. H.

III. A Malpighian corpuscle and capsule ; shows the capsule of two layers at *a*. After Duncan.

IV. Part of uriniferous tube after natural injection with sulphindigotate of sodium (Hartnack, Oc. I, Syst. 3).—G. H.

V. Transverse section of one of the larger branches of the ureter, from *Rana esculenta* (Hartnack, Oc. I, Syst. 7).—G. H.

VI. Epithelial lining of the ureter itself while still in the kidney (Hartnack, Oc. I, Syst. 7).—G. H.

VII. Portion of a uriniferous tube from section in Fig. 217 I, stained with silver (Hartnack, Oc. I, Syst. 7).—G. H.

VIII. Renal epithelium ; *a* to *b*, tubulus contortus ; *b* to *c*, third portion of uriniferous tube ; *c* to *d*, fourth portion of tube. After Heidenhain (enlarged 210 times).

IX. Ciliated cells of the neck, after Duncan.

X. Isolated rod-cells of *Triton taeniatus*, after Heidenhain.

XI. Isolated rod-cells, after Heidenhain (enlarged 300 times).

XII. Isolated cells of the neck, after Heidenhain (enlarged 210 times).

XIII. Portion of the fourth part of a uriniferous tube, after Heidenhain (enlarged 300 times).

XIV. Ciliated epithelium of tubulus contortus, after Tornier (magnified 550 times).

XV. From kidney of *Rana temporaria*, after Spengel.

       a Uriniferous tube opening into seminiferous duct.

       b Dilated seminiferous duct cut longitudinally.

       c Vas efferens cut transversely.

of the kidney are usually more or less coloured with a golden-yellow pigment. According to Tornier it bears short cilia (Fig. 218 XIV).

The third portion corresponds with the narrow limb of Henle's loop ; it is lined with ciliated epithelium (Fig. 218 VIII, b to c), similar to that in the neck of the tube.

The fourth portion (Fig. 218 VIII, c to d, and XIII) represents the wider limb of Henle's loop. It has a winding course in the ventral part of the kidney, and then ascends dorsally to open into a collecting-tube. The fourth part of the tube is lined with a short, columnar epithelium (Fig. 218 VIII, c to d), which has a clear, cuticular, free border, large nucleus, and a peculiar arrangement of the protoplasm, which shows a rod-like structure (Fig. 218 XI).

The collecting-tubes course transversely near the dorsal surface of the kidney (Fig. 217), and the uriniferous tubes meet them at right-angles. They are lined with a short polygonal epithelium (Fig. 218 VII).

The peritoneal funnels of the kidney (nephrostomes). Spengel, Meyer, and Hoffmann describe these funnels as existing in the frog; according to them they open on the ventral surface by narrow apertures, and each is connected, by a vertical tubule, with the fourth part of the uriniferous tube (Spengel), but according to Nussbaum, with the neck of the tube. According to Spengel and Meyer the number of these funnels is in Rana from 250 to 360.

According to Wiedersheim the funnels hang free from the ventral surface like so many parasites attached by fine filaments, and do *not* open on the surface.

Heidenhain (Arch. f. mik. Anat., Vol. X) was unable to find these organs.

Being unable to find any trace of these organs in the kidneys of either R. temporaria or R. esculenta, in microscopic sections or in teased preparations, I inserted canulae into the ureters of both male and female specimens of both species, and injected the uriniferous tubes with a solution of Berlin blue. Although the tubules were, in some cases, completely injected, in no case could I find any trace of a peritoneal funnel, nor was there any escape of the solution from the kidney as would be the case if the funnels were open and communicated with any part of the uriniferous tubes. Even when the pressure was increased to the extent of a column of 25 cm. high of the injection-mass, no escape took place from the surface of the kidney, though in numerous cases the uriniferous tubes were ruptured by the abnormally high pressure.

Properly dissected frogs were placed in 0·6 °/₀ sodium chloride solution, in which finely divided gamboge was suspended. No trace of ciliary action was, in any case, found on either surface of the kidneys.

One may therefore conclude that if the peritoneal funnels exist in the adult frog (1) they are very difficult to find; (2) they do not form a free communicating path between any part of the uriniferous tubes and the abdominal cavity; (3) their superficial terminations have no free cilia. As before stated I have found no trace of any such organs.

The **lobules** of the kidney. When treated with proper reagents the kidney shows a marked tendency to separate into lobules (Fig. 219 I).

The **lymphatics** of the kidney (Fig. 216 III [1]) form an irregular network of fine canals with elongated meshes. They run chiefly in the direction of the blood-vessels. The large vessels, which supply the kidney, are surrounded by large lymphatics.]

The **nerves** of the kidney (Fig. 219 II) [1]. Little is known of these. Nerve-fibres have been traced alongside the larger blood-vessel through the greater part of the kidney.

B. The ureters.

a. General description. In the males the ureters are, at the same time, the seminiferous ducts. Each ureter commences on the dorsal surface of the kidney by bifurcating branches, which are continuous with the collecting-tubes of the kidney. In the anterior two-thirds of the kidney the ureter is wholly on the dorsal surface; at the junction of the middle and posterior thirds it winds round to the outer border of the kidney (Fig. 214 *Ur*), and there lies in a groove accompanied by the renal portal vein (Fig. 220 *Ur* and *Va*), the two organs being intimately attached to the kidney substance and enclosed by the fibrous capsule (*Bg*).

This portion of the ureter possesses a spindle-shaped enlargement, which represents the *Receptaculum seminis*. In *Rana temporaria* the *Receptaculum seminis* forms a large saccular dilatation.

In its further course the ureter runs backwards and slightly inwards, converging with its fellow of the opposite side; the ureters lie free in the abdominal cavity, and terminate by two openings placed side by side in a groove on the dorsal wall of the cloaca (Fig. 214 *S, S*[1]).

In females the ureters are intimately attached to the dilated oviduct, immediately after leaving the kidney; they pursue a similar course to those of the males, but are attached to the oviduct in the whole of their course to the cloaca.

b. Minute structure. The ureter is a tube composed of connective-

---

[1] See Plate II.

Two portions from a gold preparation of the kidney of *Rana esculenta*.—G. H.

I. Showing the tendency to split into lobules.
II. Nerve-fibres accompanying the blood-vessels.
    a Blood-vessels.
    b Nerves.

tissue and involuntary muscular fibre, and lined with a mucous membrane. The mucous membrane is thrown into longitudinal folds, and consists, in the larger tubes, of two or three layers of epithelium (Fig. 218 V), that on the free surface is columnar; the deeper cells being rounded or polygonal. The larger branches of the ureter are lined with columnar epithelium (Fig. 218 VI), with small intervening cells. In some parts of the branches the columnar epithelium bears short cilia.

Fig. 220.

Transverse section of the kidney, enlarged.

Bg Connective-tissue capsule.
D Dorsal surface.
NC Renal parenchyma.
Ur Ureter.
V Ventral surface.
Va Renal portal vein.

No glands have been found in the ureter or *Receptaculum seminis*; in *Rana temporaria*, however, the *Receptaculum seminis* possesses large, branching mucous glands (Wiedersheim).

C. The bladder.

a. General description. The urinary bladder (Fig. 185 *HB*) is closely attached to the ventral wall of the cloaca and is easily distended from that organ. In relation to the animal it is of very large size; in consequence of its being contracted in the middle it has two lobes, which may be of unequal size. The organ is somewhat heart-shaped (Figs. 184 and 185), with the narrow neck attached to the cloaca, into which it opens by a smaller aperture on the ventral surface. The aperture is surrounded by a small fold of mucous membrane.

b. Minute structure. The urinary bladder is bounded by a thin, transparent wall, lined internally with mucous membrane, and covered externally by peritoneum.

(1) The muscular coat is formed of a network of fine bands of unstriated muscular fibre (Fig. 221); it is supported and completed by a connective-tissue layer, rich in connective-tissue corpuscles and yellow elastic fibres.

(2) The peritoneal coat is a single layer of endothelial cells derived from the peritoneum and resting on a very thin layer of subperitoneal tissue.

(3) The mucous coat is formed of epithelium resting on a layer of loose, areolar tissue. The epithelium (Fig. 221 I, II, and IV) is

Fig. 221.

Various preparations from the bladder.

I. Silver preparation of the mucous membrane; seen from the surface. After List (enlarged 400 times).

        a   Cells of the surface.
        d   Goblet-cells.
        e   Young cells.

II. Vertical section of the mucous membrane; after List (enlarged 600 times).

        a   Cells of upper layer.
        b   Cells of middle layer.
        c   Cells of lower layer.

III. Large multicellular ganglion; after Wolff.

IV. Vertical section from a silver preparation of the mucous membrane; after List (enlarged 600 times).

        a   Upper layer.
        b   Middle layer.
        c   Lower layer.
        d   Goblet-cells.

V. Small ganglion of bladder; after Wolff.

        a   Non-medullated nerve-fibre leading to ganglion.
        b   Process of a ganglion cell.

arranged in three layers: the cells of the uppermost (II and IV, *a*) always present a flat or convex border to the cavity of the organ; seen from their free surfaces (I) they have polygonal outlines intermixed with round apertures belonging to goblet-cells, the remaining surfaces of these cells are serrated. The cells of the middle layer (II and IV, *b*) are polygonal in outline, they are not so tall as the cells of the layer above; all their borders are serrated. The cells of the deepest layer (II and IV, *c*) are more or less pointed above where they project between the cells of the second layer; their lowest surfaces are flattened towards the subepithelial tissue, and all their surfaces are serrated.

The cells of all three layers possess a cell-wall, and finely granular contents, and each cell has a large oval nucleus (List).

The goblet-cells (Fig. 221 I and IV, *d*) vary very much in shape; they are always more or less rounded in outline : they vary greatly in size (from 190 μ to 54 μ in length); some possess 'feet' or basal prolongations, in others these are absent. They usually open freely by rounded apertures on the surface of the mucous membrane, but are sometimes closed. The nucleus is placed towards the base of the cell and surrounded by a smaller or larger amount of protoplasm. These cells usually extend into the middle layer of the epithelium, and they probably constitute unicellular mucous glands (List).

(4) The **blood-vessels** of the urinary bladder (p. 235) are very numerous and run in very tortuous courses; they are accompanied by large lymphatics and by nerves.

(5) The **nerves** of the urinary bladder (p. 191) are of both medullated and non-medullated fibres, which course together towards their points of distribution; the non-medullated fibres are, however, much more frequent than the medullated fibres (Wolff).

The non-medullated nerve-fibres stand in close relation with the nerve-ganglia of the bladder. These ganglia may be unicellular, or composed of groups of nerve-cells; the cells vary considerably in shape, round, oval, triangular, and other forms being equally frequent in their occurrence; to some extent the form appears to depend upon the number and position of the processes of the cells. The diameter of the cells varies from 0·05 mm. to 0·1 mm.; the nucleus has a diameter of 0·025 mm., that of the nucleolus measures 0·005 mm. (Wolff).

The cells may be unipolar or multipolar; the former are however rare. The processes of these cells supply the muscle-fibres (Fig. 221 V, *a*), and other non-medullated processes connect the cells with the nerves (V, *b* (Wolff)).

The number of muscular fibres is far in excess of the number of the fibres of distribution of the ganglia; Wolff hence concludes that the nervous impulse may pass from one muscle-fibre to another.]

II. THE REPRODUCTIVE ORGANS.

A. The **male reproductive organs are** the testes and their ducts.

a. General description. The relations of the testes have already been given (p. 234); the organs vary much in shape and size in different individuals and with the different seasons; when greatest they are spherical, or of a rounded oval form, occasionally cone-shaped or pear-shaped. The surface of the testes is not

Fig. 222.

I.

II.

The male reproductive organs (enlarged).

CC	Vasa efferentia within the kidney.
H	Testis.
LL	Collecting-tube at inner border of kidney.
N	Kidney.
Ne	Vasa efferentia within the mesorchium.
Ur	Ureter.
††	Vasa efferentia ending blindly.

smooth, but presents a series of convexities, each corresponding to a lobule of the gland. At the *hilus* on the inner border the vessels pass to and from the organ, and the *Vasa efferentia* leave the testis.

The number of *Vasa efferentia* (Fig. 222 I and II) is subject to considerable variation, not only in different animals, but on the two sides of the same animal. In some cases these ducts form a network (I), in other cases this is absent (II); usually the ducts

bifurcate at acute angles, just before entering the kidney. Most of
the tubes so formed open into the collecting-tube; a few, however,

Fig. 223.

Various preparations from the testis.

I. Various stages of the spermatozoa; from testis of *Rana temporaria*. After Neumann.
II. Section from testis of *Rana esculenta* (Hartnack, Oc. I, Syst. 7).—G. H.
    a   Thin connective-tissue capsule.
    b   Trabeculae.
    c and *d* Seminiferous tubes.
III. From testis of *Rana temporaria*. After Neumann.
    x   Rounded epithelium of seminiferous tubes.
    y   Spermatoblasts.
IV. Surface view of seminiferous tube of *Rana temporaria*. After Neumann.
    a   Granular protoplasmic feet of spermatoblasts.
    b   Rounded epithelium.

end blindly in the mesorchium (I, †). The course of the *Vasa efferentia*
from the testis is first inwards, within the mesorchium; on reaching
the kidney they curve dorsalwards between that organ and the

corresponding testis: the ducts then travel in the ventral surface of the kidney towards its inner border, where they open into a longitudinal canal (Bidder), (Fig. 222 I, *L*). Just before their terminations each duct has an enlargement (I, *C*), the exact import of which is unknown (see also Fig. 218 XV).

The collecting-tubes open into the ureter at the hinder extremity of the kidney.

b. [**Minute structure.** The testis possesses a thin connective-tissue capsule underneath its peritoneal covering (Fig. 223 II, *a*); this sends in trabeculae (*b*) towards the centre of the organ, and so encloses the separate lobules. Each seminiferous tube arises from an elongated irregular sinus placed towards the middle of the organ; the tubes (*c*) are slightly convoluted in their course towards the periphery, near which they branch (Spengel). The tubes are from 0·16 mm. to 0·12 mm. in diameter (Kölliker), and are lined with two kinds of cells (Fig. 222 III); the cells (*x*) nearer the periphery are rounded and have large rounded nuclei, the diameters of which vary from 0·013 to 0·02 mm.; these again possess large and distinct nucleoli. The other cells (*y*) are of elongated, spindle-shaped form; and have oval nuclei, with an average length of 0·016 mm. and an average breadth of 0·005 mm. (Neumann).

The rounded cells lie in groups which vary in thickness and arrangement, and are often compressed so as to have polygonal outlines. The spindle cells are arranged so as to radiate from the lumen of the tube to the periphery, at an angle which varies from 45 to 90 degrees; these are the spermatoblasts.

The various changes which the spermatoblasts undergo in the formation of spermatozoa will easily be understood by reference to Fig. 223 I, *a* to *k*, where *i* and *k* represent the fully developed spermatozoa. These have three parts, head, middle part, and tail, the respective lengths of which in the two species are, according to Neumann, the following :—

	Head.	Middle part.	Tail.
Rana esculenta	0·0140 mm.	0·0025 mm.	0·040 mm.
Rana temporaria	0·0066 „	0·0330 „	0·045 „

At the hilus of the testis the rounded cells of the seminiferous tubes are gradually modified to form short cylindrical cells (0·01 mm. long and 0·006 mm. broad), the spindle cells being absent (Neumann). The *Vasa efferentia* are also lined with a similar columnar epithelium (Spengel).]

B. The female reproductive organs.

The position of these organs has already been given (p. 335).

I. The ovaries.

Fig. 224.

The female reproductive organs; the ovary of the right side has been removed.

N Kidney.
O.T. Opening of the oviduct into pleuro-peritoneal cavity.
Oe Oviduct.
Ova Ovary.
P Opening of oviduct into the cloaca.
S, S1 Openings of the ureters.
Ut Dilated hinder portion of the oviduct.
† Groove in which ureters lie.
* Fold in groove separating the openings of the ureters.

a. General description. Each sac-like ovary (Fig. 224) is subdivided by thin-walled septa into numerous complete chambers, to the inner walls of which the ova are attached. The walls of adjacent sacs are intimately attached to each other, and the subdivision corresponds with the external lobulated appearance of the organ. According to Spengel the number of lobules is about fifteen (Rathke nine to thirteen, Brandt nine). Whether this segmentation of the ovary corresponds with the segmentation of the body has not been determined (Spengel). No part corresponding with Bidder's organ has been found in *Rana esculenta*.

During the breeding season the ovaries undergo an extraordinary increase in size so as to occupy the greater part of the body-cavity and to displace the other viscera. The ovaries are entirely surrounded by peritoneum.

b. Minute structure. [The layer of peritoneum covering the ovary possesses cilia (Thiry), the ciliated cells being arranged in isolated patches (Schweigger-Seidel, Waldeyer) on the ventral surface of the organ, and on the mesovarium; these patches are some-

times united by very fine connecting lines of ciliated epithelium; the ciliated epithelium is always sharply marked off from that surrounding it (Kolessnikow). Under the peritoneum is a thin layer of connective-tissue, which is prolonged inwards to form the septa above-described. To these septa are attached the ova.

Between the connective-tissue layer and the peritoneum are isolated patches of germinal epithelium (Fig. 225 IV); these are easily distinguished, by the rounded outlines of their cells, from the surrounding epithelial cells (Waldeyer, Kolessnikow). These patches of germinal epithelium measure from 0·093–0·186 mm. in diameter; the germinal cells average 0·0139–0·0232 mm. in diameter (Kolessnikow). The patches are most numerous on the outer surface of the ovary, and particularly so near the mesovarium.

The follicles contained in the ovary have a connective-tissue coat developed in a manner similar to that of higher animals; the primordial ova which they contain have large nuclei (0·0325 mm.). The epithelium of the follicles has an average diameter of 0·0232– 0·0325 mm. (Kolessnikow).

Schultze's description of the ovaries (*l. c.*) varies considerably from that of Waldeyer and Kolessnikow. Briefly he describes the ovaries as a series of sacs separated by and lined externally and internally by endothelium; between these two layers are found the germinal epithelium and follicles: the structures being held together by an extremely minute quantity of connective-tissue.]

II. The **oviducts.**

a. **General description.** In young animals the oviducts are quite straight, thin-walled, and of small calibre. During the breeding season, however, they undergo an immense increase in size, and become much convoluted; in this state they are forced in between the other abdominal viscera, and usually cover the whole of the kidneys, and sometimes even part of the ovaries (Fig. 224 *Ov*).

The openings of the oviducts into the pleuro-peritoneal cavity (p. 304) are semilunar slits, directed inwards and lined with ciliated epithelium (p. 306).

Immediately behind this opening (*Ostium abdominale*) the oviduct is contracted, and is there narrower than in the rest of its length; beyond this it expands, and then retains an even size nearly to its hinder extremity, where it suddenly expands (Fig. 224 *Ut*). This dilatation gradually diminishes in size as it proceeds backwards towards the cloaca, into which each tube opens on a small papilla. The dilated portions of the tubes lie close together,

but do not communicate with each other; the opening of the right tube is always slightly behind that of the left side (Fig. 224 *P*). From the papillae, into which the oviducts open, a fold of mucous membrane extends backwards on the dorsal surface of the cloaca to meet its fellow of the opposite side at an acute angle (Fig. 224 *). The orifices of the ureters are placed within these folds.

b. Minute structure.

(1) The **tubular portion** of the oviduct has **three walls**: a peritoneal covering with sub-peritoneal tissue (*a*); a glandular layer (*b*); and an epithelial lining (*c*). Of these the glandular layer forms by far the thickest layer, especially during the breeding season, when it is much increased in thickness. It consists of long cylindrical glands, often bifurcated at their blind, peritoneal ends. The epithelial cells, with which they are lined,

Fig. 225.

Preparations from ovary and oviduct.

I. Ciliated epithelium and goblet-cells of the oviduct; after Neumann.
II. Isolated goblet-cells and secretory cells from oviduct; after Neumann.
    a, b, c Goblet-cells.
    d, e, f Secretory cells after treatment with Müller's fluid.
    x Stoma of secretory cells.
III. Surface view of the ovary; after Kolessnikow.
    a Peritoneal endothelium.
    b Germinal epithelium.

have the power of absorbing more than a hundred times their own weight of water (Boettcher). This layer is absent at the anterior opening of the oviduct.

The cells have an average diameter of 0·012 mm., the lumen of the individual glands 0·1 mm. (in spirit-hardened specimens, Neumann). The cells contain small rounded bodies of very varying size, which may exist singly, grouped, or even arranged in rows ; they swell on the addition of water. Each cell possesses, in addition, an oval, granular, distinct nucleus. When treated with Muller's fluid many of the secretory cells have the appearances shown in Fig. 225 II, *d, e, f* ; they each possess an opening (*x*),(Neumann).

According to Neumann the great power of absorbing water, which the oviducts possess, is due to the presence of these bodies, which he names 'colloid granules.' The mucous secretion of these glands passes into the oviduct and surrounds the eggs on their passage towards the cloaca : it is due to this secretion that the egg-spawn is so extremely slippery and difficult to handle.

The inner surface of the oviducts is lined with a ciliated, columnar epithelium (Fig. 225 I), containing numerous goblet-cells (I and II).

(2) The **dilated portion** of the oviduct has much thinner walls than the anterior, narrower portion ; the glands cease abruptly at the junction of the two parts. The outer coat also contains unstriated muscular fibre ; the inner surface is lined with ciliated epithelium similar to that of the anterior portion.

The **lymphatics** of the oviducts form a net with polygonal meshes on their outer surfaces ; from this branches pass inwards in the spaces between adjacent glands to the inner surface, where a network with elongated meshes is formed (Langer).

C. [The Cloaca.

a. General description. The cloaca is a short tube lying beneath the urostyle ; anteriorly it receives the openings of the ureters, rectum, and bladder ; and in the female the openings of the oviducts, in addition : posteriorly it terminates at the anus.

b. Minute structure. The cloaca is lined internally with a mucous membrane resembling that of the rectum, *e.g.* a simple layer of columnar epithelium, which rests on a submucous, areolar layer.

The outer walls consist of a thick superficial, longitudinal muscular layer, and a deeper, ill-developed, transverse muscular layer.

c. Special muscles of the cloaca.

(1) The *M. sphincter ani* surrounds the end of the cloaca from the anus to the tip of the urostyle. It consists of striated muscle.

(2) The *M. compressor cloacae* arises from the tip of the urostyle, and is inserted into the hinder end of the rectum; it is also attached to the symphysis of the iliac bones; from this point a few fibres pass to the anus (Hoffmann).]

III. THE ADRENALS.

a. General description. The adrenals are small yellow bodies attached to the renal veins on the ventral surface of the kidney, towards its outer border.

Fig. 226.

The male urino-genital organs.

Ao Aorta.
Cl Cloaca.
Cv Inferior vena cava.
FK Fat-body.
N Kidney.
S, S₁ Openings of ureters.
T Testis.
Ur Ureter.
Vr Renal veins.
✝ Appearance of ureters on the ventral surfaces of kidneys.

b. [**Minute structure.** The superficial layer of the adrenals consists of solid, rounded, or elongated groups of polygonal cells, containing numerous fat-granules; these represent the cortical substance of the corresponding organs of higher animals. The medullary part is present only in small quantity; it consists of small groups of polygonal cells, placed between trabeculae of connective-tissue; both trabeculae and cell-groups are covered with an endothelium. The whole organ is surrounded by a connective-tissue capsule, which sends in trabeculae to support the parenchyma (Hoffmann).

No nerves have been traced into these organs (Eberth).]

IV. THE FAT-BODIES.

a. General description. The fat-bodies (Fig. 226) are bright yellow, lobulated bodies, placed in front of the testes and ovaries respectively. The greater portion of each organ lies parallel to the long axis of the body, and from its anterior, posterior, and external

borders are given off finger-like processes; these may divide dichotomously either near the base or more peripherally. The external processes are much the longest, and in the male often conceal the greater part of the testis (Fig. 226 FK). The organs vary greatly in size with the season of the year.

Fig. 227.

Two preparations from the fat-body of *Rana esculenta* [1].—G. H.

I. Section of fat-body, stained with borax-carmine (Hartnack, Oc. I, Syst. 7).
b Fat-cells.
c Adenoid tissue.
II. Three lobes of fat-body of *Rana esculenta*; coarsely injected (Hartnack, Oc. I, Syst. 3).
Arteries striped. Veins shaded.

b. [Minute structure. Each organ is completely surrounded by peritoneum, under which is a very fine layer of connective-tissue. The interior of the organ (Fig. 227 I) consists of large fat-cells with small patches of adenoid tissue interspersed. The organs are extremely vascular; each lobe has a main artery which gives off lateral branches: each of these immediately divides to form two vessels, which run in opposite directions and almost parallel with the main stem; the vessels then break up into a fine network of capillaries.]

[1] From specimens collected in November.

SECTION VIII.

THE SKIN AND THE SENSE-ORGANS.

THE SKIN AND THE SENSE-ORGANS.

LITERATURE.

———◆———

I. THE SKIN.

Ascherson, Ueber die Hautdrüsen der Frösche. Arch. f. Anat. u. Physiol. 1810, p. 15.

Axmann, Beiträge zur mikroskopischen Anatomie und Physiologie des Ganglien-nervensystems. 1853.

de Betta, Erpétologia delle provincie Venete e del Tirolo meridionale. 1857.

Biesiadecki, Ueber Basenbildung und Epithelregeneration an der Schwimmhaut des Frosches. Untersuchungen aus d. Krakauer path.-anatom. Institut. 1872, pp. 60-84. Abstract in Centralbl. f. d. med. Wiss. 1873, No. 7, p. 106.

Bimmermann, E. H., Ueber den Einfluss der Nerven auf die Pigmentzellen des Frosches. Dissert. Strasburg, 1878.

Bimmermann, E. H., Ueber den Einfluss der Nerven auf die Pigmentzellen des Frosches. Centralbl. f. d. med. Wiss. 1879, p. 545.

de Blainville, M. H. M. Ducrotay, De l'Organisation des animaux. Paris, 1822, pp. 142, 225.

Bolaw, Beitrag zur Kenntniss der Amphibienhaut. Göttingen, 1866.

Bruch, Beiträge zur Naturgeschichte und Classification der nackten Amphibien. Würzburger naturwiss. Zeitsch. 1864. Vol. III.

Brücke, Untersuchungen über den Farbenwechsel des afrikanischen Chamaeleon. Sitzungsb. der Wiener Acad. 1852. Vol. IV, p. 196.

Bugnion, Recherches sur les organes sensitifs qui se trouvent dans l'épiderme du Protée et de l'Axolotl. Dissert. Zürich.

Canini, A., Die Endigungen der Nerven in der Haut des Froschlarvenschwanzes. Arch. f. Anat. u. Physiol. 1880, pp. 143-153.

Ciaccio, J. V., Intorno alla minuta fabbrica della pella della Rana esculenta. Palermo, 1866. Giornale di Scienze naturali ed economiche. Vol. II, pp. 103-158.

Ciaccio, J. V., On the distribution of the nerves to the skin of the frog, with physiological remarks on the ganglia connected with the cerebro-spinal nerves. Trans. Micros. Soc. London, 1864. Vol. XII, pp. 15-31.

Czermak, J. N., Ueber die Hautnerven des Frosches. Arch. f. Anat. u. Physiol. 1849, p. 252.

Da Collin, Danemarks Froer og Tudser. Naturhist. Tidsskrift. 1870.

Dewits, Ueber das verschiedene Aussehen der gereizten und ruhenden Drüsen im Sehenballe des Laubfrosches. Biol. Centralbl. 1883, p. 558.

Dogiel, Neue Untersuchungen über den pupillenerweiterden Muskel, etc. Arch. f. mik. Anat. 1886. Vol. XXVII, p. 403.

Duméril et Bibron, Erpétologie générale. 1841. Vol. VIII.

Eberth, C. J., Untersuchungen zur normalen und path. Anatomie der Froschhaut. Leipzig, 1869.

Eberth, C. J., Zur Entwickelung der Gewebe im Schwanze der Froschlarven. Arch. f. mik. Anat. 1866. Vol. II, pp. 490–503.

Eckhard, Ueber den Bau der Hautdrüsen der Kröten und die Abhängigkeit der Entleerung ihres Secretes vom centralen Nervensystem. Arch. f. Anat. u. Physiol. 1849.

Ehrmann, S., Ueber Nervenendigungen in den Pigmentzellen der Froschhaut. Sitzungsb. der Wiener Acad. 1882. Vol. LXXXIV, Pt. III, pp. 165–170.

Engelmann, T. W., Pflüger's Arch. f. d. ges. Physiol. 1871, Vol. IV, p. 321, and 1872, Vol. V, pp. 500–513. (Contractile glands in skin of frog.)

Harless, E., Ueber die Chromatophoren des Frosches. Zeitsch. f. wiss. Zool. 1854, Vol. V, p. 372 ; also in Münchener Gelehrten Anzeiger, 1853, No. 35.

Harley, G., On the organs of cutaneous respiration; principally on those of Rana temporaria. Trans. Micros. Soc. London, 1857. Vol. V, p. 148.

Hensche, A., Ueber die Drüsen und glatten Muskeln in der äusseren Haut von Rana temporaria. Zeitsch. f. wiss. Zool. 1856. Vol. VII, p. 273.

Henslow, Way in which toads shed their skin. Annals of Nat. History, 1850, p. 69.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs. Leipzig und Heidelberg, 1873–1878. Vol. VI.

Huber, O., Ueber Brustwarzen bei Rana temporaria, L. Zeitsch. f. wiss. Zool. 1887. Vol. XLV, p. 664.

Huizinga, D., Untersuchungen über die Innervation der Gefäsze in der Schwimmhaut des Frosches. Pflüger's Arch. 1875. Vol. XI, p. 207.

Huxley, H. T., Tegumentary organs. Todd and Bowman's Cyclopædia of Anat. and Physiol. p. 500.

Klein, E., On the lymphatic system of the skin and mucous membranes. Quart. Journ. Micros. Sci. 1881. Vol. XXI, pp. 379–406.

Kölliker, A., Stiftchenzellen in der Epidermis von Froschlarven. Zoolog. Anzeiger. 1885.

Krause, Handbuch der Gewebelehre. 1862.

Krukenberg, C. F. W., Die Hautfarbstoffe der Amphibien, in Vergleich. physiol. Studien, by same author, 1882, pp. 43–49.

Kutschenko, N., Ueber die Krappfärbung der Froschgewebe. Arch. f. mik. Anat. 1882. Vol. XXVIII, pp. 360–364.

Langer, Ueber das Lymphgefässsystem des Frosches. Wiener Sitzungsberichte. 1867. Vol. LV, pp. 593–636.

Langerhans, Anat.-hist. Untersuchungen über Fische und Reptilien. Berlin, 1853. Journal de Medicine. Vol. XI.

Lebouucq, H., Recherches sur le développement et la terminaison des nerfs chez les larves des Batraciens. Bull. de l'acad. roy. de Belgique. 1876. Vol. XLI, p. 4.

Leydig, F., Histologisch-anatomische Untersuchungen über Fische und Reptilien. 1853.

Leydig, F., Tastkörperchen und Muskelstruktur. Arch. f. Anat. u. Physiol. 1856, pp. 150–159.

Leydig, F., Lehrbuch der Histologie. 1857.

Leydig, F., Ueber die Nervenendigung in den sogenannten Schleimkanälen der Fische und über entsprechende Organe der durch Kiemen athmenden Amphibien. Arch. f. Anat. u. Physiol. 1861.

Leydig, F., Ueber die Organe eines sechsten Sinnes. Nov. act. acad. Leop. Carol. 1868. Vol. XXXIV, pp. 1–102.

Leydig, F., Ueber die allgemeinen Bedeckungen der Amphibien. Arch. f. mik. Anat. 1875. Vol. XII, p. 119.

Leydig, F., Ueber die Schleichenlurche. Zeitsch. f. wiss. Zool. Vol. XVIII.

Leydig, F., Ueber die Schwanzflosse, Tastkörperchen und Endorgane der Nerven bei Batrachiern. Arch. f. mik. Anat. 1876. Vol. XII, pp. 513–527.

Leydig, F., Die anuren Batrachier der deutschen Fauna. Bonn, 1877, p. 123.

Lister, J., On the cutaneous pigmentary system of the frog. Phil. Trans. 1857. Vol. CXLVIII, p. 627.

Macallum, A. B., The nerve terminations in the cutaneous epithelium of the tadpole. Quart. Journ. Micros. Sci. 1886. Vol. XXVI, p. 53.

Mayer, A., Ueber das Epithelium bei den Amphibien. Froriep's Notizen, 1839. Vol. IX, coll. 49–51.

Menke, Rana rubita, Linn. Zeitschr. Isis von Oken. 1827. Vol. XX, p. 172.

Merkel, Ueber die Endigungen der sensiblen Nerven in der Haut der Wirbelthiere. Rostock, 1880.

Meyer, Ueber die Abhängigkeit der Gefässe und Pigmentzellen beim Frosch von dem Nerveneinfluss. Virchow's Arch. 1854. Vol. VI, p. 581.

Openchowski, T., Histologisches zur Innervation der Drüsen. Pflüger's Arch. 1882. Vol. XXVII, pp. 223–232.

Pfitzner, W., Die Epidermis der Amphibien. Morph. Jahrb. 1880. Vol. VI, p. 469.

Rainey, On the structure of the cutaneous follicles of the toad. Quart. Journ. Micros. Sci. Vol. III, p. 257.

Roesel, Historia natur. rana. nostrat. Nürnberg, 1758, p. 3, etc.

Budneff, Ueber die epidermoidale Schicht der Froschhaut. Arch. f. mik. Anat. 1865. Vol. I, p. 295.

Sattler, E. E., Die Verwendung des Lapisstiftes zur Untersuchung der Epithelien. Arch. f. mik. Anat. 1882. Vol. XXI, p. 672.

Schneider, Historia amphibiorum. 1739.

Schultze, F. E., Epithel und Drüsenzellen. Arch. f. mik. Anat. 1867. Vol. III, p. 145.

Schultze, F. E., Ueber cuticulare Bildungen und Verhornung von Epithelzellen bei den Wirbelthieren. Arch. f. mik. Anat. 1869. Vol. V, p. 295.

Schultze, M., Ueber die Nervenendigung in der Netzhaut des Auges bei Menschen und Thieren. Centralbl. f. med. Wiss. 1869, p. 885.

Stieda, L., Ueber den Bau der Haut des Frosches. Arch. f. Anat. u. Physiol. 1865, pp. 52–66.

Stricker, S., and **Spina, A.**, Untersuchungen über die mechan. Leistungen d. acinösen Drüsen. Wiener med. Jahrb. 1880, p. 355; und Wiener Sitzungsb. 1880. (Skin and Membrana nictitans.)

Swammerdam, J., Biblia naturae. Vol. II, p. 808.

Szoesny, Beiträge zur Kenntniss der Textur der Froschhaut. Dissert. inaug. Dorpat, 1867.

Turner, Way in which toads shed their skins. Annals of Nat. History, 1850, p. 430.

Wagner, R., Handwörterbuch der Physiologie. Vol. III, p. 389.

Walter, Ueber die Drüsen des Daumenballens des Froschmännchens. Verhandl. d. naturf. Vereins der pr. Rheinlande und Westphalen. 1851, p. 351.

v. Wittich, Die grüne Farbe der Haut unserer Frösche, etc. Arch. f. Anat. u. Physiol. 1854, p. 41.

v. Wittich, Entgegnung auf Herm. Harless's über die Chromatophoren des Frosches. Arch. f. Anat. u. Physiol. 1854, p. 264.

II. SPECIAL ORGANS OF TACTILE SENSATION.

a. The lateral sense-organs.

Beard, J., On the segmental sense-organs of the lateral line and on the morphology of the vertebrate auditory organs. Zool. Anz. 1884. Vol. VII, p. 162.

Bugnion, E., Recherches sur les organes sensitifs qui se trouvent dans l'épiderme du Protée et de l'Axolotl. Dissert. inaug. Zürich. Tiré du Boll. No. 7, de la société vaucloise des Sc. nat. Vol. XII. Lausanne, 1873. Verhandl. d. schweiz. naturforsch. Gesells. Zürich, 1873. Vol. LVI, p. 49.

Froriep, A., Ueber Anlagen von Sinnesorganen am Facialis, Glossopharyngeus und Vagus. Arch. f. Anat. u. Physiol. 1885.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs. Leipzig and Heidelberg, 1873-1878.

v. Kölliker, A., Ueber neue Sinnesorgane von Froschlarven. Sitzungsb. Würzburg. 1885, p. 79.

Krause, W., Die Nervenendigung innerhalb der terminal Körperchen. Arch. f. mik. Anat. 1880. Vol. XIX, pp. 53-137.

Leydig, F., Ueber die Organe eines sechsten Sinnes. Nova acta Acad. Leopold. Carol. Dresden, 1868. Vol. XXXIV, pp. 1-102.

Leydig, F., Ueber die allgemeinen Bedeckungen der Amphibien. Arch. f. mik. Anat. 1875. Vol. XII, pp. 513-527.

Leydig, F., Ueber Tastkörperchen und Muskelstructur. Arch. f. Anat. u. Physiol. 1856, p. 150.

Malbranc, M., Bemerkung betreffend die Sinnesorgane der Seitenlinie der Amphibien. Centralbl. f. med. Wiss. 1875, p. 5.

Malbranc, M., Von der Seitenlinie und ihren Sinnesorganen bei Amphibien. Zeitsch. f. wiss. Zool. 1876. Vol. XXVI, pp. 24-86.

Schultze, E E., Ueber die Nervenendigung in den sogenannten Schleimkanälen der Fische und über entsprechende Organe der durch Kiemen athmenden Amphibien. Arch. f. Anat. u. Physiol. 1861, p. 759.

Schultze, F. E., Ueber die Sinnesorgane der Seitenlinie bei Fischen und Amphibien. Arch. f. mik. Anat. 1870. Vol. VI, p. 62.

b. The touch-corpuscles of Golgi.

Golgi, C., Della terminazione dei nervi nei tendini e di un nuovo apparato nervoso terminale musculo-tendineo. Atti della Società Italiana di scienze naturali. Milan, 1879. Vol. XXI; and abstracted in Centralbl. f. med. Wiss. 1879, p. 725.

Golgi, C., Intorno alla distribuzione e terminazione dei nervi nei tendini dell' uomo e di altri vertebrali. Estratto dai Rendiconti del R. Istituto Lombardo. Serie II. Vol. XI. Fasc. IX. Milan, 1878. Abstract in Centralbl. f. med. Wiss. 1879. Vol. 41, p. 725.

Löwe, L., Ueber eine eigenthümliche Art von Gelenknervenkörperchen beim Frosch. Arch. f. mik. Anat. 1880. Vol. XVI, p. 613.

III. THE ORGANS OF TASTE.

Beale, L. S., New observations upon the minute anatomy of the frog's tongue. Phil. Trans. 1865, p. 443.

Biedermann, W., Ueber morphologische Veränderungen der Zungendrüsen des Frosches, etc. Wiener acad. Sitzungsb. 1882. Vol. LXXXVI, Pt. III, p. 67.

Billroth, T., Ueber die Epithelzellen der Froschzunge, etc. Arch. f. Anat. u. Physiol. 1858, p. 159.

Engelmann, T. W., Ueber die Endigungsweise der Geschmacksnerven des Frosches. Centralbl. f. med. Wiss. 1867, p. 785.

Engelmann, T. W., Ueber die Endigungen der Geschmacksnerven in der Zunge des Frosches. Zeitsch. f. wiss. Zool. 1868. Vol. XVIII, p. 142.

Engelmann, T. W., Die Geschmacksorgane. Stricker's Handbuch der Gewebelehre. 1872.

Fixsen, C., De linguae raninae structura. Dorpat, 1857.

Gottschau, M., Ueber Geschmacksorgane der Wirbelthiere. Biol. Centralbl. 1882, pp. 240-248.

Hartmann, R., Ueber die Endigungsweise der Nerven in den Papillae fungiformes der Froschzunge. Arch. f. Anat. u. Physiol. 1863, p. 634.

Hoyer, Mikroskopische Untersuchungen über die Zunge des Frosches. Arch. f. Anat. u. Physiol. 1859, p. 481.

Hoyer, Ueber die Epithelzellen der Froschzunge, etc. Arch. f. Anat. u. Physiol. 1858, p. 163 ; also in Deutscher Klinik, 1857. No. 21.

Hyrtl, Ueber abwickelbare Gefässknäuel in der Zunge der Batrachier. Wiener Acad. Sitzungsb. 1863. Vol. XLVIII, Pt. I, p. 437.

Key, E. A., Ueber die Endigungsweise des Geschmacksnerven in der Zunge des Frosches. Arch. f. Anat. u. Physiol. 1861, p. 329.

Lépine (On the nerve supply of the glands of the tongue). Arbeiten aus d. physiol. Anstalt zu Leipzig, 1870, p. 113.

Molin, R., Ueber die Theilung der Nervenprimitivröhren in den Papillae fungiformes der Froschzunge. Wiener acad. Sitzungsb. 1849. Vol. III, p. 183.

Schultze, F. E., Die Geschmacksorgane der Froschlarven. Arch. f. mik. Anat. 1870. Vol. VI, p. 407.

Waller, A., Minute structure of the organ of taste in vertebrate animals. Proc. Roy. Soc. 1848. Vol. V, p. 751.

Waller, A., Minute structure of the papillae and nerves of the tongue of the frog and toad. Phil. Trans. 1848. Pt. I, p. 139.

Waller, A., Microscopic examination of some of the principal tissues of the tongue, etc. Phil. Mag. 1847. Vol. XXX, p. 277.

IV. THE NOSE.

Babuchin, Das Geruchsorgan, in Stricker's Handbuch der Gewebelehre. 1872, p. 964.

de Blainville, M. H. M. Ducrotay, L'Organisation des animaux. Paris, 1822, p. 328.

Blaue, J., Untersuchungen über den Bau der Nasenschleimhaut bei Fischen und Amphibien, namentlich über Endknorpel als Endapparate des Nervus olfactorius. Arch. f. mik. Anat. 1884. Vol. XXX, pp. 231-309. Zool. Anzeiger. Vol. V, pp. 657-680.

Born, G., Ueber die Nasenhöhlen und den Thränennasengang der Amphibien. Morph. Jahrb. 1875. Vol. II, p. 4.

Born, G., Ueber die Nasenhöhlen und den Thränennasengang der Amphibien. Breslau. Habilit.-Schrift. 1877.

Born, G., Die Nasenhöhlen und der Thränennasengang der amnioten Wirbelthiere. Morph. Jahrb. 1879. Vol. V, p. 62. 1882. Vol. VIII, pp. 188-232.

v. Brunn, Die Membrana limitans olfactoria. Centralbl. f. med. Wiss. 1874, p. 709.

v. Brunn, Untersuchungen über das Riechepithel. Arch. f. mik. Anat. 1875. Vol. XI, pp. 468-478.

v. Brunn, Weitere Untersuchungen über das Riechepithel u. sein Verhalten zum N. olfactorius. Arch. f. mik. Anat. 1880. Vol. XVII, p. 141.

Cisoff, Zur Kenntniss der Regio olfactoria. Centralbl. f. med. Wiss. 1874, pp. 689-691.

Cisoff, Zur Frage über die Endigung der Riechnerven beim Frosche. Arbeiten der naturf. Gesells. an der Universität Kassan. 1879. Vol. VIII (in Russian).

Clarke, J. Lockhart, Ueber den Bau des Bulbus olfactorius und der Geruchsschleimhaut. Zeitsch. f. wiss. Zool. 1862. Vol. XI, p. 31.

Colossanti, Untersuchungen über die Durchschneidung des N. olfactorius bei Fröschen. Arch. f. Anat. u. Physiol. 1875.

Dirkinck-Holmfield-Christmas, J., Experimentalle Undersögelen Bijgningen. Nordiskt medicinskt Arkiv., 1883. Vol. XXVI, pp. 50-60.

Dogiel, A., Ueber die Drüsen der Nasenschleimhaut, besonders die Bowmanschen Drüsen. Arch. f. mik. Anat.

Dogiel, A., Ueber den Bau des Geruchsorgans bei Garroirren, Knochenfischen, und Amphibien. Arch. f. mik. Anat. 1887. Vol. XXIX, p. 74.

Dogiel, A., Ueber den Bau des Geruchsorgans bei Fischen und Amphibien. Biol. Centralbl. Vol. I, pp. 428-431.

Dogiel, A., Ueber die Drüsen d. Regio olfactoria. Arch. f. mik. Anat. 1885. Vol. XXVI, p. 50.

Ecker, E., Bericht über die Verhandl. der Gesellschaft für Beförd. der Naturw. zu Freiburg, 1855, p. 199; and in Zeitsch. f. wiss. Zool. 1856, Vol. VIII, p. 303.

Eckhard, C., Beiträge zur Anatomie und Physiologie. Pt. I, 1855, p. 77.

Eckhard, C., Ueber die Endigungsweise der Geruchsnerven. Beiträge zur Anat. u. Physiol. Giessen, 1882. Vol. I, p. 77.

Erichsen, J., De textura nervi olfactorii ejusque ramorum. Dissert. inaug. 1857.

Exner, S., Untersuchungen über die Riechschleimhaut des Frosches. Sitzungsb. der Wiener Acad. 1871. Vol. LXIII, Pt. II, p. 44.

Exner, S., Weitere Studien über die Structur der Riechschleimhaut bei Wirbelthieren. Sitzungsb. der Wiener Acad. 1872. Vol. LXV, Pt. III, p. 7.

Exner, S., Fortgesetzte Studien über die Endigungsweise des Geruchsnerven. Sitzungsb. der Wiener Acad. 1878. Vol. LXXVI, Pt. III, p. 171.

Gastaldi, Nuove Ricerche sovra la terminazione del nervo olfatt. Mem. della reale Acad. della scienze di Torino. 1858. Vol. XVII, Series II, p. 369.

Hoffmann, Lehrbuch der Anatomie der Sinnesorgane.

Hoffmann, C. K., Ondersockingen over den anat. bouw van de membrana olfactoria en het periph. uitiende van den Nervus olfactorius. Dissert. inaug. 1866.

Hoffmann, C. K., Amphibia in Bronn's Klassen und Ordnungen des Thierreichs. Leipzig und Heidelberg, 1873-1878. Vol. VI, pp. 335-347.

Horn, H., Ueber die Endschlingen des Geruchsnerven (nervus olfactorius) der Rana temporaria. Arch. f. Anat. u. Physiol. 1850.

Hoyer, H., De tunica mucosa narium textura. Dissert. inaug. Berol., 1857.

Hoyer, H., Ueber die mikroskopischen Verhältnisse der Nasenschleimhaut, etc. Arch. f. Anat. u. Physiol. 1860, p. 50.

Langer, C., Ueber das Lymphgefässsystem des Frosches. Wiener Acad. Sitzungsb. 1867. Vol. LV, Pt. I, p. 615.

Legal, E., Die Nasenhöhlen und der Thränennasengang der amnioten Wirbelthiere. Morph. Jahrb. 1882. Vol. VIII, p. 353.

Martin, Studies from the physiological laboratory in the University of Cambridge. Pt. I. 1873.

Paschutin, V., Ueber den Bau der Schleimhaut der Regio olfactorio beim Frosch. Medicinisky Wjestnik. 1872. Nos. 38-40.

Paschutin, V., Ueber den Bau der Schleimhaut der Regio olfactoria des Frosches. Arbeiten aus d. phys. Laborat. Leipzig, 1873.

Paulsen, E., Ueber die Drüsen der Nasenschleimhaut besonders die Bowman'schen Drüsen. Arch. f. mik. Anat. 1886. Vol. XXVI, pp. 307-321.

Piersol, G. A., Beiträge zur Histologie der Harderschen Drüsen der Amphibien. Arch. f. mik. Anat. 1887. Vol. XXIX, p. 594.

Reichert, B., Arch. f. Anat. u. Physiol. 1857. p. 39. Bericht.

Schultze, M., Ueber die Endigungsweise des Geruchsnerven und die Epithelial-gebilde der Nasenschleimhaut. Monatsb. Acad. z. Berlin. 1856, p. 504.

Schultze, M., Untersuchungen über den Bau der Nasenschleimhaut, namentlich die Structur und Endigungsweise der Geruchsnerven bei dem Menschen und den Wirbelthieren. Halle, 1862. Vol. VII, pp. 32-41; also published in Berlin, 1875. Abstract in Centralbl. f. med. Wiss. 1863, p. 97.

Seeberg, Disq. microsc. de textura membr. pitnit. nasi. Dorpat, 1855. Dissert. inaug.

Stirling, W., and Macdonald, The minute structure of the palatine nerves of the frog and the termination of nerves in blood-vessels and glands. Journ. of Anat. and Physiol. 1884. Vol. XVII, p. 293.

Wiedersheim, R., Ueber die Kopfdrüsen der Amphibien. Sitzungsb. d. phys.-med. Gesell. in Würzburg, 1876. Febr. 5.

Wiedersheim, R., Die Kopfdrüsen der geschwänzten Amphibien und die Glandula intermaxillaris der Anuren. Zeitsch. f. wiss. Zool. 1876. Vol. XXVII, pp. 1-50.

Wiedersheim, R., Lehrbuch der vergl. Anatomie der Wirbelthiere. Pt. I. Jena, 1882.

V. THE EAR.

Chatin, J., Recherches pour servir a l'histoire du noyau dans l'épithelin auditif des batrachiens. Annales des sciences nat. Zool. 1883. Vol. XVI, Series VI, Art. No. 2.

Comparetti, A., in gymnasio patavino observationes anatomicae de aure interna comparatae. Patavii, 1789.

Crombie, J. M., On the membrana tympani. Journ. of Anat. and Physiol. 1883, pp. 523-536.

Cuvier, G., Leçons d'anatomie comparée. Paris, 1800. Vol. II.

Deiters, O., Ueber das innere Gehörorgan der Amphibien. Arch. f. Anat. u. Physiol. 1862, p. 277.

Eberth, C. J., Zur Kenntniss der Verbreitung der glatten Muskelfasern (Tympanic membrane). Zeitsch. f. wiss. Zool. 1863. Vol. XII, p. 364.

Ferré, Étude sur la crête auditive chez les vertébrés. Ann. Sci. Nat. Bordeaux. Vol. I, No. III.

Hasse, C., Die Histologie des Bogenapparates und des Steinsacks der Frösche. Zeitsch. f. wiss. Zool. 1868. Vol. XVIII, p. 71.

Hasse, C., Das Gehörorgan der Frösche. Zeitsch. f. wiss. Zool. 1868. Vol. XVIII, p. 359.

Hasse, C., Das knöcherne Labyrinth der Frösche. Anatomische Studien, 2nd Pt. 1872, p. 377.

Hasse, C., Die vergleichende Morphologie und Histologie des häutigen Gehörorgans der Wirbelthiere. Supplement to the Anatomische Studien. Vol. I, 1873.

Hasse, C., Die Lymphbahnen des inneren Ohres der Wirbelthiere. In the Anatomische Studien of Hasse, 1873. No. XIX.

Hasse, C., Das Gehörorgan der Wirbelthiere von Gustav Retzius. Arch. f. Ohrenheilk. 1884. Vol. XXI, pp. 314-324.

Hoffmann, Lehrbuch der Anatomie der Sinnesorgane.

Hoffmann, Bronn's Klassen und Ordnungen des Thierreichs. Leipzig and Heidelberg, 1873-1878. Vol. VI, pp. 304-335.

Ibsen, J., Anatomiske Undersögelser over orets Labyrinth. Udgivet vet P. L. Panum. Kjöbenhawn, 1846 (abstract in Virchow and Hirsch's Jahresb. 1881, p. 88).

Kuhn, Ueber das häutige Labyrinth der Amphibien. Arch. f. mik. Anat. 1880. Vol. XVII, pp. 479–550.

Kuhn, Zur Anatomie des inneren Ohres der Wirbelthiere. Compt. rend. du III Congrès internat. d'Otologie à Bàle, 1884, pp. 228–238.

Leydig, F., Lehrbuch der Histologie des Menschen und der Thiere. Frankfurt a. M. 1857.

Leydig, F., Ueber neuere den Aquaeductus vestibuli des Menschen und der Thiere betreffende Forschungen. Sitzungsb. d. Niederrheinischen naturf. Gesellsch. in Bonn, 1874. Vol. XXXIV, p. 124.

Moldenhauer, Vergleichende Histologie des Trommelfells. Arch. f. Ohrenheilk. 1878, p. 1.

Pappenheim, S., Ueber Verbreitung der Flimmerbewegung. Arch. f. Anat. u. Physiol. 1840, p. 533.

Retzius, G., On hörselnervens ändningssätt i maculae och cristae acusticae. Nordiskt medicinskt arkiv. 1871. Vol. III.

Retzius, G., Zur Kenntniss der Morphologie des inneren Ohres bei Wirbelthieren. Nord. Med. Ark. 1880. Vol. XII, No. 12.

Retzius, G., Zur Kenntniss des Gehörorgans der Wirbelthiere. Arch. f. Anat. u. Physiol. 1880, pp. 235–244.

Retzius, G., Das Gehörorgan der Wirbelthiere. Pts. I and II, 1881. Stockholm.

Retzius, G., Das Gehörorgan der Wirbelthiere. Congr. internat. de Copenhagen. Anatomy, p. 29.

Retzius, G., Das Gehörorgan der Fische und Amphibien. Pt. I, 1881. Stockholm.

Retzius, G., Zur Kenntniss der Morphologie des inneren Ohres bei Wirbelthieren. Nord. Med. Ark. 1880. Vol. XII, p. 6.

Retzius, G., Ueber die peripherische Endigungsweise der Gehörnerven. Biol. Untersuch. Stockholm and Leipzig, pp. 51–61.

Schultze, F. E., Zur Kenntniss der Endigungsweise der Hörnerven bei Fischen und Amphibien. Arch. f. Anat. u. Physiol. 1862, p. 381.

Stannius, H., Handbuch der Zootomie von v. Siebold und Stannius. Berlin, 1856. 2nd Edit., Pt. II.

Tafani, A., L'organo dell' udito. Firenze, 1885.

Waldeyer, W., Hörnerv und Schnecke. Stricker's Handbuch der Gewebelehre, pp. 915–963.

Weber, E., Amtlicher Bericht über die neunzehnte Versammlung deutscher Naturforscher und Aerzte in Braunschweig im Sept. 1841. Printed Braunschweig, 1842.

Windischmann, De penitiori auris in amphibiis structura Lipsiae, 1831.

VI. THE EYE.

a. *The cornea and sclerotic.*

Angelucci, A., Ueber den Bau u. die Entwickelung des vorderen Uvealtractus der Vertebraten. Centralbl. f. d. med. Wiss. 1879. No. 24, p. 417.

Altmann, R., Ueber die Verwerthbarkeit der Corrosion in der mikroskopischen Anatomie. Arch. f. mik. Anat. 1879. Vol. XVI, p. 471 (Corneal corpuscles).

Arnold, J., Die Vorgänge bei der Regeneration epithelialer Gebilde. Virchow's Arch. 1869. Vol. XLVI, p. 168.

Arnold, J., Experimentale Untersuchungen über die Entwicklung der Blutcapillaren. Virchow's Arch. 1871. Vol. LIII, p. 70. 1872. Vol. LIV, p. 1.

Boddaert, Zur Histologie der Cornea. Centralbl. f. med. Wiss. 1871, p. 337.

Ciaccio, J. V., On the nerves of the cornea and of their distribution in the corneal tissue of man and animals. Trans. Micros. Soc. London, 1863. Vol. XI, p. 77.

Clasow, E., Om corneal epithel. Upsala läkareförenings förhandlingar. 1869. Vol. IV, p. 411.

Cohnheim, J., Ueber die Endigung der sensiblen Nerven in der Hornhaut. Virchow's Arch. 1867. Vol. XXXVIII, p. 343.

Durante, F., Sulla terminazione dei nervi della cornea. Richerche fatte nel laborat. di anat. normal. Roma, pubbl. dal dott. F. Tocharo. 1873, pp. 81–87.

Engelmann, T. V., Ueber die Hornhaut des Auges. Leipzig, 1867.

v. Ewetsky, Ueber das Endothel der Membrana Descemeti. Untersuch. aus d. pathol. Institut. Zürich, 1875. Vol. III.

Frey, H., Handbuch der Histologie und Histochemie.

Generisch, Zur Lehre von den Saftkanälchen in der Cornea. Med. Jahrb. der Gesellsch. d. Aerzte in Wien. 1871, p. 1.

Guye, A. G., Over bekercellen en in het byzonder over de bekercellen in de membrana nictitans van den Kikvouch. Nederl. Tydschrift v. Gewesh. 1868. Vol. II, p. 135.

Hansen, A., Untersuchungen über die entzündlichen Veränderungen der Hornhautkörper. Wiener Med. Jahrb. 1871, p. 210.

Harpeck, C., Ueber die Bedeutung der nach Silberimprägnation auftretenden weissen lücken- und spaltähnlichen Figuren in der Cornea. Arch. f. Anat. u. Physiol. 1864, p. 222.

Hartmann, R., Ueber die durch den Gebrauch der Höllensteinlösung künstlich dargestellten Lymphgefässanhänge, Saftcanälchen und epithelähnlichen Bildungen. Arch. f. Anat. u. Physiol. 1864, p. 235.

Heiberg, H., Ueber die Neubildung des Hornhaut-Epithels. Wiener Med. Jahrb. 1871.

Heisrath, F., Ueber d. Zusammenhang d. vordern Augenkammer mit d. vord. Ciliarvenen. Arch. f. mik. Anat. 1878. Vol. XV, p. 209.

Helfreich, Ueber die Nerven der Conjunctiva und Sclera. Würzburg, 1870.

Henle, J., Handbuch der systematischen Anatomie, 1866. Vol. II.

His, W., Untersuchungen über der Bau der Hornhaut, in Verhandlungen der phys.-med. Gesellschaft in Würzburg. 1856. Vol. IV, p. 90.

His, W., Ueber die Einwirkung des salpetersauren Silberoxydes auf die Hornhaut. Schweizerische Zeitsch. f. Heilkunde. 1864. Vol. II, p. 1.

Hoffmann, F. A., Ueber Contractilitätsvorgänge im vorderen Epithel der Froschhornhaut. Diss. Berlin, 1868.

Hoffmann, F. A., Epithelneubildung auf der Cornea. Virchow's Arch. 1870. Vol. LI, p. 373.

Hosch, F., Ueber die angebliche Contractilität der Knorpelzellen und Hornhautkörperchen. Pflüger's Arch. f. d. ges. Physiol. 1873. Vol. VII, p. 515.

Hoyer, H., Ueber den Austritt von Nervenfasern in das Epithel der Hornhaut. Arch. f. Anat. u. Physiol. 1866, pp. 180–195.

Hoyer, H., Ueber die Nerven der Hornhaut. Arch. f. mik. Anat. 1873. Vol. IX, p. 220.

Klebs, E., Das Epithel der hintern Hornhautfläche. Centralbl. f. d. med. Wiss. 1864, p. 513.

Klein, E., Some remarks on the finer nerves of the cornea. Monthly Journ. Micros. Sci. 1872. Vol. VII, pp. 156–164.

Klein, E., Beiträge zur Kenntniss der peripherischen Verzweigung markloser Nervenfasern. Centralbl. f. d. med. Wiss. 1871, p. 594.

Klemensiewics, R., Karyokinese in den fixen Hornhautzellen bei Entzündung. Centralbl. f. d. med. Wiss. 1884, p. 163.

v. Kölliker, A., Ueber die Nerven der Hornhaut. Mittheilungen der naturforschenden Gesellschaft in Zürich. 1849.

v. Kölliker, A., Ueber die Nervenendigungen in der Hornhaut. Würzb. naturw. Zeitschr. 1866. Vol. VI, p. 121.

Königstein, L., Histologische Notizen. Arch. f. Ophthalmologie. 1881. Vol. XXVII, p. 56.

Königstein, L., Beobachtungen über die Nerven der Cornea und ihre Gefässe. Wiener Sitzungsber. 1877. Vol. LXXVI, Pt. III, p. 17.

Königstein, L., Beobachtungen über die Nerven der Cornea und ihre Gefässe. Wiener Sitzungsber. 1877. Vol. LXXVI, Pt. III, p. 37.

Krause, W., Ueber das vordere Epithel der Cornea. Göttinger Nachrichten, 1870. Arch. f. Anat. u. Physiol. 1870.

Krause, W., Anatomischer Jahresbericht für 1871 in Prager Vierteljahrschrift.

Kühne, W., Untersuchungen über Protoplasma und die Contractilität. 1864.

Lavdowsky, M., Das Saugadersystem und die Nerven der Cornea. Arch. f. mik. Anat. 1872. Vol. VIII, p. 538.

Leber, T., Zur Kenntniss der Imprägnationsmethoden der Hornhaut und ähnlicher Gewebe. Arch. f. Ophthalmologie. 1867. Vol. XIV, p. 300.

Leydig, F., Lehrbuch der Histologie. 1857.

Lightbody, W. H., Observations on the comparative anatomy of the cornea of vertebrates. Journ. of Anat. and Phys. 1867. Vol. I, p. 15.

Lipmann, H., Ueber die Endigung der Nerven im eigentlichen Gewebe und im hinteren Epithel der Hornhaut des Frosches. Virchow's Arch. 1869. Vol. XLVIII, p. 218.

Lott, G., Ueber den feineren Bau und die physiologische Regeneration der Epithelien, insbesondere des Cornea-Epithels. Centralbl. f. d. med. Wiss. 1871.

Moseley, H. N., Some remarks on the nerves of the cornea of the rabbit and frog. Quart. Journ. Micros. Sci. 1871. Vol. XI, p. 261.

Müller, C. F., Histologische Untersuchungen über die Cornea. Virchow's Arch. 1867. Vol. XLI, p. 110.

v. Recklinghausen, F., Notiz über Silberimprägnation. Virchow's Arch. 1860. Vol. XIX, p. 451.

v. Recklinghausen, F., Die Lymphgefässe und ihre Bedeutung zum Bindegewebe. Berlin, 1862.

Robinski, Die Kittsubstanz auf Reaction des Argentum nitricum. Arch. f. Anat. u. Physiol. 1871, p. 184.

Rollett, A., Ueber das Gefüge der Substantia propria corneae. Sitzungsb. Wiener Akad. 1859. Vol. XXXIII, p. 516.

Rollett, A., Ueber die Contractilität der Hornhautkörper und die Hornhauthöhlen. Centralbl. f. d. med. Wiss. 1871, p. 193.

Rollett, A.. Ueber die Hornhaut. Stricker's Gewebelehre. 1872, p. 1091.

Saemisch, T., Beiträge zur normalen und pathologischen Anatomie des Auges (Nerves of Cornea). Leipzig, 1862.

Sattler, E. E., Die Verwendung des Lapisstiftes zur Untersuchung der Epithelien. Arch. f. mik. Anat. 1882. Vol. XXI, p. 672.

Schalygen, C., Ueber Hornhautepithel und besonders über Vermehrung der Zellen desselben. Arch. f. Ophthalmol. 1866. Vol. XII, p. 83.

Schneider, A., Ueber die Vermehrung der Epithelzellen der Hornhaut. Würzb. naturw. Zeitsch. 1862. Vol. III, p. 105.

Schwalbe, G., Ueber ein mit Endothel bekleidetes Höhlensystem zwischen Choroidea und Sclerotica. Central. f. d. med. Wiss. Berlin, 1868. No. 54.

Schweigger, Ueber den Bau der Hornhaut. Allg. med. Centralzeitung. Berlin, 1862. No. 4.

Schweigger-Seidel, F., Ueber die Grundsubstanz und die Zellen der Hornhaut des Auges. Berichte d. math.-physik. Classe der Königl. Sächs. Gesellsch. d. Wissenschaft. 1869. Vol. XXI, pp. 305-359.

Stricker, S., Conjunctiva und Sclerotica im Handb. der Lehre von den Geweben des Menschen und der Thiere. 1872, p. 1142.

Swaen, M. A., Des éléments cellulaires et des canaux plastiques dans la cornée de la grenouille. Bulletin de l'Acad. roy. de Belgique. 1876. 2nd Series, Vol. XLII, pp. 144–183.

Tamamscheff, T., Ueber die Membrana Demoursiana. Centralbl. f. d. med. Wiss. Berlin, 1869.

Waldeyer, W., Microscopische Anatomie der Cornea, Sclera, Lider und Conjunctiva, in Handbuch der gesammten Augenheilkunde. 1874.

Wolff, W., Die Nerven der Cornea. Arch. f. mik. Anat. 1882. Vol. XX, p. 373.

Zielonko, J., Ueber die Entwicklung und Proliferation von Epithelien und Endothelien. Arch. f. mik. Anat. 1874. Vol. X, p. 351.

b. The lens, choroid, iris, appendages, anterior and posterior chambers.

Altmann, R., Ueber Corrosion in der Histologie. Centralbl. f. d. med. Wiss. 1878, p. 245.

Altmann, R., Ueber die Verwerthbarkeit der Corrosion in der mikroskopischen Anatomie. Arch. f. mik. Anat. 1879. Vol. XVI, p. 471 (Blood-vessels of the choroid).

Angelucci, A., Ueber den Bau und die Entwickelung des vorderen Uveatractus der Vertebraten. Centralbl. f. d. med. Wiss. 1879, p. 417.

Arnold, Die Linse. Handbuch der gesammten Augenheilkunde. 1874.

Barkau, A., Beiträge zur Entwicklungsgeschichte des Auges der Batrachier. Wiener Sitzungsber. 1866. Vol. LIV, Pt. I, pp. 70–75.

Becker, Untersuchungen über den Bau der Linse bei dem Menschen und den Wirbelthieren. Arch. f. Ophthalmologie. 1863. Vol. IX, Pt. II, pp. 1–42.

Biedermann, W., Zur Histologie und Physiologie der Schleimsekretion (Membrana nictitans). Wiener Sitzungsber. 1886. Vol. XCIV.

Born, G., Ueber die Nasenhöhlen und den Thränennasengang der Amphibien. Morph. Jahrb. 1875. Vol. II, p. 4.

Bubuchin, Die Linse. In Stricker's Handb. der Gewebelehre. 1872.

Burow, De vasis sanguif. ran. Diss. Regiomonti, 1838.

Ciaccio, C. V., Beobachtungen über den inneren Bau des Glaskörpers im Auge des Menschen und der Wirbelthiere im Allgemeinen. Moleschott's Untersuchungen. 1870. Vol. X, p. 385.

Faber, C., Der Bau der Iris des Menschen und der Wirbelthiere. Leipzig, 1876.

Frey, Handbuch der Histologie und Histochemie des Menschen. 1874.

Fubini, S., Beiträge zum Studium der Krystalllinse. Moleschott's Untersuchungen. 1876. Vol. XI, p. 291.

Golubew, Beiträge zur Kenntniss des Baues und der Entwicklungsgeschichte der Capillargefässe des Frosches. Arch. f. mik. Anat. 1869. Vol. V, p. 49.

Grünhagen, Ueber das Vorkommen eines Dilatator pupillae in der Iris. Zeitsch. f. rat. Med. Vol. XXVIII, pp. 178, 186.

Heisrath, F., Ueber den Zusammenhang der vorderen Augenkammer mit den vorderen Ciliarvenen. Arch. f. mik. Anat. 1878. Vol. XV, p. 209.

Henle, J., Zur Anatomie der Crystalllinse. Abhandl. Gesells. d. Wiss. zu Göttingen. 1878. Vol. XXIII.

Henle, J., Zur Entwicklungsgeschichte der Krystalllinse und zur Theilung des Zellkerns. Arch. f. mik. Anat. 1882. Vol. XX, p. 413.

Hirschberg, Zur Dioptric und Ophthalmologie der Amphibienaugen. Arch. f. Anat. u. Physiol. 1887, p. 493.

Iwanoff, Beiträge zur normalen und pathologischen Anatomie des Froschglaskorpers. Centralbl. f. d. med. Wiss. 1868, p. 129.

Klein, E., On the peripheral distribution of non-medullated nerve-fibres (Nerves of the nictitating membrane). Quart. Journ. Micros. Sci. 1872. Vol. XII, pp. 21–32.

Koganeï, J., Untersuchungen über den Bau der Iris des Menschen und der Wirbelthiere. Arch. f. mik. Anat. 1885. Vol. XXV, p. 1.

Koganeï, J., Untersuchungen über den Bau der Iris. Sitzungsber. d. Acad. d. Wiss. Berlin, 1885, p. 105.

v. Kölliker, A., Handbuch der Gewebelehre. 1867.

Langer, C., Ueber das Lymphgefässsystem des Frosches. Wiener Acad. Sitzungsb. 1867. Vol. LV, Pt. I, p. 603.

Leydig, F., Anatomisch-histologische Untersuchungen über Fische und Reptilien, 1853.

Leydig, F., Lehrbuch der Histologie des Menschen und der Thiere. 1857.

Manz, W., Ueber den Mechanismus der Nickhautbewegung beim Frosche. Berichte über d. Verhandl. d. naturforsch. Gesell. Freiburg, 1862. Vol. II, p. 391.

Moriggia, A., Ueber die beste Darstellungsweise und die Entwicklung der Röhrchen der Krystalllinse. Moleschott's Untersuchungen. 1870. Vol. X, p. 658.

Openchowski, T., Histologisches zur Innervation der Drüsen. Pflüger's Arch. f. d. ges. Physiol. 1882. Vol. XXVII, pp. 223–232.

Petit, Sur l'œil de la grenouille. Mém. de l'académie d. Sciences, 1737 ; see also Lehrbuch d. vergleich. Anatomie, Stannius, Berlin, 1846, p. 198.

Robinski, S., Zur Anatomie, Physiologie und Pathologie der Augenlinse des Menschen und der Wirbelthiere. Arch. f. Anat. u. Physiol. 1872, p. 178.

Robinsky, S., Die Augenlinsensterne des Menschen und der Wirbelthiere. Centralbl. f. d. med. Wiss. 1877, p. 51.

Sattler, E. E., Die Verwendung des Lapisstiftes zu Untersuchungen der Epithelien. Arch. f. mik. Anat. 1882. Vol. XXI, p. 672.

Stricker, S., Untersuchungen über die capillaren Blutgefässe in der Nickhaut des Frosches. Wiener Sitzungsb. 1865, Vol. LI, Pt. II, pp. 16–27 ; and Moleschott's Untersuchungen, 1866, Vol. X, pp. 168–180.

Stricker, S., Untersuchungen über die mechan. Leistungen d. acirrösen Drüsen. Wiener med. Jahrb. 1880, p. 355 ; also Wiener Sitzungsb. 1880 (Membrana nictitans and skin); also in Moleschott's Untersuchungen. 1870. Vol. X, p. 237.

Stricker, S., Studien über den Bau und das Leben der capillaren Blutgefässe. Wiener Sitzungsb. 1866. Vol. LII, Pt. II, p. 379.

Stricker, S., Untersuchungen über die capillaren Blutgefässe in der Nickhaut des Frosches. Moleschott's Untersuchungen. 1870. Vol. X, p. 168.

Thin, G., Contribution to the anatomy of the lens. Journ. of Anat. and Physiol. 1876. Vol. X, p. 223.

Valentin, Handbuch der Physiologie v. Wagner. 1842.

Virchow, H., Ueber die Gefässe im Auge und in der Umgebung des Auges beim Frosche. Zeit. f. wiss. Zool. 1881. Vol. XXXV, pp. 247–281.

Virchow, H., Ueber die Gefässe des Kopfes und des Auges des Frosches. Verhandl. Würzburg. 1881. Vol. XV, p. xxxiv.

Virchow, H., Mittheilungen zur vergleichenden Anatomie des Wirbelthierauges. Versamml. deutsch. Naturf. und Aerzte. Strassburg. 1885, pp. 409, 410.

Virchow, H., Ueber den ciliaren Muskel des Frosches. Verhandl. d. physiol. Gesell. zu Berlin. 1885, p. 571.

Virchow, H., Ueber die verschiedenen Formen des Ligamentum pectinatum iridis. Versamml. d. Naturf. und Aerzte. 1885, p. 409.

Zimmermann, W., Ueber circumvasale Safträume der Glaskörpergefässe von Rana esculenta. Arch. f. mik. Anat. 1886. Vol. XXVII, p. 410.

c. *The retina.*

www.libtool.com.cn

Babuchin, Vergleichende histologische Studien. Würzburger naturwissensch. Zeitsch. 1864. Vol. V, p. 127.

Beauregard, M. H., Contribution à l'étude du rouge rétinien. Journ. de l'anat. et de la physiol. 1879. Vol. XV, p. 161.

Boll, F., Zur Anatomie und Physiologie der Retina. Berlin. Acad. Monatsber. 1876, p. 783.

Dennissenko, G., Vorläufige Bemerkungen zur Lehre über den Bau der Netzhaut. Mitt. aus dem embryolog. Institut. d. Wiener Universität, 1880, Vol. II, p. 1 ; Abstract in Centralbl. f. d. med. Wiss. 1880, p. 739.

Dennissenko, G., Ueber den Bau der äusseren Körnerschicht der Netzhaut bei den Wirbelthieren. Arch. f. mik. Anat. 1881. Vol. XIX, p. 395.

Dietl, M. J., Beitrag zur Kenntniss des feineren Baues der Stäbchenaussenglieder in der Netzhaut des Frosches. Arch. f. Augen- u. Ohrenheilkunde. 1878. Vol. VII, pp. 17-24.

Dobrowolsky, Die Doppelzapfen. Arch. f. Anat. u. Physiol. 1871.

Dobrowolsky, Zur Anatomie der Retina. Arch. f. Anat. u. Physiol. 1871.

Ewart, J. C., Notes on the minute structure of the retina and vitreous humour. Journ. of Anat. and Physiol. 1875. Vol. IX.

Ewart, J. C., and Thin, G., On the structure of the retina. Journ. of Anat. and Physiol. 1876. Vol. IX, p. 166.

Frisch, Gestalten des Choroidalpigments. Wiener Sitzungsber. 1868. Vol. LVIII, pp. 316-320.

Heinemann, C., Beiträge zur Anatomie der Retina. Arch. f. mik. Anat. 1877. Vol. XIV, p. 409.

Helfreich, Ophthalmoscopische Mittheilungen über den Purpur der Retina. Centralbl. f. d. med. Wiss. 1877, p. 113.

Henle and Merkel, Ueber die sogenannte Bindesubstanz der Centralorgane des Nervensystems. Zeitsch. f. rat. Med. 3rd Series, 1869. Vol. XXXIV.

Hensen, Ueber das Sehen in der Fovea centralis. Virchow's Arch. 1867. Vol. XXXIX, p. 75.

Hoffmann, Lehrbuch der Anatomie der Sinnesorgane.

Hoffmann, Bronn's Thierbuch. Leipzig and Heidelberg, 1873-1878. Vol. VI, pp. 274-297.

Hulke, J. W., A contribution to the anatomy of the amphibian and reptilian retina. Quart. Journ. Micros. Sci. 1864, Vol. IV, p. 236 ; and London Ophthalmic Hospital Reports, 1864.

Hulke, J. W., On the retina of amphibia and reptiles. Journ. of Anat. and Physiol. 1867. Vol. I, p. 94.

Kühne, W., Ueber den Sehpurpur. Centralbl. f. d. med. Wiss. 1877, p. 193.

Kühne, W., Fortgesetzte Untersuchungen über die Retina und die Pigmente des Auges. Heidelberger physiol. Untersuch. 1878, Vol. II, p. 89 ; Abstract in Centralbl. f. d. med. Wiss. 1879, p. 276.

v. Kölliker, A., Zur Anatomie und Physiologie der Retina. Verhandl. d. phys.-med. Gesellsch. Würzburg, 1852. Vol. III, p. 316.

v. Kölliker, A., Microscopische Anatomie. 1854. Vol. II.

v. Kölliker, A., Handbuch der Gewebelehre. 1867.

Krause, W., Die Nervenendigung in der Retina. Arch. f. mik. Anat. 1876. Vol. XII, pp. 742-790.

Krause, W., Die Nervenendigung innerhalb der terminalen Körperchen. Arch. f. mik. Anat. 1881. Vol. XIX, p. 53.

Landolt, Beitrag zur Anatomie der Retina vom Frosch, Salamander und Triton. Arch. f. mik. Anat. 1871. Vol. VII, p. 81.

Leydig, F., Anatomisch-histologische Untersuchungen über Fische und Reptilien. 1853.

Leydig, F., Die Farbe der Retina und das Leuchten der Augen. Arch. f. Naturgesch. 1877. Vol. XXXIII, p. 8.

Manz, W., Ueber den Bau der Retina des Frosches. Zeitsch. f. rat. Med. 3rd Series, 1861. Vol. X, pp. 301–322.

Manz, W., Die Ganglienzellen der Froschnetzhaut. Zeitsch. f. rat. Med. 3rd Series, 1866. Vol. XXVIII.

Merkel, Zur Kenntniss der Stäbchenschicht der Retina. Arch. f. Anat. u. Physiol. 1870, p. 642.

Morano, F., Die Pigmentschicht der Retina. Arch. f. mik. Anat. 1872. Vol. VIII, p. 81.

Morano, F., Stomata in der Pigmentschicht der Retina. Centralbl. f. d. med. Wiss. 1875, p. 67.

Müller, H., Histologie der Netzhaut. Zeitsch. f. wiss. Zool. 1851–52. Vol. III, p. 234.

Müller, H., Ueber sternförmige Zellen der Retina. Würzb. Verhandl. 1852. Vol. II, pp. 216–218.

Müller, H., Ueber einige Verhältnisse der Netzhaut bei Menschen und Thieren. Würzb. Verhandl. 1853. Vol. IV, p. 96.

Müller, H., and **Kölliker, A.**, Retina-Tafel. Plate XIX in Ecker's Icones Physiol. Leipzig, 1854.

Müller, H., Observations sur la structure de la rétine de certains animaux. Compt. rend. 1856, Vol. XLIII, p. 743; and Annales hist. nat. 1856, Vol. XVIII, p. 492.

Müller, H., Anatomisch-physiologische Untersuchungen über die Retina des Menschen und der Wirbelthiere. Zeitsch. f. wiss. Zool. 1857. Vol. VIII, p. 27.

Müller, W., Ueber die Stammentwicklung des Sehorgans der Wirbelthiere. Leipzig, 1874, Festgabe an Carl Ludwig; Abstract in Centralbl. f. d. med. Wiss. 1877, pp. 372 and 388.

Ogneff, J., Histogenese der Retina. Centralbl. f. d. med. Wiss. 1881, p. 641.

Ogneff, J., Ueber die moleculäre Schicht und die sogenannte reticuläre Substanz der Retina. Centralbl. f. d. med. Wiss. 1883, p. 801.

Oppenheimer, L. S., Die Stäbchen in der Netzhaut der Froschembryonen. Schenk's Embryol. Mitt. Wien. 1878, p. 163.

Ranvier, L., Traité technique d'histologie, sixième fasicule. 1882.

Ritter, Ueber den Bau der Stäbchen und äusseren Endigungen der Radialfasern an der Netzhaut des Frosches. Arch. f. Ophthalmol. 1859.

Ritter, Zur Histologie des Auges. Arch. f. Ophthalmol. 1868. Vol. XI.

Schifferdecker, Studien zur vergleichenden Histologie der Retina. Arch. f. mik. Anat. 1886. Vol. XXVIII. p. 305.

Schultze, M., Zur Anatomie und Physiologie der Retina. Arch. f. mik. Anat. 1866. Vol. II, pp. 175–286.

Schultze, M., Ueber Stäbchen und Zapfen der Retina. Arch. f. mik. Anat. 1867. Vol. III, p. 215.

Schultze, M., Bemerkungen zu dem Aufsatze des Dr. W. Steinlin. Arch. f. mik. Anat. 1868. Vol. IV, pp. 10–21.

Schultze, M., Die Retina. Stricker's Handbuch der Gewebelehre. 1871.

Schultze, M., Ueber die Nervenendigung in der Netzhaut des Auges bei Menschen und bei Thieren. Arch. f. mik. Anat. 1869. Vol. V, p. 380.

Schwalbe, Lehrbuch der Anatomie der Sinnesorgane. Erlangen, 1885, p. 392, etc.

Steinlin, W., Zur Anatomie und Physiologie der Retina. Arch. f. mik. Anat. 1868. Vol. IV, p. 10.

THE SKIN AND THE SENSE-ORGANS.

———•———

I. THE SKIN AND ITS APPENDAGES.

THE general characters and the colouring of the skin have already been described (pp. 4 to 7). The skin consists of the *cutis vera* or corium, and the cuticle or epidermis, and is possessed of numerous glands.

Fig. 228.

a. The **epidermis** (Figs. 228, 230) consists of several layers of epithelial cells, those of the deepest layer being more or less columnar in form, those of the middle layer shorter and polygonal, while those of the superficial layer are flattened, very transparent, and horny.

All the surfaces of these cells are serrated, the serrations being, however, with difficulty seen on the free surface of the superficial cells (Leydig). Each cell has a distinct nucleus; in the deeper cells· the

Vertical section through the epidermis from the head of *Rana esculenta*; after F. E. Schultze. Magnified 600 times.

A Horny layer.
B Middle layer.
C Deep layer.
D Isolated mucous-cells.

nucleus is oval, broad, and rounded, in the superficial cells flattened and thin.

The surface of the epidermis (Fig. 230) forms a very beautiful mosaic of flat cells, chiefly hexagonal in form, with pale, central, oval nuclei. Here and there two adjacent cells appear to enclose a semilunar space (Fig. 228 *D*); these spaces are occupied by peculiar cells (goblet-cells, E. Schultze; mucous cells, Leydig), which do not belong to the superficial cells but the layer of cells immediately beneath the horny layer (Schultze, Pfitzner). The cells are rounded or flask-shaped, and closely resemble the epithelial goblet-cells or chalice-cells. According to Rudneff they open on the free surface by stomata; this is, however, denied by Schultze and others.

According to Pfitzner these cells secrete a substance, which has

Fig. 229.

Vertical section through the skin of the back; after Wiedersheim.

Co	Superficial layer of cutis.	*Ep*	Epidermis.
Co¹	Middle layer of cutis.	*H*	Horny layer of epidermis.
Co²	Deep layer of cutis.	*P*	Pigment-cells.
D	Cutaneous glands.	*W*	Papillae.
D¹	Ducts of cutaneous glands.		

an important function in connection with the process of casting the skin, which consists in the separation of the upper layer from that

Fig. 230.

Fig. 231.

Surface view of epidermis of *Rana temporaria*; after Eberth.

A Epidermal cell.
B Stoma-cell.
C Attached cuticle from duct of gland.
D Protoplasm and nucleus of stoma-cell.

Nerve terminations in the branched pigment-cells of the cutis; after Ehrmann. Hartnack, Obj. 8, Oc. 3.

I. Pigment ceasing abruptly at junction of nerve.
II. Pigment gradually ceasing along the nerve.

below brings about a complete shedding of the skin (Wiedersheim).

[The horny layer is, for the most part, very thin, as it consists of one or two layers of flattened cells only (Schultze), but in some situations, as on the back and especially on the under surface of the toes, it is much thickened, and is then rough.

Deeply pigmented, branched cells, capable of contractile movements, are also found, somewhat sparsely distributed, in the epidermis (Leydig, H. Müller, Schultze).]

b. The cutis (Fig. 229, Co, Co^1, Co^2). The epidermis is generally attached to the corium by means of a continuous layer of branched cells, which is deeply stained when the animals are fed with madder (Katschenko). Many of these cells are pigmented. This layer is seldom flat, but is raised into papillae and folds, which are repeated by the superimposed epidermis. In addition to this layer the corium has, except in the webs and supplemental toes, three distinct layers of connective-tissue, together with much unstriped muscle-fibre (Eberth).

The superficial layer (Fig. 229 Co) is a loosely-meshed, much pigmented, vascular layer; it forms a loose support for the numerous glands, and is traversed by numerous nerves.

The middle layer (Co^1) forms the groundwork of the cutis; it is much firmer and more compact than the superficial layer; in section it appears as a broad band, bounded superficially by a sharp line. It is chiefly composed of closely packed connective-tissue fibres, which have, for the main part, a horizontal or wavy course; at certain points, however, vertical fibres are seen passing towards the surface and hiding the sharp contour (between Co and Co^1). At such points the two sets of fibres form a sort of basket-work arrangement.

The deepest layer (Fig. 229 Co^2) is composed of very delicate, white and yellow elastic fibres, and vessels and nerves; it attaches the whole integument to the underlying organs. By the looseness of its structure it forms an important lymph-space.

[The muscle-fibre of the cutis is very unevenly distributed. It is found somewhat freely in the region of the back, the dorsal surface of the head, and the neck; less freely on the dorsal surfaces of the extremities, very sparsely on the abdomen, breast, and ventral surfaces of the extremities; in the feet it appears to be absent (Eberth).

The pigment of the skin. As already mentioned pigmented cells

B b

occur in the epidermis, but by far the greater quantity of the cutaneous pigment is found in the cutis, and more especially in the loose layer of branched cells, which form the boundary between epidermis and true cutis. These cells, known as chromatophore-cells, have been carefully investigated by Harless. They play an extremely important part in bringing about the well-known changes in the colouring of the skin. Bimmerman has proved that these cells are influenced by stimulation of the nerves supplying the region in which they occur. Ehrmann has been able to trace a direct connection between the nerve-fibres and the pigment-cells (Fig. 231 I, II). In such cases the pigment was sometimes sharply marked off, at others was gradually lost along the nerve.]

c. The **papillae** and **ridges** of the skin are classified by Leydig as follows: (1) Small ridges, (2) larger ridges, (3) papillae with touch-bodies, (4) papillae without touch-bodies, (5) papillae with the ducts of glands, (6) capillaries in the form of papillae, (7) small elevations, including the lateral organs.

[All these structures are derived from the cutis, the epithelium above simply repeating the elevation, and being itself either not increased in thickness or only to a slight degree. (For further description of some of these papillae, see Organs of Tactile Sensation, p. 380.)

Peculiar wart-like papillae are found on the articulations of the first phalanges with the metatarsus, on the same articulations and on the articulations between the first and second phalanges of the third and fifth toes, and on the articulations between the first, second, and third phalanges of the fourth toe. These papillae are connected with the long flexor tendons by fine tendinous bands (Klein).

Temporary papillae are developed in the females of *Rana temporaria* during the breeding season; according to O. Huber (*l. c.*), who has described them, their distribution and structure is as follows:—

During the breeding season the skin of the sides of the trunk of female specimens of *Rana temporaria* is rough; the small elevations, to which this roughness is due, are each about the size of the head of a pin, and have the appearance of small, rounded, white or pale rose-coloured, warty growths. The papillae reach their greatest development and are most numerous on the sides of the trunk (Fig. 232 I); they may be traced on to the tympanic membrane, where they are arranged in a ring, and in some cases under the eyes to the sides of the snout.

Anteriorly the papillae are absent from the median portion of the dorsal surface of the trunk, but posteriorly, behind a line joining the anterior extremities of the two iliac bones, the papillae cover the whole surface.

The papillae are large and very numerous around the arms, and pass by gradual, transitionary stages into the ordinary papillae of the region. Further they may be traced backwards along the anterior or extensor surface of the thigh, the upper surface

Fig. 232.

I. Diagram to show the distribution of the temporary papillae in *Rana temporaria*; after Huber.
II, III. Vertical sections through a temporary papilla; after Huber.

of the leg, foot, and fifth toe. Occasionally a few papillae were found on flexor surfaces of the third and fourth metatarsus, and very rarely were any discovered on the fore-limbs. They occur in no other batrachian of Germany (Huber).

Each papilla (Fig. 232 II and III) consists of a hemispherical elevation of the cutis, and is covered either by a layer of normal epidermis or in some very rare cases the epidermis was slightly thickened. The papilla consists of a firm connective-tissue stroma, and is from 0·2-0·4 mm. in height, 0·4-0·5 mm. broad (after hardening in alcohol). Such glands as exist in the papilla usually open laterally (Fig. 232 III), and the blood-vessels are numerous.

The epidermis covering the papilla is well supplied with nerve-fibres, derived from large ganglion-cells in the papilla (Fig. 232 III). The branched pigment-cells, so numerous in the rest of the skin, are absent from the upper parts of the papillae (Fig. 232 II); the pigment-cells may cease either abruptly or gradually.

The rose-colour of the papillae is due to the presence of a golden red pigment. After the breeding season the papillae are gradually lost, and the pigment-cells wander into the unoccupied parts.

Huber compares the arrangement of the nerves to that of the 'touch-spots' of Merkel.

d. The **glands** of the skin are of two kinds, serous and mucous; they have been fully described by Engelmann and Openchowski.

(1) The **serous glands** (Körnerdrüsen, Engelmann) are large, averaging in diameter 0·2–0·4 mm., but others vary in size from 0·13–0·8 mm. in diameter. They are found chiefly on the dorsum of the trunk and arranged in groups, which vary in dimensions from 3–20 mm. in length and 2–4 mm. in breadth. They may be found in any part between the ear-region and the anus, on the dorsal surface of the thigh, especially towards the outer and inner borders. They are found very sparsely distributed on the ventral surface of the trunk and on other parts of the extremities, though as a rule a few are found on the dorsal surface of the feet and near the phalanges. They are wanting in the nictitating membrane.

The glands have a rounded form, with the ducts placed at their superficial poles. The glands possess three coats; externally is a coat of connective-tissue, the fibres of which are arranged closely together, and cross one another at acute angles: these fibres are continuous with the connective-tissue of the surrounding cutis. Inside this coat is a thick layer of muscle-fibre (0·005–0·015 mm.); the muscle-cells are arranged meridionally, with the one pole towards the superficial surface of the gland, the other pole at the deep surface (Hensche). Many of the fibres, however, extend only one-fourth or one-third of this distance.

The innermost coat is a simple layer of epithelial cells, which rests directly on the muscle-layer; no basement-membrane or space of any kind having been discovered between the two layers. When examined in the recent state these cells are conical or cylindrical in shape, and have the appearance of goblet-cells: they possess a delicate but distinct cell-wall, but are open towards the lumen of the gland. One or sometimes two rounded nuclei are found towards the base of the gland, and surrounded by a small amount of granular protoplasm; the rest of the cell is occupied by a mass of small, rounded, highly refractive granules of about 0·002–0·01 mm. in

diameter. These granules are also to be found in the protoplasm of the cell; they contain a substance capable of swelling freely, and present many points of resemblance to the granules found in the cells of the oviducts.

These glands represent the poison-glands or lateral glands of toads, and the ear-glands or parotids of Caecilia (Leydig). According to Leroux [1], Gratiolet and Cloëz [2], the reaction of these glands in toads varies; according to du Bois-Reymond [3] the reaction is, in frogs, acid; Engelmann [4] found the reaction of these glands, in frogs, to be neutral, frequently, however, with a tendency to either acidity or alkalinity.

These glands correspond with the 'large glands' of Hensche, the 'contractile glands' of Stieda, the 'large, dark glands' of Eberth, and the 'large contractile glands' of Leydig's earlier publications.

(2) The **mucous glands** are, as a rule, smaller, more numerous, and more evenly distributed than the serous glands. Usually they lie in such close proximity as almost to touch one another; according to Engelmann an average number of sixty is found in one square millimeter; on the abdomen 62–68; flexor surfaces of the posterior extremities in some places 76, but in others only 30–40; on the webs only 2–6 to the square millimeter. On the nictitating membrane they are arranged in two or three parallel rows, are large, and closely applied to each other. They are wanting on the deeper surface of the nictitating membrane.

The glands are generally rounded in form and have a short neck (Fig. 229). Glands in the recent condition, and not fully contracted, have a diameter of 0·06–0·21 mm., the majority measure 0·12–0·16 mm. in diameter. The upper pole of the gland is usually placed directly under the boundary between epidermis and cutis, and, as a rule, about 0·06–0·1 mm. beneath the superficial surface of the skin. The duct usually passes directly to the surface, in a straight line.

The structure of the glands corresponds, in general, with that of the serous glands. Externally is a coat of connective-tissue, which is, however, more firmly attached to the muscular coat than in the case of the serous glands, and may easily be mistaken for a structureless basement-membrane [5] (Eberth). The muscular coat is very thin, and consists of 16–20 flat, spindle-shaped fibres; extending from the upper to the lower pole as in the serous glands. At a

[1] Journal de Médicine, Vol. XI, p. 75.
[2] Comptes rendus, 1851, Vol. XXXII, p. 581.
[3] Untersuchungen über thier. Electricität, 1830, Vol. I, p. 17.
[4] Arch. f. d. ges. Physiol., 1852, Vol. V, p. 505.
[5] Openchowski (l. c.) describes a basement-membrane.

short distance (0·015–0·022 mm.) from the upper or superficial
pole each fibre has an ellipsoid thickening, composed of granular
protoplasm, and containing a clear oval nucleus.

The inner coat is composed of a single layer of epithelium, placed
directly on the muscular coat. The epithelium has a thickness of
about 0·01–0·02 mm.; it is, however, usually thicker towards the
base than towards the duct. The boundaries between the cells are
very indistinct, and so give the epithelium the appearance of a con-
tinuous layer of protoplasm. The glandular epithelium is not
directly continuous with the epithelium of the duct.

The shape of the cells depends upon their physiological condition.
In a state of semi-contraction of the gland, the cells are cubical, and
their free borders pushed into the lumen in a slight convexity;
when the gland is fully distended the cells are two or three times as
broad as deep; in a fully contracted gland the cells are conical or
cylindrical. In the first-mentioned condition their diameter varies
from 0·006–0·018 mm. The larger glands are estimated to possess
about 150 cells, the smaller only thirty to forty (Engelmann).

The cells appear to have no cell-wall, certainly they possess none
on their free surfaces. Their protoplasm distends very freely on
the addition of water. As a rule some cells are much more gran-
ular than others of the same gland; each cell has a rounded oval,
clear nucleus, and vacuoles are frequently met with.

The lumen of the gland contains a colourless, transparent, watery
fluid, which contains mucous material.

The ducts of the glands are thick-walled cylinders, circular in
section. Their diameter varies from 0·02–0·05 mm., their length is
equal to the depth of the superimposed epidermis. The wall of the
duct is lined with two or three concentric layers of highly refrac-
tive, nucleated cells. The cells are arranged parallel to the length
of the duct: in transverse section they are sickle-shaped or semi-
lunar. In the upper third or fourth of the duct the inner wall is
lined with a cuticle, very resistent to the action of acids or alkalies:
it is thrown off with the skin in the process of casting. In the horny
layer of the epidermis this cuticle is partially closed by a stoma-
cell (Eberth), (Fig. 230), which possesses a tri-radiate opening.

The glands correspond with the 'non-contractile glands' of Hensche, the 'dark
and bright glands' of Stieda, the 'glandule mezzane, piccole e piccolissime (ad epitelio
pavimentoso)' of Ciaccio, and the 'small, dark, and medium-sized, bright glands' of
Eberth.

e. The **peculiarities** of the **skin** of the **supplemental toe** and

webs. The supplemental toe presents, in the male, a rounded, oval swelling (Fig. 234 I, *D*), with the end of the digit projecting from the distal end.

Normally this swelling is usually of a grey colour; during the breeding season, however, the swelling enlarges, and becomes of a black or deep brown colour (Leydig).

The epidermis covering this swelling (Fig. 233) is much thickened and produced into projecting papillae. The cutis also shows a marked thickening and an increase in vascularity; the glands are of the kind described as mucous glands (Engelmann). They present, however, an immense increase in size, and at the same time are so closely applied to one another as to form

Fig. 233.

Vertical section through the epidermis of the supplemental toe of *Rana esculenta*; after E. Schultze. Magnified 400 times.

Fig. 234.

I.

II.

Fore-foot of a male frog.
D Glandular swelling on the supplemental toe.
W Warty papillae on the inter-phalangeal joints.

Vertical section through the swelling on the supplemental toe of a male frog.

B Blood-vessels.
Co Cutis.
D Glands.
Ep Epidermis.
M Muscles.
P Pigment-cells.

the main part of the enlargement (see also Organs of Tactile Sensation).

In the **webs** the various layers of the corium are more or less

fused together, and cannot be distinguished from each other; the glands are, as a rule, smaller than on the general surface of the skin.

f. The **blood-vessels** and **lymphatics** of the skin.

(1) The **blood-vessels** of the skin are arranged in two networks; the one is situated immediately beneath the epidermis, and consists of fine capillaries, forming a fine-meshed network, which enclose the ducts of the glands. The meshes vary considerably in size and

Fig. 235.

The blood-vessels and lymphatics of the skin; after Langer. Arteries striped, lymphatics shaded.

I. Vertical section through skin of thigh.
II. Horizontal view of arteries and lymphatics of the skin.
III. Peculiar tortuous arteries of the lamina inguinalis.
IV. Arteries and lymphatics of the web.

shape (Hyrtl and Langer). The second network of vessels is situated under the cutis; the vessels forming it are small, and the meshes formed are large. From this network vertical branches pass to form the superficial network; these branches usually course along the strands of vertical fibres already described, and break up to form capillaries only when they reach the deeper surface of the epidermis (Langer), (Fig. 235 I).

In *some situations*, however, the vertical branches divide earlier; this is especially the case in parts where the glands are very closely packed, as in the nictitating membrane, the upper lip, and the

swelling of the supplemental toe (in the male). In these parts the division takes place at the deeper surface of the glands (Langer).

A *peculiar arrangement* of the cutaneous blood-vessels is found in the lamina inguinalis, where a chain of reddish points can be made out with the naked eye; examined more carefully (Fig. 235 III) each reddish point is found to be a complex loop of capillaries. They extend from the skin to the hinder lymph-hearts, where they form a close network which partially invests the lymph-hearts (Langer).

(2) The **lymphatics of the skin** (see also p. 252), like the arteries, reach the deeper surface of the epidermis by coursing along the bands of vertical fibres; they then form a network of capillaries with rounded meshes (Fig. 235 I, II, IV), and lying immediately under the epidermis, and a network which surrounds the various glands. The lymphatic-capillaries are as a rule larger than the blood-capillaries. The lymphatic network lies beneath the blood network, and the vessels of the two systems branch independently (Langer).

In those parts where the glands are placed closely together this arrangement is modified, and corresponds with the modifications found in the blood-capillaries in these regions. The vertical branches divide so as to form a network below the glands, and from this vertical branches pass in the same direction between the glands to form a secondary network on the superficial surface of the glands (Langer).

g. The **nerves** of the skin. The cutis is very richly supplied with both medullated and non-medullated nerves. In the subcutaneous tissue the nerves destined for the skin branch freely to form numerous fine twigs, which, without actually inosculating, form a fine meshwork. From the larger trunks numerous vertical branches pass vertically to form a secondary network, from which both coarse and very fine twigs pass to encircle the glands. The fine fibres which supply the glands are non-medullated and possess oval nuclei; their diameter varies from 0·001–0·002 mm. The number of nerve-fibres is not much smaller than that of the muscle-fibres (Engelmann). (See also Organs of Tactile Sensation.)]

II. THE ORGANS OF TACTILE SENSATION.

The organs of tactile sensation are the nerve-plexus of the epidermis, the touch-spots of Merkel, the lateral sense-organs, and the touch-corpuscles of the tendons.

a. [The **nerve-plexus** of the epithelium is very incomplete as compared with the plexus found in the epithelium of the cornea; here and there a few non-medullated fibres have been traced a short distance between the epithelial cells. No such mode of nerve-terminations in the epithelium as is described by Eberth and Macullum in the tadpole can be found in the adult.]

b. The **touch-spots**. What knowledge we possess of these organs is due to the labours of Leydig, Ciaccio, Eberth, and more particularly those of Merkel.

At the base of each papilla, which contains such a touch-organ, is found a number of colourless, flattened cells, arranged either in a single layer, or heaped up and connected with very fine nerve-fibres.

Fig. 236.

I.

II.

I. Lateral sense-organ of tadpole of frog. Half-schematic.

c   Central zone (nerve-epithelium).
Ml   Membrana limitans.
p   Peripheral zone (sustentacular cells).
R   Hyaline tube.

II. Touch-corpuscle from the sheath of a digital tendon of the frog; after Löwe. Schieck, Oc. O., Obj. 9.

The flat surface of the cells is parallel to the surface of the body, and they do not form a separate or circumscribed body, they are therefore better spoken of as touch-spots than as true touch-bodies (Merkel). The larger organs are found in the papillae, but smaller ones may be found on any part of the skin.

These organs are best seen in the prominence or swelling upon the supplemental toe during the breeding season; they are numerous on the dorsal surface of the trunk, but occur most frequently on the under surface of the hinder feet (*Planta pedis*). After the

breeding season the organs of the thumb undergo a retrogressive change, which results in a network of spindle-shaped and branched cells with fibres (Wiedersheim).

c. The **lateral sense-organs** attain their highest development in the tadpole; in the adult the organs have undergone a retrogressive change, the result of which is that the organs are diminished in size; the whole organ sinks by the formation of a tube, which is then closed by a mucous secretion, consequently the organ is functionless: with this loss in function and change in position of the organs a corresponding diminution of the ramus lateralis nervi vagi occurs (Merkel).

Each lateral organ (Fig. 236 I) consists of a slightly elevated papilla, with the centre depressed, and in each may be distinguished a central and a peripheral zone (c, p). The central zone consists of a group of pear-shaped cells, with the narrower ends directed towards the free surface; each is connected below with a nerve-fibril, while above it bears a short, stiff cilium. The cilia are enclosed in a delicate hyaline tube (R), which is open superficially, closed by the papilla below; consequently the cilia are in direct contact with the sur-rounding medium. The peripheral zone is a layer of pale, flattened, cylindrical cells (p); they possess, at their upper borders, a perforated *membrana limitans* (Ml), through which the cilia pass. These cells serve as a support to the central cells, and are themselves surrounded by ordinary epithelial cells.

The distribution and arrangement of the lateral organs is alike in fish and larval amphibia. They are most numerous on the head, where they surround the eye, and are continued forwards to the snout and on to the lower jaw. All these organs on the head are in connection with the trigeminal nerve. A line of these organs passes from the hinder part of the circumference of the eye along the gill-cover to the neck, where the lines of opposite sides are usually, though not constantly, joined by a transverse line of the same organs; thence the lines are continued along the trunk to the tip of the tail. In fish there exists, as a rule, only one pair of such longitudinal lines (*Linea lateralis*); in anura-larvae, proteus, and in all salamanders there are three pairs: of these one pair lies near the vertebral column, the second at the junction of the flank with the abdomen, and the third corresponds to the lateral line in fish (Malbranc).

At an early developmental period each metamere possesses one pair of such lateral organs; in later life, however, this simple arrangement is lost, and each segment usually possesses a group of organs.

The organs of the trunk and tail are supplied by branches of the Ramus lateralis nervi vagi. Both in fish and amphibia a reparative process, by means of fission, occurs; as a consequence the organs are found in various stages of development.

d. [The **touch-corpuscles** of Golgi and Löwe (Fig. 236 II) are found on the joints of the digits. They are surrounded by con-

nective-tissue and are spindle-shaped; the two ends of the spindle are glassy in appearance, the middle portion is fibrous. In the thickest part of the corpuscle is a zone of nuclear bodies.

They are regarded as touch-bodies (Golgi and Löwe). Golgi (*l. c.*) describes two kinds of touch-organs in connection with muscle and tendon; one class correspond with those just described, he names them 'nervous muscle-tendon organs.' The second class he compares with the touch-bodies found in the conjunctiva.]

III. THE ORGANS OF TASTE.

The organs of taste are not confined to the surface of the tongue, but are also found on the mucous membrane of the roof of the mouth, especially in the neighbourhood of the vomerine teeth; on both roof and floor of the mouth these organs can be traced to the commencement of the oesophagus.

[The mucous membrane of the tongue possesses two kinds of papillae and numerous glands.

a. The **filiform papillae** are the more numerous; they are conical or thread-like in form, and consist of connective-tissue, with a few striated muscle-fibres; they include blood-capillaries, but no nerves have been traced into them (Leydig). They are covered with ciliated epithelium and goblet-cells.

b. The **fungiform papillae** are much larger, and are paler than the filiform papillae. The free ends of these papillae are broader than the bases, and when the epithelium is removed the free ends present a concavity. From the base to the border of the free surface each papilla is covered with the usual oval, ciliated epithelium, but at this border an abrupt transition takes place. The epithelium covering the end of the papillae is of three kinds: goblet-cells, cylindrical cells, and forked cells; the three forms of cells are quite characteristic, and no intermediate transitionary forms are met with.

(1) The **goblet-cells** (Fig. 237 I) are arranged vertically to the free surface of the papilla; they are from 0·020–0·024 mm. in length, and from 0·01–0·02 mm. in diameter. In the lower third of the cell is found a nucleus of about 0·008 mm. in diameter, and this encloses a nucleolus of about 0·001 mm. in diameter. Close underneath the nucleus the cell is contracted to form an irregular process or foot. The contents of the cells are a very finely granular,

transparent protoplasm.   These cells form the outermost part of the
epithelium, covering the end of the papilla; all the cells belonging
to the same papilla are of the same size.   In consequence of the
mutual pressure which they exert on each other they present, in
transverse section, six-sided outlines (Fig. 237, 2).   The nuclei of
adjacent cells are placed at almost exactly the same level.   By the

Fig. 237.

I. Various parts from the fungiform papillae ;
        after Engelmann.

1. Nerves of a fungiform papilla. Magnified 450
    . times.
2. Surface view of the epithelium, after five
    minutes' action of iodized serum. Magnified
    600 times.
3. Goblet-cell with adjacent forked cell. Magni-
    fied 450 times.
4. Portion of the papilla, after removal of the

      goblet- and forked cells ; only cylindrical
      cells remaining. Magnified 400 times.
5. Goblet-cell, with swollen contents. Magni-
    fied 450 times.
6-13. Various forms of isolated forked cells.
      Magnified 450 times.
II. Sections of two glands of the tongue ;
        after Biederman.
    1. Resting-gland.
    2. Gland after stimulation.

action of reagents on these cells very remarkable forms are obtained,
in consequence of the protoplasm swelling and being forced up-
wards (Fig. 237, 5).

(2) The **cylindrical cells** (Fig. 237 I) have rounded free extre-
mities, which reach to the general surface of the epithelium; the
remainder of the cell is cylindrical except towards its lower ex-

tremity, where it is slightly dilated and encloses an oval nucleus : the protoplasm of the cells is very finely granular. These cells rest on the connective-tissue of the papilla, and are in close juxtaposition, so that several hundreds of them are found on one papilla.

The spaces between the upper parts of the cylindrical cells are occupied by the goblet-cells and by the forked cells.

(3) The **third form** of cell found on the fungiform papillae are named **forked cells** (Fig. 237 I) by Engelmann. The body of the cells has an ellipsoidal form, is from 0·006–0·008 mm. in its longer diameter, and 0·003–0·004 mm. in the shorter diameter. Processes arise from both poles. The peripheral processes arise by a short common stem, which then divides into two or rarely three branches ; the whole process is from 0·004–0·008 mm. in length, and is always just sufficiently long to reach the general surface of the epithelium : when the peripheral process is long the central is usually shorter, and *vice versâ*.

The central processes arise by a stem from 0·001–0·002 mm. in thickness, which usually divides dichotomously. The length of this process may be as much as 0·025 mm. or almost nil.

The forked cells are about twice as numerous as the goblet-cells, they occupy the spaces between the cylindrical cells and the goblet-cells. The branched central processes form a network on the connective-tissue of the papilla, which is, at this point, perforated by a rich plexus of fine non-medullated nerve-fibrils. It is not decided whether the processes of various cells inosculate. Engelmann regards these forked cells as the taste-cells and as the sensory nerve-endings.

The **bodies** of the fungiform papillae contain blood-vessels and nerves, the latter enter as medullated nerves, but lose the medulla somewhat abruptly towards the upper end of the papilla, where they form a sort of nerve-cushion (Nervenkissen, Engelmann).]

Taste-organs are also found on the roof and other parts of the mouth, and present many points of resemblance to the lateral sense-organs. Like them they present a peripheral zone and a central zone ; the cells of the latter, however, are not longer than the peripheral cells, and possess no cilia (J. van der Hoeven, Merkel).

IV. THE NOSE.

The **anterior nares** or nostrils are two small openings, placed directly in front of the anterior angle of the eye; the distance between the eye and the corresponding nostril being, in the case of adult animals, about five or six millimeters. The anterior nares are surrounded by rims, which are contracted below, and so form very short, tentacular-like prominences.

The **posterior nares** (choanae) are about four millimeters from the anterior nares, consequently the long axis of the nose is, approximately, of this length. (For the external muscles of the nose, see p. 59.)

The **boundaries** of the **nasal cavities** are as follows:—the roof of each cavity is formed by the dorsal plate of the sphenethmoid, the nasal bone, and the premaxillary bone; the floor is formed by the vomer and the palatine bone, the inner wall by the vertical septum of the sphenethmoid, the outer wall by the premaxillary and maxillary bones, the anterior wall by the premaxillary bone, and the posterior wall by the sphenethmoid. The cartilaginous portion of the nasal skeleton (see also p. 27) projects into the general cavity and subdivides it into various sinuses, which have been the subject of careful investigation by Born and Wiedersheim.

a. The **nasal cavities** are best examined by means of serial transverse sections; in a section through the anterior nares (Figs. 238, 239) there will be seen three sinuses on either side:—

(1) The **superior sinus** (*on*) is large, rounded, and placed against the cartilaginous septum; the sinus is lined with olfactory epithelium. Posteriorly the sinus extends beyond the posterior nares, and is bounded by the anterior surface of the sphenethmoid. In front it ends in a rounded concavity, likewise lined with olfactory mucous membrane. Opposite the anterior nares the cavity is partially subdivided, by a longitudinal process on the floor, into two cavities; the anterior nares open into the external chambers, and therefore not directly into the main cavity of the superior sinus. The superior sinus communicates with the inferior sinus by a narrow, almost vertical, slit.

(2) The **inferior sinus** (*un*) is narrow and flattened from above downwards; it is placed against the maxillary bone, and represents the maxillary sinus of the frog. Externally it possesses a descending arm.

The inferior sinus is continued backwards and opens on its

inner side into the posterior nares, or rather into the mouth. The descending arm extends only a short distance forwards, to terminate near the point where the superior and inferior sinuses communicate by only a narrow opening. This sinus is on the whole broader in front than behind, and has a general direction from without, inwards and forwards underneath the superior sinus.

Fig. 238.

Fig. 239.

Frontal sections through the nose of two tadpoles ; after G. Born.

A	Anterior naris.
b	Cartilaginous floor.
C	Cutis.
d	Cartilaginous roof.
Ep	Epidermis.
gi	Intermaxillary gland.
gni	Lower nasal gland.
gms	Upper nasal gland.
K	Maxillary sinus.
l	Concha narium (os lachrymale).
m	Maxillary bone.
MS	Oral mucous membrane.
ok	Cartilage.
on	Upper blind sac.
R	Pharyngeal gland.
S	Nasal septum.
se	Septum between the upper and lower nasal cavity.
sn	External blind sac.
T	Trabeculae.
Th	Lachrymal duct.
un	Lower blind sac.

(3) The **lateral sinus** (*sn*) is situated in the partition between the superior and inferior sinuses, or rather between the external chamber of the upper sinus and the inferior sinus. The lateral sinus is triangular in form, being narrow in front and broad behind ; at its

inner posterior angle it opens on the free border of the horizontal partition between the superior and inferior sinuses; this opening is, however, continued along its roof, so that the lateral sinus opens also into the superior sinus.

b. **The nasal cartilages.** The two nasal cavities are completely separated by the cartilaginous septum (Figs. 238 and 239 *S*), and are for the most part lined by cartilage. The anterior end is formed of concave cartilages, while the posterior, being situated in the sphenethmoid, is usually more or less ossified in the adult. The posterior wall has two openings : a larger near the septum for the olfactory nerve, and a smaller, more externally, for the nasal branch of the trigeminal nerve.

The anterior wall is more complex than the posterior, being thicker in the middle than at the sides, and possessing three blind sacs for the three sinuses. From the anterior wall two processes project backwards between the sacs and enclose them more or less completely.

Of the three sacs or cavities only the lower is completely surrounded by cartilage. The upper sac is in part bounded by a shell-shaped, concave cartilage (*Concha narium*, of various authors; *Os lachrymale*, Born), which covers it anteriorly and externally, and is attached by a small base to the roof of the lower sac (Fig. 239, *l*), its upper border bounding the anterior naris (Fig. 15). The upper and external parts of the upper sac have no cartilage. The cartilages of the outer wall of the lower, blind sac extend backwards to the point where the maxillary sinus commences to descend : the roof, however, is prolonged further backwards by two small cartilaginous processes ; the inner is short, the outer forms the roof of the descending arm of the sinus, and joins a cartilaginous process, which commences at the anterior portion of the roof of the nasal cavity, passes backwards and downwards to a broad plate, and forms an incomplete outer wall to the nasal cavity. There are also three cartilaginous processes—a. One arising from the outer side of the floor at the level of its junction with the anterior wall ; it is a flattened process and passes outwards, and bifurcates at its end to meet the premaxillary and maxillary bones (this is the Oberkieferfortsatz of Ecker), (p. 28, Fig. 14 *n″*)). β. A delicate process on either side, described by Wiedersheim (see p. 280). γ. The third pair of processes are fully described for the first time by Born ; each arises at the lower border of the corresponding *Concha narium*, passes forwards and downwards under the ascending process of the premaxillary to

the point where process β is attached to this bone. The processes are flat and approach one another obliquely; in older animals they are united at the point of contact.

At the junction of the anterior wall, the septum, and the floor is a large aperture in the cartilaginous capsule, through which passes the chief nasal branch of the trigeminus, which supplies numerous branches to the intermaxillary gland.

c. The **glands** of the **nasal region** are Bowman's glands, the intermaxillary glands (Wiedersheim), the lower nasal gland (Born), the upper nasal gland (Born), the pharyngeal gland (Born), and the lachrymal duct.

Fig. 240.

I. A. Bowman's glands in situ from *Rana temporaria*; after C. K. Hoffmann. Magnified 150 times.
B. Section of Bowman's gland; after C. K. Hoffmann. Magnified 300 times.
II. Vessels of nasal mucous membrane of *Rana esculenta*; after Langer. Blood-vessels striped, lymphatics shaded.

(1) The **intermaxillary gland** (see p. 280).

(2) The **lower nasal gland** is placed along the septum and extends as far back as the posterior nares, opening by its ducts (Figs. 238 and 239 *gni*) into the inferior blind sac of the nasal cavity. In histological structure it corresponds with the intermaxillary glands, except that the glandular tubes are somewhat smaller, and the glandular epithelium stains somewhat less easily with carmine (Born).

(3) The **upper nasal gland** occupies the space between the *Concha narium* (*Os lachrymale*, Born) and the neighbouring cartilages, it also surrounds the anterior naris and the opening of the lachrymal canal (Figs. 238 and 239 *gns*). The numerous ducts open on the mucous membrane covering the oblique cartilage (above described, as passing from in front, downwards and backwards, and forming an incomplete outer wall of the cavity), and its hinder prolongation.

(4) The **pharyngeal gland** is placed transversely behind the posterior nares, and surrounds the vomerine teeth. A portion of the

ducts open into the posterior nares, the remainder on the mucous membrane of the pharyngo-oral cavity at two symmetrically placed points (Fig. 238 R).

(5) The **lachrymal duct** (see p. 428) opens into the nasal cavity at the point where the lateral sinus opens into the external chamber of the superior nasal sinus.

(6) [The **glands** of **Bowman** (Fig. 240 I) are freely distributed in the nasal mucous membrane. Each gland is usually rounded or flask-shaped, and consists of a single layer of large epithelial cells possessing distinct nuclei and nucleoli. The epithelium of the glands possesses no basement membrane (M. Schultze and Hoffmann[1]), but is bounded externally by a layer of nerve-fibres and connective-tissue.

The glands situated more superficially have straight ducts opening on the surface; those placed more deeply have usually curved ducts (Paschutin).]

d. The **mucous membrane** of the nasal cavities. That part of the superior sinus immediately around the anterior naris is lined with stratified epithelium; the rest of the nasal cavity is lined with columnar ciliated epithelium. The epithelial layer rests on a sub-epithelial network, and this again on a submucous connective-tissue layer possessing numerous vessels and nerves.

(1) The **epithelial layer** (Fig. 241) consists of columnar cells, which in the olfactory region are of two kinds; in other regions the epithelium consists of closely-applied ciliated, thick cells, possessing large oval nuclei, and having irregular, branched bases or 'feet.' The cells are 0·032–0·048 mm. long; the nuclei 0·016–0·018 mm. long, and 0·006–0·008 mm. broad. The free borders of the cells bear a number of fine cilia.

In the olfactory region a second set of cells, olfactory cells, are met with; these cells (Fig. 241 II) possess each an oval body, enclosing a large nucleus, and a peripheral and central process. The peripheral processes reach to the general surface of the surrounding epithelium and there terminate in a number (5–8) of stiff cilia; these cilia are sometimes 0·09 mm. long, they are thicker at their bases than the ordinary cilia (Schultze); according to Hoffmann, a second system of stiffer and longer cilia is met with; of which each olfactory cell possesses as a rule only one. The bodies of the olfactory cells are 0·009–0·010 mm. long, and 0·007–0·008 mm. broad; the peripheral

---

[1] Paschutin describes a basement membrane.

processes vary considerably in length, according to the position of the body (0·03–0·05 mm.). The central processes vary from 0·02–0·03 mm. in length. The peripheral processes are considerably thicker than the central processes. No *membrana limitans olfactoria* has been discovered in the frog.

(2) The **second layer** consists of a network of processes belong to the bases of the central processes of the superimposed epithelial and olfactory cells. Numerous highly refractive nuclei possessing nucleoli are situated in the meshes of this network; they correspond in all particulars with the nuclei of the olfactory cells (M. Schultze). According to Exner the branched processes of the epithelial cells and of the olfactory cells unite to form a complex plexus. Other observers, Paschutin, Cissoff, v. Brunn, Schultze, and Hoffmann oppose this view, and hold that the central processes of the olfactory cells do not unite with the processes of the epithelial cells, but that they are in direct continuity with the fibrils of the olfactory nerve. This view is probably correct.

The submucous layer has a loose connective-tissue matrix, which encloses the glands, nerves, and vessels; according to Paschutin two pigment-layers may be distinguished: the one, immediately under the middle layer of this mucous membrane, is continuous and deeply pigmented; the second is deeper and does not form a continuous layer. This layer is extremely rich in blood-vessels and lymphatics (Langer and Paschutin), (Fig. 240 II). The lymphatics are relatively very large and are very numerous (Langer).

Fig. 241.

Separations from the olfactory mucous membrane of *Rana temporaria*; after C. K. Hoffmann.

I. Surface view of the olfactory membrane. Magnified 350 times.

II. Epithelial and olfactory cells. Magnified 600 times.

III. Epithelial cells. Magnified 600 times.

In this layer the central processes of the olfactory cells form bundles of fibres, lying parallel with the surface of the mucous membrane (Paschutin, Cissoff, and Schultze).]

V. THE EAR.

(Re-written by the translator from Das Gehörorgan der Wirbelthiere,
by G. Retzius, 1881.)

The organ of hearing is divisible into two parts, the tympanum
or middle ear, and the labyrinth or internal ear; an external ear is
absent, unless a very slight depression of the tympanic membrane
be regarded as such.

A. **The tympanum** (*Cavum tympani*) is a cavity, bounded ex-
ternally by the tympanic membrane and internally by the capsule
of the internal ear; it communicates by means of the Eustachian
tube (tuba Eustachii) with the pharyngo-oral cavity (Fig. 178).

a. The **tympanic membrane** lies immediately underneath the
skin, but can be separated from that structure; externally it
possesses a very slight depression, the only
trace of an external ear found in the frog.

The tympanic membrane is of a rounded
oval form, being a little wider in the trans-
verse than in the longitudinal diameter; the
membrane is directed outwards.

After detaching the skin (Fig. 242 I) the
membrane is seen to be attached by its circum-
ference to a ring of cartilage (*Annulus mem-
branae tympani*; see also p. 26) (*at*); the ring
is attached anteriorly and above to the squa-
mosal bone (*sq*), and in the rest of its circum-
ference to the surrounding soft parts, *i. e.* the
M. depressor maxillae (*dm*), the *M. temporalis*
(*t*), and their fasciae. In the middle of the
membrane is a small, rounded, white part (*col*)
which can be traced backwards and upwards
towards the circumference.

The membrane consists of fibres of con-
nective-tissue which radiate peripherally from
the central point of attachment of the colu-
mella; in the peripheral portion unstriated muscular fibres are
also found (Leydig).

Internally the tympanic membrane is covered by columnar epi-

Fig. 242.

I. The tympanic membrane
of *Rana esculenta*;
natural size. After
Retzius.

II. The tympanum as seen
after removing the
tympanic membrane;
natural size. After
Retzius.

at Annulus membranae
tympani.
col Columella.
ct Fissure-like cavity.
dm M. depressor maxillae.
mt Tympanic membrane.
sq Squamosal.
t M. temporalis.

thelium, a continuation of the mucous membrane lining the tympanic·
cavity.   www.libtool.com.cn

b. The **tympanic cavity** (Fig. 242 II) is seen, after removing the
tympanic membrane, as a flattened, funnel-shaped cavity. The
walls of the cavity are lined with a pigmented mucous membrane,
under which the cartilaginous ring (*annulus membranae tympani*)
extends internally to form the greater part of the wall of the cavity.
The cavity is an elongated oval slit (Fig. 242 II, *ct*), with its longer
axis directed from above and in front, downwards and backwards,
and leading inwards ; it is bounded above, below, and in front by the
squamosal, behind by the soft parts ; above in the roof is the cartila-
ginous part of the *columella*. The inner or deeper portion of the
tympanic cavity is bounded in front by the squamosal, and by the
squamous process of the prootici (*proc. squamosus prootici*) in front
and above ; internally by the cartilage (primordial-cranium) between
the prootic and the exoccipital ; behind by the *M. depressor maxillae*.
This part of the cavity is rounded and covered with mucous mem-
brane, and has in its roof the bony part of the columella, which
covers the *foramen ovale* (*fenestra ovalis*) by its oval, widened end-
piece. This deeper portion of the cavity communicates by a short,
wide Eustachian tube with the pharyngo-oral cavity; the tube is
wide and is of a rounded oval form in section : anteriorly, externally,
and internally it is bounded by the pterygoids, posteriorly by soft
parts, in which is embedded the styloid process.

The tympanic cavity can be examined from without after re-
moving the tympanic membrane, or from below by means of the
Eustachian tube.

c. The **columella auris** (Figs. 12, 243) is described by Retzius
as consisting of three portions, of which the middle is bony, the
external and internal cartilaginous. Parker divides it into four
parts (see pp. 25, 26).

The **extrastapedial** (Fig. 243 *a'*, *a''*) is attached to the middle of·
the tympanic membrane by the oval surface opposite *a'*, and is
attached by the process *a'''* to the *annulus tympanicus*; this process
of Retzius is the **suprastapedial** of Parker.

The **mediostapedial** (Parker), or middle bony piece of Retzius
(Figs. 12 *a'*, 243 *b*, *b'*), is narrow externally but widens internally
to articulate with the interstapedial. Just before reaching the
latter it gives off a process (*b'*), to which are attached a few fibres of
striated muscle (*m*).

The **interstapedial** (Figs. 12 *a*, 243 *c*) is cartilaginous; it is thick with a sharply cut-off, slightly concave end, which is placed against the *fenestra ovalis*. The inner surface of the interstapedial is, however, distinctly larger than the opening of the *fenestra ovalis*, consequently it does not fit in accurately, but is attached to the border of the opening by means of connective - tissue; the margins of the *fenestra ovalis* are hollowed (Fig. 245 II) so as to form a *fossa fenestrae ovalis*, and it is really to the margin of this fossa that the connective-tissue capsule of the interstapedial is attached.

B. The labyrinth or internal ear is contained in a capsule formed of bone and cartilage.

Fig. 243.

The columella; after Retzius.   Magnified eight times.

A. Seen from above.
B. Seen from behind.

a'   Extrastapedial (Parker). Outer cartilaginous portion attached to middle of tympanic membrane (Retzius).
a'' Attachment of extrastapedial to mediostapedial.
a''' Suprastapedial (Parker). Portion embedded in mucous membrane (Retzius).
b   Mediostapedial (Parker). Bony part (Retzius).
b'   Process of mediostapedial.
c   Interstapedial (Parker). Inner cartilaginous piece (Retzius).
m   Insertion of small muscle.

a. **The capsule of the labyrinth** (Fig. 244) is formed of two bones, the prootic and the exoccipital (according to Hasse this includes the opisthotic), which are united by cartilage belonging to the primordial-cranium. The fronto-parietal, squamosal, and parasphenoid take only an indirect part in its formation.

On the whole the anterior half of the capsule is formed by the prootic, and the hinder half by the exoccipital; the cavity has its long axis directed from within and above, downwards and outward; the cavity is comparatively large and rounded, and contains the membranous ear.

Four surfaces can be distinguished : a supero-external, an interno-inferior, an anterior, and a posterior (Retzius).

(1) **The supero-external surface** is divided into two parts by a strong, transverse, bony ridge, the *processus squamosus prootici*. The upper half is concave, is directed upwards and outwards, and is formed by the prootic; it is separated from the anterior surface

by a bony ridge, which marks the position of the anterior semi-circular canal. Posteriorly and medianly it is separated from the posterior surface by a cartilaginous ridge, running from above, downwards and outwards, which marks the position of the posterior semicircular canal. The cartilaginous hinder root of the *processus squamosus prootici* arises in the cartilaginous ridge just mentioned, and runs outwards and forwards, covering the external semicircular canal.

Fig. 244.

Antero-posterior section through the capsule of the right labyrinth of *Rana esculenta*; after Retzius. Enlarged five times.

ac.   Aquaeductus cochleae.
av.   Aquaeductus vestibuli.
cp.   Posterior semicircular canal.
cra.   Canalis rami anterioris acustici.
crp.   Canalis rami posterioris acustici.
fr.   Fenestra rotunda.
fsc.   Fovea sacculi et cochleae.
ft.   Trigeminal foramen.
kn.   Cartilaginous suture.
ol.   Exoccipital.
pr.   Prootic.
ps.   Parasphenoid.

The lower half of the supero-external surface (under the *processus squamosus*) is irregularly concave; immediately under the *proc. squamosus* is a shallow groove in the prootic; it is continued on the exoccipital to the jugular foramen. The remaining part of this surface consists of a rounded cartilage, and is part of the primordial-cranium cartilage between the prootic and the exoccipital; posteriorly it has a small oval aperture, the *foramen ovale* (*fenestra vestibulare*), which with the groove is covered by the *columella*. Above the aperture the cartilage narrows and is continued to the *processus squamosus*.

(2) The **posterior surface** is directly continuous with the supero-external surface, and is formed by the exoccipital. This surface lies behind the ridge formed by the posterior semicircular canal, it is concave, and has two small apertures, separated by a narrow, bony process, and situated near the jugular foramen; these are the *foramen rotundum* (*fr.*) and the *aquaeductus cochleae* (*ac.*).

(3) The **anterior surface** is altogether bony and formed by the prootic (*pr.*); the anterior surface of this part of the wall is continuous with the surface of the cranium, and abuts on to the large trigeminal foramen (*ft.*); below it is continuous with the under surface of the cranium, below and externally it articulates with the pterygoid.

(4) The **interno-inferior surface** is as a whole hollowed internally, the upper part being pushed in towards the cranial cavity. It is formed by the prootic anteriorly, by the exoccipital posteriorly, and is completed by the cartilage lying between these bones. In

the middle of the upper part of the cartilage is a small oval opening (*av.*), the *ap. aquaeductus vestibuli*: about midway between this aperture and the jugular foramen is a second opening in the cartilage (*cra.*), the opening of the *canalis rami anterioris (vestibularis) acustici*: a little behind and above this is the opening of the *canalis rami posterioris (cochlearis) acustici*, situated in the exoccipital. The cartilage between the prootic and exoccipital in the lower half of the interno-inferior surface rests on the parasphenoid.

b. The **position** of the **soft parts** in the capsule. The large outer, rounded part of the cavity contains the saccule and cochlea (*fovea sacculi et cochleae*) (*fsc.*). Above, the cavity is more irregular, and contains the utricle and the *sinus utriculi superior*. In front and externally, imbedded in a deep groove, are the anterior and external ampullae (*fovea ampullae anterioris et amp. externae*); to these are attached the corresponding semicircular canals. The anterior semicircular canal opens above and externally into the canal of the *sinus utriculi superior*; the posterior passes into a groove for the posterior ampulla (*fovea ampullae posterioris*), and opens above and internally into the posterior semicircular canal. The external semicircular canal courses in the *processus squamosus prootici*, the posterior in the cartilage (Fig. 244 *cp*) between the prootic and exoccipital, and the anterior in the prootic. The upper and posterior part of the anterior semicircular canal is imbedded in cartilage, on which rests the parasphenoid.

c. The **perilymphatic space** (Fig. 245 I and II. The membranous labyrinth does not occupy the whole space enclosed by the hard parts but is surrounded by the perilymphatic space, which contains the perilymph. The periosteum and perichondrium form the outer lining of the space, and are for the most part pigmented.

The perilymphatic space is widest in the lower part of the organ, in the region of the *fovea sacculi et cochleae*, especially externally and behind (*per*); in front it is much narrower (*per'*). A little higher, in the region of the *tegmentum vasculosum*, the space is wanting, as the membranous labyrinth is here attached to the periosteum.

Around the utricle and saccule the space is comparatively wide; it is continued into the bony canals and ampullae. In the semicircular canals the space is wider on the concave side than on the convex side, the membranous canals being placed eccentrically, as are also the ampullae, though to a less extent. The periosteum and

perichondrium lining this cavity form a very delicate, pigmented membrane, formed of numerous fine elastic fibres which cross each other irregularly; its inner surface is lined with an incomplete layer of branched protoplasmic cells with large oval nuclei. From

Fig. 245.

The membranous labyrinth of *Rana esculenta*, within its natural covering of periosteum; after Retzius.

I.   Seen from the side; magnified ten times.
II. The hinder half; magnified ten times. Seen obliquely from above, and in front, and from the side.

aa	Anterior ampulla.	*pb*	Pars basilaris cochleae.
adf	Apertura fenestrae ovalis.	*prr*	Wider part of perilymphatic space.
al.	Apertura lagenae.	*per'*	Narrower part of perilymphatic space.
ap.	Posterior ampulla.	*ra.*	Ramus anterior.
apb.	Opening into the pars basilaris.	*rn.*	Ramulus neglectus.
ca	Anterior semicircular canal.	*rp.*	Ramus posterior.
ce	External semicircular canal.	*rs.*	Ramulus sacculi.
cp	Posterior semicircular canal.	*s.*	Saccule.
dfo	Ductus fenestrae ovalis.	*sfo*	Saccus fenestrae ovalis.
dp	Ductus perilymphaticus.	*spl*	Saccus perilymphaticus.
dp'	Saccus perilymphaticus.	*tv*	Tegmentum vasculosum.
l.	Lagena cochlea.	*u*	Utricle.
ms.	Macula sacculis.		

this membrane numerous irregular bundles of fibres, in the form of trabeculae, pass into the space and form a rich network, which is attached internally to the outer surface of the membranous labyrinth and holds it in position. Free nucleated leucocytes are occasionally met with in the meshes of this network. The perilymphatic space is prolonged into two subsidiary cavities :—

(1) The **ductus fenestra ovalis** (Retzius), (Fig. 245 *dfo*) commences as an opening (*adf*) immediately opposite the *foramen ovale* of the hard capsule, which leads into a moderately large canal, the structure under consideration. It passes forwards and outwards through the *fenestra ovalis* between the interstapedial and the outer wall of the capsule into the oval depression (*fossa fenestrae ovalis*),

and rapidly widens to form a short, flattened, blind sac (*saccus fenestrae ovalis*), which is lodged in the fossa (*sfo*). Its walls are thin and pigmented.

(2) The **ductus perilymphaticus** (Hasse), (Fig. 245 *dp*) passes above and behind the *ductus fenestrae ovalis*, behind the auditory nerve, and near the cochlea, then behind and above the *lagena* to the *aquaeductus cochleae* (Fig. 244 *ac*), where it forms a short, wide tube, which passes backwards and inwards through this canal to the *canalis jugularis*; here it lies close to the nerves and forms a short oval

Fig. 246.

Part of the outer wall of the perilymphatic space : after Retzius. Vérick's Syst., Obj. III, Oc. 3.

per. Periosteum.
pg. Perilymphatic network.
zn. Leucocytes.

sac (*saccus perilymphaticus*) (*dp'*), which communicates with the subarachnoid space of the cranial cavity by means of a tube from the neck of the sac. The walls of this structure are thin and formed of connective-tissue with very few pigment-cells. The other extremity of the tube passes to the *pars basilaris* and under the *sinus post. utri.*, between it and the *pars neglecta*; it then courses to the outer side of the hinder end of the external semicircular canal: the tube then bends downwards to the outer side of the utricle and saccule to open into the general perilymphatic space.

d. The **membranous labyrinth** (Figs. 247, 248) has the following parts : the utricle and *sinus superior*, the *recessus utriculi*, the anterior semicircular canal and anterior ampulla, the external semicircular canal and external ampulla, the posterior semicircular canal and the posterior ampulla, the saccule, *ductus endolymphaticus*, and *saccus endolymphaticus*, the *pars neglecta*, the *lagena cochleae*, the *pars basilaris cochleae*, and the so-called *tegmentum vasculosum*.

In addition the following nerve-terminations can be distinguished : (1) The *macula ac. recessus utriculi*, (2) the three *cristae acusticae ampullorum*, (3) the *macula ac. sacculi*, (4) the *macula ac. neglecta*, (5) the *papilla ac. lagenae cochleae*, and (6) the *papilla ac. basilaris cochleae*.

The auditory nerve divides immediately beyond its origin from the *medulla oblongata* to form a *ramus anterior* and a *ramus posterior*, which course alongside each other for a short distance, the latter lying behind and above the former. The *R. anterior* runs forwards

and outwards under the utricle, giving off the *R. sacculi*, which runs downwards and outwards; the *R. rec. utriculi* is then given off as a number of fibres, which run upwards and forwards; the main nerve then divides to form the *R. ampullae anterioris* and the *R. ampullae externae*, which course together for a short distance and then separate to reach their respective ampullae. The *R. posterior* runs backwards and outwards, gives off the *R. lagenae*, and then divides to form the *R. neglectus*, running upwards, the *R. basilaris* running downwards and backwards, and the *R. ampullae posterioris* which courses backwards and outwards.

(1) The **utricle** (*utriculus*) (Figs. 247 and 248 *u*) is irregularly cylindrical in form : commencing at the *recessus utriculi* it passes forwards and outwards; then backwards, inwards, and upwards, to terminate at the *sinus posterior*, where it is slightly contracted. At about its middle it is divided into an anterior and a posterior part by an incomplete, sickle-shaped partition, formed by the posterior semicircular canal opening obliquely into the utricle, and so causing a fold in the posterior wall: on the anterior wall there is no fold ; the aperture left in the partition is the *apertura utriculi*.

The posterior part of the utricle receives the *sinus superior*, which is formed by the junction of the two vertical semicircular canals. The anterior part of the utricle receives the hinder dilated end of the external semicircular canal by an opening in its posterior wall, close to the *apertura utriculi*. In the lower wall or floor is the narrow opening leading into the *saccule* (*canalis utriculo-saccularis*) : this opening is placed with its long axis parallel to the long axis of the utricle, with its broader end posterior, and the narrower end anterior.

(2) The **recessus utriculi** (Figs. 247 and 248 *rec*). The anterior end of the utricle widens and curves downwards and outwards to form the *recessus utriculi* ; on its floor is a thin, kidney-shaped plate or otoliths, resting on the *macula ac. recessus utriculi* (*mu*), which receives the *ramulus rec. utriculi* ; under it the *ramulus amp. anterioris* and the *ramulus amp. externae* run forwards and close together to reach their respective ampullae, which are close together at the antero-external wall of the *recessus utriculi*. The otolith is a glassy, homogeneous plate, with numerous vacuole-like spaces and striated borders ; it covers the whole of the *macula*.

(3) The **anterior ampulla** and **semicircular canal** (Figs. 247, 248, *aa*, *ca*). The anterior ampulla is a rounded, oval vesicle, with a depressed roof (Fig. 250 I) ; on the floor is a transverse

low septum, which bears the *crista acustica* (*cr*) on its free border; seen from above the *crista acustica* (Fig. 249 II, *aa, cr*) has concave

Fig. 247.

Fig. 248.

The right membranous labyrinth of *Rana esculenta*; after Retzius. Magnified 20 times. Fig. 247 seen from the inner side; Fig. 248 seen from the outer side.

aa	Anterior ampulla.	*mn*	Macula acustica neglecta.	*rb*	Ramulus basilaris.
ae	External ampulla.	*ms*	Macula acustica sacculi.	*rrc*	Recessus utriculi.
ap	Posterior ampulla.	*mu*	Macula acustica recessus	*rl*	Ramulus lagenae.
apn	Apertura partis neglectae.		utriculi.	*rn*	Ramulus neglectus.
au	Apertura utriculi.	*pb*	Pars basilaris cochleae.	*rs*	Ramulus sacculi.
ca	Anterior semicircular canal.	*pl*	Papilla ac. lagenae.	*s*	Saccule.
ce	External semicircular canal.	*ppb*	Papilla ac. basilaris	*sp*	Sinus utriculi posterior.
cp	Posterior semicircular canal	*raa*	Ramulus ac. anterioris.	*ss*	Sinus utriculi superior.
cus	Canalis utriculo-saccularis.	*rae*	Ramulus amp. externae.	*tv*	Tegmentum vasculosum.
de	Ductus endolymphaticus.	*rap*	Ramulus amp. posterioris.	*u*	Utriculus.
l	Lagena cochleae.				

borders anteriorly and posteriorly; the ends are broad, rounded, and

somewhat raised; and in the middle it presents a small elevation
(Fig. 249 *cr*). On the *crista acustica* rests the *cupula terminalis*
(Fig. 250 I, *cu*); this is arched above but of the same form as the
crista acustica below, from which it is separated by an even slit-like
space; the ends are not rounded but hollowed out. The substance
of the *cupula* is very soft and has parallel striations, formed of fine
fibres and running from above downwards; it separates very easily
from the *crista acustica*. The anterior ampulla is directed forwards,
outwards, and slightly upwards, to open into the anterior semicir-
cular canal (*canalis m. anterior*) (*ca*), which curves first upwards and
forwards, then backwards, inwards, and upwards, to open by means
of a slightly dilated end into the *sinus superior utriculi*.

(4) The **external ampulla** and **semicircular canal** (Figs. 247,
248 *ae*, *ce*). The external ampulla lies immediately external to the
anterior ampulla; it also is an oval vesicle, and corresponds with the
anterior ampulla in size and shape, except that the roof is higher.
The roof is directed backwards, the floor forwards; the *septum
transversum* is low, placed vertically, and bears a triangular, slightly
depressed *crista acustica*: the broader, rounded end of the *crista* is
directed upwards, the apex downwards. The corresponding *cupula
terminalis* is relatively high, and is of the same shape as the *crista*,
and is striated. The external ampulla is continuous with the ex-
ternal semicircular canal (*canalis m. externus*) (*ce*), which courses
outwards and backwards; then backwards, inwards, and slightly
upwards, touches the roof of the posterior ampulla; then curves
forwards and inwards to terminate by a slightly dilated end in the
anterior part of the utriculus.

(5) The **posterior ampulla** and **semicircular canal** (Figs. 247,
248, and 249 *ap*, *cp*). The posterior ampulla commences at the
posterior end of the *sinus post. utriculi*, and is directed outwards
and backwards. It corresponds in all other points with the anterior
ampulla. The posterior semicircular canal (*ce*) (*canalis m. post.*),
into which the ampulla opens, curves upwards, inwards, and for-
wards, to open into the upper end of the *sinus superior*.

(6) The **saccule** (*s*), **ductus endolymphaticus** (*de*), and the
saccus endolymphaticus (Figs. 247, 248, 249). The saccule (*s*)
is an oval vesicle, placed under the anterior part of the utricle and
directed outwards and downwards; below it is flattened in a di-
rection from in front and within, outwards and backwards; above
it is wider. In the inner and anterior surface is the rounded, oval
macula acustica sacculi (Figs. 247 and 248 *ms*), to which is distri-

buted the *R. sacculi* (*rs*) from above; a large otolith rests on the macula and occupies a large portion of the cavity, more especially the lower portion. The tubular *ductus endolymphaticus* (*de*) arises by a narrow oval opening placed in the upper and inner part of the

Fig. 249.

The membranous labyrinth of *Rana esculenta*; after Retzius.

I. Part of membranous labyrinth to show relations of the ductus and saccus endolymphaticus to the cochlear part; magnified.
II. The recessus utriculi and the external ampulla; magnified.
III. To show tegmentum vasculosum, pars basilaris, pars neglecta, etc.
IV. To show relations of the cochlear part to the pars neglecta.

aa. Ampulla anterior.	*l.* Lagena cochleae.	*rap.* Ramulus amp. posterioris.
ae. Ampulla externa.	*ma.* Macula ac. recessus utri-	*rb.* Ramulus basilaris.
al. Apertura lagenae.	culi.	*rec.* Recessus utriculi.
ap. Posterior ampulal.	*mn.* Macula ac. neglecta.	*rl.* Ramulus lagenae.
apn Apertura partis neglectae.	*mp.* Membrana basilaris.	*rn.* Ramulus neglectus.
au. Apertura utriculi.	*pb.* Pars basilaris cochleae.	*rp.* Ramus posterior.
ca. Canalis m. anterior.	*p'.* Dark spot on either side of	*rs.* Ramulus sacculi.
ce. External semicircular canal.	crest of ampulla.	*s.* Saccule.
cp. Posterior semicircular canal.	*pl.* Pars ac. lagenae.	*sp.* Posterior semicircular
cpb. Opening into pars basilaris.	*pn.* Pars neglecta.	canal.
cr. Crista acustica.	*ppb.* Papilla ac. basilaris.	*spl.* Saccus perilymphaticus.
cus. Canalis utriculo-saccularis.	*ra.* Ramus anterior.	*ss.* Sinus utriculi superior.
de. Ductus endolymphaticus.	*raa.* Ramulus amp. anterioris.	*tv.* Tegmentum vasculosum.
dp. Ductus perilymphaticus.	*rae.* Ramulus amp. externa.	*u.* Utricle.

wall, runs upwards and to the angle between the utricle and the *sinus superior*, continues in the same direction for a short space, and then curves inwards to pierce the *apertura aquaeductus vestibuli*, and so reach the cranial cavity. It then forms a large, thin-walled sac

(*saccus endolymphaticus*), placed between the brain and cranium. The sac is very vascular and contains crystalline otoliths.

(7) The **pars neglecta** (Figs. 247, 248, 249) was described by Hasse as the 'first part of the cochlea' ('Anfangstheil der Schnecke'), but according to Retzius it does not belong to the cochlea. It is placed above and in front of the *pars basilaris cochleae*, above and a little behind the *lagena cochleae,* therefore above the upper and posterior part of the saccule, and under the middle part of the utricle. It is really a prolongation of the saccule, with which it communicates by an elongated oval opening placed externally and immediately below the opening of the *canalis utriculo-saccularis.* It is an oval vesicle, with its roof intimately united with the lower wall of the utricle; anteriorly it is broad, posteriorly narrowed. The *macula acustica neglecta* is attached to the roof of the vesicle and consists of an anterior heart-shaped and a posterior semilunar portion united by a narrow connecting piece (Fig. 250 III and VII). The *ramulus neglectus* divides into two branches, which supply the two parts of the *macula.* On the *macula acustica neglecta* rests the *membrana tectoria* (Deiters); the membrane is S-shaped, with the anterior end narrow, the posterior broad (Fig. 250 VII); the borders of the membrane are pierced by numerous small round holes, the central part has smaller and fewer perforations, and is finely striated. From the middle of the posterior part of the upper surface a thicker portion projects downwards into the cavity of the *pars neglecta*; it has a narrow, deep notch for the nerve at about its middle; anteriorly it points towards a sickle-shaped piece, which is curved inwards. Canals run obliquely downwards and inwards from the apertures on the superior surface. The membrane is clear, homogeneous, partly finely striated, and corresponds with the *membrana tectoria* of the *pars basilaris*, etc.

(8) The **lagena cochleae** (Figs. 247, 248, and 249 *l*) is an oval swelling of the membranous labyrinth; it lies close to the sacculus with its broader end forwards, the narrower directed backwards. By a large rounded opening at the posterior end it communicates with the saccule by means of a rounded space common to the *lagena cochleae* and the *cochlea.* The *papilla acustica lagenae* (*pl*) is situated in the posterior wall of the *lagena*; it is elongated, oval, and supplied by the *ram. lagenae.* The *papilla* is covered by a plate-like otolith formed of numerous rounded particles.

(9) The **pars basilaris cochleae** (Figs. 247, 248, and 249 *pb*) is placed on the posterior thickened wall of the saccule and lies above

and behind the *lagena*. It forms a small, oval, pocket-like protuberance, with the long axis directed from in front and above, backwards and outwards, its opening being directed forwards and

Fig. 250.

The membranous labyrinth of *Rana esculenta* ; after Retzius.

I. Transverse section of the anterior ampulla. Magnified 50 times.
II. Piece from under surface of the cupula from the anterior ampulla. Vérick's Syst., Obj.VIII, Oc. 3.
III. The macula acustica neglecta, seen from below. Vérick's Syst., Obj. IV, Oc. 3.
IV. Part of wall of the anterior ampulla.
V. Part of the cochlea, the pars basilaris cut longitudinally. Vérick's Syst., Obj. I, Oc. 3.
VI. Longitudinal section of the pars basilaris. Vérick's Syst., Obj. I, Oc. 3.
VII. The macula ac. neglecta, seen from below. Vérick's Syst., Obj. IV, Oc. 3.
VIII. The pars basilaris, seen from behind and the outer side. Vérick's Syst., Obj. I, Oc. 3.
IX. Transverse section of the external ampulla. Magnified 175 times.

apb	Oval opening into sacculo-cochlear space.	*n*	Nerve-fibres.
cr	Crista acustica.	*pb*	Pars basilaris.
cu	Cupula terminalis.	*pe'*	Area of coarsely granular cells.
dp	Ductus perilymphaticus.	*ppb*	Papilla acustica basilaris.
mb	Section of thinner wall of pars basilaris.	*r*	Epithelium on raphe.
		rb	Ramulus basilaris.
mt	Tectorial membrane.	*rn*	Ramulus neglectus.
mw	Thickened membranous wall.	*tv*	Tegmentum vasculosum.

outwards. The short *ram. basilaris* passes in from above to supply it. The walls of this dilatation are thick and stiff, with the exception

D d

of a small portion, the *membrana basilaris* (Hasse) (*mb*), which closes the opening into a small dilatation on the anterior inner wall. The *ramulus basilaris* (*rb*) divides into, at least, two branches, and passes close to the *membrana basilaris* (*mb*), where the elongated and oval *papilla ac. basilaris* (Fig. 250 *ppb*) is placed. The *papilla* is covered by a *membrana tectoria* (Fig. 250 *mt*), which is often found separated from the papilla, probably by the action of the

Fig. 251.

Preparations from the ear of *Rana esculenta* ; after Retzius.

I. Part of the membranous wall seen from the surface. Vérick, Obj. VI, Oc. 3.
II. Transverse section of the membranous wall. Vérick, Obj. III, Oc. 3.
III. Epithelium from the neighbourhood of the macula ac. rec. utriculi. Vérick, Obj. III, Oc. 3.
IV. Branched cells from the yellow spot on the floor of the anterior ampulla. Vérick, Obj. III, Oc. 3.
V. Epithelium from the roof of the anterior ampulla. Vérick, Obj. III, Oc. 3.

re Epithelium of raphe.	*pe* Protoplasmic cells.
e Pavement epithelium.	*pg* Perilymphatic tissue.

reagents used. The form of this membrane is peculiar but will easily be understood from the figure (Fig. 250 *mt*). In structure it is similar to the corresponding structures found in other parts of the ear.

(10) The **tegmentum vasculosum** (Deiters) (Figs. 245, 248, and 250 *tv*) is an oval, shell-shaped dilatation of the membranous labyrinth ; its long axis is directed from above and in front, downwards and backwards. The walls of the *tegmentum* are thin and intimately attached to the periosteum.

e. The **minute structure** of the membranous labyrinth (Figs. 251, 252).

(1) The **walls** of the membranous labyrinth have the same general structure throughout; the walls are usually thicker at the nerve terminations, in the ampullae, semicircular canals, *pars neglecta*, and especially the *pars basilaris*; the wall of the *tegmentum tympani* are the thinnest. The walls are transparent, homogeneous, refractive, and, at places, show a faint striation, which is, as a rule, not due to the presence of fibres; in parts of the *recessus utriculi*, and in the outer wall of the *saccule*, especially near the *tegmentum vasculosum*, more or less distinct fibres can be made out. Sections of the wall show spindle-shaped cells, with the processes usually arranged parallel to the surfaces; seen from the surface, the cells are seen to branch in all directions (Fig. 251 I, II). In the thinner parts of the walls the cells are few or altogether absent. The outer surface of the membranous labyrinth is uneven, in consequence of the attachment of the perilymphatic network. Blood-vessels are also attached to the outer surface, and pierce the wall, especially near the nerve-terminations.

The whole of the inner surface is lined with a layer of polygonal, tesselated epithelium-cells. The size and height of the epithelium varies in different parts. On the outer wall of the saccule the cells are large, but on the inner wall small; they are also large in the semicircular canals, except on a small raphe on the inner and outer side, where they are smaller but higher (Fig. 251 *re*); in the ampullae the cells are large, except on the roof. In the utricle and *sinus superior* they are also moderately large. In addition to the places mentioned, a smaller epithelium is found on the floors of the ampullae, in the *recessus utriculi*, and near all the nerve-terminations and on the sides of the ampullar septa. Surrounding the nerve-terminations of the *macula rec. utriculi*, *macula sacculi*, and *papilla lagenae* are found narrow, branched, yellowish cells (Fig. 251 *pe*) with spindle-shaped nuclei. Cells of a third kind, first described by Deiters, Hasse, and Kuhn, in the *tegmentum vasculosum*, and in the ampullae by Hasse and Kuhn, are also found in the utricle. They contain a yellowish pigment, and are collected into two sharply differentiated groups in each ampulla (Hasse has one placed before and one behind the septum on the floor). The cells are cylindrical, the upper parts striated, the lower narrower, and the bases again widened to a polygonal, more homogeneous plate, which is fixed to the wall. On the *tegmentum vasculosum* the corresponding cells are not so high.

(2) The **nerve-terminations.** The larger branches of the auditory

nerve contain medullated fibres of various dimensions and bipolar, spindle-shaped ganglion-cells. The nerves pierce the walls obliquely or vertically, and retain their medullary sheaths until near their final distribution. On each of the nerve-terminations is found nerve-epithelium, which varies in height in different parts. In the *crista acustica* it measures 0·075 mm. in height in the middle part, 0·06 mm. at the sides; on the *macula rec. utriculi* 0·09 mm., on the *macula sacculi* 0·075 mm., on the *papilla lagenae* 0·06 mm., on the *papilla part. basil.* 0·045 mm., on the *macula neglecta* 0·075 mm. The epithelium is of two kinds, hair-cells and sustentacular cells.

Fig. 252.

The nerve-terminations in the membranous labyrinth of *Rana esculenta*; after Retzius.

I. Vertical section through the crista acustica of the anterior ampulla. Vérick's Syst., Obj. III, Oc. 3.

II. Vertical section through the macula ac. recessus utriculi. Vérick's Syst., Obj. VIII, Oc. 3.

III. Three isolated hair-cells from the crista ac. of the anterior ampulla. Vérick's Syst., Obj. VIII, Oc. 3.

IV. Two isolated sustentacular cells from the crista ac. of the anterior ampulla. Vérick's Syst., Obj. VIII, Oc. 3.

cr	Crista acustica.
cu	Cupula terminalis.
fz	Sustentacular cells.
h	Hairs of hair-cells.
hz	Hair-cells.
n	Nerve-fibres.

a. The hair-cells (Fig. 252 *hz*) have, on the whole, elongated, flask-like forms, but are not all of the same length (0·024–0·04 mm.). The free ends of the cells are rounded, flattened, and yellowish, and each bears a stiff cilium, which is fixed by a broad base to the cell, and thins out towards its free end: the cilia vary in length; in the ampullae their greatest length is 0·13 mm., on the *macula rec. utriculi* 0·011 mm., and on the *papilla lagenae* 0·017 mm. The

cells are granular, possess rounded oval nuclei, and are fixed by a fine, narrow process (Fig. 252 *hz*), though they usually seem to be rounded off without possessing a process.

β. The sustentacular cells. Under the hair-cells is a finely granular substance, possessing numerous rounded oval nuclei, which are placed in superimposed rows (Fig. 252 *fz*), the deepest row being placed close together and immediately on the membranous wall. After proper treatment and isolation these nuclei are seen to belong to narrow, elongated cells, which rest by a slightly widened base on the wall, and are continued upwards between the hair-cells to reach the surface of the epithelium, where their upper processes are again slightly widened.

γ. The nerve-fibres (Fig. 252 *n*) lose their medullary coats, ascend towards the epithelium, and frequently divide to form two unequal branches, which ascend to the level of the hair-cells, and curve so as to course horizontally as extremely fine varicose fibrillae; these frequently form a network, of which the exact method of termination has not been made out. In some cases a fine fibril may be traced to the base of a hair-cell, but a direct continuation of the one into the other has not yet been traced.

VI. THE EYE.

(Re-written by the translator.)

The organ of sight, the eyeball (*bulbus oculi*), together with its appendages (*tutamina oculi*), will be described in this chapter.

A. The Eye is flattened on the outer surface, more convex on the inner or deeper surface. Its principal axis is directed from behind, forwards and outwards.

The outer transparent portion of the eyeball is the cornea, which forms the outer boundary of the anterior chamber. The larger, white, opaque, and inner portion is the sclerotic coat, which, together with two deeper tunics, the choroid coat and the retina, enclose the posterior chamber of the eye. The pigmented ring placed behind the cornea is the iris, and the aperture it encloses the pupil. The lens is placed immediately behind the iris. On the inner side the optic nerve pierces the sclerotic to enter the eyeball.

a. The sclerotic coat (*sclerotica s. sclera*) forms about three-

fourths of the surface of the eyeball; posteriorly it is pierced by the optic nerve at a point (*porus opticus*) nearer the temporal side than the nasal. The sclerotic coat consists of fibrous tissue externally, with a layer of hyaline cartilage internally (Helfreich). The fibrous layer

Fig. 253.

is formed of bundles of parallel fibres, which cross each other, chiefly at right angles (Hoffmann). The cartilaginous layer ends just behind the line of insertion of the extrinsic muscle of the eye, and is thickest at the point of entrance of the optic nerve (Helfreich).

Endothelium from the inner surface of the sclerotic coat; after Hoffmann.

The sclerotic coat is rich in nerve-fibres, which form a close network; the fibres, however, do not unite but form the meshes of the network by simply crossing each at acute angles.

The deeper surface of the sclerotic coat is lined with a layer of large endothelial cells (Hoffmann), (Fig. 253), which form the outer wall of the capsule of Tenon.

b. The **cornea** and the **anterior chamber.** The cornea forms about one-fourth of the surface of the eyeball and is directly continuous with the sclerotic. In it five layers can be distinguished: a layer of stratified epithelium or conjunctiva, an anterior hyaline membrane, the true corneal substance, a posterior hyaline membrane, and a layer of endothelium.

(1) The **corneal epithelium** is a layer of stratified epithelium covering the superficial surface of the cornea. The superficial layer forms a beautiful mosaic of polygonal cells; the middle layers are polygonal in all sections, while the deepest layer is more or less columnar. Except in the most superficial layer, all the cells have serrated surfaces. Smaller cells possessing each two nuclei are also found between the columnar cells, and are evidently cells in process of division; according to Waldeyer, cell-proliferation may also take place in the middle layers.

The basal or deeper portions of the columnar cells possess a clear border, which reminds one of the hyaline border found on the free border of columnar epithelium in other parts. The cells are here so closely applied to one another that these borders have the appearance of a continuous, highly refracting membrane (Rollett); according to Henle, the border consists of a network of very fine processes from the cells above.

(2) The **true corneal substance,** and (3) the **anterior hya-**

line membrane. The corneal substance consists of flat bundles of fibres arranged in laminae, with cement-substance and connective-tissue corpuscles interposed. The fibrils are extremely fine (0·0001 mm., Engelmann), and bound together into bundles by cement-substance. The bundles of the laminae are arranged at various angles, though many are placed at right angles to each other (Waldeyer).

Between the laminae are flattened spaces, which seen in section are spindle-shaped. By proper treatment they are seen to be irregular, branched spaces, which communicate by fine canals and form part of the Recklinghausen-canals or lymph-system. These spaces contain branched, connective-tissue corpuscles (Toynbee), and a colourless fluid.

Fig. 254.

Preparation from cornea of *Rana esculenta*; after Klein. Hartnack's Syst., Obj. VII, Oc. 3.

a Nerve of first order.
b Nerve of second order.
c Nerve of third order.
d Nerve of fourth order.
e Corneal corpuscles.

The corpuscles (Fig. 254 *e*) do not fill the spaces which they occupy. They possess large nuclei, surrounded by granular protoplasm.

The canals by which these spaces communicate ('Saftcanälchen' of Recklinghausen) lie, in general, parallel to the surfaces of the cornea, and communicate by joining at acute angles or by short transverse branches. According to Lavdowsky, these canals have a distinct lining membrane.

The anterior hyaline [1] layer (Bowman's or Reichert's lamella) is not so well seen in the frog as in some higher animals; it is simply a portion of the corneal substance, of somewhat denser structure than the rest, into which it passes by a gradual transition.

(4) The **posterior hyaline membrane** (Descemet's membrane) is a highly elastic, very transparent layer, placed behind the true corneal substance; in the frog some few bundles of fibres

[1] Tamanscheff and Schweigger-Seidel consider the anterior and posterior hyaline membranes to be composed of fine fibrils.

belonging to the true corneal substance appear to pass into the posterior hyaline layer, although they cannot be traced further through its substance. The structure of the membrane is, in consequence of its transparency, unknown, though the above observation seems to point to a fibrillar origin.

(5) The **corneal endothelium** is a single layer of polygonal cells of 0·02 mm. diameter. The cells possess the power of altering their shape when stimulated (Klebs).

Fig. 255.

Preparation from cornea of *Rana esculenta* ; after Klein. Hartnack's Syst., Obj. X immers., Oc. 3.

a Endothelial cells.
b Nuclei of endothelial cells.
c Nerves of third order in the tissue of the cornea propria.
d Nerves of the fourth order.

(6) The **nerves** of the cornea are derived from the *ramus ophthalmica trigemini*; they pierce the sclerotic coat in front of the sclerotic cartilage and then course towards the cornea, at the margin of which they form a coarse network of medullated fibres. From this about thirty nerves pass towards the cornea, which they enter, and then very quickly lose the main part of their medullary sheaths. According to Wolff, a portion of the nerves retain their medullary sheaths, or in some cases appear to regain it after having lost it.

The nerves passing from the plexus (nerves of the first order, Klein) give off smaller branches, which for a short distance have a serpentine or rectilinear course. By a few anastomoses they form a loose plexus (nerves of the second order, Klein). After a longer or shorter course they give off numerous lateral fibres, or terminate in several such fibres arising at one point (nerves of the third order, Klein). These are distinguished by their size, varying only within small limits, and by the possession of more or less regularly placed varicosities; the clearer portions are longitudinally striated as though made up of fibrillae; they have a nearly rectilinear course, and, after a longer or shorter course, turn into a direction which is at right angles to the former one; lastly, they remain for long distances unbranched. These nerves are connected one with another by cross fibres running at

right angles to them, and in this way a rectangular trellis-work is formed. www.libtool.com.cn

The fibrils (nerves of the fourth order) given off by these nerves form networks around the connective-tissue corpuscles, but no direct connection between nerve and corpuscle has been traced; they always appear to lie on that surface of the corneal corpuscle which is directed towards the superficial surface of the cornea (Klein). In the endothelium covering the membrane of Descemet these fibrils can be traced coursing along the margins of the cells (Fig. 255 *d*), and sometimes undergoing dichotomous division (Klein).

Almost all observers have described these fibrils as possessing varicosities; Hulke, and more recently Wolf, however, deny their presence. Lavdowsky traces nerve-fibrils to the nuclei of the connective-tissue corpuscles.

(7) The **anterior chamber** is the space between the cornea and the iris, and is filled with a watery fluid, the aqueous humour. At the circumference of the chamber are a number of spaces (spaces of Fontana), formed by interruptions in the tissue between the posterior surface of the cornea and the iris; the result is that bands or trabeculae (*ligamentum pectinatum iridis*) pass from the one structure to the other, and between these are the spaces of Fontana.

According to Angelucci these trabeculae are of three kinds: trabeculae passing from the cornea to the iris, formed of connective-tissue; trabeculae from the cornea to the ciliary processes, which contain elastic tissue; trabeculae from the interstitial connective-tissue of the ciliary muscle to the cornea, and formed almost entirely of elastic tissue.

At the junction of the cornea and sclerotic, and just in front of the spaces of Fontana, is a larger and similar space, which may be traced round the whole circumference of the cornea; this, the canal of Schlemm (*Sinus circularis iridis*), is held to be a venous plexus by some observers (Angelucci, and others), according to others it is a lymphatic space in connection with the anterior chamber (Schwalbe, and others). It is certain that the vessels can be very easily injected from the anterior chamber, although a direct communication has not yet been seen.

c. The **choroid coat** and the **iris** (*tunica choroidea et iris, tunica vasculosa*).

1. The **choroid coat** lines the deeper surface of the sclerotic coat, but is also prolonged under the cornea to form the iris.

Fig. 256.

The choroid is firmly attached to the sclerotic in two positions, at the point of entrance of the optic nerve, and at the line of junction of the sclerotic and the cornea. Its external surface is closely applied to the deeper surface of the sclerotic, from which it is only separated by a very narrow serous cavity (supra-choroidal space), and to which it is attached by numerous vessels and nerves. The deep surface of the choroid is covered by the retina, to which it is closely attached, except at the ora serrata, the attachment being especially intimate at the *processus ciliares*.

The choroid coat consists of a fibrous layer containing corpuscles and traversed by a very rich vascular anastomosis. The corpuscles of this layer are deeply pigmented, in some cases to such an extent that the oval nucleus cannot be seen; the fibrous tissue is also pigmented, and has consequently a brownish tinge. That portion of the layer immediately below the sclerotic is termed the *lamina fusca* or *suprachoroidea*, the vessels on the deeper surface forming the *membrana choriocapillaris*. This again is lined on its deeper surface by a hyaline membrane.

a. The arteries (Fig. 256 VI, VII, VIII) supplying this coat are two branches of the *arteria ophthalmica*; these form a capillary network (Fig. 256 VII) resembling the corresponding structure found in mammals. The meshes have approximately the same size, while the capillaries themselves vary considerably in size. This network is, however, only complete on the nasal, temporal,

---

Fig. 256.

The vessels of the choroid and iris ; after Hans Virchow.

    I. The two roots of the V. bulbi superior. Magnified 10 times.
   II. Vessels of the iris. Magnified 9 times.
  III. Origin of the ventral vein.
  IV. Schema of the choroid vessels ; seen from the proximal pole.
   V. Transverse section through the choroid at the equator.
  VI. The origin of the choroid arteries from the ophthalmic artery. The greater part of the sclerotic has been removed. Left eye twice natural size. A. From the proximal pole. B. From the temporal side.
 VII. Part of a choroidal artery attached to the choriocapillaris. Magnified 10 times.
VIII. A portion of the choriocapillaris, more highly magnified.
  IX. The V. ophthalmica and V. bulbi superior on the sclerotic of the right eye. A. Seen from proximal pole. B. Seen from above. Twice natural size.

A	Art. ophthalmica.	*R*	Branches of the circulus iridis major.
A'	Art. choroidea.	*Rd*	Distal root of vein of under surface of eye.
An	R. nasalis of the ophthalmic artery.	*Rd'*	Distal root of nasal vein.
At	R. temporalis of the ophthalmic artery.	*Rd"*	Proximal root of nasal vein.
ch	Area of membrana choriocapillaris.	*Rp'*	Nasal root of ventral vein.
Le	Outer pigmented layer of choroid.	*Rp"*	Temporal root of ventral vein.
Li	Inner pigmented layer of choroid.	*Vts*	V. bulbi superior.
N	Optic nerve.	*Vh*	V. hyaloidea.
r	Vasa recta.	*Vo*	V. ophthalmica.
r'	Transitional part between choriocapillaris and ventral whorl.	*Vp*	Proximal root of vein of under surface of eye.
r"	Transitional part between choriocapillaris and upper whorl.	*Vs'*	Nasal root of V. bulbi superior.
		Vs"	Temporal root of V. bulbi superior.

and proximal part of the upper surfaces. Towards the *corpus ciliare* the meshes become wider and elongated ; the capillaries then unite at acute angles parallel with the longitudinal axis of the eye. The network (*choriocapillaris*) exists in a simple layer within the two arteries which form it, and superficial to the veins (Virchow).

β. The veins of the choroid (Fig. 256 III, IV, IX) are (1) a vein which unites at the lowest point of the equator of the eye with the *V. hyaloidea* to form (2) the *V. ophthalmica*, two small branches of the *V. bulbi superior*, which unite outside the sclerotic, and (3) the *vasa recta*.

(1) The larger vein arises from the greater part of the under surface of the eye ; it gives off branches to each side, which radiate to form a ' whorl' or star-shaped capillary anastomosis (Fig. 256 III), the two halves of which have no connection. A proximal and a distal root can be distinguished in the anastomosis ; the distal lies towards the *corpus ciliare*, and occupies exactly one-fourth of the circumference of the choroid at its junction with the *corpus ciliare*.

(2) The two branches of the *V. bulbi superior* lie alongside the *corpus ciliare* on the upper surface, and each occupies one-fourth of the circumference ; they form a similar though simpler figure (Fig. 256 I) to the foregoing, each forming one half.

(3) The *vasa recta* are numerous parallel vessels which arise in the iris, and coursing centrally empty themselves into the branches of the *V. bulbi superior* on the superior surface, and into the branches of the venous capillaries on the inferior surface.

2. The **iris** is covered anteriorly by a layer of endothelium, continuous with that covering the posterior surface of the cornea, and of similar character. The border of the pupil (*margo pupillaris*) is of a golden colour, outside this bright ring to its outer margin (*margo ciliaris*) the iris is black ; the golden colour is due to the presence of cells containing a pale yellow pigment ; the nuclei of these cells are round and granular ; the cells themselves have rounded outlines (Hoffmann). The black portion of the iris contains more irregular, spindle-shaped cells, with round nuclei, which are hidden by a dense mass of pigment-granules (Iwanoff and Hoffmann).

The true substance of the iris consists of muscle, nerves, blood-vessels, and a connective-tissue stroma, but on the posterior surface is another layer of black, pigmented cells, and this is again covered with a hyaline membrane, in which, however, a fibrous structure may be made out (Koganeï).

The muscle-fibres are long, spindle-cells, which are abruptly swollen in the middle, where the nuclei are situated; the nucleus is oval, 0·009–0·0012 mm. in length, 0·0025 mm. broad, and occupies nearly the whole of the swollen part of the cell (Hoffmann, Grünhagen).

According to Koganeï the iris possesses a *M. constrictor iridis* (*l. c.* Berlin Sitzungsber.), but no *M. dilatator iridis*; in a former publication (*l. c.* Arch. mik. Anat.) he was unable to find any muscular fibre, and holds the muscle-fibres of Grünhagen to be connective-tissue elements.

The stroma consists of delicate connective-tissue fibrils, enclosing a very large number of pigmented, branched cells.

a. The **arteries** of the iris (Fig. 256 II) arise from an arch (see Vessels of Eye) formed by the *A. ophthalmica* in the *corpus ciliare.* It commences between the ventral and temporal surfaces by two branches : one courses. along the temporal border, the other along the nasal, to meet each other on the nasal surface; the former courses through one-third, the latter embraces two-thirds of the circumference at the iris.

The temporal artery courses along the ciliary border during the first third of its course, it then gradually approaches the border of the pupil; the nasal artery runs at once towards the pupil. On the nasal border of the pupil they anastomose by their branches, and so form a *circulus iridis major.*

Except near their termination, no small vessels arise from this arterial circle; in Fig. 256 II, for example, only five larger branches are given off, three from the temporal side and two from the nasal. The five large branches run towards the circumferential border of the iris and break up into numerous vessels, which form a very irregular and open network. From this network arise the *vasa recta* already described.

d. The **lens** is almost spherical, and is composed of cellular elements enclosed in a capsule (*capsula lentis*).

The capsule is a homogeneous, transparent, structureless, and highly elastic membrane. The deeper surface of the anterior capsule is lined with a simple layer of regular nucleated six-sided epithelial cells.

The lens itself consists of long, flat fibres; seen from the surface these are broad, narrow edge-wise, and in section six-sided prisms. Those lying parallel to the anterior and posterior surfaces are

broad and thicker, those towards the border are narrower. These cells are striated both longitudinally and transversely (Arnold). The cells near the margin, however, have no transverse striation (Hoffmann). The cells of the central parts form a much closer and firmer structure than those at the periphery (Arnold). The peripheral cells are nucleated, and sometimes even possess two nuclei to one cell; the central cells have no nuclei (Arnold).

The cells are held together by a cement-substance and by their serrated surfaces; the serrations are the cause of the transverse striations. The fibres of the lens have a simple arrangement: commencing at the middle point or pole of one surface they pass over the equator to the opposite pole; consequently the long borders of adjacent cells are in juxtaposition, and their pointed extremities meet at points in the axis of the lens (Hoffmann).

Ritter has described short, nucleated cells in the centre of the lens; these are held by Babuchin to be cells which have been arrested in their development.

Fig. 257.

Fibres from the lens of the frog; after Hoffmann. Magnified 700 times.

e. The **retina** is the innermost coat of the eye; in the recent state it is pale, soft, and smooth. The structures composing it are arranged in ten layers; from the deeper surface towards the choroid these are: the internal limiting membrane, the optic-fibre layer, the ganglion layer, the inner molecular layer, the inner nuclear layer, the outer molecular layer, the outer nuclear layer, the external limiting membrane, the layer of rods and cones, and the pigment layer.

These layers are held together by connective-tissue elements.

(1) The **internal limiting membrane** (*Membrana limitans interna*) will be described together with the connective-tissue elements (10).

(2) The **optic-fibre layer** is formed by the fibres of the optic nerve. The nerve-fibres in their course towards the eye are possessed of medullary sheaths, but on piercing the sclerotic these sheaths are lost. The fibres are now pale, non-medullated, and of very varying thickness. In the mass of fibres nothing can be seen except an extremely fine fibrillation and very fine varicosities; the

latter, however, appear to be artificial productions (Hoffmann). This layer of fibres extends over the inner surface of the retina, and gradually thins from the point of entrance of the optic nerve to the limits of the retina.

(3) The **ganglion-layer** lies immediately without the nerve-fibre layer (Fig. 258 *b*). The ganglion-cells are small and usually pear-shaped. The cells possess large nuclei, round which is a thin layer of very granular protoplasm. The cells have inner and outer processes; the inner pass into the nerve-fibre layer, the outer into the inner molecular layer in more or less radiating directions. Manz claims to have traced a direct connection between the inner processes and the fibres of the nerve-fibre layer.

Each ganglion-cell, whatever its shape or size, has only one inner process, which is easily distinguished from the outer process by its being more glistening, by the possession of varicosities, and because this process never branches.

The outer processes are single (Schwalbe) or rarely double (Hoffmann), and have as a rule a direction at right angles to the inner processes. Each outer process is finely granular, which suggests rather a prolongation of the cell-substance than a true process. Frequently they are branched, sometimes forming two equal sized processes, which give off finer twigs; at other times they appear to pass through the whole of the inner molecular layer without undergoing division (Schwalbe). The processes do not inosculate (Santi Sirena).

(4) The **inner molecular layer** (Fig. 258 *c*) is 0·07–0·08 mm. thick (Hoffmann), and consists of a finely

Fig. 258.

Vertical section through retina of frog; after Hoffmann. Magnified 500 times.

a   Internal limiting membrane.
b   Ganglion-cell layer.
c   Internal molecular layer.
d   Internal nuclear layer.
e   External molecular layer.
f   External nuclear layer.
g   Layer of rods and cones.
h   Pigmented epithelium layer.
1. Inner segments of rods and cones.
2. Outer segments of rods and cones.
3. Outer transparent segments of pigmented epithelium.

granular mass together with the outer processes of the ganglion-layer, and connective-tissue elements.

The granular matter consists of an extremely fine network or reticulum, through which numerous fine fibres course (Schultze, Kölliker, Manz, Heinemann, and others); according to Schultze the supposed molecules or granules of others (Henle, Merkel, and Retzius) are simply the fine meshes of this reticulum. The branched, outer processes of the ganglion-cells form a rich anastomosis in this layer.

(5) The **inner nuclear layer** (Fig. 258 *d*) contains parts of two kinds of cellular elements ; these are radial nerve-fibres with large nuclei, and connective-tissue elements (see below, par. 10). The nerve-fibres are easily distinguished by their spindle-shaped varicosities ; both cellular elements possess large oval nuclei. The bodies of the cells surrounding the nerve nuclei are almost filled by the nuclei, which have sharply-defined, rounded nucleoli. The fibres to which these cells are attached may be distinguished as inner and outer processes ; the inner process is fine, irregularly varicose, and unbranched ; the outer process is thicker, finely granular, and is not varicose (Schwalbe). At the margin of the outer molecular layer the outer processes divide, usually into two branches, and at an acute angle to each other, though sometimes at a right angle. The further course of these branches in the outer molecular layer is unknown.

(6) The **outer molecular layer** (Fig. 258 *e*) corresponds in general with the inner molecular layer as regards its structure ; it is, however, much thinner.

(7 and 9) The **outer nuclear layer** and the **layer of rods and cones** (Figs. 258 *f*, *g*, 259). The rods and cones are intimately connected with the elements of the outer nuclear layer, hence the two layers are best described together.

The rods (*bacilli*) have two parts or limbs, an outer and an inner, which differ in structure, and in chemical and physical characters. The outer part is highly refractive, the inner more homogeneous and less refractive, the two parts being sharply differentiated from one another.

The outer part is also weakly doubly refracting, the inner has no trace of this property. The rods are 0·05–0·06 mm. in length, of which 0·035–0·04 mm. belongs to the inner limb. The outer end of the outer limb is more or less rounded ; the whole has a longitudinal striation (Schultze), due to its being composed of

rounded fibrils, about twenty-four to each rod (Hensen). The fibrils are sharply differentiated from each other and have a slightly spiral course; when seen in transverse section these outer limbs do not appear to be round (Schultze), although others hold them to be perfectly rounded (Hoffmann and others), and that the loss of the cylindrical form is due to the methods of treatment. According to Merkel the longitudinal striation is caused by a canalisation of the outer limb, which according to him encloses the processes of the pigmented epithelial layer; he is also of opinion that the spiral appearance is an artificial product. In the latter opinion he is probably wrong, as perfectly fresh rods examined in aqueous humour show the same spiral appearance (Hoffmann): against the canalisation view others observe that the longitudinal striation is most distinct near the inner limit of the outer limb, and that it is impossible to conceive that the processes of the pigment-cells should

Fig. 259.

Various preparations from the eye of the frog: chiefly from the retina.

1. Rod from retina in aqueous humour, showing spiral striation.
2. Three rods and one cone after treatment with osmic acid.
3, 4, 5. Rods examined in recent state.
6, 7. Inner segments of two rods after treatment with osmic acid.
    a Outer limb.
    b Inner limb.
    c Lenticular body.
    d Nucleus of outer nuclear layer.
    e External limiting membrane.
8. Nuclear body from inner nuclear layer.
9. Twin-cone.
10. Sustentacular fibre of retina.
11. Surface view of pigmented epithelium of retina.
12, 13. Isolated pigmented cells of retina.
14. Four pigmented cells, rods and cones, external limiting membrane, and part of outer nuclear layer attached.
15. Two pigmented cells; each showing three attached rods.
16. Muscle-fibre from the iris.

Figs. 1, 2, 3, 4, 5, 6, 7, 8, 9 are magnified 500 times. Fig. 10, 300 times. Fig. 16, 400 times. All are copied from Hoffmann's figures.

Figs. 12, 13, 14, 15 are copied from Morano's figures; Hartnack, Oc. II, Obj. 9.

terminate with such extremely regular ends (Hoffmann).

In the central part of the inner end of the outer limb is seen a dark point when the structures are examined in transverse section (Ritter, Manz, Schiess, Schultze, and others). The

E e

cause of this is not clearly understood; some hold it to be a fibre (Ritter's fibres), others hold it to be an artificial product (Hensen).

After treatment with certain reagents the outer limbs show a transverse striation, which is probably produced by the action of these reagents on the sheath of the outer limbs; that a sheath is present is proved by its possession of a different refractive index (Zenker, Schultze) to the rest of the outer limb, and this transverse striation is not seen until the whole organ has undergone considerable *post-mortem* changes (Hoffmann). Should this change be allowed to proceed a stage further, the outer limbs of the rods split transversely and form small discs from 0·0005–0·00055 mm. thick; this takes place in the outer limb only.

The inner segments of the rods (Figs. 258, 259) are short (0·020–0·022 mm.) and of the same thickness as the outer limbs. When perfectly fresh they appear homogeneous; very quickly changes commence, which are probably due to coagulation. A plano-convex figure (Fig. 259) is then seen at the outer portion of the segment (lens-shaped figure of Schultze); with staining reagents it gives the same reactions as the outer segment of the rods. The rest of this segment forms a short cylinder, which probably has no distinct sheath (Hoffmann, Merkel); some observers are inclined to think that a sheath exists (Landolt, Schwalbe).

The outer segments of the rods are of two chief sizes (Schwalbe). Those of the one kind are large; the second variety occurs less frequently, and the segments are shorter, measuring only 0·002 to 0·0025 mm. The inner segment is a long, thread-like process, except where it is swollen to enclose the lens-shaped body.

The rods are much more numerous than the cones, except at one small spot (*macula lutea*) on the posterior surface of the retina, where only cones are found (Krause).

The cones (*coni*) have each two segments like the rods (Figs. 258, 259). The outer segments are short (4–5 μ), they are slightly conical and terminate externally in a blunt point; they possess a longitudinal striation (Schultze), and very easily break up transversely into small discs, which, however, do not separate so completely as in the case of the rods, in consequence of the presence of a sheath continuous with a sheath on the inner segment.

The inner segments (Figs. 258, 259) have convex sides and measure 12–14 μ; like the corresponding parts of the rods they possess lens-shaped bodies at their junction with the outer segments,

but the bodies differ in shape, being bi-convex or rather oval in form. The inner segments are enclosed in a delicate sheath continuous with that of the outer segments.

In some cases two cones are united to form a twin-cone; in such cases the one is always larger than the other (Fig. 259 9), and has several peculiarities which distinguish it from the smaller.

The smaller or secondary member of a twin-cone is longer, and possesses a lens-shaped body which is plano-convex. The larger or principal member of a twin-cone is shorter, has a plano-convex body, but also an oval, homogeneous, glistening body, which is directly attached to the plano-convex body. The shape of the two members is also different.

The **outer nuclear layer** (Fig. 258 *f*) is 14–16 μ thick; the nuclei lie in two layers. The nuclei belonging to rods and cones have the same characters, each nucleus being a large, oval, hyaline body, and enclosing a bright nucleolus. Each nucleus is surrounded by an extremely thin layer of finely granular matter. The inner processes of the nuclear bodies both of the rods and the cones extend to the outer molecular layer, are there dilated and serrated, where they become attached to the outer molecular layer (Schultze, Hoffmann). In some cases, however, the inner process of the nuclear bodies, belonging to the rods, forms only a short fine fibre.

In the case of twin-cones the corresponding parts in the outer nuclear layer possess two nuclei (Schultze).

(8) The **pigment layer** (Figs. 258 *h*, and 259 11, 12, 13, 14, 15) is not intimately attached to the rest of the retina. It consists of cylindrical cells in which two parts or segments are sharply differentiated; the external part, directed towards the choroid coat, is of pale, or colourless granular protoplasm, and occupies one-third of the length of the cell; this part encloses a large, round, nucleolated nucleus. This colourless segment of the cell also includes one or two bright yellow, fat globules (Morano). Seen from the surface the cells are hexagonal (Fig. 259 11). The remaining two-thirds of the cells consists of a brush formed of numerous fine pigmented processes; the ultimate terminations of the processes, which lie parallel to each other, are frequently unpigmented; each cell possesses thirty to forty such processes (Morano).

The processes extend between the rods and cones as far as the external limiting membrane (Figs. 258, 259), or sometimes a little further (Merkel, Morano, Hoffmann). The processes from one pigment-cell surround a number of rods and cones; according to

Morano twelve to fifteen rods and cones may be encased or surrounded by the processes of a single cell.

The thickness of this layer varies from 60–70 μ; the nuclei of the cells have a diameter of 10–12 μ, the width of a single cell is from 20–25 μ (Hoffmann).

(10) The **connective-tissue elements** of the retina and the **external** and **internal limiting membranes**. The elements of the retina are supported by connective-tissue elements or sustentacular cells, which have a radial arrangement, and which form the two limiting membranes (Müller).

Each sustentacular cell (Fig. 259 10) has two segments, an inner and an outer, the boundary between these lying in the inner nuclear layer, and being marked by the presence of a large oval nucleus. The inner segment of each cell terminates internally in a wide ' foot ' or base, or may form several such after having undergone division (Schultze): these bases together form a transparent, thin membrane, the internal limiting membrane (*membrana limitans interna*).

Within the ganglion-layer these cells possess peculiar appendages, which fit round the ganglion-cells and support them (Schwalbe).

The outer segments of the sustentacular cells extend into the outer molecular layer, and then break up into irregular processes which extend radially to the external limiting membrane, and which they probably form. The external limiting membrane (*membrana limitans externa*) is therefore a membrane corresponding to the internal limiting membrane, and formed by the flattened ends of the processes belonging to the sustentacular cells.

The sustentacular cells have a distinct, resistant cell-wall (Schwalbe); the cell-contents are a finely granular protoplasm, and a large oval, nucleated nucleus placed in the inner nuclear layer.

f. The **ciliary processes** have the same structure as the rest of the choroid coat : the vessels form more or less longitudinal meshes and are more irregular than in the rest of the choroid.

g. The **posterior chamber** and **vitreous body** (Fig. 260). The vitreous humour occupies the greater portion of the cavity of the eyeball, *i. e.* the posterior chamber. The humour consists of a mass of cells enclosed in a transparent hyaloid membrane (*membrana hyaloidea*), which is in contact with the internal limiting membrane of the retina.

The cells forming this structure are small, flattened, transparent,

and nucleated (Iwanoff and Virchow); according to the former observer the cells have contractile powers.

The hyaloid membrane is described as structureless by Schwalbe, as fibrous by Pappenheim, Bowman, and Fuikbeiner.

The vessels of the vitreous body (Fig. 260) are as follows. The *A. hyaloidea* arises at the lowest point of the *corpus ciliare*; it almost immediately divides into two branches, which form a ring at a distance of about 0·5 mm. from the lens and lying on the surface of the vitreous body (Fig. 260 I, II). One, *R. nasalis*, passes to the nasal side and courses through one-fourth of the circle; the

Fig. 260.

The vessels of the vitreous body; after Hans Virchow.

I. Vessels of the vitreous body; seen from the deeper pole and slightly from above. Magnified 6 times.

II. Arteries of the vitreous body of the right eye.
    A Seen from the proximal pole.
    B Seen from the nasal side.

III. Veins of the vitreous body of the left eye.
    A Seen from the proximal pole.
    B Seen from the nasal side.

    a Nasal vein.
    b Temporal vein.
    c Branch (constant) of temporal vein.
    n R. nasalis of the ophthalmic artery.
    t R. temporalis of the ophthalmic artery.
    t' Termination of the R. temporalis.
    V Ventral vein.

other, *R. temporalis*, courses through three-fourths of the circle. The branches are all given off proximally and at right angles to the circle (Fig. 260 I, II). From the *R. nasalis* only one branch arises, from the *R. temporalis* seven, the first of which corresponds in point of origin with the branch from the *R. nasalis*. The branches on the nasal and temporal surfaces of the vitreous body are the shortest.

These branches form a capillary network (Fig. 260 I) with elongated meshes, formed by the capillaries anastomosing at acute angles. The capillary network is more dense towards the middle of the proximal surface than in other parts.

The veins arising from this network are three in number (Fig. 260 III); two of these accompany the arteries from their origin, and form a somewhat similar circle around the lens, while the third passes backwards along the ventral surface of the vitreous body to the *papilla nervi optici*. The nasal vein, however, takes a more proximal course than the corresponding artery, the branches of which it crosses; consequently the venous ring is not so perfect as the arterial. The nasal vein is larger and the temporal vein smaller than the corresponding arteries.

The ventral vein is formed near the *papilla nervi optici* by the union of two smaller branches. The capillary system of these vessels has the usual structure of capillaries, the cells being united by cement-substance (Zimmermann).

The blood-vessels of the vitreous body are accompanied by lymphatics; according to Iwanoff they completely enclose the capillaries: Zimmerman contradicts this view, as he has been unable to find lymphatics on that side of the capillaries directed towards the vitreous body.

B. Appendages of the eye.

The appendages of the eye are the eye-muscles (see pp. 55–59), the eyelids, the Harderian gland, and the lachrymal duct.

a. The **eyelids** are two in number, an upper and a lower. The upper eyelid is intimately attached to the eyeball and follows the movements of that organ.

The **lower eyelid** (*membrana nictitans*) is much larger than the upper and has the same functions as the lower eyelid of higher vertebrates. It forms a transparent covering for the eyeball, and is raised by a special muscle (see p. 58); functionally it takes the place of both eyelids of higher vertebrates.

The lower eyelid is a prolongation of the skin, but has only a few pigment-cells, except at its free margin, and no serous glands. Mucous glands are found in two or three rows, closely applied to one another, on the superficial surface of the lid; on the deeper surface they are wanting. The stroma of the lid, like the cutis, is of connective-tissue.

Nerve-fibres can be traced in all directions through the substance

of the lid, forming a wide-meshed plexus. Around each gland the plexus becomes finer and by numerous branchings much closer; from the plexus twigs are given off, which divide to form a number of fibrils traceable into the epithelial cells of the glands (Openchowski).

The vessels of the lower eyelid have been investigated by Stricker, (*l. c.*); according to him they possess some interesting peculiarities. Many of these capillaries course within a lymphatic vessel, in some places the capillary being contracted by a projection from

Fig. 261.

Preparations from the nictitating membrane of *Rana esculenta* to show distribution of nerves.

I. Preparation of the nictitating membrane to show nervous supply to a capillary vessel; after Klein. Hartnack, Oc. III, Obj. 8.
       a Capillary vessel.
       b Blood-corpuscles.
       c and *d* Non-medullated nerve-fibres.

II. To show distribution of nerves in the epithelium; after Klein. Hartnack, Oc. IV, Obj. 8.
       a *b* } Subepithelial nerve-fibres.
       c Fine fibrils between the deepest epithelial cells.
       d Deepest epithelial cells.

its inner wall; where this is found the accompanying lymphatic is correspondingly dilated. Such points are especially met with where the capillaries branch; in many cases the capillary was contracted to such an extent that the blood-corpuscles were unable to pass the obstruction. Stricker further observed in the living tissue that such constrictions could take place in a part which a short time previously had been comparatively wide and dilated; further, that many of the nerves were enclosed in similar lymphatics. Langer, however (*l. c.*), describes the vessels as being accompanied by an irregular network of small lymphatic vessels.

The distribution of the nerves in the lower eyelid has been described by Klein. In the epithelium they form a network resembling that found in the cornea (Fig. 261 II); along the blood-vessels the fine fibrils form a perivascular network, which supplies

fine twigs to the walls of the vessels (Fig. 261 I). He distinguishes three kinds of pigmented cells.

b. The **Harderian gland** is situated at the inner angle of the eye, and is pear-shaped in form. It consists of a number of racemose glands held together by connective-tissue, the whole being enclosed in a relatively thick and strong capsule of connective-tissue.

The alveoli have a diameter of 0·040–0·060 mm. : they possess a lining of epithelium and a lumen which varies considerably in size. The epithelial layer is bounded externally by a membrana propria. The cells are placed eccentrically, they are cylindrical, and composed of finely granular protoplasm ; each cell contains a pale, rounded nucleus. The ducts of the alveoli are lined with a single layer of cylindrical epithelium, the cells of which are usually shorter and narrower than those of the epithelium of the alveoli; the ducts open into a single main tube, lined with similar epithelium but strengthened externally by a layer of connective-tissue. The glands secrete a fluid which moistens the free surface of the eye.

The Harderian glands are surrounded by a rich capillary anastomosis which completely invests the alveoli.

c. The lachrymal duct opens behind and below into the nasal cavity (see p. 389), anteriorly it can be traced forwards, as a small tube imbedded in connective-tissue and lying immediately beneath the skin, to the outer angle of the eye, where it opens by numerous tubules.

The lachrymal duct is lined with ciliated columnar epithelium.

ADDENDA.

HISTOLOGY OF MUSCLE, CARTILAGE, BONE, AND THE CONNECTIVE TISSUES.

LITERATURE.

———◆———

I. MUSCLE AND NERVE-ENDINGS IN MUSCLE.

Arnold, J., Gewebe der organischen Muskeln. Stricker's Gewebelehre, 1871. Vol. I, p. 142.

Arnold, J., Ueber die Abscheidung des indigschwefelsauren Natrons im Muskelgewebe. Virchow's Arch. Vol. LXXI, p. 1.

Babuchin, Ueber den feineren und Ursprung des Axencylinders. Centralbl. f. med. Wiss. 1868, p. 755.

Barfurth, D., Die Rückbildung des Froschlarvenschwanzes und die sogenannten Sarkoplasten. Arch. f. mik. Anat. 1887. Vol. XXIX, p. 35.

Biedermann, W., Zur Lehre vom Bau der quergestreiften Muskelfaser. Wiener Sitzungsber. 1876. Vol. LXXIV, Pt. III, pp. 49-62.

v. Biesiadecki, A., and Herzig, A., Die verschiedenen Formen der quergestreiften Muskelfasern. Wiener Sitzungsber. 1859, Vol. XXXIII, p. 146: and in Moleschott's Untersuchungen, 1860, Vol. VI, p. 105.

du Bois-Reymond, E., Ueber facettenförmige Endigung der Muskelbündel. Berlin. Acad. Monatsber. 1872, pp. 791-814. Abstract in Centralbl. f. d. med. Wiss. 1873. No. 55, p. 868.

Bowman. On the minute structure and movements of voluntary muscle. Phil. Trans. 1840, p. 457.

Bremer, L., Ueber die Endigungen der markhaltigen und marklosen Nerven im quergestreiften Muskel. Arch. f. mik. Anat. 1882. Vol. XXI, p. 165.

Bremer, L., Ueber die Muskelspindeln nebst Bemerkungen über Structur, Neubildung, und Innervation der quergestreiften Muskelfaser. Arch. f. mik. Anat. 1883. Vol. XXII, p. 318.

Calberla, E., Studien über die Entwicklung der quergestreiften Muskeln und Nerven der Amphibien und Reptilien. Arch. f. mik. Anat. 1875. Vol. XI, p. 442.

Calberla, E., Ueber die Endigungsweise der Nerven in den quergestreiften Muskeln der Amphibien. Dissert. Freiburg i. B. 1874; also in Zeitschr. f. d. wiss. Zool. 1874. Vol. XXIV, pp. 164-178.

Chittenden, R. H., Histochemische Untersuchungen über das Sarkolemm und einige verwandte Membranen. Untersuch. d. physiol. Instituts d. Universität Heidelberg. Vol. III.

Cohnheim, J., Ueber die Endigung der Muskelnerven. Centralbl. f. d. med. Wiss. 1863, p. 865.

Eberth, C. J., Untersuchungen über die normale und pathologische Leber. Virchow's Arch. 1864. Vol. XXXIX, p. 74.

Engelmann, T. W., Zur Lehre von der Nervenendigung im Muskel. Jenaische Zeitschr. 1868. Vol. IV, p. 307.

Engelmann, T. W., Untersuchungen über den Zusammenh. von Nerven u. Muskelfasern. Leipzig, 1863.

Engelmann, T. W., Microscopische Untersuchungen über die quergestreifte Muskelsubstanz. Pflüger's Arch. 1873. Vol. VII, pp. 33–71, and pp. 155–187.

Engelmann, T. W., Ueber die Endigung der motorischen Nerven in den quergestreiften Muskeln der Wirbelthiere. Centralbl. f. med. Wiss. 1863, p. 289.

Ewald, A., Ueber die Endigung der motorischen Nerven in den quergestreiften Muskeln. Pflüger's Arch. 1876. Vol. XII, p. 529.

Ewald, A., and **Kühne, W.,** Die Verdauung als histologische Methode. Heidelb. naturhistor.-med. Verhandl. 1877. Vol. I, p. 451.

Exner, S., Notiz zu der Frage von der Faserverteilung mehrerer Nerven in einem Muskel. Pflüger's Arch. 1885. Vol. XXXVI, p. 572.

Fischer, E., Ueber die Endigung der Nerven im quergestreiften Muskel der Wirbelthiere. Arch. f. mikrosk. Anat. 1877. Vol. XIII, p. 365.

Froriep, A., Ueber das Sarcolemm und die Muskelkerne. Arch. f. Anat. u. Physiol. 1878, p. 416.

Gerlach, J., Ueber das Verhalten der Nerven in den quergestreiften Muskelfäden der Wirbelthiere. Sitzungsb. Erlangen. 1873. Vol. V, p. 97; Abstract in Centralbl. f. d. med. Wiss. 1874, p. 227.

Gerlach, J., Das Verhältniss der Nerven zu den willkürlichen Muskeln der Wirbelthiere. Leipzig, 1874.

Gerlach, J., Ueber das Verhältniss der nervösen und contractilen Substanz des quergestreiften Muskels. Arch. f. mik. Anat. 1877. Vol. XIII, p. 399.

Golgi, C., Sui Nervi dei Tendini dell' Uomo e di altri Vertebrati e di un nuovo Organo Nervoso terminale Musculo-tendineo. Torino. Estr. dalle Memorie della Reale Acc. di Torino. Series II. 1880, Vol. XXXII.

Grützner, P., Zur Anatomie und Physiologie der quergestreiften Muskeln. Recueil Zoolog. Suisse. 1884. Vol. I, pp. 665–684.

Haycraft, J. B., Upon the cause of the striation of voluntary muscular tissue. Quart. Journ. Micros. Soc. 1881. Vol. XXI, p. 307.

Hensche, Ueber die Drüsen und glatten Muskeln in der äusseren Haut von Rana temporaria. Zeitschr. f. wiss. Zool. 1856. Vol. VII, p. 273.

Hensen, V., Ueber die Entwicklung des Gewebes und der Nerven im Schwanze der Froschlarve. Virchow's Arch. 1864. Vol. XXX, p. 51.

Jakimovitsch, Ueber die Regeneration der glatten Muskelfasern. Centralbl. f. d. med. Wiss. 1879, p. 897.

Key, A., Bidrag till Nervernas ändningsätt i Musklerna. Förhandlingar vid Skandinaviska Naturforskaemötet i Stockholm, 1863. Abstract in Centralbl. f. d. med. Wiss. 1866, p. 212. (Muscles of frog's tongue.)

Klebs, E., Die Nerven der organischen Muskeln. Centralbl. f. d. med. Wiss. 1863, p. 561.

Klebs, E., Die Nerven der organischen Muskeln. Virchow's Arch. 1865. Vol. XXXII, pp. 169-198.

v. Kölliker, A., Gewebelehre.

v. Kölliker, A., Einige Bemerkungen über die Endigung der Hautnerven u. den Bau der Muskeln. Zeitschr. f. wiss. Zool. 1857. Vol. VIII, p. 311.

Krause, W., Ueber den Bau der quergestreiften Muskelfaser. Zeitschr. f. rat. Med. Vol. XXIII.

Krause, W., Die Nervenendigungen in den Froschmuskeln. Internat. Monatschr. 1884. Vol. I, pp. 194-203.

Krause, W., Die motorischen Endplatten, etc. Hannover, 1869.

Krause, W., Ueber die Endigungen der Muskelnerven. Göttinger Nachrichten. 1863, p. 21.

Krause, W., Ueber die Endigungen der Muskelnerven. Henle and Pfeufer's Zeitschr. 1863. Vol. XX, pp. 1-19.

Kühne, W., Untersuchungen über Bewegungen und Veränderungen der contractilen Substanzen. Arch. f. Anat. u. Phys. 1859, p. 816.

Kühne, W., Die Muskelspindeln. Virchow's Arch. 1864. Vol. XXVIII, pp. 528–538.

Kühne, W., Untersuchungen über das Protoplasma und die Contractilität. Leipzig, 1864.

Kühne, W., Ueber die peripherischen Endorgane der motorischen Nerven. Leipzig, 1862.

Kühne, W., Zur Lehre von den Endplatten der Nervenhügel. Virchow's Arch. 1866. Vol. XXXIV, pp. 412–422.

Kühne, W., Ueber das Verhalten des Muskels zum Nerven. Verhandl. d. naturhist.-med. Vereins zu Heidelberg. 1880. Vol. II, p. 227.

Kühne, W., Ueber Nervenendigungen in den Muskeln nach Beobachtungen von M. B. van Sykel. Abdruk. aus den Verhandl. d. Naturh. med. Verein zu Heidelberg. 1884. Vol. III, pp. 238–242.

Kühne, W., Wiederlegung der Bemerkung E. du Bois-Reymond's über mehrfache. Nervenendigungen einer Muskelfaser. Zeitschr. f. Biol. 1884. Vol. XX, pp. 531–539.

Kühne, W., Ueber die Endigung der Nerven in den Muskeln. Virchow's Arch. 1866. Vol. XXVII, pp. 508–533.

Kühne, W., and Voit, C., Neue Untersuchungen über motorische Nervenendigung. Zeitschr. f. Biologie. Vol. XXXIII.

Lavdowsky, M., Die feinere Struktur und die Nervenendigungen der Froschharnblase. Arch. f. Anat. u. Physiol. 1872, p. 55.

Leboucq, H., Recherches sur le développement et la terminaison des nerves chez les larves des Batrachiens. Bull. de l'Acad. de roy. de Belgique. 1876. Vol. XLI, p. 561.

Letzerich, L., Ueber die Endigungsweise der motorischen Nerven. Med. Centralz. 1863, No. 37.

Leydig, F., Ueber Tastkörperchen und Muskelstructur. Arch. f. Anat. u. Physiol. 1856, p. 150.

Löwit, Die Nerven der glatten Muskulatur. Sitzungsb. d. Wiener Acad. 1875. Vol. LXXI, Pt. III, p. 355.

Marshall, C. F., The structure and distribution of striped and unstriped muscle. Quart. Journ. Micros. Sci. 1887. Vol. XXV.

Martin, H., Sur la structure de la fibre musculaire striée et sur les analogies de structure et fonction entre les tissus musculaires et les cellules à bâtonnets (protoplasma strié). Arch. de physiol. norm. et pathol. 1882, p. 465.

Mayer, S., Die sogenannten Sarkoplasten. Anat. Anzeiger, 1886. No. 9, p. 231.

Mayer, S., Einige Bemerkungen zur Lehre von der Rückbildung der quergestreiften Muskelfasern. Prager Zeitschr. f. Heilkde. 1887. Vol. VIII, p. 177.

Mays, K., Histo-physiol. Untersuchungen über die Verbreitung der Nerven in den Muskeln. Zeitschr. f. Biol. Vol. XX.

Mays, K., Ueber die Nervatur des Musculus rectus abdominis des Frosches. Heidelberg, 1886.

Melland, B., A simplified view of the histology of the striped muscle-fibre. Quart. Journ. Micros. Sci. 1885. Vol. XXV, p. 371.

Merkel, F., Der quergestreifte Muskel. Arch. f. mik. Anat. 1873. Vol. IX, pp. 293–367.

Minra, M., Untersuchungen über die motorischen Nervenendigungen der quergestreiften Muskelfasern. Virchow's Arch. 1886. Vol. CV, p. 129.

Nasse, O., Zur Anatomie und Physiologie der quergestreiften Muskelfasern. Leipzig, 1882. Abstract in Centralbl. f. d. med. Wiss. 1882, pp. 884 and 908.

Newman, D., New theory of contraction of striated muscle and demonstration of the composition of the broad dark bands. Journ. of Anat. and Physiol. 1879, p. 4.

Nicolaides, R., Ueber die caryokynetischen Erscheinungen der Muskelkörper während des Wachstums der quergestreiften Muskeln. Arch. f. Anat. u. Physiol. 1883, p. 441.

Odenius, M. W., Undersökungen öfer de sensibla muskelnervena. Nord. Medic. Arch. Vol. IV, No. 18.

Paneth, J., Die Entwickelung von quergestreiften Muskelfasern aus Sarkoplasten. Wiener Sitzungsber. 1886. Vol. XCII, Pt. III, p. 561.

Petrowsky, Zur Frage über das Wachstum der Muskelfasern des Muskelgewebes beim Frosch. Med. Centralbl. No. 49, pp. 769–772.

Pohl-Pinous, Ueber die Muskelfasern des Froschherzens. Arch. f. mik. Anat. 1884, Vol. XXIII, p. 500; and Verhandl. der Physiol. Gesell. zu Berlin. 1882–3. No. 9.

Ranvier, L., Appareils nerveux terminaux des muscles de la vie organique; cœurs sanguins, cœurs lymphatiques; œsophagus; muscles lisses. Leçons recueillies par Weber et Lataste. Leçons d'Anatomie générale faites au Collège de France. Paris, 1880. Vol. VII, p. 350.

Ranvier, L., Leçons sur l'histologie du Système nerveux. 1878. Vol. II.

Reichert, K. E., Ueber das Verhalten der Nervenfasern bei dem Verlauf und Endigung in einem Hautmuskel des Frosches, Rana temporaria. Arch. f. Anat. u. Physiol. 1851, p. 29.

Retzius, Zur Kenntniss der quergestreiften Muskelfaser. Biologische Untersuchungen. 1881, p. 1.

Rouget, Note sur la terminaison des nerfs moteurs dans les muscles chez les reptiles, les oiseaux et les mammifères. Comptes rendus. 1862. LV, p. 548.

Sachs, C., Die quergestreifte Muskelfaser. Arch. f. Anat. u. Physiol. 1872, pp. 607–648.

Sachs, C., Die Nerven der Sehnen. Arch. f. Anat. u. Physiol. 1875, p. 402.

Sandmann, D. G., Ueber die Verteilung der motorischen Nervenendapparate in den quergestreiften Muskeln der Wirbelthiere. Arch. f. Anat. u. Physiol. 1885, p. 240.

Schönn, Anatomische Untersuchungen im Bereich des Muskel- und Nervengewebes. Jenaische Zeitschr. 1865. Vol. II, pp. 26–60.

Schultze, M., Ueber Muskelkörperchen und das was man eine Zelle zu nennen habe. Arch. f. Anat. u. Physiol. 1816, p. 17.

Sokolow, A. A., Sur les transformations der terminaisons des nerfs dans les muscles de la grenouille après les section des nerfs. Arch. de Physiol. normale et pathologique, 1874, pp. 300–315.

Sokolow, A. A., Ueber die Nervenendigungen in den Muskeln ausgehungerter Frösche. Medicin. Bote. 1876, St. Petersburg.

Tergast, P., Ueber das Verhältniss von Nerve und Muskel. Arch. f. mik. Anat. 1873. Vol. IX, p. 36.

v. Thanhoffer, L., Beiträge zur Histologie und Nervenendigung der quergestreiften Muskelfasern. Arch. f. mik. Anat. 1882. Vol. XXI, p. 26.

Thin, G., On the structure of muscular fibre. Quart. Journ. Microsc. Sci. 1877. Vol. XVI, pp. 251–259.

Tolotschinoff, Ueber das Verhalten der Nerven zu den glatten Muskelfasern der Froschharnblase. Arch. f. mik. Anat. 1869. Vol. V, p. 510.

Trinchese, S., Mémoire sur la terminaison périphérique des nerfs moteurs dans la série animale. Journ. de l'Anat. et de la Physiol. 1867, pp. 485–504 (original in Italian, 1867).

Tschiriew, S., Sur les terminaisons nerveuses dans les muscles striés. Arch. de physiol. norm. et path. 1879. Vol. VI, p. 89.

Tschiriew, S., Sur les terminaisons nerveuses dans les muscles striés. Compt. rend. 1878. Vol. LXXXVII, p. 604.

Unger, Untersuchungen über die quergestreiften Muskelfasern des lebenden Thieres. Wiener med. Jahrb. 1879, p. 61; and in Centralbl. f. d. med. Wiss. 1879, No. 34, p. 622.

Wagener, G. R., Ueber die Verbindung von Muskel und Sehne unter einander. Sitzungsber. naturw. Gesells. Marburg. 1874, pp. 38–46.

Waldeyer, W., Ueber die Endigung der motorischen Nerven in den quergestreiften Muskeln. Centralbl. f. d. med. Wiss. 1863, p. 369.

Waldeyer, W., Untersuchungen über den Ursprung und den Verlauf des Axencylinders bei Wirbellosen und Wirbelthieren, sowie über dessen Endverhalten in der quergestreiften Muskelfaser. Henle and Pfeuffer's Zeitschr. 1864. Vol. XX, pp. 193–257.

Weismann, A., Ueber die Musculatur des Herzens beim Menschen und in der Thierreihe. Arch. f. Anat. u. Physiol. 1861, p. 41.

Wolff, W., Ueber den Zusammenhang des Muskels mit der Sehne. Diss. Berlin, 1877; Abstract in Centralbl. f. d. med. Wiss. 1877, p. 733.

Consult also: Arnold, J., Kühne, W., and Schweigger-Seidel, F., in Stricker's Handbuch der Gewebelehre.

II. CARTILAGE AND BONE.

Arnold, J., Ueber die Abscheidung des indigschwefelsauren Natrons im Knochengewebe. Virchow's Arch. 1877. Vol. LXXI, p. 17.

Arnold, J., Die Ausscheidung des indigschwefelsauren Narions im Knorpelgewebe. Virchow's Arch. 1878. Vol. LXXIII, p. 125.

Bigelow, W. S., Notiz über den Theilungsvorgang bei Knorpelzellen sowie über den Bau des Hyalinknorpels. Arch. f. mik. Anat. 1879. Vol. XVI, p. 457.

Boll, F., Untersuchungen über den Bau und die Entwicklung der Gewebe. Arch. f. mik. Anat. 1871. Vol. VII, p. 275.

Bruch, C., Ueber die Verknöcherung der Wirbelsäule bei den Batrachiern. Würzb. naturw. Zeitschr. 1862. Vol. III, pp. 225–238.

Bush, F., Das Knochengewebe der Batrachier nach den Untersuchungen von N. Kastschenko. Verhandl. d. physiol. Gesells. zu Berlin. 1881, pp. 358–361.

Flesch, Untersuchungen über die Grundsubstance des Hyalinknorpels. Würzburg, 1880.

Heidenhain, Zur Kenntniss des hyalinen Knorpels. Studien aus d. physiol. Inst. zu Breslau. 1863. Pt. II, p. 1.

Hertwig, O., Anatomisch histologische Untersuchung des Skelets der Mundhöhle und der Zähne der Amphibien; supplement to Vol. XI. Arch. f. mikroskopische Anat. 1874, pp. 29–32.

Kastschenko, N., Ueber die Genese und Architectur der Batrachierknochen. Arch. f. mik. Anat. 1881. Vol. XIX, pp. 1–52.

Kastschenko, N., Ueber die Krappfärbung der Froschgewebe. Arch. f. mik. Anat. 1882. Vol. XXI, p. 357.

v. Kölliker, Gewebelehre Leipzig. 1867, p. 66.

Lehmann, J. C., Ueber den Knorpel in der Achillessehne des Frosches. Zeitschr. f. wiss. Zool. 1864. Vol. XIV, p. 109.

Levschin, L., Ueber die Entwicklung des Knochengewebes des Frosches. Centralbl. f. med. Wiss. Nos. 18, 19.

Mays, C., Ueber den Bau der Sehnen, etc. Virchow's Arch. 1879. Vol. LXXV, p. 112.

Renaud, M. J., Système hyalin de soutènement des centres nerveux et de quelques organes des sens. Arch. de Physiol. 1881, p. 6.

Schleicher, W., Die Knorpelzelltheilung. Arch. f. mik. Anat. 1879. Vol. XVI, p. 248.

Spina, A., Ueber die Saftbahnen des hyalinen Knorpels. Wiener Sitzungsber. 1879. Vol. LXXX, Pt. III, p. 267.

Stadelmann, E., Die Histologie des 'Pseudoknorpels' in der Achillessehne des Frosches, etc. Virchow's Arch. 1880, Vol. LXXX, p. 105; also as Dissert. inaug. Königsberg, 1878.

van Stricht, O., Recherches sur le cartilage hyalin. Annales de la société de médicine de Grand. 1885, pp. 221-232.

Thin, G., On the structure of hyaline cartilage. Quart. Journ. Micros. Sci. 1876. Vol. XVI, pp. 1-22.

v. Török, A., Der feinere Bau des Knorpels des Achillessehne des Frosches. Centralbl. f. d. med. Wiss. 1872, No. 5, p. 66; and Verhandl. d. phys.-med. Gesells. zu Würzburg, 1872, Vol. III, pp. 1-26.

III. THE CONNECTIVE TISSUES.

Billroth, T., Ueber die Epithelzellen der Froschzunge, den Bau des Cylinder- und Flimmerepithel und ihr Verhältniss zum Bindegewebe. Arch. f. Anat. u. Physiol. 1858, p. 159.

Bizzozero, G., Ueber den Bau des Sehnengewebes. Moleschott's Untersuchungen. 1876. Vol. XI, p. 36.

Bobinsky, C., Zur Kenntniss des Baues, der Entwicklung und der regressiven Metamorphose der Fetzellen. Centralbl. f. d. med. Wiss. 1885. No. 43, pp. 753-755.

Boll, F., Untersuchungen über den Bau und die Entwicklung der Gewebe. Arch. f. mik. Anat. 1871. Vol. VII, p. 276.

Ciaccio, G. V., Nuove Ricerche sull' interna tessitura dei tendi. Memorie dell' Academie delle scienze dell Istituto di Bologna, 1872. Series III, Vol. II. Abstract in Centralbl. f. d. med. Wiss. 1873.

Csumak, J., Notiz über elastische Sehnen. Centralbl. f. med. Wiss. 1863, p. 785.

Flemming, W., Ueber Bildung und Rückbildung der Fettzelle im Bindegewebe; und Bemerkungen über die Structur des letztern. Arch. f. mik. Anat. 1871. Vol. VII, p. 32.

Gerlach, J., Ueber Bindegewebe. Sitzungsb. d. phys.-med. Societät zu Erlangen. 1872, p. 78.

Ginsburg, L., Ueber das Verhalten der Sehnenzellen bei der Entzündung. Virchow's Arch. 1882. Vol. LXXXVIII, p. 263.

Golgi, C., Sui Nervi dei Tendini dell' Uomo e di altri Vertebrati e di un nuovo Organo nervoso terminale Musculo-tendineo. Estr. dalle Memorie della Reale Acc. di Torino. 1880. Series II, Vol. XXXII, p. 29; No. 6, p. 86.

Hensen, V., Ueber die Entwicklung des Gewebes und der Nerven im Schwanze der Froschlarve Virchow's Arch. 1864. Vol. XXXI, p. 51.

Hoyer, Ueber den Bau der Cylinder- und Flimmerepithelien und ihr Verhältniss zum Bindegewebe. Arch. f. Anat. u. Physiol. 1858, p. 163; also Deutsche Klinik. 1857, No. 21.

Iwanoff, A., Beiträge zur normalen und pathologischen Anatomie des Frosch-Glaskörpers. Centralbl. f. d. med. Wiss. 1868, p. 129.

Kollmann, Ueber den Bau der Sehne. Münchener Sitzungsber. 1878. Abstract in Centralbl. f. d. med. Wiss. 1879, p. 881.

Maddox, On the apparent relation of nerve to connective-tissue corpuscles. Proc. Roy. Soc. Lond. 1868. Vol. XVI, p. 61.

Mays, C., Ueber den Bau der Sehnen mit besondere Berücksichtigung über Saftbahnen. Virchow's Arch. 1879. Vol. LXXV, p. 112.

Sachs, C., Die Nerven der Sehnen. Arch. f. Anat. u. Physiol. 1875, p. 402.

Spina, A., Untersuchungen des lebenden Bindegewebes. Oesterr. med. Jahrb. 1884. Pt. II.

NOTE BY THE TRANSLATOR.

REFERENCE has already been made to the views of Messrs. Melland and Marshall on the structure of muscle-fibres. The opinion that the striation of voluntary muscle is wholly or in part due to the presence of a regularly arranged network was previously published by Retzius, Bremer, and others. The authors referred to have now for the first time shown the importance of this network in all vertebrate muscular tissues, whether voluntary or involuntary.

Mr. Marshall gives the following summary of the result of his researches, which the Translator has confirmed by his own observations :—

1. In all muscles which have to perform rapid and frequent movements, a certain portion of the muscle is differentiated to perform the function of contraction, and this portion takes on the form of a very regular and highly modified intracellular network.

2. This network, by its regular arrangement, gives rise to certain optical effects which cause the peculiar appearances of striped muscle.

3. The contraction of the striped muscle-fibre is probably caused by the active contraction of the longitudinal fibrils of the intracellular network ; the transverse networks appear to be passively elastic, and by their elastic rebound cause the muscle to rapidly resume its relaxed condition when the longitudinal fibrils have ceased to contract ; they are possibly also paths for the nervous impulse.

4. In some cases where muscle has been hitherto described as striped, but gives no appearance of the network on treatment with the gold and other methods, the apparent striation is due to optical effects caused by a corrugated outline in the fibre.

5. In muscles which do not perform rapid movements, but whose contraction is comparatively slow and peristaltic in nature, this peculiar network is not developed. In most if not all of the

unstriped muscles of invertebrates there does not appear to be an intracellular network present in any form, but in the unstriped muscle of vertebrates there are longitudinal fibres only; these possibly represent a form of network intermediate between the typical irregular intracellular network of other cells and the highly modified network of striped muscle.

6. The cardiac muscle-cells contain a network similar to that of ordinary striped muscle.

DESCRIPTION OF THE FIGURES ON PLATE II.

Fig. 180 (p. 278).

I. Preparation of the mucous membrane of the dorsal surface of the mouth and oesophagus to show the vascular supply. Arteries red, veins blue; after Schöbl.

II. Small portion of the above to show the dilatations on the capillaries ; after Schöbl.

Fig. 187 (p. 285).

Transverse section through the mucous membrane of the fundus of the stomach of *Rana esculenta*. Alcohol preparation, doubly stained with carmine and anilin blue. After Biedermann. (Oc. II, Syst. 7, Hartnack.)

Fig. 196 (p. 298).

I. Partial injection of the liver from the portal vein (blue): *Rana esculenta*.—G. H.

II. Partial injection of the liver from the hepatic vein (red): *Rana esculenta*.—G. H.

III. Complete injection of the liver from the hepatic artery (red) and from the portal vein (blue) : *Rana esculenta*.—G. H.

        A Portal (interlobular) veins and their branches.

        B Hepatic (intralobular) veins and their branches.

        C Hepatic arteries and their branches.

Fig. 208 (p. 318).

Two sections from the lung of *Rana temporaria* ; stained with borax-carmine.—G. H.

I. The lung dilated (Hartnack, Oc. I, Syst. 3).

II. The lung contracted (Hartnack, Oc. I, Syst. 7).

        A Band of muscle cut transversely.

        B Band of muscle cut longitudinally.

        C Muscular layer of surface.

Fig. 217 (p. 334).

Portions of two transverse vertical sections through the kidney.—G. H.

I. Kidney of *Rana esculenta*, partial injection of the uriniferous tubes with silver nitrate (Hartnack, Oc. I, Syst. 7).

II. Kidney of *Rana temporaria*, stained with borax-carmine (Hartnack, Oc. I, Syst. 7).

Fig. 219 (p. 337).

Two portions from a gold preparation of the kidney of *Rana esculenta*.—G. H.

I. Showing the tendency to split into lobules.

II. Nerve-fibres accompanying the blood vessels.

        a Blood-vessels.   *b* Nerves.

APPENDIX.

I. WORKS WHICH DESCRIBE ORGANS OR SETS OF ORGANS IN THE FROG.

Bettade, E., Sulle diverse forme delle R. temp. in Europa e più particolarmmente nell' Italia. Venezia, 1885.

Brehm, A. C., Illustriertes Thierleben. Hildburghausen, 1869. Vol. V.

Burdon-Sanderson, Handbook for the Physiological Laboratory. London, 1873.

Camerana, L., Recherches sur les variations de la R. esculenta et du Bufo viridis dans le bassin de la Méditerranée. Paris, 1883.

Carus, C. G., Lehrbuch der vergleichenden Zootomie. 2nd Edit. Leipzig, 1834.

Cepède, Comte de la, Histoire naturelle des quadrupèdes ovipaires et des serpens. Paris, 1808.

Dugès, Recherches anatomiques et physiologiques sur les Reptiles. Ext. des Annales des Sciences naturelles. Paris, 1827.

Duméril and Bibron, Erpétologie générale ou histoire complète des Reptiles. 1836.

Ecker, A., Icones physiologicae. Leipzig, 1851–1859.

Fatio, V., Faune des vertébrés de la Suisse. Genève et Bâle, 1872.

Gegenbaur, C., Grundzüge der vergl. Anatomie. Leipzig, 1870.

Gegenbaur, C., Grundriss der vergl. Anatomie. Leipzig, 1878.

Gerlach, Handbuch der Histologie. 1853–1854.

Gesner, C., Historia Animalium. Liber I. 1551.

Gesner, C., Icones Animalium. 1560.

v. Griesheim, A., Ueber die Zahlenverhältnisse der Geschlechter bei R. fusca. Pflüger's Arch. f. d. ges. Physiol. 1881. Vol. XXVI, p. 3.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs. Vol. VI, Amphibien. Leipzig, 1873–1878.

Howes, G. B., An Atlas of Practical Elementary Biology. London, 1885.

Huxley, T., Anatomy of the Vertebrated Animals. London, 1871.

Huxley, T., Lectures on the Elements of Comparative Anatomy.

Huxley, T., Article Amphibia, Encyclopaedia Britannica. IXth Edit. 1875.

Klein, E., Beiträge zur Anatomie der ungeschwänzten Batrachier. Jahreshefte. Württemberg, 1850, pp. 1–84.

Klein, E., and Noble Smith, Atlas of Histology. London, 1879–1880.

Kloeske, C. G., Dissertatio anatomica de Rana cornuta. Berolini, 1816.

v. Kölliker, A., Handbuch der Gewebelehre. 5th Edit. Leipzig, 1867.

Kuhl, H., Beiträge zur Zoologie der Rana esculenta : in Beitr. z. Zool. Frankfurt a. M., 1820.

Laurenti, J. N., Synopsis Reptilium. Viennae, 1768.

Leydig, F., Lehrbuch der Histologie. Frankfurt a. M., 1857.

Marshall, A. M., The Frog. 3rd Edit. London and Manchester, 1888.

Mayer, A. F., Beiträge zu einer anatomischen Monographie der Rana pipa. Acad. Caes. Leop. Nov. Acta, 1825. Vol. XII, p. 527.

Meckel, J., Beiträge zur vergleichenden Anatomie. Leipzig, 1811.

Meckel, J., System der vergleichenden Anatomie. Halle, 1833.

Mivart, St. Geo., On the Classification of the Anurous Batrachians. Proc. Zool. Soc. 1869.

Mivart, St. Geo., The Common Frog. London, 1874.

Müller, J., Beiträge zur Anatomie und Naturgeschichte der Amphibien. Tiedemann's Zeitschr. 1831, p. 190.

Müller, J., The Physiology of the Senses, etc. Translated by W. Baly. London, 1848.

Owen, R., Anatomy of the Vertebrates. London, 1866.

Ranvier, L., Leçons d'anatomie générale. Paris, 1880.

Rösel v. Rosenhof, Historia naturalis ranarum nostratium. Nürnberg, 1758.

Rudolphi and Breyer, Observationes anatomicae circa abricam Ranae pipae. Berolini, 1811.

Rusconi, M., Développement de la grenouille commune. Milan, 1826.

Schneider, J. G., Historia amphibiorum. Jenae, 1799.

Schwalbe, G., Lehrbuch der Anatomie der Sinnesorgane. Erlangen, 1885.

Stannius, H., Zootomie der Amphibien (Handb. der Zoot. der Wirbelthiere, 2 Buch). 2nd Edit. Berlin, 1856.

Stricker, S., Beiträge zur Biologie der Batrachier. Wien. Zool. Bot. Verhandl. 1866. Vol. XVI, pp. 451–456.

Stricker, S., Handbuch der Gewebelehre.

Stricker, S., Manual of Human and Comparative Histology. Translated by H. Power. London, 1870.

Swammerdam, J., Biblia Naturae Amstelodamensis. (Dutch and Latin by Gaubius. Leidae, 1738.)

Todd and Bowman, The Physiological Anatomy and Physiology of Man. London, 1845–1857.

Vogt, C., Zoologische Briefe. Frankfurt a. M., 1851.

Wagler, J., Natürliches System der Amphibien. München, Stuttgart, and Tübingen, 1830.

Wagner, R., Lehrbuch der vergleichenden Anatomie. Leipzig, 1834–1835.

Wagner, R., Icones Zootomicae. Leipzig, 1841.

Wagner, R., Handwörterbuch der Physiologie. 1842.

Waters, W. H., Histological Notes. Manchester and London, 1884.

Wiedersheim, R., Lehrbuch der vergleichenden Anatomie der Wirbelthiere. 2nd Edit. Jena, 1886.

Wiedersheim, R., Elements of Comparative Anatomy of Vertebrates. Translated by N. Newton Parker. London, 1886.

II. WORKS RELATING TO THE EMBRYOLOGY AND DEVELOPMENT OF THE FROG.

Balfour, F. M., Treatise on Comparative Embryology. London, 1880.

Born, G., Beiträge zur Bastardirung zwischen den einheimischen Anurenarten. Pflüger's Arch. f. d. ges. Physiol. 1883. Vol. XXXII, p. 453.

Durham, H. E., Note on the presence of a Neurenteric Canal in Rana. Quart. Journ. Micros. Sci. 1886. Vol. XXVI, p. 509.

Giles, A. E., The development of the fat-bodies in Rana temporaria. Quart. Journ. Micros. Sci. 1888. Vol. XXIX.

Goette, A., Kurze Mittheilungen aus der Entwicklungsgeschichte der Unke. Arch. f. mik. Anat. 1873. Vol. IX, p. 396.

Goette, A., Entwicklungsgeschichte der Unke. Leipzig, 1875.

Hertwig, O., Die Entwicklung des mittleren Keimblattes der Wirbelthiere. Jena, 1883.

Johnson, A., and Sheldon, L., Notes on the Development of the Newt (Triton cristatus). Quart. Journ. Micros. Sci. 1886. Vol. XXVI, p. 573.

Marshall, A. M., The Frog : An Introduction to Anatomy, Histology, and Embryology. 3rd Edition. Manchester and London, 1888.

Pflüger, E., Einige Beobachtungen zur Frage über die das Geschlecht bestimmenden Ursachen. Pflüger's Arch. f. d. ges. Physiol. 1881. Vol. XXVI.

Pflüger, E., Hat die Concentration des Samens einen Einfluss auf das Geschlecht ? Pflüger's Arch. f. d. ges. Physiol. 1883. Vol. XXIX, p. 1.

Pflüger, E., Zusammenstellung der Ergebnisse und Erörterung der Principien der Zeugung. Pflüger's Arch. f. d. ges. Physiol. 1883. Vol. XXXII, p. 542.

Pflüger, E., and Smith, W. J., Experimente über Bastardirung der anuren Batrachier. Pflüger's Arch. f. d. ges. Physiol. 1883. Vol. XXXII, p. 519.

Remak, Untersuchungen über die Entwickelung der Wirbelthiere. Berlin, 1855.

Schultze, O., Zur ersten Entwickelung des braunen Grasfrosches. Leipzig, 1887.

Schultze, O., Die Entwicklung der Keimblätter und der Chorda dorsalis von Rana fusca. Zeitschr. f. wiss. Zool. 1888. Vol. XLVII, p. 325.

Spencer, W. B., Some Notes on the Early Development of Rana temporaria. Quart. Journ. Micros. Sci. 1885. (Supplement.)

Stricker, S., Untersuchungen über die Entwicklung des Kopfes der Batrachier. Arch. f. Anat. u. Physiol. 1864, p. 52.

Török, A., Beiträge zur Kenntniss der ersten Anlagen der Sinnesorgane und der primären Schädelformation bei den Batrachiern. Moleschott's Untersuchungen, 1870. Vol. X, p. 338.

III. ADDITIONS TO THE LISTS GIVEN AT THE HEADS OF THE SECTIONS.

1. THE BONES.

Albrecht, P., Note sur le basi-occipital des batraciens anoures. Extr. d. Bullet. d. Musée royal d'hist. nat. de Belgique. 1883. Vol. II.

Born, G., Die sechste Zehe der Anuren. Morphol. Jahrb. 1876. Vol. I.

Born, G., Ueber das Skelet des Fersenhöckers von Rana fusca, etc. Sitzungsb. d. Schles. Gesell. f. vaterländ. Cultur. 1879.

Born, G., Nachträge zu Carpus und Tarsus. Morph. Jahrb. 1880. Vol. VI.

Ecker, A., Icones physiologicae. Leipzig, 1881–1889.

Ecker, A., Die Anatomie des Frosches. 2nd Edition. Braunschweig, 1888, pp. 17–62.

Gegenbaur, Untersuchungen zur vergl. Anatomie der Wirbelsäule bei Reptilien und Amphibien. Leipzig, 1862.

Gegenbaur, Grundzüge der vergl. Anatomie. Leipzig, 1870.

Goette, A., Brustbein und Schultergürtel auf entwickelungsgeschichtlicher Grundlage verglichen bei Amphibien und Anurioten. Arch. f. mik. Anat. 1877. Vol. XIV, p. 502.

Howes, G. B., On some abnormalities of the Frog's vertebral column. Anat. Anz. 1886. Vol. I, Pt. II.

Leydig, F., Ueber den Bau der Zehen bei Batrachiern und die Bedeutung des Fersenhöckers. Morphol. Jahrb. 1876. Vol. II.

Parker, W. K., A monograph on the structure and development of the shoulder-girdle and sternum. Ray. Soc. 1867.

Schneider, J. G., Historia amphibiorum. Jenae, 1799.

Stöhr, P., Zur Entwickelungsgeschichte des Anurenschädels. Zeitschr. f. wiss. Zool. 1881. Vol. XXXVI.

Török, A., Beiträge zur Kenntniss der ersten Anlagen der Sinnesorgane und der primären Schädelformation bei den Batrachiern. Moleschott's Untersuchungen. 1870. Vol. X, p. 338.

2. THE MUSCLES.

Albrecht, P., Beitrag zur Morphologie des M. omohyoides und der ventralen inneren Interbranchial-Musculatur. Inaug. Dissert. Kiel, 1876.

Ecker, A., Die Anatomie des Frosches. 2nd Edition. Braunschweig, 1888, pp. 65–139.

Hoffmann, C. K., Bronn's Klassen und Ordnungen des Thierreichs. Vol. VI. Amphibien. Leipzig, 1873–1878.

Howes, G. B., An Atlas of Practical Elementary Biology. London, 1885.

3. NERVOUS SYSTEM.

Engelmann, T. W., Ueber die Discontinuität des Axencylinders und den fibrillären Bau der Nervenfasern. Pflüger's Arch. f. d. ges. Physiol. 1880. Vol. XXII, p. 1.

Grandry, Recherches sur la structure interne du cylindre de l'axe et des cellules nerveuses. Bull. de l'Acad. Roy. du Belgique. 1868.

Hodge, C. F., Some effects of stimulating ganglion-cells. (Some anatomical details regarding the relations of nerve-fibres with nerve-cells are given.) American Journ. of Phys. 1888.

Owsjannikow, P., Ueber die Rinde des Grosshirns. Mémoires de l'acad. impériale des sciences de St. Pétersbourg. 1879. Series VII, Vol. XXVI, No. 11.

Spiro, Physiologisch-topographische Untersuchungen am Rückenmark des Frosches. Mémoires de l'acad. impériale des sciences de St. Pétersbourg. 1870. Series VII, Vol. XVI, No. 7.

Waldeyer, W., Untersuchungen über den Ursprung und Verlauf des Axencylinders. Henle u. Pfeuffer's Zeitschr. 1864. Vol. XX, pp. 193–257.

Consult also: **Gerlach, J., Mayer, S.,** and **Schultze, M.,** in Stricker's Handbuch der Gewebelehre.

4. THE VASCULAR SYSTEM.

Barthol, P., Sopra il sistema linfatico dei Rettili. Pavia, 1833.

Blaschek, A., Untersuchungen über Herz, Pericard, Endocard, und Pericardhöhle. Schenk's Mitt. 1885. New Series, p. 32.

Eberth, C. J., in Stricker's Handbuch der Gewebelehre.

Klein, E., On the peripheral distribution of non-medullated nerve-fibres (nerves of the blood-vessels in the frog's tongue). Quart. Journ. Micros. Sci. 1872. Vol. XII, p. 123.

Mayer, S., Studien zur Histologie und Physiologie des Blutgefässsystems. Wiener Sitzungsb. 1886. Vol. XCIII, Pt. III, p. 45.

v. Recklinghausen, F., (The lymphatics) in Stricker's Handbuch der Gewebelehre.

Rollett, A., (The Blood) in Stricker's Handbuch der Gewebelehre.

Teichmann, L., Untersuchungen über das Saugadersystem. Leipzig, 1861.

5. THE ALIMENTARY CANAL.

Heidenhain, R., Beiträge zur Kenntniss des Pancreas. Pflüger's Arch. f. d. ges. Physiol. 1875. Vol. X, p. 557.

Krause, W., Anatomische Untersuchungen (Tongue). Hannover, 1861.

Consult also: Klein, E., The Oral Cavity and the Oesophagus; Müller, W., The Spleen; Eberth, C. J., The Liver, in Stricker's Handbuch der Gewebelehre.

6. THE LUNGS AND LARYNX.

Holmgren, F., Methode zur Beobachtung des Kreislaufs in der Froschlunge. Beitr. z. Anat. u. Physiol. Festgabe f. C. Ludwig. Leipzig, 1874.

Meckel, J. F., Beiträge zur Geschichte des Respirations-Systemes der Amphibien. Meckel's Arch. 1849. Vol. V.

Schmidt, C., De l'épithelium pulmonaire. 1866.

Williams, Article Respiration, in Todd's Cyclopaedia of Anat. and Physiol. 1859. Vol. V.

7. THE URINO-GENITAL SYSTEM, THE ADRENALS, AND THE FAT-BODIES.

Aeby, C., Ueber glatte Muskelfasern im Ovarium und Mesovarium von Wirbelthieren. Arch. f. Anat. u. Physiol. 1859, p. 675.

Giles, A. E., The development of the fat-bodies in Rana temporaria. Quart. Journ. Micros. Sci. 1888. Vol. XXIX.

Grohe, F., Ueber die Bewegung der Samenkörper. Virchow's Arch. 1865. Vol. XXXII, p. 416.

Virchow, R., Ueber die Dotterplättchen bei den Fischen und Amphibien. Zeitschr. f. wiss. Zool. 1849. Vol. IV.

Consult also: Eberth, C. J.; v. La Valette St. George; Ludwig, C.; Grünwald; Obersteiner, H.; and Stricker, S., in Stricker's Handbuch der Gewebelehre.

8. The Skin and Sense-Organs.

www.libtool.com.cn

a. *The Skin.*

Busch, A., Phänomene aus dem Leben der Pigmentzellen. Arch. f. Anat. u. Physiol. 1856, p. 415.

b. *Special Organs of Tactile Sensation.*

Mitrophanow, P., Zur Entwicklungsgeschichte und Innervation der Nervenhügel der Urodelenlarven. Biologisches Centralb. 1887, p. 174.

c. *The Organs of Taste.*

Beale, L. S., New Observations upon the Minute Anatomy of the Papillae of the Frog's Tongue. Phil. Trans. 1865. Vol. CLV, p. 443.

Engelmann, T. W., in Stricker's Handbuch der Gewebelehre.

Maddox, R. L., A Contribution to the Minute Anatomy of the Fungiform Papillae and terminal arrangement of Nerve to striped Muscular Tissue in the Tongue of the common Frog. Monthly Micros. Journ. 1869, p. 1.

d. *The Ear.*

Albrecht, P., Sur la valeur morphologique de la trompe d'Eustache. Communication faite à la Société d'Anatomie Pathologique de Bruxelles. 1884.

v. Kölliker, Handbuch der Gewebelehre. 5th Edit. Leipzig, 1867.

Leydig, F., Handbuch der Histologie. Frankfurt a. M., 1857.

Rüdinger, in Stricker's Handbuch der Gewebelehre.

e. *The Nose.*

Marshall, A. M., Morphology of the Vertebrate Olfactory Organ. Quart. Journ. Micros. Sci. 1879. Vol. XIX, p. 330.

f. *The Eye.*

Ciaccio, G. V., Beobachtungen über den inneren Bau des Glaskörpers im Auge des Menschen und der Wirbelthiere im Allgemeinen. Moleschott's Untersuchungen, 1870. Vol. X, p. 383.

Hannover and Finkbeiner, Vergleichende Untersuchungen der Stärke des Glaskörpers bei den Wirbelthieren. Zeitschr. f. wiss. Zool. 1855. Vol. VI, p. 335.

Hirschberg, J., Zur Dioptric und Ophthalmologie der Fish- und Amphibienaugen. Arch. f. Anat. u. Physiol. 1887, p. 493.

Ranvier, L., Le mécanisme de la Sécrétion. Leçons faites au Collége de France en 1886–1887. (Nictitating membrane.)

Consult also: Rollett and Stieda, in Stricker's Handbuch der Gewebelehre.

INDEX.

—◆—

THE END.

www.libtool.com.cn

X^2

M'

X^3

$X3t$
$X3p$

Lg

g

g Fig. 112.

Bulb

VI

Memb.
tymp.

Ve'

Vd

·

www.libtool.com.cn